


BIDDING DATA SHEET

This section should be filled by procuring agency before issuing bidding documents.

| | | |
|----|---|---|
| 1 | Name of Procuring Agency | Town Committee Daulatpur |
| 2 | Brief Description of Work | Construction & repairing Surface Drain from house of Maqbool Kathio to Gird road & from house of Aziz to house of Abdul Kareem Soomro Ward No. 04 Town Committee Daulatpur District Shaheed Benazir Abad (Scheme No:05) |
| 3 | Procuring Agency Address | Town Committee Daulatpur District Shaheed Benazir Abad |
| 4 | Estimated Cost | 1448000 |
| 5 | Amount of Bid Security | 2% |
| 6 | Tender Fee | Rs: 2000/- DD No. _____ Date: _____ Bank _____ |
| 7 | Time Period of Bid Validity (days) | 90 Days |
| 8 | Security Deposit including Bid Security | 10% (2% at the time of Bid Submission and 8% deductible from the running bills) |
| 9 | Percentage if any deduct from bill | Any Tax payable to Government |
| 10 | Deadline of bid submission along with time | 19/12/2025 @ 11:00 AM |
| 11 | Opening Venue, Date & Time | Office of the Town Officer Town Committee Daulatpur. Date: 19/12/2025 @ 12:00 PM |
| 12 | Time of Completion from written order of commence | 06 Months |
| 13 | Deposit Receipt No. Date & Amount (in words and figure) | CD No. _____ Date: _____ Amount Rs: _____ Bank _____ M/s _____ |

Issuing Authority of Bidding Documents




Assistant Executive Engineer
Town Committee Kazi Ahmed

**OFFICE OF THE TOWN COMMITTEE DAULATPUR
TALUKA KAZI AHMED DISTRICT SHAHEED BENAZIR ABAD**

BILL OF QUANTITY/ SCHEDULE -B

NAME OF WORK:

**CONSTRUCTION & REPAIRING SURFACE DRAIN FROM HOUSE OF
MAQBOOL KATHIO TO GIRD ROAD & FROM HOUSE OF AZIZ TO HOUSE
OF ABDUL KAREEM SOOMRO WARD NO. 04 TOWN COMMITTEE
DAULATPUR DISTRICT SHAHEED BENAZIR ABAD (SCHEME NO:05)**

NAME OF AGENCY :

| Sr. No. | QTY | ITEMS | RATE | UNIT | RS | AMOUNT |
|---------|-----|-------|------|------|----|--------|
|---------|-----|-------|------|------|----|--------|

| | | | | | | |
|---|---------|---|-------------|--------|-----|---------|
| 1 | 150.00 | Dismateling Rcc work for sepreating & Cleaning GSI No.20 P/20 | @Rs 229.72 | P. Cft | Rs. | 34458 |
| 2 | 1425.00 | Excavation in Foundation of building bridges and other structure I/C Dagbelling dresing refilling around with excavated earth etc (SI No:18 P-17) | @Rs: 11.88 | P.Cft | Rs: | 16929 |
| 3 | 470.25 | Cement Concerate Plain curring and watering shingle agregrate 1:4:8 (SI No:05 P-25) | @Rs: 348.83 | P.Cft | Rs: | 164037 |
| 4 | 1068.75 | Pacca brick work in foundation and plinth (1:6) S.I NO 4 P-29 | @Rs 359.2 | P.CFT | Rs: | 383895 |
| 5 | 1425.00 | Cement Plaster (1:4)3/4 Thick (GSI 11 P-52) | @Rs 53.82 | P.SFT | Rs: | 76693.5 |
| 6 | 93.75 | RCC Work in Roof & Slabes beams colums lintels and other structure laid in position etc (GSI 6 P-25) | @Rs 717.59 | P.CFT | Rs: | 67274 |
| 7 | 3.77 | Fabrication of M.S Steel Rainforced i/c cutting jointing bending laying in position etc (GSI 8B P-226) | @Rs 17936 | PCWT | Rs: | 67560 |
| 8 | 570.00 | Construction of Standard open type surface drain i/c counttee Block design profile saction as per drawing etc (PHD NO D-P-146) | @Rs: 585.00 | P.RFT | Rs: | 333450 |

Total CSR a) Rs: 1144297

_____ % below / above on the rates of CSR
Total (A)=a+b in word & figure
Amount to be added / deducted on the

1,144,297

b) Rs. _____

Total Rs.

SRB 5% Rs. _____

G. Total Rs. _____

Total Amount in words (a+b) _____

CONTRACTOR



(Signature)
**Assistant Executive Engineer
Town Committe Qazi Ahmed**