


BIDDING DATA SHEET

This section should be filled by procuring agency before issuing bidding documents.

1	Name of Procuring Agency	Town Committee Daulatpur
2	Brief Description of Work	Construction & Repairing Type-II Surface Drain From Gird Station Road To House Of Liaquat Ward No:04 Town Committee Daulatpur District Shaheed Benazir Abad (Scheme No:04)
3	Procuring Agency Address	Town Committee Daulatpur District Shaheed Benazir Abad
4	Estimated Cost	1781000
5	Amount of Bid Security	2%
6	Tender Fee	Rs: 2000/- DD No. _____ Date: _____ Bank _____
7	Time Period of Bid Validity (days)	90 Days
8	Security Deposit including Bid Security	10% (2% at the time of Bid Submission and 8% deductible from the running bills)
9	Percentage if any deduct from bill	Any Tax payable to Government
10	Deadline of bid submission along with time	19/12/2025 @ 11:00 AM
11	Opening Venue, Date & Time	Office of the Town Officer Town Committee Daulatpur Date: 19/12/2025 @ 12:00 PM
12	Time of Completion from written order of commence	06 Months
13	Deposit Receipt No. Date & Amount (in words and figure)	CD No. _____ Date: _____ Amount Rs: _____ Bank _____ M/s _____

Issuing Authority of Bidding Documents




Assistant Executive Engineer
Town Committee Kazi Ahmed

OFFICE OF THE TOWN COMMITTEE DAULATPUR

TALUKA KAZI AHMED DISTRICT SHAHEED BENAZIR ABAD

BILL OF QUANTITY/ SCHEDULE -B

NAME OF WORK:

CONSTRUCTION & REPAIRING TYPE-II SURFACE DRAIN FROM GIRD STATION ROAD TO HOUSE OF LIAQAT WARD No:04 TOWN COMMITTEE DAULATPUR DISTRICT SHAHEED BENAZIR ABAD (SCHEME NO:04)

NAME OF AGENCY :

Sr. No.	QTY	ITEMS	RATE	UNIT	RS	AMOUNT
---------	-----	-------	------	------	----	--------

1	37.50	Dismateling Rcc work for sepreating & Cleaning GSI No.20 P/20	@Rs 229.72	P. Cft	Rs	8615
2	1425.00	Excavation in Foundation of building bridges and other structure I/C Dagbelling dresing refilling around with excavated earth etc (SI No:18 P-17)	@Rs: 11.88	P.Cft	Rs:	16929
3	470.25	Cement Concerate Plain curring and watering shingle	@Rs: 348.83	P.Cft	Rs:	164037
4	1282.50	Pacca brick work in foundation and plinth (1:6) S.I NO 4 P-29	@Rs 359.2	P.CFT	Rs:	460674
5	1710.00	Cement Plaster (1:4)3/4 Thick (GSI 11 P-52)	@Rs 53.82	P.SFT	Rs:	92032.2
6	62.50	RCC Work in Roof & Slabes beams columns lintels and other structure laid in position etc (GSI 6 P-25)	@Rs 717.59	P.CFT	Rs:	44849
7	2.23	Fabrication of M.S Steel Rainforced i/c cutting jointing bending laying in position etc (GSI 8B P-226)	@Rs 17936	PCWT	Rs:	40036
8	570.00	Construction of Standard open type surface drain i/c counttee Block design profile saction as per drawing etc (PHD NO D-P-146)	@Rs: 1,014.00	P.RFT	Rs:	577980

Total CSR a) Rs: 1405152

_____ % below / above on the rates of CSR

Total (A)=a+b in word & figure

1,405,152

Amount to be added / deducted on the

b) Rs. _____

Total Rs. _____

SRB 5% Rs. _____

G. Total Rs. _____

Total Amount in words (a+b) _____

CONTRACTOR



[Signature]
Assistant Executive Engineer
Town Committe Qazi Ahmed