


# BIDDING DATA SHEET

This section should be filled by procuring agency before issuing bidding documents.

1	Name of Procuring Agency	Town Committee Daulatpur
2	Brief Description of Work	Construction & repairing Surface Drain from house of Juman Unar to Water Course Village Chhar, from house of Anwar Otho to watercourse village Chhar & from Uris Hothipoto cattle farm to house of Ameer BuxDahri Ward No. 03 Town Committee Daulatpur District Shaheed Benazir Abad (Scheme No:03)
3	Procuring Agency Address	Town Committee Daulatpur District Shaheed Benazir Abad
4	Estimated Cost	2371000
5	Amount of Bid Security	2%
6	Time Period of Bid Validity (days)	90 Days
7	Tender Fee	Rs: 2000/- DD No. _____ Date: _____ Bank _____
8	Security Deposit including Bid Security	10% (2% at the time of Bid Submission and 8% deductible from the running bills)
9	Percentage if any deduct from bill	Any Tax payable to Government
10	Deadline of bid submission along with time	19/12/2025 @ 11:00 AM
11	Opening Venue, Date & Time	Office of the Town Officer Town Committee Daulatpur Date: 19/12/2025 @ 12:00 PM
12	Time of Completion from written order of commence	06 Months
13	Deposit Receipt No. Date & Amount (in words and figure)	CD No. _____ Date: _____ Amount Rs: _____ Bank _____ M/s _____

Issuing Authority of Bidding Documents



  
Assistant Executive Engineer  
Town Committee Kazi Ahmed

# OFFICE OF THE TOWN COMMITTEE DAULATPUR

TALUKA KAZI AHMED DISTRICT SHAHEED BENAZIR ABAD

## BILL OF QUANTITY/ SCHEDULE -B

NAME OF WORK:

CONSTRUCTION & REPAIRING SURFACE DRAIN FROM HOUSE OF JUMAN UNAR TO WATER COURSE VILAGE CHHAR, FROM HOUSE OF ANWAR OTHO TO WATER COURSE VILLAGE CHHAR & FROM URIS HOTHIPOTO CATTLE FARM TO HOUSE OF AMEER BUX DAHRI WARD NO. 03 TOWN COMMITTEE DAULATPUR DISTRICT SHAHEED BENAZIR ABAD (SCHEME NO:03)

NAME OF AGENCY :

Sr. No.	QTY	ITEMS	RATE	UNIT	RS	AMOUNT
1	45.00	Dismateling Rcc work for sepreating & Cleaning GSI No.20 P/20	@Rs 229.72	P. Cft	Rs	10337
2	2937.50	Excavation in Foundation of building bridges and other structure I/C Dagbelling dresing refilling around with excavated earth etc (SI No:18 P-17)	@Rs: 11.88	P.Cft	Rs:	34898
3	969.38	Cement Concerate Plain curring and watering shingle	@Rs: 348.83	P.Cft	Rs:	338147
4	1762.50	Pacca brick work in foundation and plinth (1:6) S:I NO 4 P-29	@Rs 359.2	P.CFT	Rs:	633090
5	2350.00	Cement Plaster (1:4)3/4 Thick (GSI 11 P-52)	@Rs 53.82	P.SFT	Rs:	126477
6	37.50	RCC Work in Roof & Slabes beams columns lintels and other structure laid in position etc (GSI 6 P-25)	@Rs 717.59	P.CFT	Rs:	26910
7	1.51	Fabrication of M.S Steel Reinforced i/c cutting jointing bending laying in position etc (GSI 8B P-226)	@Rs 17936	PCWT	Rs:	27024
8	1175.00	Construction of Standard open type surface drain i/c counttee Block design profile saction as per drawing etc (PHD NO D-P-146)	@Rs: 585.00	P.RFT	Rs:	687375

Total CSR a) Rs: 1884258

% below / above on the rates of CSR

Total (A)=a+b in word & figure

Amount to be added / deducted on the

1,884,258

b) Rs. \_\_\_\_\_

Total

Rs. \_\_\_\_\_

SRB 5%

Rs. \_\_\_\_\_


G. Total

Rs. \_\_\_\_\_

Total Amount in words (a+b) \_\_\_\_\_

CONTRACTOR



  
Assistant Executive Engineer  
Town Committee Qazi Ahmed