


# **BIDDING DATA SHEET**

This section should be filled by procuring agency before issuing bidding documents.

1	Name of Procuring Agency	Town Committee Daulatpur
2	Brief Description of Work	Providing & Lying Pavor Block From National Highway To House Of Asadullah Langah, From Mehboob Shah Chowk To Shop Of Jani Buriro & From House Of Gul Muhammad Soomro To Sayed Ali Gohar Shah Street Ward No: 02 Town Committee Daulatpur District Shaheed Benazir Abad (Scheme No:02)
3	Procuring Agency Address	Town Committee Daulatpur District Shaheed Benazir Abad
4	Estimated Cost	2995000
5	Amount of Bid Security	2%
6	Tender Fee	Rs: 2000/- DD No. _____ Date: _____ Bank _____
7	Time Period of Bid Validity (days)	90 Days
8	Security Deposit including Bid Security	10% (2% at the time of Bid Submission and 8% deductible from the running bills)
9	Percentage if any deduct from bill	Any Tax payable to Government
10	Deadline of bid submission along with time	19/12/2025 @ 11:00 AM
11	Opening Venue, Date & Time	Office of the Town Officer Town Committee Daulatpur Date: 19/12/2025 @ 12:00 PM
12	Time of Completion from written order of commence	06 Months
13	Deposit Receipt No. Date & Amount (in words and figure)	CD No. _____ Date: _____ Amount Rs: _____ Bank _____ M/s _____

Issuing Authority of Bidding Documents



  
Assistant Executive Engineer  
Town Committee Kazi Ahmed

**OFFICE OF THE TOWN COMMITTEE DAULATPUR  
TALUKA KAZI AHMED DISTRICT SHAHEED BENAZIR ABAD**

**BILL OF QUANTITY/ SCHEDULE -B**

NAME OF WORK: PROVIDING & LYING PAVOR BLOCK FROM NATIONAL HIGHWAY TO HOUSE OF ASADULLAH LANGAH, FROM MEHBOOB SHAH CHOWK TO SHOP OF JANI BURIRO & FROM HOUSE OF GUL MUHAMMAD SOOMRO TO SAYED ALI GOHAR SHAH STREET WARD NO: 02 TOWN COMMITTEE DAULATPUR DISTRICT SHAHEED BENAZIR ABAD (SCHEME NO:02)

NAME OF AGENCY : \_\_\_\_\_

Sr. No.	QTY	ITEMS	RATE	UNIT	RS	AMOUNT
1	5130.00	Barrow pit excavation undressed etc SI NO.3 P/15	@Rs 7.29	P. Cft	Rs	37398
2	5130.00	Earth work compaction in 6"layer dressing & leveling etc S.I no 3B P/16	@Rs: 1.58	P.Cft	Rs:	8105
3	2257.20	C.C Plain 1:4:8 I/C placing compacting , finishing and Curing etc (CSI No. 5 P/25	@Rs: 348.83	P.Cft	Rs:	787379
4	547.20	Laying, Murrum, Flooring consisting of 25 mm layer of fine powdery or vriety laid over good hard layer murrum (CSI No.	@Rs 100.78	P.Cft	Rs:	55147
5	6840.00	Providing and fixing paving block flooring having size of 197 x 97 x 60 (MM) of city / quddra /coble shape with natural color strength b/w 5000 psi to 8500 psi i/c filling the joints with hill sand & laying in spacefied. (SI No. 67 P/50)	@Rs: 197.48	P/Sft	Rs:	1350763

**Total CSR      a) Rs: 2238792**

\_\_\_\_\_ % below / above on the rates of CSR  
Total (A)=a+b in word & figure  
Amount to be added / deducted on the

2,238,792

b) Rs. \_\_\_\_\_

**Total      Rs.**

SRB 5%      Rs. \_\_\_\_\_

**G. Total      Rs. \_\_\_\_\_**

Total Amount in words (a+b) \_\_\_\_\_

CONTRACTOR



*(Signature)*  
**Assistant Executive Engineer  
Town Committe Qazi Ahmed**