



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ SAEEDABAD
TOLL PLAZA WEST SIDE
DISTRICT MATIARI
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Saedabad Toll Plaza West Side, District Matiyari.**

Estimated Cost : Rs. 8.479 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
SAEEDABAD TOLL PLAZA WEST SIDE DISTRICT MATIARI.
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173


BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base i/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet 1/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkhats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkhats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926




BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**


1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with & e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3 Nos.	1647.07	Each	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40 Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30 Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5 Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3 Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2 Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1 Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4 Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1 Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2 Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of circular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thick, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nuts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in ¾" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in ¾" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187

Total 540,960

Above / Below %

Total W/S & S/F Rs. _____

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit
- Electrical Internal Work - Non Schedule Items				
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Phillips)	8	Nos	Each
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)			
	i) ONE SWITCH PLATE	2	Nos	Each
	ii) TWO SWITCH PLATE	2	Nos	Each
	iii)FOUR SWITCH PLATE	2	Nos	Each
	iv)SIX SWITCH PLATE	2	Nos	Each
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)

2



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ AKRO NEAR
PETARO TOLL PLAZA
DISTRICT JAMSHORO FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Akro Near
Petaro Toll Plaza, District Jamshoro.

Estimated Cost : Rs. 8.190 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on
website EPADs at or before **10:00 AM on 02.04.2026 in
the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with
required documents as per bidders qualification
criteria. : _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D:No: : _____

Date: : _____

Bidding Documents Fee : _____


Signature of Bidder with Stamp

SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.


**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
AKRO NEAR PETARO TOLL PLAZA DISTRICT JAMSHORO.
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removeal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft	168,173

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed in position including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below					%
Total Rs.					

**Part "2" Civil Work, Plinth Protection & Platform.****I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648



Total Rs. 1,384,718


Above / Below %

Total Part 2 Rs.


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187

Total 540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
<u>Electrical Internal Work - Non Schedule Items</u>					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule _____
Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ BHIT SHAH
DISTRICT MATIARI
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Bhit Shah, District Matiyari.**

Estimated Cost : **Rs. 8.341 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents :From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids :**On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. _____

Venue, Time and date of bids opening :**On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
BHIT SHAH DISTRICT MATIARI.
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1 1/2"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below					%
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648

Total Rs. 1,384,718


Above / Below %

Total Part 2 Rs. _____

B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555


BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

**Electrical Internal Work - Schedule Items**


1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in ¾" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in ¾" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
<u>Electrical Internal Work - Non Schedule Items</u>					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Phillips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewireable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ DAUR
DISTRICT SHAHEED BENAZIRABAD
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD**



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Daur,
District Shaheed Benazirabad.

Estimated Cost : Rs. 8.921 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on
website EPADs at or before **10:00 AM on 02.04.2026 in
the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with
required documents as per bidders qualification
criteria. : _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____

Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
DAUR DISTRICT SHAHEED BENAZIRABAD
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11).	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1 1/2"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base i/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" i/c and frame of flat iron patti of 3/4" x3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926


BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

B Water Supply and Sanitary Fittings


1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104


BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16" thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos.	3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos.	16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos.	37698.31	Each.	37,698
Total Rs.						258,032
Above / Below					%	
Total W/S & S/F Rs.						

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187

Total 540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit
- Electrical Internal Work - Non Schedule Items				
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each
4	Providing & fixing Distribution Pannel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)			
	i) ONE SWITCH PLATE	2	Nos	Each
	ii) TWO SWITCH PLATE	2	Nos	Each
	iii)FOUR SWITCH PLATE	2	Nos	Each
	iv)SIX SWITCH PLATE	2	Nos	Each
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)

14



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640**

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ KEENJHAR
DISTRICT THATTA
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD**



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: **12.03.2026**

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Keenjhar, District Thatta.**

Estimated Cost : **Rs. 8.216 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents :From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids :**On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening :**On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: : _____


Date: : _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
KEENJHAR DISTRICT THATTA
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft	168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1 1/2"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkhats of size 7"x2" or 4-1/2"x3" for window using 20 gauge G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" I/c and frame of flat iron patti of 3/4" x3/4" I/c circle shape at 1-0 apart equivalent fitted with screws and pins I/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkhats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed in position including chowkhat. Holdfast, hinges. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundatiion of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.						1,384,718
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit		
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16" thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit		
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceiling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in ¾" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in ¾" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960

Above / Below %


Total W/S & S/F Rs.



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S
Total Non Schedule					
Total Scheduel + Non Schedule					

General Abstract

Part "A" Civil Work	
Part "B" W/S & S/F	
Part "C" Electrical Work	
Total	
Add 5% SRB	
G.Total	

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ KHADHAR
DISTRICT SHAHEED BENAZIRABAD
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Khadhar
(Beat No.75, &76), District Shaheed Benazirabad.

Estimated Cost : Rs. 4.995 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before 10:00 AM on 02.04.2026 in the office of SSP Hyderabad

Dead line for submission of bids : On 02.04.2026 upto 10.30 AM

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening : On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad

Issued to (Name of Bidder) : _____

D.D:No: _____


Date: _____

Bidding Documents Fee : _____


Signature of Bidder with Stamp

SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

RENOVATION OF POLICE HALT STATION IN SINDH @ KHADHAR DISTRICT
SHAHEED BENAZIRABAD
BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling Glazed or encaistic tiles etc:(S.No.56/P-8)	1192	Sft	31.19	P.Sft	37,178
2	Dismantling Cement concrete plain 1:2:4 (S.No.55/P-8)	1677	Cft	133.08	P.Cft	223,175
3	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	1677	Cft.	443.54	P.Cft	743,817
4	Laying Verona marble flooring Size 24"x 12"x 1 1/2"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	1325	Sft	369.59	P.Sft	489,707
5	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortor 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	160	Sft	247.28	P.Sft	39,565
6	Providing & Laying Full Body Porcelain Tile in Flooring or Facing of Approved Design Set in Gry Cement Motor 1:2 or of 3/4" Thickinss l/c Washing & Joints With White Cement Slurry Using Colour Pigment for matching complete as per Spacification. (ix)	1192	Sft	439.57	P.Sft	523,967
7	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools	99	Rft	690.67	P.Rft	68,376
8	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inoposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	170	Sft	1897.56	P.Sft	322,585
9	Removing cement or lime plaster. (SoR-2024,Ch-2,I-53,P-	1440	Sft	5.39	P Sft	7,762
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick.	1440	Sft	37.01	P.Sft	53,294
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick.	1440	Sft	37.78	P.Sft	54,403



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
12	Preparing the surface and painting with matt finish i/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	5418 Sft	49.27	P.Sft	266,945
13	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2184 Sft	39.38	P.Sft	86,006
14	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	466 Sft	18.41	P.Sft	8,579
15	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil, wood etc.(S.No.41) (P#29).	2964 Sft	95.62	P.Sft	283,418
16	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	96 Sft	341.78	P.Sft	32,811
17	Providing and fixing iron steel grill using solild square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	80 Sft	833.27	P.Sft	66,662


Total Rs. 3,308,250

Above / Below %

Total Rs. _____


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	6 Nos.	11282.90	Each.	67,697
---	---	--------	----------	-------	--------



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with & including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4. (S.No.20) (P#9).	12	Nos.	1647.07	Each.	19,765
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	65	Rft.	836.36	P. Rft.	54,363
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	55	Rft.	950.38	P. Rft.	52,271
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	8	Nos.	1673.10	Each.	13,385
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	12	Nos.	2784.60	Each.	33,415
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	12	Nos. 637.65	Each.	7,652
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos. 14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos. 9051.80	Each.	18,104
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles. 21" inch dia (S.No.1) (P#29).	3	Nos. 3238.79	Each.	9,716
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	3	Nos. 16771.18	Each.	50,314
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698

Total Rs. 429,130


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
Electrical Internal Work - Schedule Items						
1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	18	Nos	5958.53	Each	107254
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	4	Nos	3442.83	Each	13771
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceiling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm2) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	50	Rft	468.00	P.Rft	23400
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
16	Providing & fixing voltmeter size 96/96mm 500volt as required & as per instruction of EI(SI-No:240 P-No:22)	1	4186.50	Each	4,187
Total					377,464

Above / Below %

Total W/S & S/F Rs. _____

- Electrical Internal Work - Non Schedule Items

1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	3	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Phillips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battis 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule _____

Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ KHUDABAD
DISTRICT DADU FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Khuda-abad District Dadu.

Estimated Cost : Rs. 4.973 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____


D.D.No: : _____

Date: : _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.



RENOVATION OF POLICE HALT STATION IN SINDH @ KHUDABAD DISTRICT DADU

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling Glazed or encaistic tiles etc:(S.No.56/P-8)	1192	Sft	31.19	P.Sft	37,178
2	Dismantling Cement concrete plain 1:2:4 (S.No.55/P-8)	1677	Cft	133.08	P.Cft	223,175
3	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	1677	Cft.	443.54	P.Cft	743,817
4	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	1325	Sft	369.59	P.Sft	489,707
5	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	160	Sft	247.28	P.Sft	39,565
6	Providing & Laying Full Body Porcelain Tile in Flooring or Facing of Approved Design Set in Gry Cement Motor 1:2 or of 3/4" Thickinss l/C Washing & Joints With White Cement Slurry Using Colour Pigment for matching complete as per Spacification. (ix)	1192	Sft	439.57	P.Sft	523,967
7	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools	99	Rft	690.67	P.Rft	68,376
8	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	170	Sft	1897.56	P.Sft	322,585
9	Removing cement or lime plaster. (SoR-2024,Ch-2,I-53,P-	1440	Sft	5.39	P Sft	7.762
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick.	1440	Sft	37.01	P.Sft	53.294
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick.	1440	Sft	37.78	P.Sft	54.403



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
12	Preparing the surface and painting with matt finish i/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	5418	Sft	49.27	P.Sft	266,945
13	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2184	Sft	39.38	P.Sft	86,006
14	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	466	Sft	18.41	P.Sft	8,579
15	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and teh laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil, wood etc.(S.No.41) (P#29).	2964	Sft	95.62	P.Sft	283,418
16	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	96	Sft	341.78	P.Sft	32,811
17	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" i/c and frame of flat iron patti of 3/4" x3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	80	Sft	833.27	P.Sft	66,662


Total Rs. 3,308,250

Above / Below %

Total Rs.


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	6	Nos.	11282.90	Each.	67,697
---	---	---	------	----------	-------	--------



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4. (S.No.20) (P#9).	12	Nos.	1647.07	Each.	19,765
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	65	Rft.	836.36	P. Rft.	54,363
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	55	Rft.	950.38	P. Rft.	52,271
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	8	Nos.	1673.10	Each.	13,385
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	12	Nos.	2784.60	Each.	33,415
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	12	Nos. 637.65	Each. *	7,652
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos. 14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos. 9051.80	Each.	18,104
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	3	Nos. 3238.79	Each.	9,716
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	3	Nos. 16771.18	Each.	50,314
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698

Total Rs. 429,130

Above / Below %

Total W/S & S/F Rs.




BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
Electrical Internal Work - Schedule Items						
1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	18	Nos	5958.53	Each	107254
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	4	Nos	3442.83	Each	13771
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	50	Rft	468.00	P.Rft	23400
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
16	Providing & fixing voltmeter size 96/96mm 500volt as required & as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each
Total					377,464




Above / Below %

Total W/S & S/F Rs.

- Electrical Internal Work - Non Schedule Items

1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos		Each
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos		Each
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	3	Nos		Each
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft		P.Sft
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos		Each
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos		Each
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos		Each
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos		Each
	ii) TWO SWITCH PLATE	2	Nos		Each
	iii)FOUR SWITCH PLATE	2	Nos		Each
	iv)SIX SWITCH PLATE	2	Nos		Each



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewireable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ LAL BAGH
SEHWAN DISTRICT JAMSHORO
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD**



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No: A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Lal Bagh Sehwan, District Jamshoro.**

Estimated Cost : Rs. 8.454 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D:No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**

REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @ LAL
BAGH SEHWAN DISTRICT JAMSHORO.
BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hinges. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	112,249
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below					%
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below %						
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items


1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Batttris 440-W (01-No) complete in all respect.	1		Job	L.S
Total Non Schedule					
Total Scheduel + Non Schedule					

General Abstract

Part "A" Civil Work	
Part "B" W/S & S/F	
Part "C" Electrical Work	
Total	
Add 5% SRB	
G.Total	

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ MAKHDOOM
BILAWAL DISTRICT DADU
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No: A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @
Makhdoom Bilawal Johi Morr, District Dadu.

Estimated Cost : Rs. 8.704 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on
website EPADs at or before 10:00 AM on 02.04.2026 in
the office of SSP Hyderabad

Dead line for submission of bids : On 02.04.2026 upto 10.30 AM

Duly completed in all respects and along with
required documents as per bidders qualification
criteria. _____

Venue, Time and date of bids opening : On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
MAKHDOOM BILAWAL DISTRICT DADU
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 : 3 : 6 Cement concrete solid Block masorany set in 1 : 6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkhats of size 7"x2" or 4-1/2"x3" for window using 20 gauge G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" i/c and frame of flat iron patti of 3/4" x3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkhats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed in position including chowkhat. Holdfast, hinges. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below					%
Total Rs.					

**Part "2" Civil Work, Plinth Protection & Platform.****I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648



Total Rs. 1,384,718

Above / Below %


Total Part 2 Rs.

B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

**Electrical Internal Work - Schedule Items**

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in ¾" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in ¾" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Privinging & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187


Total**540,960****Above / Below %****Total W/S & S/F Rs.**

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	



BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule

Total Scheduel + Non Schedule

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ MATIARI TOLL
PLAZA DISTRICT MATIARI
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Matiyari Toll Plaza, District Matiyari.**

Estimated Cost : **Rs. 8.265 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents :From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids :**On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening :**On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D:No: : _____


Date: : _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.


**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
MATIARI TOLL PLAZA DISTRICT MATIARI.
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188 Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2 Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339 Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592 Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735 Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362 Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683 Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000 Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023 Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544 Sft	37.01	P.Sft	168,173

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortor 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortor 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortor 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400



BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkhats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkhats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inoposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	112,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below					%
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P. Sq	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4. (S.No.20) (P#9).	3	Nos.	1647.07	Each	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below %					
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items


1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15 Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3 Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20 Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2 Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2 Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175 Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50 Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4 Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1 Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130 Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1 Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1 Nos	4186.50	Each	4,187
Total					540,960

Above / Below %


Total W/S & S/F Rs.



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
10	Solar System P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Batttris 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule

Total Scheduel + Non Schedule

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640**

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ MIRPURKHAS
TOLL PLAZA
DISTRICT MIRPURKHAS
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Toll Plaza
Mirpurkhas, District Mirpurkhas.

Estimated Cost : Rs.8.500 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents :From the date of publication in press/hosted on
website EPADs at or before **10:00 AM on 02.04.2026** in
the office of SSP Hyderabad

Dead line for submission of bids :**On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with
required documents as per bidders qualification
criteria. _____

Venue, Time and date of bids opening :**On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D:No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
MIRPURKHAS TOLL PLAZA DISTRICT MIRPURKHAS
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188 Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2 Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339 Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592 Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735 Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362 Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683 Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removeal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000 Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023 Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544 Sft	37.01	P.Sft	168,173


BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544	Sft	37.78	P.Sft 171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061	Cft	6.50	P.Cft 6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385	Cft	47.02	P.Cft 112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125	Cft.	443.54	P.Cft 55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678	Sft	369.59	P.Sft 250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25	Sft	325.40	P.Sft 8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30	Sft	389.36	P.Sft 11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base i/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865	Sft	247.28	P.Sft 213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628	Sft	108.75	P.Sft 68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548	Sft	95.62	P.Sft 52,400

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet 1/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkhats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkhats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926




BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below %					
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.


I.SCHEDULE ITEMS.

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

**B Water Supply and Sanitary Fittings**

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4. (S.No.20) (P#9).	3	Nos.	1647.07	Each	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16" thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

**Electrical Internal Work - Schedule Items**

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in ¾" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in ¾" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187


Total**540,960****Above / Below %****Total W/S & S/F Rs.**

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	



BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule
Total Scheduel + Non Schedule

General Abstract

Part "A" Civil Work	
Part "B" W/S & S/F	
Part "C" Electrical Work	
Total	
Add 5% SRB	
G.Total	

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ OONGHER
DISTRICT THATTA
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Oonghar, District Thatta.**

Estimated Cost : **Rs. 8.205 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINGH @
OONGHER DISTRICT THATTA
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1 1/2"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc. (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	30	Nos	5958.53	Each	178756
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceiling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						493,291

Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit
- Electrical Internal Work - Non Schedule Items				
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each
4	Providing & fixing Distribution Pannel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)			
	i) ONE SWITCH PLATE	2	Nos	Each
	ii) TWO SWITCH PLATE	2	Nos	Each
	iii)FOUR SWITCH PLATE	2	Nos	Each
	iv)SIX SWITCH PLATE	2	Nos	Each
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
10	Solar System P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ SAEEDABAD
TOLL PLAZA EAST SIDE
DISTRICT MATIARI
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Saeedabad Toll Plaza East Side, District Matiari.**

Estimated Cost : **Rs. 8.479 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
SAEEDABAD TOLL PLAZA (EAST SIDE) DISTRICT MATIARI
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1 1/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solild square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each 5601
6	Providing & Fixing A.C Electric Ceiling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each 44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each 9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each 1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each 1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft 70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft 33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each 10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each 28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft 60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each 4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each 4,187

Total 540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Pannel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640**

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ SAKRAND
DISTRICT SHAHEED BENAZIRABAD
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Sakrand
Khabar Stop, District Shaheed Benazirabad.

Estimated Cost : Rs. 8.696 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on
website EPADs at or before 10:00 AM on 02.04.2026 in
the office of SSP Hyderabad

Dead line for submission of bids : On 02.04.2026 upto 10.30 AM

Duly completed in all respects and along with
required documents as per bidders qualification
criteria. : _____

Venue, Time and date of bids opening : On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH
SAKRAND DISTRICT SHAHEED BENAZIRABAD
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188 Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2 Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339 Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592 Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735 Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362 Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683 Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000 Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023 Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544 Sft	37.01	P.Sft	168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gauge G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" I/c and frame of flat iron patti of 3/4" x 3/4" I/c circle shape at 1-0 apart equivalent fitted with screws are pins I/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed in position including chowkhat. Holdfast, hinges. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with & including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos.	3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of circular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos.	16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos.	37698.31	Each.	37,698
Total Rs.						258,032
Above / Below					%	
Total W/S & S/F Rs.						

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15 Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3 Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20 Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2 Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2 Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175 Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50 Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4 Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1 Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130 Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1 Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1 Nos	4186.50	Each	4,187

Total 540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)

20



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640**

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ TAPAL PLAZA
KANDIARO DISTRICT N-FEROZ
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD**



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**


(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference	: NIT No:A/ <u>5834-40</u> Dated: 12.03.2026
Name of Scheme: Work	: Repair Renovation Work of Halting Point @ Toll Plaza Kandiara, District Noushero Feroz.
Estimated Cost	: <u>Rs.9.282 (M)</u>
Completed Period	: <u>30 days</u>
Bid Security	: <u>5% of Bid Price</u>
Call Deposit/pay Order No:	: _____
Date	: _____
Name of Bank	: _____
Amount of Call Deposit/Pay Order	: _____
Receipt of applications and issuance of bidding documents	:From the date of publication in press/hosted on website EPADs at or before 10:00 AM on 02.04.2026 in the office of SSP Hyderabad
Dead line for submission of bids	: On 02.04.2026 upto 10.30 AM
Duly completed in all respects and along with required documents as per bidders qualification criteria.	: _____
Venue, Time and date of bids opening	: <u>On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad</u>
Issued to (Name of Bidder)	: _____
D.D.No:	: _____
Date:	: _____
Bidding Documents Fee	: _____

Signature of Bidder with Stamp

**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**


**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
TOLL PLAZA KANDIARO DISTRICT NAUSHAHRO FEROZE
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188 Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2 Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339 Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592 Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735 Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362 Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683 Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000 Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023 Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544 Sft	37.01	P.Sft	168,173

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortor 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortor 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortor 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividind into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc. (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400




BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solild square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below %					
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.

I.SCHEDULE ITEMS.

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.i. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connectioin & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16" thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

**Electrical Internal Work - Schedule Items**

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15 Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3 Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20 Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2 Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2 Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175 Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm2) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50 Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4 Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1 Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130 Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1 Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1 Nos	4186.50	Each	4,187
Total					540,960
Above / Below					%
Total W/S & S/F Rs.					




BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
<u>Electrical Internal Work - Non Schedule Items</u>					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	



BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule _____
 Total Scheduel + Non Schedule _____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


**HALTING POINT PP @ TOLL PLAZA
MORO DISTRICT N/FEROZ
FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Toll Plaza Moro, District Noushero Feroz.**

Estimated Cost : **Rs.8.976 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
TOLL PLAZA MORO DISTRICT NAUSHAHRO FEROZE
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling cement concrete reinforced 1:2:4 separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft	168,173


BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc. (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also inclucing all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solild square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inoposition including chowkhat. Holdfast, hinges. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coaat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below					%
Total Rs.					


Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundatioin of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192




BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

**B Water Supply and Sanitary Fittings**

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below %					
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items


1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceiling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Priving & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960
Above / Below					%	
Total W/S & S/F Rs.						


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
- Electrical Internal Work - Non Schedule Items					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
-----	---------------	----------	------	------	--------



Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	

Total Non Schedule

Total Scheduel + Non Schedule

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ AMRI
TOLL PLAZA**


**DISTRICT JAMSHORO FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD**



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Amri Toll Plaza, District Jamshoro.**

Estimated Cost : **Rs. 8.507(M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents :From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids :**On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening :**On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: : _____


Date: : _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
AMRI TOLL PLAZA DISTRICT JAMSHORO.
BOQ / Schedule-B**



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" gauge.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 : 3 : 6 Cement concrete solid Block masorany set in 1 : 6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount:
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base i/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet I/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below %					
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648

Total Rs.

1,384,718

Above / Below %


Total Part 2 Rs.

B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555



BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15 Nos	373.39	Each	
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3 Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20 Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2 Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2 Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175 Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50 Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4 Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1 Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130 Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1 Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1 Nos	4186.50	Each	4,187

Total 540,960


Above / Below %

Total W/S & S/F Rs. _____

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit
- Electrical Internal Work - Non Schedule Items				
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)			
	i) ONE SWITCH PLATE	2	Nos	Each
	ii) TWO SWITCH PLATE	2	Nos	Each
	iii)FOUR SWITCH PLATE	2	Nos	Each
	iv)SIX SWITCH PLATE	2	Nos	Each
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewireable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	
Total Non Schedule					_____
Total Scheduel + Non Schedule					_____

General Abstract

Part "A" Civil Work	
Part "B" W/S & S/F	
Part "C" Electrical Work	
Total	
Add 5% SRB	
G.Total	

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640**

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ LOONIKOT
DISTRICT JAMSHORO FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Looni Kot,
District Jamshoro.**

Estimated Cost : **Rs. 8.103 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price** _____

Call Deposit/pay Order No: : _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents :From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids :**On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening :**On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: : _____


Date: : _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH
LOONIKOT DISTRICT JAMSHORO
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft	168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortor 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortor 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortor 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet 1/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkhats of size 7"x2" or 4-1/2"x3" for window using 20 gauge G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expanded metal 3/32 -20 Gauge fixed to chowkhats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed in position including chowkhat. Holdfast, hinges. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926


BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coaat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundatioin of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.						1,384,718
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with & e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16" thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	6,478
16	Constructing mainhole or inspection chamber for the required diameter of circular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thick, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nuts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5504
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44808
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit
- <u>Electrical Internal Work</u> - Non Schedule Items				
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)			
	i) ONE SWITCH PLATE	2	Nos	Each
	ii) TWO SWITCH PLATE	2	Nos	Each
	iii)FOUR SWITCH PLATE	2	Nos	Each
	iv)SIX SWITCH PLATE	2	Nos	Each
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S
Total Non Schedule					_____
Total Scheduel + Non Schedule					_____

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640**

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ MANJHAND
DISTRICT JAMSHORO FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD**



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No: A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @
Manjhand, District Jamshoro.**

Estimated Cost : Rs. 8.362 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D:No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

**SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.**


**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
MANJHAND DISTRICT JAMSHORO.
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188 Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2 Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339 Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592 Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735 Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362 Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683 Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000 Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 : 3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023 Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544 Sft	37.01	P.Sft	168,173


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base i/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400



BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solid square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inoposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbing brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below %					
Total Rs.					

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each.	
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

Electrical Internal Work - Schedule Items


1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required & as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960


Above / Below %

Total W/S & S/F Rs.

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
- <u>Electrical Internal Work</u> - <u>Non Schedule Items</u>					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	L.S

Total Non Schedule

Total Scheduel + Non Schedule

General Abstract

Part "A" Civil Work _____

Part "B" W/S & S/F _____

Part "C" Electrical Work _____

Total _____

Add 5% SRB _____

G.Total _____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD
Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK


HALTING POINT PP @ THOREE PHATAK
DISTRICT JAMSHORO FOR THE
CURRENT FINANCIAL YEAR 2025-2026

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : **Repair Renovation Work of Halting Point @ Thoree Phatak, District Jamshoro.**

Estimated Cost : **Rs. 8,408 (M)**

Completed Period : **30 days**

Bid Security : **5% of Bid Price**

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before **10:00 AM on 02.04.2026 in the office of SSP Hyderabad**

Dead line for submission of bids : **On 02.04.2026 upto 10.30 AM**

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening : **On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad**

Issued to (Name of Bidder) : _____

D.D.No: _____

Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp


SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.

**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH
THOREE PHATAK DISTRICT JAMSHORO
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount	
Part "A" Civil Work						
I.SCHEDULE ITEMS.						
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft	43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each	1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft	8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft	18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft	218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft	130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting centering,shuttering and curring. (including screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft	490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt	749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft	493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft	168,173

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	174,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base i/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount	
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet i/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36	Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136	Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solild square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232	Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88	Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88	Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176	Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415	Sft	3.59	P.Sft	1,490
28	Distemping (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415	Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360	Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
				Total Rs.	4,984,146
				Above / Below	%
				Total Rs.	

Part "2" Civil Work, Plinth Protection & Platform.**I.SCHEDULE ITEMS.**

1	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curring, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.						1,384,718
Above / Below					%	
Total Part 2 Rs.						


B Water Supply and Sanitary Fittings

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555

BOQ / Schedule-B




S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each.	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder,soap tray,shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount	
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos.	3238.79	Each.	
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) from the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos.	16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of niuts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos.	37698.31	Each.	37,698
Total Rs.						258,032
Above / Below					%	
Total W/S & S/F Rs.						

Electrical Internal Work - Schedule Items


1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceilling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/029 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/044 (6mm ²) copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187
Total						540,960

Above / Below %

Total W/S & S/F Rs.


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
-----	---------------	----------	------	------	--------

Electrical Internal Work - Non Schedule Items

1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Pannel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B



S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1	Job	L.S	
Total Non Schedule					_____
Total Scheduel + Non Schedule					_____

General Abstract

Part "A" Civil Work	_____
Part "B" W/S & S/F	_____
Part "C" Electrical Work	_____
Total	_____
Add 5% SRB	_____
G.Total	_____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
HYDERABAD**

Tel # 022-9200640

BIDDING DOCUMENT

REPAIR / RENOVATION OF WORK

**HALTING POINT PP @ INDUS RIVER
BRIDGE EAST SIDE B.NAGAR DISTRICT
HYDERABAD FOR THE
CURRENT FINANCIAL YEAR 2025-2026**

Issued to:

M/s _____



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD



**SPPRA BIDDING DOCUMENTS
STANDARD FORM OF BIDDING DOCUMENTS
FOR PROCUREMENT WORKS**

(For Contracts (small) amounting between Rs: 0.500 million to Rs: 50.000 million)

Reference : NIT No:A/5834-40 Dated: 12.03.2026

Name of Scheme: Work : Repair Renovation Work of Halting Point @ Indus River Bridge East Side B.Nagar, District Hyderabad.

Estimated Cost : Rs. 8.127 (M)

Completed Period : 30 days

Bid Security : 5% of Bid Price

Call Deposit/pay Order No: _____

Date : _____

Name of Bank : _____

Amount of Call Deposit/Pay Order : _____

Receipt of applications and issuance of bidding documents : From the date of publication in press/hosted on website EPADs at or before 10:00 AM on 02.04.2026 in the office of SSP Hyderabad

Dead line for submission of bids : On 02.04.2026 upto 10.30 AM

Duly completed in all respects and along with required documents as per bidders qualification criteria. : _____

Venue, Time and date of bids opening : On 02.04.2026 at 11.00 AM @ SSP Office Hyderabad

Issued to (Name of Bidder) : _____

D.D.No: _____


Date: _____

Bidding Documents Fee : _____

Signature of Bidder with Stamp

SSP HYD
Secretary/Member Procurement Committee
SSP Office Hyderabad.


**REPAIR & RENOVATION WORK OF POLICE HALT STATION IN SINDH @
INDUS RIVER BRIDGE EAST SIDE DISTRICT HYDEABAD.
BOQ / Schedule-B**




S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Part "A" Civil Work					
I.SCHEDULE ITEMS.					
1	Dismantling cement concrete reinforced separating reinforced cement from concrete cleaning and straightening the same (S.No.20/P-10)	188	Cft.	229.72	P.Cft 43,187
2	Removing Door with chowkat (S.I.No.32/P-21)	2	Nos	574.26	Each 1,149
3	Dismantling brick work in mud mortar (S.I.No.32/P-21)	339	Cft	23.76	P.Cft 8,055
4	Excavation in foundation of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft. ,lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	1592	Cft.	11.88	P.Cft 18,913
5	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	735	Cft	296.69	P.Cft 218,067
6	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	362	Cft.	359.20	P.Cft 130,030
7	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also incudes all kinds of forms moulds lifting centering,shuttering and curring. (inluding screening and washing of shingle.) (a) R.C.C work in roof slab, beams, coloumn,rafts, Intels and other structural members laid in situ or present laid in position complete in all respects.(i) Ratio 1 : 2 : 4 90 Lbs of cement. 2 Cft sand and 4 Cft shingle 1/8" to 3/4" guage.(S.No.6) (P#11.	683	Cft.	717.59	P.Cft 490,114
8	Fabrication of deformed steel reinforcement for cement concrete including cutting,bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) a) i) Grade-60 (SINIO.8(a-i) P-26)	41.000	Cwt	18271.01	P.Cwt 749,111
9	Providing and laying 1 :3 : 6 Cement concrete solid Block masorany set in 1 :6 cement sand mortar in plinth and foundation in cluding raking out joints and curing etc. complete (SINO.22/P-30)	1023	Cft	481.95	P.Cft 493,035
10	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	4544	Sft	37.01	P.Sft 168,173

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
11	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P#38).	4544 Sft	37.78	P.Sft	171,672
12	Filling, watering and ramming earth in under floors with surplus earth from foundation etc. lead upto one chain and lift upto 5 feet. with Surplus earth from foundation etc (SINO.21 P-17)	1061 Cft	6.50	P.Cft	6,897
13	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	2385 Cft	47.02	P.Cft	112,143
14	Cement concrete plain including placing compacting, finishing and curring, complete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	125 Cft.	443.54	P.Cft	55,443
15	Laying Verona marble flooring Size 24"x 12"x 1"/12"x 12"x 1" fine dressed on the surface without winding set in lime mortar 1:2 including rubbing and polishing of the joints. (SoR-2024,Ch-8, I-28, P-32) (a) 3/4" thick marble	678 Sft	369.59	P.Sft	250,582
16	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing. (S.I.No. 25 P-43)	25 Sft	325.40	P.Sft	8,135
17	Laying floor of approved with glazed tiles 1/4" thick dado of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing(SINO.24 P-45)	30 Sft	389.36	P.Sft	11,681
18	P/F 3/8" thick Marble Tiles of Approved Quality & Colour & Shade size 8"x4" or 6"x4" in dado Skirting & facing removal tucking of existung plaster surface etc.over 1/2" thick base of cement mortar 1:3 setting of tile in slurry of white cement over motor base l/c filling & joints &washing the tile with white cemebt slurry curent finishing cleaning & polishing etc, complete (New Work) (SoR-2024,Ch-8, I-61, P-35)	865 Sft	247.28	P.Sft	213,897
19	Providing and laying 2" thick topping of cement concrete (1:2:4) including Surface finishing and dividiing into panels: (SoR-2024,Ch-8, I-16, P-31)	628 Sft	108.75	P.Sft	68,295
20	Providing and fixing with bitumen felt paper of 60 Lbs over roof i/c cleaning of roof with wire brush an removing dust, applying bitumen coat at the rate of 34 Lbs per P.Sft as premix inter coats and tehn laying felt papper with 10% over laps, then applying and spreading hill sand at the rate of 1 cft for 100 sft. The coast also i/c necessary for material, kerosene oil wood etc. (S No 41) (P#29)	548 Sft	95.62	P.Sft	52,400




BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
21	Providing and fixing G.I frames /Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 guage G.I sheet l/c wedded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage. tools and plants used in making and fixing. (S.No.29) (P#63).	36 Rft	690.67	P.Rft	24,864
22	P/F G.I. Frame / Chowkats of size 7"x2" or 4-1/2"x3" for window using 20 gague G.I.sheet including welded hinges and fixing at site with necessary holds fasts filling with cement sand slurry or ratio 1:6 and repairing the jambs the cost also including all carriage tolls and plants used in making and fixing . (S.I.No. 28 P-76)	136 Rft	908.25	P.Rft	123,522
23	Providing and fixing iron steel grill using solild square bars of size 1/2" x 1/2" placed at 4" 1/c and frame of flat iron patti of 3/4" x3/4" 1/c circle shape at 1-0 apart equivalent fitted with screws are pins 1/c painting 3 coats with 1st coat of red oxide paint etc. (S.No.30) (P#63).	232 Sft	833.27	P.Sft	193,319
24	Galvanized wire gauge 144 mesh per square inch of 22 S.W.G fixed to chowkhats without deodar patti. (SoR-2024,Ch-10, I-62, P-47)	88 Sft	341.78	P.Sft	30,077
25	Providing & fixing Aluminum expaned metal 3/32 -20 Gauge fixed to chowkats with 3/4" deodar strips & screws. (SoR-2024,Ch-17, I-34, P-64)	88 Sft	538.87	P.Sft.	47,421
26	First class deodar wood wrought joinery in doors and windows etc: panelled or panelled or glazed or fully glazed fixed inposition including chowkhat. Holdfast, hingers. Tower bolt rubber stop cleats/G I clamp,handles and chord with hooks etc. complete (excluding sliding bolts or lock). (S.No.7-i) (a) 1 3/4" thick. (P-42) Without Chowkat.	176 Sft	1897.56	P.Sft	333,971
27	Priming coat of chalk under distemper. (SoR-2024,Ch-9, I-23, P-39)	415 Sft	3.59	P.Sft	1,490
28	Distempering (S.No.24) (P#39) (c) New Surface (iii) Three coats.	415 Sft	17.23	P.Sft	7,150
29	Making and fixing fiber glass sun shade standard size 3mm sheet (02 layer) molded in panel in/c M.S Pipe 6" dia 20' height at 20' center fixing C.C foundation with M.S Square pipe 1-1/2" x 1-1/2" double kanchi around from with internal M.S Square pipe 2x2 center to center in/c welding assembling etc complete in all respect. (SoR-2024,Ch-18, I-119, P-75)	360 Sft	2041.46	Per Sft.	734,926

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.
30	(A) Preparing the surface and painting with matt finish l/c rubbing the surface with Bathy (silicon carbide rubbig brick) filling the voids with zink /chalk/ plaster of paris mixture. Applying first coat premix, making the surface smooth and then painting 3 coats with matt finish of approved make etc: complete . (new surface). (S.No.36) (A) (P#40).	2262 Sft	49.27	P.Sft	111,449
31	Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.No.38) (A) (P#40).	2282 Sft	39.38	P.Sft	89,865
32	Preparing surface and PNS painting doors and windows any type. (including edges). (S.No.5) (c) (P#49). (i) Priming coat. (ii) Each Subsequent coat	623 Sft	18.41	P.Sft	11,469
33	Painted sashes, fan lights, glazed or gaused, door & window (7.99+6.32+632)	198 Sft	18.41	P.Sft	3,645
Total Rs.					4,984,146
Above / Below %					
Total Rs.					

**Part "2" Civil Work, Plinth Protection & Platform.****I.SCHEDULE ITEMS.**

1	Excavation in foundatiion of Building Bridges and other structures including dagbelling dressing.refillingaround structure with excavated earth Watering and ramming lead upto 5ft .lead upto one chain (30 metre) and lift upto 5 ft. (1.5 metre).(S.No.18) (A) (P#3) ordinary soil	610 Cft.	11.88	P.Cft	7,247
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (S.No.4) (b) (P#10).	546 Cft	296.69	P.Cft	161,993
3	Pacca brick work in foundation and plinth in:(e)Cement sand mortar 1:6 (S.No.4 / P#15).	458 Cft.	359.20	P.Cft	164,514
4	Cement plaster 1:6 upto 12' upto 20 ft height(b) 1/2" thick. (S.No.13) (P#38)	1220 Sft	37.01	P.Sft	45,152
5	Cement plaster 1:4 upto 12' height. (a) 3/8" thick. (S.No.11) (P # 38).	1220 Sft	37.78	P.Sft	46,092
6	Cement concrete plain including placing compacting, finishing and curing, comlete (including screening and washing at stone aggregate without shuttering.(f) ration1:2:4. (S.I. No.5-F Page-11)	156 Cft.	443.54	P.Cft	69,192

BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
7	Mosaic chequer tiles of 8" x 8" x 1- 1/4" of approved shade laid flat in 1:2 grey cement mortar over a bed of 3/4" thick grey cement mortar. 1:2. (SoR-2024,Ch-8, I-51, P-34)	1610	69.25	296.82	P.Sft	477,880
10	Filling, watering and ramming earth under floor with new earth (Excavated from outside) lift upto 5 ft and lead upto 10 miles including cost of earth. (SoR-2024,Ch-1,I-22,P-3)	8776	Cft	47.02	P.Cft	412,648
Total Rs.					1,384,718	
Above / Below					%	
Total Part 2 Rs.						

**B Water Supply and Sanitary Fittings**

1	Providing and fixing Orisa type white glazed earthen ware W.C pan with front flush intel & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.3) (b) (P#6).	1	Nos.	11282.90	Each.	11,283
2	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with &e including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia chrome plated brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics). (S.No.8) (P#7).	2	Nos.	9495.14	Each.	18,990
3	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern). (S.No.9) (P#7).	2	Nos.	3276.00	Each.	6,552
4	Providing and fixing steel sinks stainless local bt make complete with cast iron or wrought iron LINA ALVH brackets 6 inches built into wall, 1-1/2" rubber plug and chrome plated brass chain 1-1/2" C.P. brass waste with 1-1/2" P.V.C. waste pipe & making requisite number of holes in walls, plinth & floor for pipe connections & making good in cement concrete 1:2:4. (S.No.19) (P#8) (a) Steel Sink stainless size 40"x20" local make (standard pattern).	1	Nos.	12555.27	Each.	12,555


BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with C.I.screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2 :4. (S.No.20) (P#9).	3	Nos.	1647.07	Each	4,941
6	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (v) 4 " dia UPVC Pipe (SDR SERIES).	40	Rft.	836.36	P. Rft.	33,454
7	Providing UPVC pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the buildings and testing with water to a pressure bead of 200 feet and handling. (S.No.2) (P#13) (vi) 6 "dia UPVC Pipe (SDR SERIES).	30	Rft.	950.38	P. Rft.	28,511
8	S/fixing concealed Tee-stop cock of superior quality with Crystal head 1/2" dia	5	Nos.	1673.10	Each.	8,366
9	Supplying & fixing long Bib -cock of Crystal head with C.P. head 1/2" dia	3	Nos.	2784.60	Each.	8,354
10	Supplying & fixing wash basin mixture of superior quality with C.P. Crystal head 1/2" dia	2	Nos.	4890.60	Each.	9,781
11	Supplying & fixing Sink mixture cock of superior quality with C.P. Head etc,complete	1	Nos.	2550.60	Each.	2,551
12	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	4	Nos.	637.65	Each.	2,551
13	Supplying & fixing bath room accessories set (7 pieces) i/c towel rod, Brush holder, soap tray, shelf of approved design including cost of screw, nuts etc. complete (Master Brand). (S.No.23) (P#19).	1	Nos.	14320.80	Each.	14,321
14	Providing chambers 15"x19" (inside dimension) x24" deep for house meters with 6" thick C.C. 1:2:4 blocks set in 1:6 cement mortar 6" thick C.C 1:4:8 in foundation, "thick cement plaster 1:3 to all inside wall surfaces and to top 1" thick C.C. 1:2:4 ft. (S.No.2) (P#20).	2	Nos.	9051.80	Each.	18,104



BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
15	Manufacturing & Supplying of R.C.C manhole cover cast in 1:2:4 cement concrete ratio 3" inch deep at center reinforced with 1/2" dia tor steel bars with 4" c/c welded to a 3/16' thick 2 inch wide M.S Plate and two hooks of 3/8" inch dia tor bars including compacting, curing and transportation within 10 miles.21" inch dia (S.No.1) (P#29).	2	Nos. 3238.79	Each	6,478
16	Constructing mainhole or inspection chamber for the required diameter of ciecular sewer and 3'-6" (1067 mm) depth with walls of B.B in cement sand mortar 1:3 cement plastered 1:3 1/2" thivk, inside of walls and 1" (25 mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457) mm) of 1.75 cwt. (88.9 kg) embaded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S Steps 6" (150 mm) wide projecting 4" (102 mm) frome the face wall at 12" (305 mm) C/C Duly painted etc. Complete as per standard specification and drawing. (a) 4"to 12" dia 2'x2'x3'-6"(S.No.1) (P#47).	2	Nos. 16771.18	Each.	33,542
17	S/F fiber glass tank of approved quality and design and wall thickness as specified including cost of nluts bolts and fixing in platform of cement concrete 1:3:6 and making connection for inlet outlet and over flow pipe etc complete (250-Gallons tank with wall thickness 3.5mm) (SoR 2024 I-1 (A) P21)	1	Nos. 37698.31	Each.	37,698
Total Rs.					258,032
Above / Below					%
Total W/S & S/F Rs.					

**Electrical Internal Work - Schedule Items**

1	Wiring for light or fan point with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I No.129 P -15)	38	Nos	5958.53	Each	226424
2	Wiring for Plug pont with (3/.029) PVC insulated wire in 20mm 3/4" channel patti on surface as required. (S.I # 130 P -15)	6	Nos	3442.83	Each	20657
3	Providing & fixing Brass Battern holder (S.I No.192 P -19)	12	Nos	1152.61	Each	13831
4	Wiring for call bell point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required(S.I.No.228 P-33)	1	Nos	6712.49	Each	6712


BOQ / Schedule-B


S.N	Name of Item.	Quantity	Rate	Unit	Amount.	
5	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No.228 P-33)	15	Nos	373.39	Each	5601
6	Providing & Fixing A.C Electric Ceiling fan 56" (Good Quality)(S.I.No.195 P-19)	3	Nos	14869.21	Each	44608
7	Providing & Fixing one Way Sp 10/15 amp switch surface type.....(S.I.No.188 P-19)	20	Nos	468.19	Each	9364
8	Providing & Fixing Two Pin 10815 amp plug & socket.....(S.I.No.189 P-19)	2	Nos	617.69	Each	1235
9	Providing & Fixing Three Pin 10815 amp plug & socket flush type.....(S.I.No.188 P-19)	2	Nos	677.36	Each	1355
10	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.029 copper conductor in ¾" dia PVC conduit recessed in the wall or column as required (SI No. 10 P-no:3)	175	Rft	400.92	P.Rft	70161
11	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/.044 (6mm ²) copper conductor in ¾" dia PVC conduit recessed in the wall or column as required S.I.No: 12 P-4	50	Rft	660.91	P.Rft	33046
12	P/F Circuit breaker 6,10,15,20,30,40,50, &63 amp SP(TB-5S) on a prepared board as required (Si-178, P-18)	4	Nos	2504.12	Each	10,016
13	Providing & fixing circuit breaker 15,20, 30,40,50 60,75 & 100 amp TP (XE-100NS) on prepared board as required.S.I.No: 183 P-18)	1	Nos	28736.16	Each	28,736
14	Prividing & Laying (Main or Sub-Main) PVC insulated with size single core copper conductor 250/440 volts size (2-7/064 16 mm	130	Rft	468.00	P.Rft	60840
15	Providing & fixing ammeters size 96/96mm Direct 15A, 30A,50A, 60A & 100A as required & as per instruction of EI (SI-No:239 P-No:22)	1	Nos	4186.50	Each	4,187
16	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI(SI-No:240 P-No:22)	1	Nos	4186.50	Each	4,187

Total 540,960

Above / Below %

Total W/S & S/F Rs.




BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount
<u>Electrical Internal Work - Non Schedule Items</u>					
1	Providing & fixing A.C. or D.C. Electric bell 200/250 volts 70 MM (2- 3/4") Gong(Imported)	1	Nos	Each	
2	Providing & fixing 10 Amps polycarbonate flame retardant bell push with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/MBPR Clipsal Make)	1	Nos	Each	
3	Providing and fixing mild steel bar fan clamp 15.8mm (5/8") dia suitable for R.C.C. roof.	4	Nos	Each	
4	Providing & fixing Distribution Panel Board of 3/8" thick sheeting double shutter with volt and ampere meter to accommodate circuit breakers i/c painting with enamelled paint.	1	Sft	P.Sft	
5	P/F 1-40 Watts tube light complete with 40 Watts 4'-0" long rod, chock, starter and putty with Phillips components including necessary electric connection and fixing on wall or ceiling etc. complete.(Philips)	8	Nos	Each	
6	P/F Energy Saver (18 to 24 watts) superior quality including fixing with PVC holder etc. complete.(Imported)	10	Nos	Each	
7	P/F Fancy Capsule Light with fancy plastic body,holder ,saver etc complete (of approved make and design)	12	Nos	Each	
8	Providing & fixing 10Amps polycarbonate flame retardant One way switch with fancy gang plate fixed on die fabricated powder coated metal board recessed in wall or column including connection as required (E31/2/3A Clipsal Make)				
	i) ONE SWITCH PLATE	2	Nos	Each	
	ii) TWO SWITCH PLATE	2	Nos	Each	
	iii)FOUR SWITCH PLATE	2	Nos	Each	
	iv)SIX SWITCH PLATE	2	Nos	Each	
9	P/F P/F on a prepared board iron-clad single pole switch fuse, with rewirable fuse link carrier 500 volts grade 60 Amps. complete with wiring connection on a prepared board. (Imported 1st quality)	1		Each	

BOQ / Schedule-B

S.N	Name of Item.	Quantity	Rate	Unit	Amount.
Solar System					
10	P/F Solar System 1.16 KV complete with two No. Solar Panel 580-W, Power point tracer, DC flexible (Copper), MS Angle Iron Structure VFD and breacker box, AC DC breaker box , tubler Battris 440-W (01-No) complete in all respect.	1		Job	
Total Non Schedule					_____
Total Scheduel + Non Schedule					_____



General Abstract

Part "A" Civil Work	_____
Part "B" W/S & S/F	_____
Part "C" Electrical Work	_____
Total	_____
Add 5% SRB	_____
G.Total	_____

TERMS & CONDITIONS.

- 1 No cartage on any item of work shall be paid.
- 2 No premium non schedule of item will be paid.
- 3 100% well graded bajri used in the RCC 1:2:4.
- 4 Arbitraction clause stand from the agreement.

(CONTRACTOR)

OFFICE OF THE SR: SUPERINTENDENT OF POLICE, HYDERABAD.
REVISED ANNUAL PROCUREMENT PLAN
(WORKS GOOD & SERVICES)
FINANCIAL YEAR 2025-2026



S.#	Description of Procurement	District	Qty (Nos)	Estimated Cost (PKR in million)	Fund Allocated	Source of Funds ADP/Non ADP	Proposed Procurement Method	Timing of Procurements				Remarks	
								1 st Qtr:	2 nd Qtr:	3 rd Qtr:	4 th Qtr:		
1	R/renovation work as Model PS City Hyd (Part-A)	Hyd	1	10.00	10.00	Non ADP (funds provided by IGP Sindh Karachi through DIGP Hyd Range.	Domestic/local through newspaper department website & EPADS website (Single Stage one envelope)	✓					
2	R/renovation work of Remaining work of Water Supply, Sanitary Fitting / EI works & External Development of Model PS City Hyd (Part-B)	Hyd	1	10.00	10.00			✓					
3	R/renovation work as Model PS Sakhi Pir Hyd (Part-A)	Hyd	1	10.00	10.00			✓					
4	R/renovation work of Roof Treatment, External Development, Water Supply & Electric work of Model PS Sakhi Pir Hyd (Part-B)	Hyd	1	10.00	10.00			✓					

Total

40.00 (Million)

5	Repair/renovation work of Wahid Bux Auditorium Hall @ PS Bhitai Nagar Hyderabad	Hyd	1	6.00	6.00	Non ADP (funds provided by IGP Sindh Karachi through DIGP Hyd Range.	Domestic/local through newspaper department website & EPADS website (Single Stage one envelope)				✓	
---	---	-----	---	------	------	--	---	--	--	--	---	--

Total

6.00 (Million)

1	Halting Point @ Indus River Bridge East Side B.Nagar	Hyd	1	8.127	8.127	Non ADP (funds provided by IGP Sindh Karachi through DIGP Hyd Range.	Domestic/local through newspaper department website & EPADS website (Single Stage one envelope)					✓		
2	Halting Point @ Akro Near Petaro Toll Plaza	Jamshoro	1	8.190	8.190									✓
3	Halting Point @ Manjhand	Jamshoro	1	8.362	8.362									✓
4	Halting Point @ Amri Toll Plaza	Jamshoro	1	8.507	8.507									✓
5	Halting Point @ Lal Bagh Sehwan	Jamshoro	1	8.454	8.454									✓
6	Halting Point @ Looni kot	Jamshoro	1	8.103	8.103									✓
7	Halting Point @ Thoree Phatak	Jamshoro	1	8.408	8.408									✓
8	Halting Point @ Makhdoom Bilawal Johi Morr	Dadu	1	8.704	8.704									✓
9	Halting Point @ Khudabad	Dadu	1	4.973	4.973									✓
10	Halting Point @ Matari Toll Plaza	Matari	1	8.265	8.265									✓
11	Halting Point @ Bhit Shah	Matari	1	8.341	8.341									✓
12	Halting Point @ Saeedabad Toll Plaza West Side	Matari	1	8.479	8.479									✓
13	Halting Point @ Saeedabad Toll Plaza East Side	Matari	1	8.479	8.479									✓
14	Halting Point @ Keenjhar	Thatta	1	8.216	8.216									✓
15	Halting Point @ Oongher	Thatta	1	8.205	8.205									✓
16	Halting Point @ Daur	S.B.A	1	8.921	8.921									✓
17	Halting Point @ Sakrand Khabar Stop	S.B.A	1	8.696	8.696									✓
18	Halting Point @ Khadhar (Beat No.75 & 76)	S.B.A	1	4.995	4.995									✓
19	Halting Point @ Toll Plaza Moro	N.Feroz	1	8.976	8.976									✓
20	Halting Point @ Toll Plaza Kandiaro	N.Feroz	1	9.282	9.282									✓
21	Halting Point @ Toll Plaza Mirpurkhas	M.P.Khas	1	8.500	8.500									✓

Total

171.183 Million

Grand Total

217.183 (Million)

(Shahzeb/Chachar) PSP, PPM,
SSP Hyderabad &
& Secretary Procurement Committee



**OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD
Tel: No.022-9200640**

NOTICE INVITING TENDER

Sealed tenders are hereby invited from the interested contractors / companies /Firms for the following works under SPPRA Rules 2010 amended 2021.

S. #	Name of Halting Points.	District	Estd. Cost in (M)	Earnest Money	Tender Fee	Time for completion
1.	Halting Point @ Indus River Bridge East Side B.Nagar	Hyd	8.127	5%	5000	30 Days
2.	Halting Point @ Akro Near Petaro Toll Plaza	Jamshoro	8.190	5%	5000	30 Days
3.	Halting Point @ Manjhand	Jamshoro	8.362	5%	5000	30 Days
4.	Halting Point @ Amri Toll Plaza	Jamshoro	8.507	5%	5000	30 Days
5.	Halting Point @ Lal Bagh Sehwan	Jamshoro	8.454	5%	5000	30 Days
6.	Halting Point @ Looni kot	Jamshoro	8.103	5%	5000	30 Days
7.	Halting Point @ Thoree Phatak	Jamshoro	8.408	5%	5000	30 Days
8.	Halting Point @ Makhdoom Bilawal Johi Morr	Dadu	8.704	5%	5000	30 Days
9.	Halting Point @ Khudabad	Dadu	4.973	5%	5000	30 Days
10.	Halting Point @ Matiari Toll Plaza	Matiari	8.265	5%	5000	30 Days
11.	Halting Point @ Bhit Shah	Matiari	8.341	5%	5000	30 Days
12.	Halting Point @ Saeedabad Toll Plaza West Side	Matiari	8.479	5%	5000	30 Days
13.	Halting Point @ Saeedabad Toll Plaza East Side	Matiari	8.479	5%	5000	30 Days
14.	Halting Point @ Keenjhar	Thatta	8.216	5%	5000	30 Days
15.	Halting Point @ Oongher	Thatta	8.205	5%	5000	30 Days
16.	Halting Point @ Daur	S.B.A	8.921	5%	5000	30 Days
17.	Halting Point @ Sakrand Khabar Stop	S.B.A	8.696	5%	5000	30 Days
18.	Halting Point @ Khadhar (Beat No.75 & 76)	S.B.A	4.995	5%	5000	30 Days
19.	Halting Point @ Toll Plaza Moro	N.Feroz	8.976	5%	5000	30 Days
20.	Halting Point @ Toll Plaza Kandiaro	N.Feroz	9.282	5%	5000	30 Days
21.	Halting Point @ Toll Plaza Mirpurkhas	M.P.Khas	8.500	5%	5000	30 Days

The blank tender forms will be issued from the date of publication during office timings. The tenders duly filled shall receive back till **02.04.2026 at 10:00 hrs** & opened on same day/date at **11:00 hrs**, in the presence of all interested bidders who wish to attend & procurement committee. The bid documents can be seen on EPAD system and interested bidders required to submit their bids through EPAD website portalsindh.eprocure.gov.pk.


TERMS & CONDITIONS

- Blank tenders will be issued to the agencies / Firms on the payment of tender fee (non refundable).
- Conditional / blank, Incomplete and not accompanied with call deposit will not be considered.
- If the competent authority remains out of Head Quarter on the date of opening of the tenders, if any holiday announced by Government, then tenders will be received & opened on the next working day on same schedule & place.
- Agencies / Firms should be registered with Sindh Revenue Board and Income Tax authorities.
- The agency / contractor should have completed at least 03 Nos works of similar nature in last (05) five years.
- Bank statement / Audit report / other documents of the last (05) years showing annual financial turnover amount equal to estimate cost of the work applied to.
- The intending participants must be registered with PEC for the year 2025-2026, limit relevant category.
- The competent authority reserved right to reject any or all tenders according SPPRA Rules 2010 amended 2021.
- The intending contractors should submit the Affidavit to affect the whether he is not involve in any litigation and not abandoned the work in any Government Department and not black listed.
- The Earnest money of Estimate Cost shall make in shape of call deposit/pay order in favour of SSP Hyd, which shall be submitted in original before or at the time of opening of bids. It may be noted that in case of failure the bid shall be rejected.
- Separate proposal be submitted for each category above.

NOTE: This NIT can be seen on EPADS Website at <https://portalsindh.eprocure.gov.pk/#/> & Sindh Police Website www.Sindhpolice.gov.pk.

INFORMATION & PROCEDURE

Complete set of bidding documents containing the scope of work and relevant detail along with specification can be obtained by the Interested Contractors/Contracting Firms To Mr. Muhammad Tahir, Accountant SSP Office Hyd Cell No. 0333-3027793 Office No.022-9200640 during working hours. Method of Procurement will be single stage one envelop Procedure


(Shahzeb Chachar) PSP, PPM,
Sr: Superintendent of Police,
Hyderabad &
Secretary Procurement Committee



OFFICE OF THE
SR. SUPERINTENDENT OF POLICE,
HYDERABAD
& SECRETARY PROCUREMENT COMMITTEE

NO.A/ 5834-40 /2026
Hyderabad, Dated. 12-3 /2026.

To : The Director Advertisement,
Block -95/96,
Information, Sindh Secretariat, Karachi.

SUBJECT:- **NIT FOR PUBLICATION.**

Enclosed please find herewith 7 copies of Notice Inviting Tender for Repair / renovation work of (21) Halting Points of Sindh Police Highway Patrol Hyderabad Unit for publication / advertisement in (03) well reputed leading daily newspapers simultaneously as per Rule 17 (2) of SPPRA-2010 amended 2021. One copy of each newspaper containing the advertisement may please be sent to this office for office record.

1. Daily Urdu "JANG"
2. Daily English "DAWN"
3. Daily Sindh "KAWISH"

(Shahzeb Chachar) PSP, PPM,
Sr. Superintendent of Police,
Hyderabad.
& Member/Secretary
Procurement Committee,

Copy forwarded for information & n/action to:-

1. The Secretary Information, Technology, Department Govt. of Sindh Secretariat No. 06, Karachi.
2. The Inspector General of Police, Sindh Karachi (Atten: AIGP Estate Management) CPO Sindh Karachi.
3. The DIGP Finance CPO Sindh Karachi.
4. The DIGP Hyderabad Range
5. The DIGP SPHP Sindh Karachi,
6. The SSP SPHP Hyderabad Unit,
7. The Manager (Assessment) SPPRA, Barrack No. 8, Sindh Secretariat No. 4-A, Court Road, Karachi.
8. The Director IT Department, CPO Sindh Karachi, with request to publish tender on Sindh Police Website.
9. The representative of Home Department Sindh Karachi.
10. The Chief Engineer, Prov. Building Hyderabad.
11. The Superintendent Engineer, Prov. Bldg. Hyderabad.
12. The Superintendent Engineer, Police Works Sindh, Karachi.
13. The AEN Provincial Buildings Works, Hyderabad
14. The member concerned Procurement Committee. _____
15. The Members of Redressal Grievances & Settlement of Dispute Committee



GOVERNMENT OF SINDH
POLICE DEPARTMENT

No. G-1/ 80 /2026/Karachi

Dated 19 .02.2026

ORDER

SUBJECT:- **REVISION OF COMMITTEES FOR REPAIR /RENOVATION WORK OF HALTING POINTS OF VARIOUS UNITS OF SINDH POLICE HIGHWAY PATROL FOR THE FINANCIAL YEAR 2025-26**

In continuation of this office order No.G-516/2025 dated:25-07-2025 and corrigendum No.G-1/681/2025 dated:06-10-2025, the following Procurement Committees only are hereby revised are as under. The rest of order is good:-

- A. Committees for Repair/Renovation Works of Halting Points of Sindh Police Highway Patrol Karachi**
- i) **Procurement Committee**
- | | |
|------------------------------------|--------------------|
| 1. DIGP/SPHP, | (Chairman) |
| 2. SSP/Syed Muhammad Ali Raza, PSP | (Member/Secretary) |
| 3. SSP/ SPHP,Karachi Unit | (Member) |
| 4. DSP/SPHP Karachi-I | (Member) |
| 5. DSP/SPHP Karachi-II | (Member) |
| 6. AEN Provincial Building Karachi | (Member) |
| 7. OS DC Office Malir | (Member) |
- B. Committees for Repair/Renovation work of Halting Points of Sindh Police Highway Patrol Hyderabad Unit**
- i) **Procurement Committee**
- | | |
|--------------------------------------|--------------------|
| 1. DIGP/Hyderabad Range | (Chairman) |
| 2. SSP/Hyderabad Range | (Member/Secretary) |
| 3. SSP/SPHP Hyderabad Unit | (Member) |
| 4. DSP/SPHP Jamshoro | (Member) |
| 5. DSP/SPHP Badin | (Member) |
| 6. AEN Provincial Building Hyderabad | (Member) |
| 7. O.S DC office Hyderabad | (Member) |
- C. Committees for Repair/Renovation work of Halting Points of Sindh Police Highway Patrol Sukkur Unit**
- i) **Procurement Committee**
- | | |
|-----------------------------------|--------------------|
| 1. DIGP/Sukkur Range | (Chairman) |
| 2. SSP/Sukkur Range | (Member/Secretary) |
| 3. SSP/SPHP Sukkur Unit | (Member) |
| 4. DSP/SPHP Sukkur | (Member) |
| 5. DSP/SPHP Larkana | (Member) |
| 6. AEN Provincial Building Sukkur | (Member) |
| 7. O.S DC office Sukkur | (Member) |

Sd/-
(Javed A. Odho)PPM.,PSP
INSPECTOR GENERAL OF POLICE,
SINDH, KARACHI.

Copy to following for information:-

1. DIGP/Sindh Police Highway Patrol.
2. DIGP/Hyderabad Range.
3. DIGP/Sukkur Range.
4. Syed Muhammad Ali Raza.PSP, SSP.
5. SSP/Hyderabad.
6. SSP/Sukkur Range.
7. SSP/SPIIP Karachi Unit.
8. SSP/SPIIP Hyderabad Unit.
9. SSP/SPIIP Sukkur Unit.
10. DSP/SPHP Karachi-I Unit.
11. DSP/SPHP Karachi-II Unit.
12. DSP/SPHP Jamshoro Unit.
13. DSP/SPHP Badin Unit.
14. DSP/SPHP Sukkur Unit.
15. DSP/SPHP Larkana Unit.
16. AEN Provincial Building Karachi.
17. AEN Provincial Building Hyderabad.
18. AEN Provincial Building Sukkur.
19. OS DC Office Malir.
20. OS DC Office Hyderabad.
21. OS DC Office Sukkur
22. PS to IGP Sindh.
23. PS to Addl.IGP/Finance, Logistics & Welfare, Sindh.
24. PS to DIGP/Finance, Sindh.


(Khawar Akbar Shaikh),PSP
AIGP/Logistics,
For Inspector General of Police,
Sindh Karachi



GOVERNMENT OF SINDH
POLICE DEPARTMENT

No. G-I/ 681 /2025/Karachi

Dated: 06 -10-2025.

CORRIGENDUM

Subject:- **CONSTITUTION OF COMMITTEES FOR CONSTRUCTION, REPAIR/RENOVATION OF NEWLY HALTING POINTS OF VARIOUS UNITS OF SINDH POLICE HIGHWAY PATROL FOR THE FINANCIAL YEAR 2025-26.**

Please refer to this office order No.G-I/516/2025 dated: 25-07-2025, regarding constitution of committees for Repair/Renovation of Newly Halting Points of Sindh Police Highway Patrol, for the year 2025-26.

2/- The following amendments in above order are made:-

1.	DIGP/Sindh Police Highway Patrol Hyderabad Sindh is hereby nominated as Chairman of Procurement Committee for the Repair & Renovation Works of newly Halting Police Work of Police Building for Sindh Police Highway Patrol Unit Karachi in place of SSP/SPHP, Karachi.
2.	DIGP/Sindh Police Highway Patrol Hyderabad Sindh is hereby nominated as Chairman of Procurement Committee for the Repair & Renovation Works of Halting Point Building Sindh Police Highway Patrol Sukkur Range in place of SSP/SPHP, Sukkur.
3.	DIGP/Sindh Police Highway Patrol Hyderabad Sindh is hereby nominated as Chairman of Procurement Committee for the Newly construction Halting Points work of Police Building of Sindh Police Highway Patrol Hyderabad Region in place of SSP/SPHP, Hyderabad.
4.	Addl.IGP/Special Branch, Sindh, Karachi is hereby nominated as Chairman of Redressal of Grievance & Settlement of Disputes Committees (i) Repair & Renovation Works of newly Halting Police Work of Police Building for Sindh Police Highway Patrol Unit Karachi (ii) Repair & Renoyation Works of Halting Point Building Sindh Police Highway Patrol Sukkur Range (iii) Newly construction Halting Points work of Police Building of Sindh Police Highway Patrol Hyderabad Region in place of DIGP/SPHP Hyderabad.

Sd/-

(GHULAM NABI MEMON) PSP
INSPECTOR GENERAL OF POLICE,
SINDH, KARACHI.

Copy to the following for information & necessary action:-

- 1. DIGP/SPHP Hyderabad.
- 2. SSP/SPHP, Karachi
- 3. SSP/SPHP Sukkur.
- 4. Addl.IGP/Special Branch, Sindh, Karachi

No.	1294
O.S	6. PS to IGP Sindh.
PS	7. PS to Addl. IGP Finance, Welfare & Logistics Sindh.
Account	PA to DIGP/Finance, GPO Sindh Karachi.
Head Clk	
Establish	
Reader	
C.B	
M.T	
Welfare	
I.T	

(KHAWAR AKBAR SHAIKH) PSP
AIGP/Logistics,
For Inspector General of Police,
Sindh, Karachi.



GOVERNMENT OF SINDH
POLICE DEPARTMENT

No. G-I/ 516 /2025/Karachi

Dated 25 -07-2025.

ORDER

Subject:- **CONSTITUTION OF COMMITTEES FOR CONSTRUCTION, REPAIR/RENOVATION OF NEWLY HALTING POINTS OF VARIOUS UNITS OF SINDH POLICE HIGHWAY PATROL FOR THE FINANCIAL YEAR 2025-26.**

The following Committees are hereby constituted for Repair/Renovation of Newly Halting Points of Various Units of Sindh Police Highway Patrol for the financial year 2025-26:-

A. Committees for Repair & Renovation Works of Newly Halting Police Work of Police Buildings for Sindh police Highway Patrol Unit Karachi

i) Procurement Committee

- | | |
|------------------------------------|-------------|
| 1. SSP/ SPHP, Karachi Unit | (Chairman) |
| 2. DSP/SPHP Karachi-I | (Secretary) |
| 3. AEN Provincial Building Karachi | (Member) |
| 4. DSP/SPHP Karachi-II | (Member) |
| 5. OS DC Office Malir | (Member) |

Functions and responsibilities of Procurement committees shall responsible for:

- Preparing bidding documents.
- Carrying out technical as well as financial evaluation of the bids.
- Preparing evaluation report as provided in Rule-45.
- Making recommendations for the award of contract to the competent authority.
- Perform any other function ancillary and incidental to the above.

ii) Redressal of Grievance & Settlement of Disputes Committee

- | | |
|-------------------------------------|------------|
| 1) DIGP/ SPHP Hyderabad | (Chairman) |
| 2) SSP/SPHP Karachi | (Member) |
| 3) SSP/SPHP Sukkur | (Member) |
| 4) Superintendent Engineer, Karachi | (Member) |
| 5) Accounts Officer Karachi | (Member) |

794 26-07-25
 14/

The complaint redressal committee upon receiving a complaint from an aggrieved bidder may, if satisfied:

- Prohibit the procurement committee from acting or deciding a manner. Inconsistent with these rules and regulation.
- Annul in whole or in part. Any unauthorized act or decision of the procurement committee and
- Reverse any decision of the procurement committee or substitute its own decision for such a decision.
- Provided that the complaint redressal committee shall not make any decision to award the contract.

12
P.P.H
Co.

B. Committees for Construction, Repair & Renovation Halting Points of Sindh Police Highway Patrol Sukkur Range

i) Procurement Committee

- | | |
|-----------------------------------|-------------|
| 1. SSP/ SPHP Sukkur | (Chairman) |
| 2. DSP/SPHP Sukkur N-5 | (Secretary) |
| 3. AEN Provincial Building Sukkur | (Member) |
| 4. O.S DC office Sukkur | (Member) |
| 5. DSP/SPHP Larkana N-55 | (Member) |

Functions and responsibilities of Procurement committees shall responsible for:

- Preparing bidding documents.
- Carrying out technical as well as financial evaluation of the bids.
- Preparing evaluation report as provided in Rule-45.
- Making recommendations for the award of contract to the competent authority.
- Perform any other function ancillary and incidental to the above.

ii) Redressal of Grievance & Settlement of Disputes Committee

- | | |
|-------------------------------------|------------|
| 1) DIGP/SPHP Hyderabad | (Chairman) |
| 2) SSP/ SPHP Karachi | (Member) |
| 3) SSP/SPHP Sukkur | (Member) |
| 4) Superintendent Engineer, Karachi | (Member) |
| 5) Accounts Officer, Karachi | (Member) |

The complaint redressal committee upon receiving a complaint from an aggrieved bidder may, if satisfied:

- Prohibit the procurement committee from acting or deciding a manner, inconsistent with these rules and regulation.
- Annul in whole or in part. Any unauthorized act or decision of the procurement committee and
- Reverse any decision of the procurement committee or substitute its own decision for such a decision. Provided that the complaint redressal committee shall not make any decision to award the contract.

C. Committees for Newly Construction Halting Points Work of Police Buildings of Sindh Police Highway Patrol Hyderabad Region

i) Procurement Committee

- | | |
|--|-------------|
| 1. SSP/ SPHP Hyderabad | (Chairman) |
| 2. DSP/SPHP Jamshoro@Hyderabad | (Secretary) |
| 3. AEN (Provincial Building Hyderabad) | (Member) |
| 4. O.S D,C Office Hyderabad | (Member) |
| 5. DSP SPHP Badin@Hyderabad | (Member) |

Functions and responsibilities of Procurement committees shall responsible for:

- Preparing bidding documents.
- Carrying out technical as well as financial evaluation of the bids.
- Preparing evaluation report as provided in Rule-45.
- Making recommendations for the award of contract to the competent authority.
- Perform any other function ancillary and incidental to the above.

ii) Redressal of Grievance & Settlement of Disputes Committee

- | | |
|---|------------|
| 1) DIGP/ SPHP Hyderabad | (Chairman) |
| 2) SSP/ SPHP Hyderabad | (Member) |
| 3) SSP/SPHP Karachi | (Member) |
| 4) Superintendent Engineer, Hyderabad | (Member) |
| 5) District Accounts Officer, Hyderabad | (Member) |

complaint redressal committee upon receiving a complaint from an aggrieved bidder may, if satisfied:

- a) Prohibit the procurement committee from acting or deciding in a manner, inconsistent with these rules and regulation.
- b) Annul in whole or in part. Any unauthorized act or decision of the procurement committee and
- c) Reverse any decision of the procurement committee or substitute its own decision for such a decision, Provided that the complaint redressal committee shall not make any decision to award the contract.

SD/-
(GHULAM NABI MEMON) PSP
INSPECTOR GENERAL OF POLICE,
SINDH, KARACHI.

Copy to the:-

1. DIGP/SPHP Hyderabad
2. SSP/ SPHP, Karachi Unit
3. SSP/ SPHP Hyderabad
4. SSP/SPHP Karachi
5. SSP/ SPHP Sukkur
6. DSP/SPHP Karachi-II
7. DSP/SPHP Karachi-I
8. DSP/SPHP Sukkur N-5
9. DSP/SPHP Jamshoro@Hyderabad
10. DSP/SPHP Larkana N-55
11. DSP SPHP Badin@Hyderabad
12. OS DC Office Malir
13. O.S D C office Sukkur
14. O.S D,C Office Hyderabad
15. Superintendent Engineer, Karachi
16. Superintendent Engineer, Hyderabad
17. Accounts Officer Karachi
18. AEN Provincial Building Karachi
19. AEN Provincial Building Sukkur
20. AEN (Provincial Building Hyderabad)
21. District Accounts Officer, Hyderabad
22. PS to IGP Sindh.
23. PS to Addl: IGP Finance, Welfare & Logistics Sindh.
24. PA to DIGP/Finance, CPO Sindh Karachi.


(KHAWAR AKBAR SHAIKH) PSP
AIGP/Logistics,
For Inspector General of Police,
Sindh, Karachi

