

EO/Bldg/ /2026 نمبر

ضلع سکھر کی پولیس عمارتوں کی مرمت / ترمیم و آرائش

ٹینڈرز کے اجراء / وصولی اور کھولنے کا پروگرام

ٹینڈر کی شرائط و ضوابط

جیٹر مین پروکیورمنٹ کمپنی

A JOB PORTAL BY
INFORMATION DEPARTMENT

1. REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE.

2. REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK
AT OFFICE SUKKUR.

SCHEDULE -B

GENERAL ABSTRACT

PART -I REPAIR / RENOVATION
CONFERENCE HALL AT SSP OFFICE

1 Part-A
Civil Work

(i) Schedule Items RS: /-

2 Part-B
Water Supply & Sanitary Fittings

(i) Schedule Items RS: /-

3 Part- C
Electrical Work

(i) Schedule Items RS: /-

(ii) Non Schedule Items RS: /-

3 Part-D
Furniture RS: /-

PART -II REPAIR / RENOVATION OF
CORRIDOR INSIDE MAIN ENTRENCE
OF OFFICE BLOCK AT OFFICE
SUKKUR.

1 Part-A
Civil Work


(i) Schedule Items RS: /-

G.TOTAL PART-I & II RS: /-

ADD: 5% SRB RS: /-

G.TOTAL RS: /-

Contractor


SENIOR SUPERINTENDENT OF POLICE
SUKKUR

PART -I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE

SCHEDULE-B

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
Part "A" Civil Work					
1	Dismantling Second Class Tiles Roofing	<u>720 CFT</u>	15.84	P-Cft	11405
	Removing door with chowket.	2 Nos	574.26	Each	1149
	Removing Window and sky light with	4 Nos	465.31	Each	1861
4	Removing cement or lime plaster.	<u>264 SFT</u>	5.39	%Sft	1423
5	Dismantling C.C Plain 1:2:4	<u>176 SFT</u>	133.08	%Sft	23422
12	Applying floating coat of cement 1/32" thick. (S.I.No:14 P-52).	<u>253 SFT</u>	22.63	%Sft	5725
13	Cement plaster (1:6) upto 20' height 1/2" thick. (S.I.No:13 (b) P-51).	<u>253 SFT</u>	37.01	%SFT	9364
14	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-51).	<u>253 SFT</u>	37.78	%SFT	9558
15	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering ratio 1:2:4. (S.I.No.05 P-15).	<u>292 CFT</u>	443.54	%Cft	129514
16	Laying floors of approved colour Tile 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing.	702 Sft	389.36	P.SFT	273331
18	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing.	<u>222 SFT</u>	389.36	p.Sft	86,438
19	Supplying & fixing in position Aluminum channels framing for hinged doors or made with 5 mm thick tinted glass glazing (Belgi.	95	1655.83	P.Sft	157304

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-----	-------------	-----	------	------	--------

- 20 Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of made with 5 mm thick tinted glass glazing (Belgium) & Aluminum fly screen I/c handles stoppers & locking arrangement etc. complete S.I.NO. 84 p- 71

80 2386.73 P.Sft 190938.4

- 21 Supplying & fixing in position iron/steel grill of 3/4" x 1/4" size flat iron of approved design including painting 3 coats etc. complete (weight not to be less than 3.7 Lbs./Sq . Foot of finished grill). (S.I No.26 P-76)

72 1124.10 P.Sft 80935.2

- 23 S/F wall panels fiber sheet of good quality i/c transporting charges making with aluminum patti of best quality complete in all respect as desired. (S.I No.106 P-86)

1154.5 315.13 P. Sft 363818

- 25 Preparing the surface and painting with weather coat I/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.I.NO.38A. P-40.)

1568 SFT 88.00 P.Sft 137984

- 29 RCC spouts i/c fixing in position with top & bottom khurras. (S.I.No.68 P-107).

14 Nos. 2,446 EACH 34248

Total Rs. 1518416


Add: Amount To Cartage 143546

Total Rs. 1661963

Rs. _____ Above/Below / At Par

TOTAL RS: _____

Contractor


SENIOR SUPERINTENDENT OF POLICE
SUKKUR

**PART -II REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE
BLOCK AT OFFICE SUKKUR**

SCHEDULE-B

S.#	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
<u>Civil Work</u>					
1	Applying floating coat of cement 1/32" thick. (S.I.No:14 P-52).	44 SFT	22.63	%Sft	996
2	Cement plaster (1:6) upto 20' height 1/4" thick. (S.I.No:13 (b) P-51).	44 SFT	37.01	%SFT	1628
3	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-51).	44 SFT	37.78	%SFT	1662
4	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering ratio 1:2:4. (S.I.No.05 P-15).	284 CFT	443.54	%Cft	125965
5	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with matching color and finishing.	885 SFT	389.36	p.Sft	344,584
6	Supplying and fixing false ceiling of plaster of paris in pannels including making frame work of deodar wood i/c painting With solignum paint. (S.I.NO.54 P-56)	500 SFT	215.18	P.SFT	107590
7	S/F wall panels fiber sheet of good quality i/c transporting charges making with aluminum patti of best quality complete in all respect as desired. (S.I No.106 P-86)	770	215.13	P. Sft	165650
8	Distemping Three Coats	1820 SFT	18.00	P.Sft	32760

Total Rs. 780836

Add: Amount To Cartage 52965

Total Rs. 833801

Rs. _____ Above/Below / At Par

TOTAL RS: _____

Contractor

SENIOR SUPERINTENDENT OF POLICE
SUUKUR

SCHEDULE-B
Electrical Works

S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
		Part "C" Int: Electrification				
1.	40	Wiring for light or fan point with 3/029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required	6,573.50	S.I.No:10 2 P-236	Each	262,940
2.	10	Wiring for plug point with 3/029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required	4,372.29	0	Each	43,723
3.	220	Providing & laying (Main or Sub Main) PVC insulated with size 2-7/029 copper conductor in ¾" Dia PVC conduit recessed in the wall or column as required.	400.92	S.I.No:10 P-229	P.Rft	88,202
6.	50	Providing & laying (Main or Sub Main) PVC insulated with size 2-7/044 copper conductor in ¾" Dia PVC conduit recessed in the wall or column	1,829.39	S.I.No:13 P-229	P.Rft	91,470
7.	4	Providing & fixing circuit breaker 6, 10, 15, 20,30,40,50&63 SP (TB-5S)on prepared board as required	2,504.12	S.I.No:1 78 P-243	Each	10,016
12.	1	Providing & fixing voltmeter size 96/96mm 500volt as required & as per instruction of EI	4,186.50	SD.I.No:2 40 P-248	Each	4,187
13.	1	Providing & fixing Bakelite ceiling rose with two terminals	373.39	S.I.No:19 1 P-244	Each	373
14.	55	Providing & fixing Brass Battern holder	1,152.61	S.I.No:19 3 P-244	Each	63,394
15.	12	Providing & fixing one way SP 10/15amp switch surface type	468.19	S.I.No:18 8 P-244	Each	5,618
16.	24	Providing & fixing Two pin 10/15amp plug & socket	617.69	S.No:189 P-244	Each	14,825
17.	4	Providing & fixing three pin 10/15amp plug & socket flush type	677.36	S.I.No:19 0 P-244	Each	2,709
18.	16	Providing & fixing A.C Electric Ceiling fan 56" (good quality)	14,869.21	S.I.No:19 5 P-244	Each	237,907
19.	2	Providing & fixing DP I/C change over switch 500volts 100amp on a prepared board	34,291.54	S.I.No:17 2 P-243	Each	68,583
		Total Schedule Items				893,947

Rs. _____ Above/Below / At Par

Total Rs.


Name of Scheme

PART-I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE

SCHEDULE-B
Electrical Works

		Part "D" Non Schedule Items				
1.	1	P/F Main panel board double shutter to accommodate heavy duty circuit breaker complete in all respects.		NSI	Each	
2.	36	P/Fixing LED Ceiling light 8" Square 18 Watt to 24 Watts (Superior quality as approved by Engineer incharge.		NSI	Each	
3.	6	P/Fixing Exhaust Fan mounted light Superior quality as approved by Engineer Incharge.		NSI	Each	
4.	12	P/Fixing fancy dimmer for Ceiling fan etc complete.		NSI	Each	
6.	1	S/Fixing Electric Motor 1/2 H.P. with pump Superior Quality as approved by Engineer Incharge.		NSI	Each	
		Total Non Schedule Items				

Contractor


SENIOR SUPERINTENDENT OF POLICE
SUKKUR

SCHEDULE-B
Water Supply & Sanitary Fittings

S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
		Part "B" -I Int: W/S & S/F				
1.	1	Providing and fixing squatting type white glazed earthen ware W.C pan with front flush inlet & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and requisite number of holes in walls plinth & floor for pipe connection & making good in cement concrete 1:2:4 Far.(23 inch)	9,990.00	S.I.No:1 A(iP-184	Each	9,990
2.	1	Providing and fixing European type white glazed earthen ware wash down W.C. pan complete with & including the cost of white / black plastic seat (Best quality) and lid with C.P. brass hinges best quality and buffers 3 gallons white glazed earthen ware low level flushing cistern with siphon fitting 1½ " dia white porcelain enameled flush bend dia and making requisite number of holes in walls plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Foreign quality) . (ICL or equivalent	44,244.72	S.I.No:4 P-186	Each	44,245
3.	1	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with & including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of ½" dia chrome plated pillar taps, 1-1/2" rubber plug & chrome plated brass chain 1-1/4" dia malleable iron or C.P. brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics)	9,495.14	S.I.No:8 P-187	Each	9,495
4.	1	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standard pattern)	3,276.00	S.I No. 9 P-187	Each	3,276

SCHEDULE-B
Water Supply & Sanitary Fittings

S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
5.	1	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with a C.I. screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4	1,647.07	S.I.No. 20 P-189	Each	1,647
6.	1	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	637.65	S.I.No. 23 P-189	Each	638
7.	2	S/fixing concealed Tee-stop cock of superior quality with C.P. head 1/2" dia	1,614.60	S.I.No:12 a P-198	Each	3,229
8.	2	Supplying & fixing long Bib -cock of superior quality with C.Phead 1/2" dia	2,316.60	S.I.No. 13 (a) P-198	Each	4,633
9.	1	Supplying & fixing jet shower with rod of superior quality with C.P. head 1/2" dia	3,486.60	S.I.No:15 (a) P-199	Each	3,487
11.	1	S/F Bath Room accessories set	14,320.00	S.I.No:4(B) P-197	Each	14,320
12.		Providing UPVC. pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling.		S.I.No:2 P-193		
12b	30	3/4" dia	199.83		P.Rft	5,995
12c	50	1" dia	272.35		P.Rft	13,618
		Providing, Laying UPVC Pressure Pipes of Class 'B' (equivalent make) fixing in trench by cutting, fitting and jointing with 'Z' joint with one rubber ring and testing with water to a head 61 meter or 200 ft. 150 mm (6" dia)		S.I.No:1(d) P-110).		
15a	30	a) 6" dia pipe,	732.09		P.Rft	21,963
15c	20	c) 4" dia pipe.	384.82		P.Rft	7,696


SCHEDULE-B
Water Supply & Sanitary Fittings

S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
16.	1	Construction manhole or inspection chamber for the required dia meter of circular sewer and 3'-6"(1067mm) depth with allso fB.Bincements and mortar 1:3 cement plastered 1:3, 1/2"thick, inside of walls and 1"(25mm)thick over benching and channeli/ cfixing C.I manhole cover with frame of clear opening 1-1/2' x1-457x457mm)of1.75cwt. (88.9kg) embadedinplain C.C1:2:4 and fixing 1"(25mm) dia M.Ssteps 6"(150mm) wide projecting 4"(102mm) from the	55,584.18	S.I.No:1 P-134	Each	55,584
17.	100	Boringfortubewellinallwaterbearingsoi lsfromgroundlevelupto100ft.or30.5met erdepthi/csinkingandwithdrawing of casing pipe. A) 80 mm (3" dia)	1,025.72	S.I.No:1 a P-129	Each	102,572
		Total Schedule Items				302,388

Rs. _____ Above/Below / At Par

Contractor

TOTAL RS:


SENIOR SUPERINTENDENT OF POLICE
SUKKUR

PART -I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE

SCHEDULE-B


Sr. #	Particulars	No. of Unit Required	Unit Cost Approx:	Total
-------	-------------	-------------------------	----------------------	-------

FURNITURE & FIXTURE

1	Revolving Chairs Speical Quality	3		
2	Office Chairs	80		
3	Conference Table Standard Size	1		
5	Providing Sound System with Mic Amplifier wire Etc Complete	1		

Total Furniture & Fixture

Contractor


SENIOR SUPERINTENDENT OF POLICE
SUKKUR



OFFICE OF THE SENIOR SUPERINTENDENT OF POLICE DISTRICT SUKKUR

Phone No (071) 9310565

No.EO/Bldg/ /2026

Sukkur, Dated .09.2026

NOTICE FOR INVITATION OF SEALED TENDERS

The Sealed Tenders are invited from interested bidders / contractors / firms and companies as well as suppliers on standard bidding documents forms (SBDs) for the procurements of the following work under SPPRA Rules-2010 (Amended till date) during current financial year 2026-27.

REPAIR / RENOVATION OF POLICE BUILDINGS OF DISTRICT SUKKUR

S.#	Name of Work	Estimate Cost	Tender Fee	Bid Security 5% (CDR only)	Completion period
1.	Repair/ Renovation of Conference Hall & Corridor inside main entrance of office Block at SSP Office, District Sukkur.	5.00 (M)	5000	250,000	02-Month

PROGRAMME FOR ISSUE / RECEIPT AND OPENING OF TENDERS

Particulars of 1st attempt		Place of Opening
1	Date of issuance of tender documents (after publication till 13.10.2026 up to 01:00 PM & submission of tenders till 02:00 PM).	Mandatory: Online via EPADS Sindh website https://portalsindh.eprocure.gov.pk/#/ (all participating bidders are advised to register themselves Online for E-Bid submission.
2	Date of opening of Tenders at 03:00 PM. 13-10-2026	
Particulars of 2nd attempt		Optional: In the Office of the Senior Superintendent of Police Sukkur @ Upper Queens Road Sukkur Sindh.
1	Date of issuance of tender documents from 14.10.2026 (till 29-10-2026 up to 01:00 PM & submission of tenders till 02:00 PM).	
2	Date of opening of Tenders (at 03:00 PM). 29-10-2026	

TERMS & CONDITIONS OF THE TENDER

- The intending participants must be registered with Pakistan Engineering Council (P.E.C) for the year valid June-2027 limit relevant category.
- Bio-data of Engineers and Technical staff working with the firm.
- Documentary evidence of [five] works executed / works in progress and certificate of satisfactory completion of works by the employers.
- List of work in progress, indicating cost of each work and copy of letter of award of work.
- List of machinery and equipment available with documentary evidence of its ownership/ rent with certificate of Bank showing credit worthiness along with Bank statement.
- Registration with Income Tax Department (NTN Certificate) and copy of CNIC.
- The approved bids will be subject to stamp duty levied by the Government.
- All the contractors/ firms should be registered with Sindh Revenue Board in terms of Rule 46-1(ii) of SPPRA Rule (Amended 2019).
- Annual Income Tax returns of last five years.
- Annual audited reports of last five years from (ICAP) registered audit firms. Audit report issued other than (ICAP) registered audit firms will not be accepted.
- Certificate of Bank showing credit worthiness of at-least 15% (average balance per year for the last 05-years) of the estimated cost of work along with Bank Statement. Bank statement must be provided separately for each year starting from 1st July to 30th June for last five years and recent bank certificate must be attached showing available balance.
- Undertaking on stamp paper that the firm/contractor is not currently involved in any kind of litigation, department rift, abandoned or un-necessary delay in completion of any work in the Government as well as in private organizations.
- Conditional or incomplete tenders will not be entertained.
- The bids shall be evaluated on single stage one envelope method of SPPRA Rules 2010 (Amended till date).
- The approved bids will be subject to stamp duty levied by the Government.
- In case of Holiday and unforeseen circumstances on opening date the bids shall be submitted and opened on the next working day.
- The bidders should submit prescribed amount of earnest money as shown against each work in shape of Call Deposit prepared from the scheduled bank in favour of the undersigned.
- Affidavit to the effect that the firm / contractor have not been black listed currently by any executing agency.
- Affidavits to the effect that all document / particulars / information furnished are true and correct.
- In case of firm, list of partners / Partnership Deed, giving full particulars of directors/ proprietors or others connected along with power of attorney. In case of being sole proprietors, such undertaking on affidavit be furnished.
- The Sindh sales tax (SRB) will be deduct as per policy and procedure.
- In case the undersigned or any member of the committee happens to be out of the Headquarter the bids shall be submitted and opened as per the given schedule on the next working day.
- The undersigned and other competent authority reserve the right to reject any one or all the Bids as per provision of SPPRA Rules, 2010.

INF-KRY/4187/2026

(AHMED FAISAL CHAUDHRY) QPM, PSP
SENIOR SUPERINTENDENT OF POLICE DISTRICT SUKKUR
CHAIRMAN PROCUREMENT COMMITTEE

I WORK FOR SINDH
www.iwork4sindh.com



A JOB PORTAL BY
INFORMATION DEPARTMENT



OFFICE OF THE
CHIEF ENGINEER (BUILDINGS) GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT SUKKUR

NO.C.E(B)/PB/B-1 227

DATED 02/09/2026

SUBJECT: ESTIMATE FOR 1. REPAIR/ RENOVATION OF CONFERENCE HALL AT SSP OFFICE (PART "A" CIVIL WORK, PART "B" INT: W/S & S/F, PART "C" INT: ELECTRIFICATION PART "D" ELETRIC NON SCHEDULE ITEM, PART "E" OFFICE FURNITURE) 2. REPAIR/ RENOVATION OF CORRIDOR INSIDE MAIN ENTRANCE OF OFFICE BLOCK AT SSP OFFICE SUKKUR (PART "F" CIVIL WORK) :

In exercise of the powers delegated to the under signed vide west Pakistan delegation of powers and re-appropriation rules-1962, as corrected & amended by Government of Sindh Notification No.B&E-1/2(18)/75-94/Pt-IX dated:05-01-2009, technical sanction amounting to Rs: 4.871 (M) (Rupees: Four Million Eight Hundred Seventy One Thousands) only, is hereby accorded to the estimate for the work mentioned above, subject to condition that work may not be allowed to be executed over & above the actual release in any case & completion of codal formalities & regularities. Incase of any deviation the Executive Agency / authorities will be held responsible personally.

The expenditure is debatable under the head of account "SC-

RCC DESIGN:-

The details of RCC design for all members shall be rechecked by the Executive Engineer / officer in charge of the work as per site condition.

It may further be insured that requisite tests are carried out to confirm that the work is executed as per specification.

QUANTITIES:-

The Executive Engineer is required to see, that the quantities / Rates provided in the detailed estimate are correct and payment to the contractor are however made, on the actual quantities of work executed by them properly measured and checked by competent authorities / officer of the Department.

CARRIAGE OF MATERIAL:-

It has been certified in the estimate that shortest route has been provided, the officer concerned will be responsible for any variation in the lead.

NON SCHEDULE ITEM:-

Rate are verified & certified by the field staff Executive Engineer, Assistant Engineer & Sub Engineer for being a market Rate & the lowest Rate.

The Executive Engineer is fully Responsible for approving the field executing of each item of work including material quite compatible with the market / sanction Rate.

If there is any error in the rate of the items, the schedule rate of CSR 2024, will be implemented.

NOTE:-

Work may be carried out in accordance with approved M&R programme for the year 2026-27.

DA AS ABOVE

(SHER MUHAMMAD MAHESAR)
CHIEF ENGINEER
BUILDINGS SUKKUR

Copy FWCS to:-

The Section Officer (B&A) to Works & Services Department Govt: of Sindh Karachi with reference to his office letter No.B&A (W&S)3-10/2026-27 dated 03-09-2026 and Superintending Engineer Police Works KARACHI his office letter No.SE/PW/ Karachi/ 252 Dated 31-08-2026

C.E LETTER BY: WAHID BUX KHASKHELI

POLICE WORKS DEPARTMENT.



HOME DEPARTMENT

DETAILED ~~REvised~~ WORKING ESTIMATE ON CSR 2024

- NAME OF SCHEME: 1. REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE.
2. REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK AT OFFICE SUKKUR.

ESTIMATE COST RS. ~~4.999~~ ^{4.871 (M)} MILLION

Office of the Assistant Engineer
Police Works
Sukkur

1. REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE.
2. REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK AT OFFICE SUKKUR.

GENERAL ABSTRACT

<u>Disription</u>	<u>Total Amount</u>
<u>PART -I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE</u>	
Part "A" Civil Work	1556189/- 1661963
Part "B" -I Int: W/S & S/F	302388 ✓
Part "C" Int: Electrification	893947 ✓ 168224/- 171500
Part "D" Non-Schedule Item	
Part " E" Offie Furniture	1135000 ✓
Total:-	4,164,798 4055748/-
<u>PART -II REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK AT OFFICE SUKKUR.</u>	
	815275/- 833801
Total:-	4,998,598 4871023/-
Say:-	4.999 (M) 4.871 (M)


ASSISTANT ENGINEER
 POLICE WORKS
 SUKKUR


Superintending Engineer
 Police Works, Sindh
 Karachi,

Technically Sanction Rs: 4.871 (M)
 Rupees. Four million Eight hundred and seventy one thousand only


TECHNICAL OFFICER
 FOR CHIEF ENGINEER
 BUILDINGS SUKKUR


CHIEF ENGINEER
 BUILDINGS SUKKUR

PART -I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE

Abstract Cum Measurement Sheet

S.#	DESCRIPTION	NO.L.B.D	QTY	RATE	UNIT	AMOUNT
Part "A" Civil Work						
1	Dismantling Second Class Tiles Roofing					
	Conference Hall	1 x 36.00 x 20.00	720 Sft <u>720 CFT</u>	15.84	P-Cft	11405
	Removing door with chowket.		2 Nos	574.26	Each	1149
	Removing Window and sky light with		4 Nos	465.31	Each	1861
4	Removing cement or lime plaster.					
	Hall	1 x 2 (36.00 + 19.50) 3.00	333 SFT <u>333 SFT</u>			
	Deduction.					
	Door.	2 x 3.50 x 7.00	= 49 SFT			
	Window.	1 x 2.50 x 8.00	= 20 "			
			<u>69 SFT</u>			
	NET QUANTITY:-	333 (-)	69 = <u>264 SFT</u>	5.39	%Sft	1423
5	Dismantling C.C Plain 1:2:4					
	Hall	1 x 36.00 x 19.50 x 0.25	176 <u>176 SFT</u>	133.08	%Sft	23422
12	Applying floating coat of cement 1/32" thick. (S.I.No:14 P-52).					
	Hall	1 x 2 (36.00 x 19.50) 3.00	333 SFT <u>333 SFT</u>			
	Deduction.					
	Door.	1 2 x 3.50 x 8.50	= 60 SFT			
	Window.	1 1 x 2.50 x 8.00	= 20 "			
			<u>80 SFT</u>			
	NET QUANTITY:-	333 (-)	80 = <u>253 SFT</u>	22.63	%Sft	5725
13	Cement plaster (1:6) upto 20' height 1/2" thick. (S.I.No:13 (b) P-51).					
	Same Quantity as per Item No.16		253 SFT <u>253 SFT</u>	37.01	%SFT	9364
14	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-51).					
	Qty same item No.14		<u>253 SFT</u>	37.78	%SFT	9558
15	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering ratio 1:2:4, (S.I.No.05 P-15).					
	Flooring					
	Conference hall	1 x 30.00 x 19.50 x 0.25	146 SFT			
	Over Roof	1 x 30.00 x 19.50 x 0.25	146 SFT			

263907/5

S.#	DESCRIPTION	NO.L.B.D	QTY	RATE	UNIT	AMOUNT
-----	-------------	----------	-----	------	------	--------

292 CFT 443.54 %Cft 129514

- 16 Laying floors of approved colour Tile 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including grouting with

Flooring

Conference hall 1 x 36.00 x 19.50

702 702 Sft 389.36 P.SFT 273331

- 18 Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including
G. Bath 1 x 8.00 x 5.00

Dado

G. Bath 1 x 2 (8.00 + 5.00) 7.00

40 182 222 SFT 389.36 p.Sft 86,438

- 19 Supplying & fixing in position Aluminum channels framing for hinged doors or made with 5 mm thick tinted glass glazing (Belgi)

Door 2 x 4.00 x 7.50
Door 2 2 x 2.50 x 7.00

60 35 95 1655.83 P.Sft 157304

- 20 Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of made with 5 mm thick tinted glass glazing (Belgium) & Aluminum fly screen l/c handles stoppers & locking arrangement etc. complete S.I.NO. 84 p- 71

W 5 x 4.00 x 4.00

80 80 2386.73 P.Sft 190938.4

- 21 Supplying & fixing in position iron/steel grill of 3/4" x 1/4" size flat iron of approved design including painting 3 coats etc. complete (weight not to be less than 3.7 Lbs./Sq . Foot of finished grill). (S.I No.26 P-76)

W 4 x 4.00 x 4.50

72 72 1124.10 P.Sft 80935.2

- 23 S/F wall panels fiber sheet of good quality i/c transporting charges making with aluminum patti of best quality complete in all respect as desired. (S.I No.106 P-86)

Room 1 x 2 (36.00 x 19.50) 11.0

1221

Deduction

2 x 3.5 x 7.0
3 x 2.5 x 7.0

Net Qty 1221 - 67 = 1154

49 53 18 67 102

4154.5 315.13 P. Sft 363818

- 25 Preparing the surface and painting with weather coat l/c rubbing the surface with rubbing brick / sand Paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make. (S.I.NO.38A. P-40.)

Pillar 1 x 2.00 x 20.00 14.00
Pillar 1 x 2.00 x 36.00 14.00

560 1008


1334997

BF=1334997/-

S.#	DESCRIPTION	NO.L.B.D	QTY	RATE	UNIT	AMOUNT
			1568 SFT	88.00	P.Sft	137984

- 29 RCC spouts i/c fixing in position with top & bottom khurras.
(S.I.No.68 P-107).

14 Nos.	2,446	EACH	34248
	26		1507229/-
		Total Rs.	4518416
		Add: Amount To Cartage	499643546
		Total Rs.	1661963
			1556189/-


ASSISTANT ENGINEER
POLICE WORKS
SUKKUR

**PART -II REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK
AT OFFICE SUKKUR.**

Abstract Cum Measurement Sheet

S.#	DESCRIPTION	NO.L.B.D	QTY	RATE	UNIT	AMOUNT
Civil Work						
1	Applying floating coat of cement 1/32" thick. (S.I.No:14 P-52).					
	Hall	1 x 2 (55.00 x 7.00) 1.00	124 SFT			
			124 SFT			
	Deduction.					
	Door.	1 2 x 3.50 x 8.50	= 60 SFT			
	Window.	1 1 x 2.50 x 8.00	= 20 "			
			80 SFT			
	NET QUANTITY:-	124 (-)	80 =	44 SFT	22.63 %Sft	996
2	Cement plaster (1:6) upto 20' height 1/2" thick. (S.I.No:13 (b) P-51).					
	Same Quantity as per Item No.16		44 SFT			
			44 SFT	37.01	%SFT	1628
3	Cement plaster (1:4) upto 20' height 3/8" thick. (S.I.No:11 (a) P-51).					
	Qty same item No.14		44 SFT	37.78	%SFT	1662
4	Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering ratio 1:2:4. (S.I.No.05 P-15).					
Flooring						
	G.F Room1	1 x 30.00 x 25.00 x 0.25	188 SFT			
	Ver	1 x 55.00 x 7.00 x 0.25	96 SFT			
			284 CFT	443.54	%Cft	125965
5	Laying floors of approved coloured glazed tiles 1/4" thick floor of approved color & size jointing in white cement and laid over 1:2 cement sand mortar 3/4" thick including					
	Ver	1 x 55.00 x 7.00	385 "			
	Front Coridor	1 x 20.00 x 25.00	500			
			885 SFT	389.36	p.Sft	344,584
6	Supplying and fixing false ceiling of plaster of paris in pannels including making frame work of deodar wood i/c painting With soliginumpaint. (S.I.NO.54 P-56)					
	Rooms	1 x 20.00 x 25.00	500 SFT			
			500 SFT	215.18	P.SFT	107590
7	S/F wall panels fiber sheet of good quality i/c transporting charges making with aluminum patti of best quality complete in all respect as desired. (S.I No.106 P-86)					
	Room	1 x 2 (20.00 x 25.00) 10.0	900			

582425/-

S.#	DESCRIPTION	NO.L.B.D	QTY	RATE	UNIT	AMOUNT
-----	-------------	----------	-----	------	------	--------

Deduction

4 x 3.5 x 7.0
2 x 4.0 x 4.0
Net Qty 900 - 130 =

98 ✓
32 ✓
130 ✓

770 ✓

215.13 ✓

P. Sft ✓

165650 ✓

8 Distemping Three Caots

ver 1 x 2.00 x 55.00 10.00
Stair 1 x 2.00 x 36.00 10.00

1100 ✓

720 ✓

1820 SFT

18.00 ✓

P.Sft ✓

32760 ✓

Total Rs. 780836 ✓

Add: Amount To Cartage 34440 - 52965

Total Rs. 833801

815275 ✓


ASSISTANT ENGINEER
POLICE WORKS
SUKKUR

MATERIAL STATEMENT.

PART -I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE

Sr.#	Discription	Qty	Cement	Sand	Bajri	Stone	Bricks	Steel
1-	Applying Floting Coat	253	1	-	-	-	-	-
2-	Cement Plaster (1:6) 1/2"	253	253 \	108	-	-	-	-
3-	Cement Plaster (1:4) 3/8"	253	45 \	8 1/4"	223	-	-	-
4-	C.C Plain (1:2:4).	292	51	128	257	-	-	-
	QTY	5350	246	2580	0	0	0.000	
	RATE	303.68	11404.94	1871.24	2506.82	1871.24	5352.96	
	UNIT	P.Bag	%Cft	%Cft	%Cft	%Nos.	P.Ton	
	AMOUNT	106367	28205	8974	0	0	0	
		16098/5	28056/5	4869	TOTAL RS:			143546
								48960/5

PART -II REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK AT OFFICE SUKKUR.

Sr.#	Discription	Qty	Cement	Sand	Bajri	Stone	Bricks	Steel
1-	Applying Floting Coat	44	0	-	-	-	-	-
2-	Cement Plaster (1:6) 1/2"	44	44	7	-	-	-	-
3-	Cement Plaster (1:4) 3/8"	44	8	19	39	-	-	-
4-	C.C Plain (1:2:4).	284	50	125	250	-	-	-
	QTY	102	2546	250289	0	0	0.000	
	RATE	303.68	11404.94	1871.24	2506.82	1871.24	5352.96	
	UNIT	P.Bag	%Cft	%Cft	%Cft	%Nos.	P.Ton	
	AMOUNT	30964	16600	5401	0	0	0	
		15184/5	14598/5	4678/5	TOTAL RS:			52965
								534460/5


 ASSISTANT ENGINEER
 POLICE WORKS
 SUKKUR.

Abstract Sheet

S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
		Part "B" -I Int: W/S & S/F				
1.	1	Providing and fixing squatting type white glazed earthen ware W.C pan with front flush inlet & complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and requisite number of holes in walls plinth & floor for pipe connection & making good in cement concrete 1:2:4 (23 inch	9,990.00	S.I.No:1A(IP-184	Each	9,990
2.	1	Providing and fixing European type white glazed earthen ware wash down W.C. pan complete with & including the cost of white / black plastic seat (Best quality) and lid with C.P. brass hinges best quality and buffers 3 gallons white glazed earthen ware low level flushing cistern with siphon fitting 1½ " dia white porcelain enameled flush bend dia and making requisite number of holes in walls , plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Foreign quality) . (ICL or equivalent	44,244.72	S.I.No:4 P-186	Each	44,245
3.	1	Providing and fixing 24x18" lavatory basin in white glazed earthen ware complete with & including the cost of W.I. or C.I. cantilever bracket 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of ½" dia chrome plated pillar taps, 1-1/2" rubber plug & chrome plated brass chain 1-1/4" dia malleable iron or C.P. brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (Standard Pattern) (Karam Ceramics)	9,495.14	S.I.No:8 P-187	Each	9,495
4.	1	Add extra for providing & fixing of earth ware pedestal white or coloured Glazed (Standarded pattern)	3,276.00	S.I.No. 9 P-187	Each	3,276
5.	1	Providing and fixing 6"x2" or 6"x3" C.I. floor trap of the approved self cleaning design with a C.I. screwed down grating with or without a vent arm including cost of making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4	1,647.07	S.I.No. 20 P-189	Each	1,647
6.	1	Providing and fixing in position nylon connection complete with " dia brass stop cock with pair of brass nuts and lining jointed to nylon connection	637.65	S.I.No. 23 P-189	Each	638
7.	2	S/fixing concealed Tee-stop cock of superior quality with C.P. head 1/2" dia	1,614.60	S.I.No:12a P-198	Each	3,229
8.	2	Supplying & fixing long Bib -cock of superior quality with C.P.head 1/2" dia	2,316.60	S.I.No. 13 (a) P-198	Each	4,633
9.	1	Supplying & fixing jet shower with rod of superior quality with C.P. head 1/2" dia	3,486.60	S.I.No:15(a) P-199	Each	3,487
11.	1	S/F Bath Room accessories set	14,320.00	S.I.No:4(B) P-197	Each	14,320

= 94960/-

Abstract Sheet

RF-94960/-

S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
12.		Providing UPVC. pipes specials and clamps etc. including fixing cutting and fittings complete with and including the cost of breaking through walls and roof making good etc. with pigment to match the colour of the building and testing with water to a pressure bead of 200 feet and handling.		S.I.No:2 P-193		
12b	30	3/4" dia	199.83		P.Rft	5,995
12c	50	1" dia	272.35		P.Rft	13,618
		Providing, Laying UPVC Pressure Pipes of Class B (equivalent make) fixing in trench / cutting, fitting and jointing with 'Z' joint with one rubber ring / testing with water to a head 61 meter or 200 ft. 150 mm (6" dia)		S.I.No:1 (d) P-110).		
15a	30	a) 6" dia pipe.	732.09		P.Rft	21,963
15c	20	c) 4" dia pipe.	384.82		P.Rft	7,696
16.	1	Construction manhole or inspection chamber for the required dia meter of circular sewer and 3'-6" (1067mm) depth with allso f.B. Bincements and mortar 1:3 cement plastered 1:3, 1/2" thick, inside of walls and 1" (25mm) thick over benching and channel / fixing C.I manhole cover with frame of clear opening 1-1/2' x 1-457x457mm) of 1.75 cwt. (88.9kg) embaded in plain C.C 1:2:4 and fixing 1" (25mm) dia M.S steps 6" (150mm) wide projecting 4" (102mm) from the face of wall at 12" (305mm) C/C duly painted etc. Complete as per standard specification and drawing at 4" to 12" dia 2' x 2' x 3' 6"	55,584.18	S.I.No:1 P-134	Each	55,584
17.	100	Boring for tubewell in all water bearing soils from ground level upto 100 ft. or 30.5 meter depth / sinking and withdrawing of casing pipe. A) 80 mm (3" dia)	1,025.72	S.I.No:1 P-129	Each	102,572
		Total Schedule Items				302,388


 ASSISTANT ENGINEER
 POLICE WORKS
 SUKKUR

Abstract Sheet


S.No.	Quantities	Item of Work	Rate	CSR 2024	Unit	Amount
(1)	(2)	(3)	(4)	(5)	(6)	(7)
		Part "C" Int: Electrification				
1.	40	Wiring for light or fan point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required	6,573.50	S.I.No:102 P-236	Each	262,940
2.	10	Wiring for plug point with 3/.029 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required	4,372.29	0	Each	43,723
3.	220	Providing & laying (Main or Sub Main) PVC insulated with size 2-7/.029 copper conductor in 3/4" Dia PVC conduit recessed in the wall or column as required.	400.92	S.I.No:10 P-229	P.Rft	88,202
6.	50	Providing & laying (Main or Sub Main) PVC insulated with size 2-7/.044 copper conductor in 3/4" Dia PVC conduit recessed in the wall or column as required	1,829.39	S.I.No:13 P-229	P.Rft	91,470
7.	4	Providing & fixing circuit breaker 6, 10, 15, 20,30,40,50&63 SP (TB-5S)on prepared board as required	2,504.12	S.I.No:17 P-243	Each	10,016
12.	1	Providing & fixing voltmeter size 96/96mm 500volt as required &as per instruction of EI	4,186.50	SD.I.No:2 40 P-248	Each	4,187
13.	1	Providing & fixing Bakelite ceiling rose with two terminals	373.39	S.I.No:191 P-244	Each	373
14.	55	Providing & fixing Brass Battern holder	1,152.61	S.I.No:193 P-244	Each	63,394
15.	12	Providing & fixing one way SP 10/15amp switch surface type	468.19	S.I.No:188 P-244	Each	5,618
16.	24	Providing & fixing Two pin 10/15amp plug & socket	617.69	S.No:189 P-244	Each	14,825
17.	4	Providing & fixing three pin 10/15amp plug & socket flush type	677.36	S.I.No:190 P-244	Each	2,709
18.	16	Providing & fixing A.C Electric Ceiling fan 56" (good quality)	14,869.21	S.I.No:195 P-244	Each	237,907
19.	2	Providing & fixing DP I/C change over switch 500volts 100amp on a prepared board	34,291.54	S.I.No:172 P-243	Each	68,583
		Total Schedule Items				893,947
		Part "D" Non Schedule Items				
1.	1	P/F Main panel board double shutter to accommodate heavy duty circuit breaker complete in all respects.	4,000.00	NSI	Each	4,000
2.	36	P/Fixing LED Celing light 8" Square 18 Watt to 24 Watts (Superior quality as approved by Engineer incharge.	2,000.00	NSI	Each	72,000
3.	6	P/Fixing Exhaust Fan mounted light Superior quality as approved by Engineer Incharge.	8,500.00	NSI	Each	51,000
4.	12	P/Fixing fancy dimmer for Ceiling fan etc complete.	224 500.00	NSI	Each	2724 6,000
6.	1	S/Fixing Electric Motor 1/2 H.P. with pump Superior Quality as approved by Engineer Incharge.	38,500.00	NSI	Each	38,500
		Total Non Schedule Items				171,500


 ASSISTANT ENGINEER
 POLICE WORKS
 SUKKUR

168224/-

PART -I REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE

Sr. #	Particulars	No. of Unit Required	Unit Cost Approx:	Total
<u>FURNITURE & FIXTURE</u>				
1	Revolving Chairs Speical Quality	3 ✓	25000 ✓	75000 ✓
2	Office Chairs	80 ✓	12000 ✓	960000 ✓
3	Conference Table Standard Size	1 ✓	55000 ✓	55000 ✓
5	Providing Sound System with Mic Amplifiler wire Etc Complete	1 ✓	45000 ✓	45000 ✓
Total Furniture & Fixture				1135000 ✓


ASSISTANT ENGINEER
POLICE WORKS
SUKKUR

CARRIAGE OF MATERIAL

NAME OF WORK 1. REPAIR / RENOVATION CONFERENCE HALL AT SSP OFFICE.

2. REPAIR / RENOVATION OF CORRIDOR INSIDE MAIN ENTRENCE OF OFFICE BLOCK AT OFFICE SUKKUR.

Carriage of 100 Cft 5 Tons of all materials like stone aggregate, spawl, coal, lime, surkhi etc. B.G. Rail fastening points and crossing bridge, girders, pipes, sheets Rail, M.S Bars etc. or 1000 Nos. bricks 10"x5"x3" or 1000 Nos. tiles. 12"x6"x2" or 150 Cft of timber or 100 Maunds of fuel wood by truck or any other means owned by the contractors.

1. Stone Material

Lead from quarry to side of work
1st to 6th Mile
7th & subsequent Mile 10 @ Rs.105.93

16 Mile

1,447.52

1,059.30

2,506.82

2. Bajiri or Shingle

Lead from quarry to side of work
1st to 6th Mile
7th & subsequent Mile 4 @ Rs.105.93

10 Mile

1,447.52

423.72

1,871.24

3. Sand

Lead from quarry to side of work
1st to 6th Mile
7th & subsequent Mile 94 @ Rs.105.93

100 Mile

1,447.52

9,957.42

11,404.94

4. Bricks

Lead from Killen to side of work
1st to 6th Mile
7th & subsequent Mile 0 @ Rs.84.74

6 Mile

1,158.02

-

1,158.02

5. Cement

Lead from Cement Factory to side of work
1st to 2 Mile
7th & subsequent Mile 203 @ Rs.1.45

205 Mile

9.33

294.35

303.68

6. Steel

Lead from Karachi Steel Mill to side of work
1st to 6th Mile
7th & subsequent Mile 239 @ Rs.105.93

245 Mile


1,447.52

25,317.27

26,764.79

26764.79 ÷ 5 = 5,352.96

Certified that route proposed is the shortest route to the destination of the scheme/ site of work and is economical.


ASSISTANT ENGINEER
POLICE WORKS
SUUKUR

EO/Bldg/ /2026: نمبر

مالي سال 2026-27 دوران SPPRA رولر 2010 (اڄ نائين شعير ٿيل) تحت هينس ڪر جي پروگنوزيسٽ لا و خواهشمند واڌ ڏيکارڻ / ليڪيڊارن / فرمن ۽ ڪمپنين ۽ سبلائز کان استيندره واڌ دستاويزن واري لارن (SBDs) تي مهربان ٿيا پر گهريل آهن.

شمار دمبر	گهر جو نالو	تخميني لاڳت ٽينڊر لپس	پاڊسيگيوريٽي 5% (نٺ ٻاٺ) (CDR)	تڪميل جو عملو
1.	SSP آفيس، ضلعو سکر جي مين بلاڪ جي اندرئين داخلا ٻواري ڪانفرنس هال ۽ اهاڏاري جي مرمت / تزيين و آرائش	5.00 (ملن)	5000	02 مهينا

پهرئين پيري جي تفصيل			ڪلاڻ جو هنڌ
1	ٽينڊر دستاويزن جاري ڪرڻ جي تاريخ (شايع ٿيڻ کان پوءِ) 13-10-2026 منجهند 1:00 وڳي تائين ۽ ٽينڊرز منجهند 2:00 وڳي تائين جمع ڪرايا وڃن.	اشاعت کان پوءِ	لازمي: EPADS سسٽم جي ويب سائيٽ https://portalsindh.eprocure.gov.pk/#/ دفعي آڻ لائڻ (سڀني حصو وٺندڙ واک ٿيندڙن کي صلاح ڏئي وڃي ٿي تہ اي۔بڊ جمع ڪرائڻ لاءِ پاڻ کي آن لائ رجسٽر ڪن).
2	ٽينڊرز کولڻ جي تاريخ منجهند 3:00 وڳي.	13-10-2026	
ٻئين پيري جي تفصيل			
1	ٽينڊر دستاويزن جاري ڪرڻ جي تاريخ 14-10-2026 کان 29-10-2026 منجهند 1:00 وڳي تائين ۽ ٽينڊرز منجهند 2:00 وڳي تائين جمع ڪرايا وڃن.	29-10-2026	اختياري: آفيس، سينٽرل سپرٽينڊڊ آف پوليس سکر ايت اهر ڪوٽڙ روڊ سکر سٽ.
2	ٽينڊرز کولڻ جي تاريخ منجهند 3:00 وڳي.	29-10-2026	

1	حصو وندڻن جو پاڪستان انجنيئرنگ ڪائونسل (P.E.C) سان مالي سال جون 2027 تائين ڪارآمد رجسٽرڊ هجڻ ضروري آهي فرم سان گڏ ڪر ڪنڊو / انجنيئرڻ وٽ ٽيڪنيڪل اسٽاف جو مائٽريٽا.
3	مڪمل ٿيل (پنج) ڪمن / هلندڙ ڪمن جا دستاويزي ثبوت و ماڻهن پاران تسلي بخش ڪر مڪمل ٿيڻ جو سرٽيفڪيٽ.
4	هلندڙ ڪمن جي فهرست، جنهن ۾ هر ڪم جي لاڳت و ڪم جي منظوري واري ليٽر جي ڪاپي منسلڪ هجي.
5	موجوده مشينري و سامان جي فهرست سان ملڪيت / مساوا جا دستاويزي ثبوت و بينڪ ڪان مالي قابليت جو سرٽيفڪيٽ سان بينڪ اسٽيٽمينٽ.
6	انڪر ٽيڪس ڊيپارٽمينٽ وٽ رجسٽريشن (NTN سرٽيفڪيٽ) و CNIC جي ڪاپي.
7	منظور ٿيل آڇون حڪومت پاران لاڳو ڪيل اسٽامپ ڊيوٽي و جون پابند هونديون.
8	سهي ٿيڪيڊارن / قومن جو SPPPA رول (تعمير ٿيل 2019) جي رول (III) 46- تحت سنڌ روينيو بورڊ وٽ رجسٽرڊ هجڻ ضروري آهي.
9	گنرل پنهن سالن جا ساليانا انڪر ٽيڪس رٽرنس.

10	گڏيل پنجن سالن جون (ICAP) رجسٽرڊ آيت ڦرمن پاران سالياني آيت ٿيل رپورٽون (ICAP) کان سواءِ ٻين ڦرمن جون آيت رپورٽون قبول نه ڪيون وينديون.
11	بنيڪ جو سرٽيفڪيٽ جيڪو ڪم جي تخميني لاڳت جو گهٽ ۾ گهٽ 15% (گڏيل 05 سالن جي ڦي سال سراسري وقتاوت) جي ڪريٽ ورتيس ظاهر ڪري، ساڻ بنيڪ اسٽيميٽ، بنيڪ اسٽيميٽ گڏيل پنجن سالن لاءِ الڳ الڳ (ٻهين جولاءِ کان 30 جون تائين) ڏني وڃي ۽ موجود رٽور ظاهر ڪندڙ تازو بنيڪ سرٽيفڪيٽ لڳائڻ لازمي آهي.
12	استامپ پيپري تي حلفنامو ڦر / ٺيڪيدار هن وقت ڪنهن به قسم جي مقدمي، بازي، محڪماتي، تڪرار، ڪراڊر چلڻ يا سرڪاري توڙي نجني ادارن ۾ ڪنهن به ڪم جي پورائيءَ ۾ غير ضروري دير ۾ ملوث ناهي.
13	مشروط يا اڻپورا ٿيندڙ قبول نه ڪيا ويندا.
14	آپن جي تشخيص SPPRA رولز 2010 (اڄ تائين ترميم ٿيل) جي هڪ مرحلي تي هڪ ذاتي طريقيڪار تحت ڪشي ويندي.
15	منظور ٿيل آڇون حڪومت پاران لاڳو ڪيل استامپ ڊيوٽيءَ جون پابند هونديون.
16	آڇ ڪرڻ واري تاريخ تي عام موڪل يا غير متوقع حالتن جي صورت ۾، آڇون ايندڙ ڪم واري ڏينهن جمع ڪيون ۽ گولين وينديون.
17	واڪ ڏينهن کي هر ڪم جي آڏو ڏيکاريل سڀني رٽور هيٺ صحيح ڪندڙ جي نالي تي ڪنهن به شيڊولڊ بنيڪ مان تيار ٿيل ڪال پهاڙت جي صورت ۾ جمع ڪرائڻي پوندي.
18	حلفنامو ڦر / ٺيڪيدار کي هن وقت ڪنهن به ايگزيڪيوٽو ايجنسيءَ پاران بليڪ لسٽ ناهي ڪيو ويو.
19	حلفنامو ڏنل سمورا دستاويز / تفصيل / معلومات سڃي ۽ درست آهي.
20	ڦير جي صورت ۾، پاران جي افسر / پارٽرشپ ڊيڊ، جنهن ۾ ڊائريڪٽرن / مالڪن يا ٻين لاڳاپيل ماڻهن جا نامڪمل تفصيل ساڻ پاور آف اٿارٽي شامل هجن سرل ٻي پرايٽيفڪيشن جي صورت ۾ استامپ پيپري تي افوا حلفنامو ڏنو وڃي.
21	سنڌ سيزليڪس (SRB) پاليسي ۽ طريقيڪار موجب ڪٽيو ويندو.
22	جيڪڏهن هيٺ صحيح ڪندڙ يا ڪمپنيءَ جو ڪو ميمبر هيڊ ڪوارٽر کان ٻاهر هوندو ته آڇون ايندڙ ڪم واري ڏينهن ڏنل شيڊول موجب جمع ڪيون ۽ گولين وينديون.
23	هيٺ صحيح ڪندڙ ۽ ٻي معيار اٿارٽي SPPRA رولز 2010 جي سڌ تحت ڪنهن به هڪ يا ٻين آڇن کي رد ڪرڻ جو حق محفوظ رکي ٿي.

عبد الوہاب بن عبد الرحمن بن عبد اللہ بن عبد المطلب

Air Portality
INFORMATION DEPARTMENT

[illegible]

حضور ازراول

«كلاريتي ايرتير ايرتير وقع وه جهتكا
بني هراسن وه خوف وه راس هلمه
هول هكلمه طيبه جو روت كندي
وه دكتمان باه ماهر نكزي كليل
تي واي»

محسن نقوي /ايران

داري هند نشين گنگراد قاتر كر
هويدي ويزر محسن نقوي
بهتوي وه جتي ايراني محاسب
ي سنس آرد يا، كيو ايراني ميديا
هويدي جو ويران وه امريضا
امتلان سنس كيو واسط نامي وه
نوخ وه بطرفن لاگيان وه سهكار
ايراني دنودن ايراني بويهزي دوت
فانيل بقالني به دننهن اچ بيو وه
ويرو محصل كود بطرفين لاگيان
ويرو محسن نقوي ايراني وه منصب
شي هتجن وه فريضا كنيا وه

[illegible]

آمريڪي صدر/ڪيس

ٻڌڻو: نوجوان مارجي ويو

کیو ایم / آر ڈی ایم رولز

ڪڍيو آيو جي رڪتي ۾ ڏوڏو پئجي
ٻن صوفن جي حوالي سان ٻيڙي
ڏان کان مقبري وچ ۾ بار بار ٽوڪڻ
۾ مٿان نازاڻي تي ويو ۽ کيس ڳالهائڻ
لاڙي جنهن تي فاروق سنار ٻيڙي
۾ ڇڏي هليو ويو ان سڄي معاملي
شترانگ ۽ سوشل ميڊيا تي سڄو
ڪنڊي ره. مختلف تبصرا پڻ ڏيندا



**OFFICE OF THE
SENIOR SUPERINTENDENT OF POLICE
DISTRICT SUKKUR**

Phone No (071) 9310565

No.EO/Bldg/ 11596-99 /2026
Sukkur, Dated 09.2026

18

NOTICE FOR INVITATION OF SEALED TENDERS

The Sealed Tenders are invited from interested bidders / contractors / firms and companies as well as suppliers on standard bidding documents forms (SBDs) for the procurements of the following work under SPPRA Rules-2010 (Amended till date) during current financial year 2026-27.

REPAIR / RENOVATION OF POLICE BUILDINGS OF DISTRICT SUKKUR

S.#	Name of Work	Estimate Cost	Tender Fee	Bid Security 5% (CDR only)	Completion period
1.	Repair/ Renovation of Conference Hall & Corridor inside main entrance of office Block at SSP Office, District Sukkur	5.00 (M)	5000	250,000	02-Month


PROGRAMME FOR ISSUE / RECEIPT AND OPENING OF TENDERS

Particulars of 1 st attempt			Place of Opening
1.	Date of issuance of tender documents (after publication till 13.10.2026 up to 01:00 PM & Submission of tenders till 02:00 PM)	After Publication	Mandatory: Online via EPADS Sindh website https://portalsindh.eprocure.gov.pk/#/ (all participating bidders are advised to register themselves Online for E-Bid submission).
2.	Date of opening of Tenders at 03:00 PM	13.10.2026	
Particulars of 2 nd attempt			Optional: In the Office of the Senior Superintendent of Police Sukkur @ Upper Queens Road Sukkur Sindh
1.	Date of issuance of tender documents from 14.10.2026 (till 29-10-2026 up to 01:00 PM & submission of tenders till 02:00 PM)	29.10.2026	
2.	Date of opening of Tenders (at 03:00 PM)	29.10.2026	

TERMS & CONDITIONS OF THE TENDER

1.	The intending participants must be registered with Pakistan Engineering Council (P.E.C) for the year valid June-2027 limit relevant category.
2.	Bio-data of Engineers and Technical staff working with the firm.
3.	Documentary evidence of [five] works executed / works in progress and certificate of satisfactory completion of works by the employers.
4.	List of work in progress, indicating cost of each work and copy of letter of award of work.
5.	List of machinery and equipment available with documentary evidence of its ownership/ rent with certificate of Bank showing credit worthiness along with Bank statement.
6.	Registration with Income Tax Department (NTN Certificate) and copy of CNIC.
7.	The approved bids will be subject to stamp duty levied by the Government.
8.	All the contractors/ firms should be registered with Sindh Revenue Board in terms of Rule 46-1(ii) of SPPRA Rule (Amended 2019).
9.	Annual Income Tax returns of last five years.
10.	Annual audited reports of last five years from (ICAP) registered audit firms. Audit report issued other than (ICAP) registered audit firms will not be accepted.
11.	Certificate of Bank showing credit worthiness of at-least 15% (average balance per year for the last 05-years) of the estimated cost of work along with Bank Statement. Bank statement must be provided separately for each year starting from 1 st July to 30 th June for last five years and recent bank certificate must be attached showing available balance.
12.	Undertaking on stamp paper that the firm/contractor is not currently involved in any kind of litigation, department rift, abandoned or un-necessary delay in completion of any work in the Government as well as in private organizations.
13.	Conditional or incomplete tenders will not be entertained.
14.	The bids shall be evaluated on single stage one envelope method of SPPRA Rules 2010 (Amended till date).
15.	The approved bids will be subject to stamp duty levied by the Government.

16.	In case of Holiday and unforeseen circumstances on opening date the bids shall be submitted and opened on the next working day.
17.	The bidders should submit prescribed amount of earnest money as shown against each work in shape of Call Deposit prepared from the scheduled bank in favour of the undersigned.
18.	Affidavit to the effect that the firm / contractor have not been black listed currently by any executing agency.
19.	Affidavits to the effect that all document / particulars / information furnished are true and correct.
20.	In case of firm, list of partners / Partnership Deed, giving full particulars of directors/ proprietors or others connected along with power of attorney. In case of being sole proprietors, such undertaking on affidavit be furnished.
21.	The Sindh sales tax (SRB) will be deduct as per policy and procedure.
22.	In case the undersigned or any member of the committee happens to be out of the Headquarter the bids shall be submitted and opened as per the given schedule on the next working day.
23.	The undersigned and other competent authority reserve the right to reject any one or all the Bids as per provision of SPPRA Rules, 2010.


(AHMED FAISAL CHAUDHRY) QPM, PSP
 SENIOR SUPERINTENDENT OF POLICE
 DISTRICT SUKKUR
 CHAIRMAN PROCUREMENT COMMITTEE

No.EO/BLDG/ _____ Sukkur, Dated/ -09-2026.

Copy submitted to following for necessary action :-

- The Secretary, Information Technology, Sindh Secretariat No.6 @ Karachi, along with copies of N.I.T for favour of information with request for placing on the web site of Sindh Government.
- The Inspector General of Police Sindh Karachi (Attention AIGP logistics).
- The Deputy Inspector General of Police Finance CPO Sindh Karachi.
- The Deputy Inspector General of Police Sukkur Range for favour of kind information please.
- The Director, Information (Advertisement) Public Relation Advertising Department Karachi, for publication in 03-leading Newspaper "Sindhi, Urdu & English".
- The Manager (Assessment) SPPRA Barrack No.08 Sindh Secretariat No.04 Court Road Karachi.
- The Director I.T Department CPO Sindh Karachi with request to publish tender on Sindh Police, website.
- The Chief Engineer Provincial Buildings Sukkur.
- The Superintending Engineer Police Works Sindh Karachi.
- The Executive Engineer Police Works Sindh Karachi/Sukkur.
- The Assistant Engineer Police Works Sukkur.
- All concerned / Members Procurement / Redressal / Inspection Committees members / notice Board.


(AHMED FAISAL CHAUDHRY) QPM, PSP
 SENIOR SUPERINTENDENT OF POLICE
 DISTRICT SUKKUR
 CHAIRMAN PROCUREMENT COMMITTEE



GOVERNMENT OF SINDH
POLICE DEPARTMENT

No. G-I/ 513 /2026/Karachi

Dated 17 -09-2026.

ORDER

Subject:- **CONSTITUTION OF COMMITTEES FOR REPAIR/RENOVATION WORKS OF GOVERNMENT BUILDINGS OF DISTRICT SUKKUR, KHAIRPUR & GHOTKI FOR THE FINANCIAL YEAR 2026-27.**

The following Committees are hereby constituted for Repair/Renovation Work of Government Buildings of Sukkur Range, for the financial year 2026-27:-

A. Repair/Renovation Works of Conference Hall & Corridor of Main Entrance of Office Block SSP Office Sukkur.

1. Procurement Committee

- | | | |
|----|---|--------------------|
| 1. | SSP/Sukkur. | (Chairman) |
| 2. | DSP/Complain Cell Sukkur. | (Secretary/Member) |
| 3. | DSP/SDPO Pano Aqil. | (Member) |
| 4. | DSP Traffic Sukkur. | (Member) |
| 5. | Assistant Engineer Police Works Sukkur. | (Member) |

2. Redressal of Grievances & Settlement of Disputes Committee

- | | | |
|----|---|------------|
| 1. | DIGP/Sukkur Range. | (Chairman) |
| 2. | District Account Officer Sukkur. | (Member) |
| 3. | Engineer Public Health Department Sukkur. | (Member) |

3. Inspection Committee

- | | | |
|----|--------------------------|--------------------|
| 1. | DSP/Headquarter Sukkur. | (Chairman) |
| 2. | DSP/SDPO Site. | (Secretary/Member) |
| 3. | Mukhtiarkar Sukkur City. | (Member) |

B. Repair/Renovation Works of SSP/Office District Ghotki.

1. Procurement Committee

- | | | |
|----|---|--------------------|
| 1. | SSP/Ghotki. | (Chairman) |
| 2. | DSP/Head Qaurter Ghotki. | (Secretary/Member) |
| 3. | DSP/SDPO Mirpur Mathelo. | (Member) |
| 4. | O.S Deputy Commissioner Ghotki. | (Member) |
| 5. | Assistant Engineer Police Works Sukkur. | (Member) |

2. Redressal of Grievances & Settlement of Disputes Committee

- | | | |
|----|--------------------------------------|------------|
| 1. | DIGP/Sukkur Range. | (Chairman) |
| 2. | District Account Officer Ghotki. | (Member) |
| 3. | Engineer Public Health Dept: Ghotki. | (Member) |

3. Inspection Committee

- | | | |
|----|----------------------|--------------------|
| 1. | DSP/SDPO Ghotki. | (Chairman) |
| 2. | DSP/SDPO Ubauro. | (Secretary/Member) |
| 3. | Mukhtiarkar Daharki. | (Member) |

C. Repair/Renovation Works of Boundary Wall Police Headquarter District Khairpur.

1. Procurement Committee

- | | |
|--|--------------------|
| 1. SSP/Khairpur. | (Chairman) |
| 2. SP/Head Quarter Khairpur. | (Secretary/Member) |
| 3. DSP/SDPO City Khairpur. | (Member) |
| 4. O.S Deputy Commissioner Khairpur. | (Member) |
| 5. Assistant Engineer Police Works Sukkur. | (Member) |

2. Redressal of Grievances & Settlement of Disputes Committee

- | | |
|---|------------|
| 1. DIGP/Sukkur Range. | (Chairman) |
| 2. District Account Officer Khairpur. | (Member) |
| 3. Engineer Public Health Dept: Khairpur. | (Member) |

3. Inspection Committee

- | | |
|-------------------------------|--------------------|
| 1. DSP/Head Quarter Khairpur. | (Chairman) |
| 2. DSP/SDPO Gambat. | (Secretary/Member) |
| 3. Mukhtiarkar Khairpur City. | (Member) |

Sd/-

(JAVED A. ODH)PPM, PSP
INSPECTOR GENERAL OF POLICE,
SINDH, KARACHI.

Copy to the:-

- | | |
|--|--|
| 1. DIGP/Sukkur Range. | 18. District Account Officer Sukkur. |
| 2. SSP/Khairpur. | 19. District Account Officer Ghotki. |
| 3. SSP/Sukkur. | 20. O.S Deputy Commissioner Ghotki. |
| 4. SSP/Ghotki. | 21. O.S Deputy Commissioner Khairpur. |
| 5. SP/Head Quarter Khairpur. | 22. Engineer Public Health Department Sukkur. |
| 6. DSP/Complain Cell Sukkur. | 23. Engineer Public Health Dept: Ghotki. |
| 7. DSP/SDPO Pano Aqil. | 24. Engineer Public Health Dept: Khairpur. |
| 8. DSP Traffic Sukkur. | 25. Mukhtiarkar Sukkur City. |
| 9. DSP/SDPO Gambat. | 26. Mukhtiarkar Daharki. |
| 10. DSP/Headquarter Sukkur. | 27. Mukhtiarkar Khairpur City |
| 11. DSP/SDPO Site. | 28. Assistant Engineer Police Works Sukkur. |
| 12. DSP/Head Qaurter Ghotki. | 29. PS to IGP Sindh. |
| 13. DSP/SDPO Mirpur Mathelo. | 30. PS to Addl: IGP Finance & Development CPO Sindh. |
| 14. DSP/SDPO Ghotki. | 31. PA to DIGP/Logistics & Welfare, CPO Sindh. |
| 15. DSP/SDPO Ubauro. | |
| 16. DSP/SDPO City Khairpur. | |
| 17. District Account Officer Khairpur. | |


(KHAWAR AKBAR SHAIKH) PSP
AIGP/Logistics,
For Inspector General of Police,
Sindh, Karachi.