OFFICE OF THE MUNICIPAL COMMITTEE
SHAHDADPUR, DISTRICT SANGHAR

No. MC/EB/SHD / 295 *2026*
Shahdadpur dated: 15-10- *2026*

NOTICE INVITING TENDER

The Municipal Committee Shahdadpur is invited e-Bid through newly methods of " EPADS" website of SPPRA in accordance of Rule-17 (1) & Rule 46 (1) of SPPRA Rules-2010 (amended upto date) for the following works from all eligible contractors firm / parties having adequate experience in the relevant field.

S. No	*Name of Work*	*Estimated Cost in (M)*	*Earnest Money*	*Bid / Tender Fee*
1.	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 03 to 04 Shahdadpur.	*10.0*	*2%*	*3000/-*
2.	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 05 to 06 Shahdadpur.	*10.0*	*2%*	*3000/-*
3.	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 07 to 08 Shahdadpur.	*10.0*	*2%*	*3000/-*
4.	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 09 to 10 Shahdadpur.	*10.0*	*2%*	*3000/-*
5.	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 11 to 12 Shahdadpur.	*10.0*	*2%*	*3000/-*
6.	Const: & Repair of Paver/CC block flooring & Rcc Sewer line 12" 18" dia i/c rising of drains, Rcc Manholes at Main Road Flyover to Teen Talwar Shahdadpur.	*10.0*	*2%*	*3000/-*
7.	Constriction / Supply & Plantation of Outdoor Landscaping & Parks M.C Shahdadpur.	*20.0*	*2%*	*3000/-*
8.	Supplying of Uniform 2 Nos (Fabrics, Sari, & Jens) for General Staff & Sanitation Staff BPS- 01 to 04 Employees of MC SHD.	*Open Rate*	*2%*	*3000/-*
9.				

TENDER PROCEEDING SCHEDULE

No	Schedule	Date & Time	Venue
1.	Availability of bidding / tender documents	21-10-2026 to 04-11-2026	The bidding / tenders documents shall be downloaded website of "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA Sindh
	Submission of Bid/Tender & Deadline	05-11-2026 at 3:00 PM	The bids / tenders shall be uploaded on the website of "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA Sindh
	Announcement of Bid/Tender & Venue	05-11-2026 at 4:00 PM	Tender opening committee in the office of Chief Municipal Officer MC Shahdadpur.

IF NOT RESPONDED 2nd ATTEMPT IS AS UNDER

No	Schedule	Date & Time	Venue
2.	Availability of bidding / tender documents	06-11-2026 to 20-11-2026	The bidding / tenders documents shall be downloaded website of "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA Sindh
	Submission of Bid/Tender & Deadline	23-11-2026 at 3:00 PM	The bids / tenders shall be uploaded on the website of "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA Sindh
	Announcement of Bid/Tender & Venue	23-11-2026 at 4:00 PM	Tender opening committee in the office of Chief Municipal Officer MC Shahdadpur.

Chief Municipal Officer
Municipal Committee Shahdadpur

3. The bidder shall submit non-refundable cost of tender fees physically mentioned against the work through pay order from any schedule Bank in favor of Municipal Committee Shahdadpur before the opening of the bid / tender.
4. The bidding documents shall be downloaded from the website of of "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA Sindh.
5. The bid security equal to 5% specified amount against the work in shape of pay order / banks drafts in favor of Municipal Committee Shahdadpur, shall be uploaded with the tender. The hard copy of original bid security shall be submitted physically in sealed envelope showing name of Firm alongwith name of work in the office of tender opening committee before opening of bid / tender otherwise the tender / bid will be rejected.
6. The contractors must mentioned their complete & correct present / postal address in the tender documents and quote the rates both in words and figures. Incomplete /conditional tender / bid will not be accepted.
7. If any fake documents are found then the tender / bid is liable to be rejected-cancelled without any compensation but penalty will be imposed as per rule.
8. The downloaded bid / tender will be opened by the Procurement Committee in the office of Chief Municipal Officer Municipal Committee Shahdadpur, on the above mentioned date, time & venue in presence of such contractors / parties / firms / bidders who wished to be present.
9. In case the date of opening is declared as a public holiday by the government or non-working day due to any reason, the next official working day shall be deemed to the date for submission and opening of tender of the same time as mentioned.
10. The procuring agency may reject bid/tender at any time prior to the acceptance of the bid or proposal, subject to the relevant provision, of SPPRA Rules 2010.
11. Tender/ Bid will not be received after the schedule time.
    The bid security shall be release to the unsuccessful bidders once the contractor has been signed with the successful bidders.
12. In case any query required regarding e-bidding please contract : "EPADS" helpline UAN# 051-111-137-237.
13. The authority of Municipal Committee Shahdadpur may accept or reject tender / bid subject to the provision of SPPRA Rule-2010 (Amended up to date).

14	**Eligibility Criteria / Qualification Criteria:-** • NTN Certification. • Valid P.E.C Category (Where application) relevant field of specialization. • Registration with Sindh Revenue Board. • Relevant Experience of 05 years (work order and completion certificate of similar nature of work) • Turn-over of at least 5 years (02 to 04 Millions). • Valid License issued from inspector of electrical license sindh of the similar region with respect to Electrical & Mechanical works (if Applicable). • Undertaking on stamp paper the firm is not involved in any litigation, Department rift, abandoned or un-necessary delay in completion of any work in the Government department. • Affidavit to effect that all documents / particulars / information furnished are true and correct. • Documentary of work equivalent cost or above executed in last 3 years & certificate of Satisfactory Completion showing data of start & completion from employer. • List of machinery & equipment available with documentary proof of its ownership. • The firm is not black listed / debarred by any procuring agency otherwise the Municipal Committee SHD Will disqualified the firm subject to rule-30 of SPPRA rule-2010 (amended up to date) Affidavit that the firm is not black listed is required. • Any other factor deemed to relevant by the Municipal Committee Shahdadpur subject to provision of SPPRA Rule-44.

Chief Municipal Officer,
Municipal Committee Shahdadpur

Copy forwarded with compliments for favour of information.

1. The Chairman, Municipal Committee Shahdadpur.
2. The Assistant Executive Engineer, Municipal Committee Shahdadpur.
3. The Accounts Officer, Municipal Committee Shahdadpur.
4. The All Procurement Committee Members.
5. Office File.

Chief Municipal Officer,
Municipal Committee Shahdadpur

GOVERNMENT OF SINDH
LOCAL GOVERNMENT & HOUSING TOWN PLANNING DEPARTMENT

Karachi, dated the 21st July, 2026

R&I 12540H Dated 23/7/26

NOTIFICATION

No.SOI/LG/3-07/2026/Sanghar: With the approval of Competent Authority, the following Procurement Committee under Rule-7 & 8 of SPPRA Rule 2010 consisting on following (03) three officers is hereby constituted to carryout the bidding process of Municipal Committee Shahdadpur as per allocation of budget during current financial year 2027-26.

1. Chief Municipal Officer, Municipal Committee Shahdadpur — Chairman
2. Assistant Executive Engineer Municipal Committee, Shahdadpur — Member
3. Assistant Executive Engineer, P.H.E.D Shahdadpur Sub-Division — Member

2. Terms of Reference: -

The functions and responsibilities of Procurement Committee shall be as under:-

i. Preparing of bidding documents.
ii. Carry out technical as well as financial evolution of bids.
iii. Preparing evolution report as provided in Rule-45 of SPPRA, 2010 (Amended upto date).
iv. Making recommendations for the award of contract to the Competent Authority.
v. Perform any other functions ancillary and incidentally.
vi. Policy guidelines of this department regarding approval of development schemes / NITs etc must be followed.

3. In case of any breach/violation of SPPRA rules, the Procuring Committee shall be held responsible accordingly.

DR. WASEEM SHAMSHAD ALI
SECRETARY TO GOVT. OF SINDH

NO.SOI/LG/3-07/2026/Sanghar **Karachi, dated 21st July, 2026**

A copy is forwarded for information and necessary action to:

1. The Director, Sindh Public Procurement Regulatory Authority, Karachi.
2. The Chairman /Chief Municipal Officer, Municipal Committee Shahdadpur.
3. The Assistant Executive Engineer, Municipal Committee Shahdadpur.
4. The Assistant Executive Engineer, P.H.E.D Shahdadpur Sub-Division.
5. The Assistant Director, Local Government Shaheed Benazirabad.
6. P.S. to Secretary, Local Government & HTP Department, Gos, Karachi.

21.07.26

(ATTAULLAH UNNAR)
SECTION OFFICER-I

OFFICE OF THE MUNICIPAL COMMITTEE
SHAHDADPUR, DISTRICT SANGHAR
No. MC/EB/SHD / 288 2026
Shahdadpur dated: 14-09- 2026

NOTIFICATION

The Competent Authority of Municipal Committee Shahdadpur has been constituted a complaint redressal committee 2026-2027 in pursuance of Rule-31 of SPPRA, Rule-210 (Amended up to date) with appropriate powers and authorization to address the complaints of aggrieved bidders that may occur during the procurement proceeding and comprehensive complaint redressal mechanism for smooth and efficient procurement in Municipal Committee Shahdadpur. The CRC comprising of the following officers, The Complaint Redressal Committee is as under:- .

1.	Mr. Tariq Ali Thahim, Accounts Office, Municipal Committee Shahdadpur.	Chairman
2.	Mr. Rasool Bux Rajar, Assistant Executive Engineer,(Electrical) Municipal Committee Shahdadpur.	Member
3.	Mr. Mohammad Tabish, Bachelor of Architecture Shahdadpur.	Member

MUNCIPAL COMMITTEE ★ SHAHDADPUR ★

Chief Municipal Officer
Municipal Committee Shahdadpur

Copy forwarded with compliments for favour of information.

1. The Chairman, Municipal Committee Shahdadpur.
2. The Chief Municipal Officer, Municipal Committee Shahdadpur.
3. The Assistant Executive Engineer, Municipal Committee Shahdadpur.
4. The Accounts Officer, Municipal Committee Shahdadpur.
5. The Mohammad Tabish, Bachelor of Architecture Shahdadpur.
6. Office File.

Chief Municipal Officer,
Municipal Committee Shahdadpur

THE ANNUAL PROCUREMENT PLAN (YEAR 2026-2027) FOR PROCURMENT WORKS IN MUNICIPAL COMMITTEE SHAHDADPUR

S. No.	Description of Procurement	Quantity where applicable	Estimated Unit cost wher applicable	Estimated Total Cost	Funds Allocated	Source of Funds ADP/Non-ADP	Proposed Procurement Method	Timing of Procurement				Remarks
1	2	3	4	5	6	7	8	9	10	11	12	13
1	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 03 to 04 Shahdadpur.		10.0	10.0		Non-ADP	Single Stage one Envelop				√	
2	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 05 to 06 Shahdadpur.		10.0	10.0		Non-ADP	Single Stage one Envelop				√	
3	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 07 to 08 Shahdadpur.		10.0	10.0		Non-ADP	Single Stage one Envelop				√	
4	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 09 to 10 Shahdadpur.		10.0	10.0		Non-ADP	Single Stage one Envelop				√	
5	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Ward No. 11 to 12 Shahdadpur.		10.0	10.0		Non-ADP	Single Stage one Envelop				√	
6	Const: of Paver/CC block flooring & Rcc Sewer line 12" , 18" dia i/c rising of drains,Rcc Slabs at Main Road Flyover to Teen Talwar Shahdadpur.		10.0	10.0		Non-ADP	Single Stage one Envelop				√	
7	Constriction / Supply & Plantation of Outdoor Landscaping & Parks M.C Shahdadpur.		20.0	20.0		Non-ADP	Single Stage one Envelop				√	
8	Supplying of Uniform 2 Nos (Fabrics, Sari, & Jens) for General Staff & Sanitation Staff BPS- 01 to 04 Employees of Municipal Committee Shahdadpur.		3.0	3.0		Non-ADP	Single Stage one Envelop				√	

SHAHDADPUR * MUNICIPAL COMMITTEE *

Accounts Officer
Municipal Committee Shahdadpur

Chief Municipal Officer
Municipal Committee Shahdadpur

Chairman
Municipal Committee Shahdadpur

OFFICE OF THE MUNICIPAL COMMITTEE SHAHDADPUR
DISTRICT SANGHAR

"B I D D I N G D A T A"

a.	**Name of Procuring Agency:-**	OFFICE OF THE MUNICIPAL COMMITTEE SHAHDADPUR, DISTRICT SANGHAR
b.	**Brief Description of Works:-**	CONSTRUCTION OF OUTDOOR LANDSCAPING & PARKS MUNICIPAL COMMITTEE SHAHDADPUR
c.	**Procuring Agency's address:-**	OFFICE OF THE MUNICIPAL COMMITTEE SHAHDADPUR, DISTRICT SANGHAR
d.	**Estimated Cost :-**	Rs. 20.0 (Million
e.	**Amount of Bid Security:-**	Rs. 2%
f.	**Period of Bid Validity (days):-**	3 Months
g.	**Security Deposit:-(including bid security):-**	10% of contract price
h.	**Percentage, if any, to be deducted from bills:-**	8% Income Tax & 8% S.D 5% SRB
i.	**Deadline for Submission of Bids along with time:-**	As Per N.I.T.
j.	**Venue, Time, and Date of Bid Opening:-**	As Per N.I.T.
k.	**Time for Completion from written order of commence:-**	1 Year
l.	**Liquidity damages:-**	0.06 of Bid Cost (per of day)
m.	**Deposit Receipt No: Date: Amount:-**	Rs. 3,000 /= (Tender Documents Fee)

ASSISTANT EXECUTIVE ENGINEER
MUNICIPAL COMMITTEE SHAHDADPUR

SPPRA BIDDING DOCUMENT

(STANDARD FORM OF BIDDING DOCUMENT)

FOR PROCUREMENT OF WORKS

WORK NO: 07

(SINGLE STAGE ONE ENVELOPE METHOD)

NAME OF WORK:

CONSTRUCTION OF OUTDOOR LANDSCAPING & PARKS MUNICIPAL COMMITTEE SHAHDADPUR

Estimated Cost :-	Rs.	20.0 (Million)
Amount of Bid Security:-	Rs.	2%
Tender Cost.	Rs.	3000/-

Tender Issue M/S _____

Pay Order of Tender Cost.

P.O No._____ Date _____

Bank _____

Rs: _____

Pay Order of Bid Security.

P.O No._____ Date _____

Bank _____

Rs: _____

Assistant Executive Engineer
Municipal Committee Shahdadpur

OFFICE OF THE MUNICIPAL COMMITTEE SHAHDADPUR, DISTRICT SANGHAR

Instructions to Bidders/ Procuring Agencies regarding N.I.T No. 295 dated 15.10.2026, for works serial No. 01 . to 09

General Rules and Directions for the Guidance of Contractors.

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Agency. It should also give information on bid submission, opening and evaluation, and on the award of contract. Matters governing the performance of the Contract or payments under the Contract, or matters affecting the risks, rights, and obligations of the parties under the Contract are included as Conditions of Contract and *Contract Data*. The *Instructions to Bidders* will not be part of the Contract and will cease to have effect once the contract is signed.

1. All work proposed to be executed by contract shall be notified in a form of Notice Inviting Tender (NIT)/Invitation for Bid (IFB) hoisted on website of Authority and Procuring Agency and also in printed media where ever required as per rules. NIT must state the description of the work, dates, time and place of issuing, submission, opening of bids, completion time, cost of bidding document and bid security either in lump sum or percentage of Estimated Cost/Bid Cost. The interested bidder must have valid NTN also.

2. Content of Bidding Documents must include but not limited to: Conditions of contract, Contract Data, specifications or its reference, Bill of Quantities containing description of items with scheduled/item rates with premium to be filled in form of percentage above/ below or on item rates to be quoted, Form of Agreement and drawings.

3. Fixed Price Contracts: The Bid prices and rates are fixed during currency of contract and under no circumstance shall any contractor be entitled to claim enhanced rates for any item in this contract.

4. The Procuring Agency shall have right of rejecting all or any of the tenders as per provisions of SPP Rules 2010.

5. Conditional Offer: Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in Bill of Quantities for items of work to be carried out: he is willing to undertake the work and also quote the rates for those items which are based on market rates. Only one rate of such percentage, on all the Scheduled Rates shall be framed. Tenders, which propose any alternative in the works specified in the said form of invitation to tender or in the time allowed for carrying out the work, or which contain any other conditions, will be liable to rejection. No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each.
The envelope containing the tender documents shall refer the name and number of the work.

6. All works shall be measured by standard instruments according to the rules.

7. Bidders shall provide evidence of their eligibility as and when requested by the Procuring Agency.

8. Any bid received by the Agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.

9. Prior to the detailed evaluation of bids, the Procuring Agency will determine whether the bidder fulfills all codal requirements of eligibility criteria given in the tender notice such as registration with tax authorities, registration with PEC (where applicable), turnover statement, experience statement, and any other condition mentioned in the NIT and bidding document. If the bidder does not fulfill any of these conditions, it shall not be evaluated further.

10. Bid without bid security of required amount and prescribed form shall be rejected.

11. Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis;

(A) In case of schedule rates, the amount of percentage quoted above or below will be checked and added or subtracted from amount of bill of quantities to arrive the final bid cost.

(B) In case of item rates, .If there is a discrepancy between the unit rate and the total cost that is obtained by multiplying the unit rate and quantity, the unit rate shall prevail and the total cost will be corrected unless in the opinion of the Agency there is an obvious misplacement of the decimal point in the unit rate, in which case the total cost as quoted will govern and the unit rate corrected. If there is a discrepancy between the total bid amount and the sum of total costs, the sum of the total costs shall prevail and the total bid amount shall be corrected.

(C) Where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.

Assistant Executive Engineer
Municipal Committee Shahdadpur

OFFICE OF THE MUNICIPAL COMMITTEE SHAHDADPUR, DISTRICT SANGHAR

Conditions of Contract

Name of work: _____

_____

Clause – 1: Commencement & Completion Dates of work.

The contractor shall not enter upon or commence any portion or work except with the written authority and instructions of the Engineer-in-charge or of in subordinate-in-charge of the work. Failing such authority the contractor shall have no claim to ask for measurements of or payment for work.

The contractor shall proceed with the works with due expedition and without delay and complete the works in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckoned from the date on which the order to commence work is given to the contractor. And further to ensure good progress during the execution of the wok, contractor shall be bound, in all in which the time allowed for completion of any work exceeds one month, to achieve progress on the prorate basis.

Clause – 2: Liquidated Damages.

The contractor shall pay liquidated damages to the Agency at the rate per day stated in the bidding data for each day that the completion date is later than the Intended completion date; the amount of liquidated damage paid by the contractor to the Agency shall not exceed 10 per cent of the contract price. Agency may deduct liquidated damages from payments due to the contractor. Payment of liquidated damages does not affect the contractor's liabilities.

Clause – 3: Termination of the Contract.

(A) Procuring Agency/Executive Engineer may terminate the contract if either of the following conditions exits:-

(i) Contractor causes a breach of any clause of the Contract;

(ii) The progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired;

(iii) In the case of abandonment of the work owing to the serious illness or death of the contractor or any other cause.

(iv) Contractor can also request for termination of contract if a payment certified by the Engineer is not paid to the contractor within 60 days of the date of the submission of the bill;

(B) The Executive Engineer/Procuring Agency has power to adopt any of the following courses as may deem fit:- (i) to forfeit the security deposit available except conditions mentioned at A (iii) and (iv) above; (ii) to finalize the work by measuring the work done by the contractor.

(C) In the event of any of the above courses being adopted by the Executive Engineer/Procuring Agency, the contractor shall have:- (i) no claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials, or entered into any engagements, or made any advances on account of, or with a view to the execution of the work or the performance of the contract, (ii) however, the contractor can claim for the work done at site duly certified by the executive engineer in writing regarding the performance of such work and has not been paid. Procuring Agency/Engineer may invite fresh bids for remaining work.

Clause 4: Possession of the site and claims for compensation for delay.

The Engineer shall give possession of all parts of the site to the contractor. If possession of site is not given by the date stated in the contract data, no compensation shall be allowed for any delay caused in starting of the work on account of any acquisition of land, water standing in borrow pits/ compartments or in according sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

Clause –5: Extension of Intended Completion Date.

The Procuring Agency either at its own initiatives before the date of completion or on desire of the contractor may extend the intended completion date, if an event (which hinders the execution of contract) occurs or a variation order is issued which makes it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final; where time has been extended under this or any other clause of this agreement, the date for completion of the work shall be the date fixed by the order giving the extension or by the aggregate of all such orders, made under this agreement. When time has been extended as aforesaid, it shall continue to be the essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

Clause –6: Specifications.

The contractor shall execute the whole and every part of the work in the most substantial and work-man-like manner and both as regards materials and all other matters in strict accordance with the specifications lodged in the office of the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm exactly, fully and faithfully to the designs, drawing, and instructions in writing relating to the work signed by the Engineer-in-charge and lodge in his office and to which the contractor shall be entitled to have access at such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so requires, be entitled at his own expense to make or cause to be made copies of the specifications, and of all such designs, drawings, and instructions as aforesaid.

Clause – 7: Payments.

(A) Interim/Running Bill.

A bill shall be submitted by the contractor as frequently as the progress of the work may justify for all work executed and not included in any previous bill at least once in a month and the Engineer-in-charge shall take or cause to be taken the requisite measurements for the purpose of having the same verified and the claim, as for as admissible, adjusted, if possible before the expiry of ten days from the presentation of the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose countersignature to the measurement list will be sufficient to warrant and the Engineer-in-charge may prepare a bill from such list which shall be binding on the contractor in all respects. The Engineer /Procuring Agency shall pass/certify the amount to be paid to the contractor, which he considers due and payable in respect thereof, subject to deduction of security deposit, advance payment if any made to him and taxes. All such intermediate payment shall be regarded as payments by way of advance against the final payment only and not as payments for work actually done and completed, and shall not preclude the Engineer-in-charge from recoveries from final bill and rectification of defects and unsatisfactory items of works pointed out to him during defect liability period.

(B) The Final Bill.

A bill shall be submitted by the contractor within one month of the date fixed for the completion of the work otherwise Engineer-in-charge's certificate of the measurements and of the total amount payable for the works shall be final and binding on all parties.

Clause – 8: Reduced Rates.

In cases where the items of work are not accepted as so completed, the Engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

Clause – 9: Issuance of Variation and Repeat Orders.

(A) Agency may issue a Variation Order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plans, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.

(B) Contractor shall not perform a variation until the Procuring Agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of 15% on the same conditions in all respects on which he agreed to do them in the work, and at the same rates, as are specified in the tender for the main work.

(C) The contractor has no right to claim for compensation by reason of alterations or curtailment of the work.

(D) In case the nature of the work in the variation does not correspond with items in the Bill of Quantities, the quotation by the contractor is to be in the form of new rates for the relevant items of work, and if the Engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.

(E) The time for the completion of the work shall be extended in the proportion that the additional work bear to the original contact work.

(F) In case of quantities of work executed result the Initial Contract Price to be exceeded by more than 15%, and then Engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval of Superintending Engineer.

(G) Repeat Order: Any cumulative variation, beyond the 15% of initial contract amount, shall be subject of another contract to be tendered out if the works are separable from the original contract.

Clause-10: Quality Control.

(A) Identifying Defects: If at any time before the security deposit is refunded to the contractor/during defect liability period mentioned in bid data, the Engineer-incharge or his subordinate-in-charge of the work may instruct the contractor to uncover and test any part of the works which he considers may have a defect due to use of unsound materials or unskillful workmanship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid.

(B) Correction of Defects: The contractor shall be bound forthwith to rectify or remove and reconstruct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the Defects Correction Period mentioned in notice.

(C) Uncorrected Defects:

(i) In the case of any such failure, the Engineer-in-charge shall give the contractor at least 14 days notice of his intention to use a third party to correct a defect. He may rectify or remove, and re-execute the work or remove and replace the materials or articles complained of as the case may be at the risk and expense in all respects of the contractor.

(ii) If the Engineer considers that rectification/correction of a defect is not essential and it may be accepted or made use of; it shall be within his discretion to accept the same at such reduced rates as he may fix therefore.

Clause – 11: (A) Inspection of Operations.

The Engineer and his subordinates, shall at all reasonable times have access to the site for supervision and inspection of works under or in course of execution in pursuance of the contract and the contractor shall afford every facility for and every assistance in obtaining the right to such access.

(B) Dates for Inspection and Testing. The Engineer shall give the contractor reasonable notice of the intention of the Engineer-in-charge or his subordinate to visit the work shall have been given to the contractor, then he either himself be present to receive orders and instructions, or have a responsible agent duly accredited in writing present for that purpose, orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

Clause – 12: Examination of work before covering up.

(A) No part of the works shall be covered up or put out of view/beyond the reach without giving notice of not less than five days to the Engineer whenever any such part of the works or foundations is or are ready or about to be ready for examination and the Engineer shall, without delay, unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations;

(B) If any work is covered up or placed beyond the reach of measurement without such notice having been given, the same shall be uncovered at the contractor's expense, and in default thereof no payment or allowance shall be made for such work, or for the materials with which the same was executed.

Clause – 13: Risks.

The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or related services at the premises and of personal injury and death which arise during and in consequence of its performance of the contract. if any damage is caused while the work is in progress or become apparent within three months of the grant of the certificate of completion, final or otherwise, the contractor shall make good the same at his own expense, or in default the Engineer may cause the same to be made good by other workmen, and deduct the expenses from retention money lying with the Engineer.

Clause-14: Measures for prevention of fire and safety measures.

The contractor shall not set fire to any standing jungle, trees, bush-wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in all cases when destroying, cutting or uprooting trees, bush-wood, grass, etc by fire, the contractor shall take necessary measures to prevent such fire spreading to or otherwise damaging surrounding property. The contractor is responsible for the safety of all its activities including protection of the environment on and off the site. Compensation of all damage done intentionally or unintentionally on or off the site by the contractor's labour shall be paid by him.

Clause-15: Sub-contracting.

The contractor shall not subcontract the whole of the works, except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, defaults and neglects of any subcontractor, his agents, servants or workmen as if these acts, defaults or neglects were those of the contractor, his agents' servants or workmen.

The provisions of this contract shall apply to such subcontractor or his employees as if he or it were employees of the contractor.

Clause – 16: Disputes.

All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, , the decision of the Superintending Engineer of the circle/officer/one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contract upon all questions relating to the meaning of the specifications, designs drawings, and instructions, hereinbefore mentioned and as to the quality of workmanship, or materials used on the work or as to any other questions, claim, right, matter, or thing whatsoever in any way arising out of, or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works, or the execution, of failure to execute the same, whether arising, during the progress of the work, or after the completion or abandonment thereof.

Clause –17: Site Clearance.

On completion of the work, the contractor shall be furnished with a certificate by the Executive Engineer (hereinafter called the Engineer incharge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at site either for use or for operation facilities including cleaning debris and dirt at the site. If the contractor fails to comply with the requirements of this clause then Engineer-in-charge, may at the expense of the contractor remove and dispose of the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor's retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any sum actually realized by the sale thereof.

Clause –18: Financial Assistance /Advance Payment.

(A) Mobilization advance is not allowed.

(B) Secured Advance against materials brought at site.

(i) Secured Advance may be permitted only against imperishable materials/quantities anticipated to be consumed/utilized on the work within a period of three months from the date of issue of secured advance and definitely not for full quantities of materials for the entire work/contract. The sum payable for such materials on site shall not exceed 75% of the market price of materials;

(ii) Recovery of Secured Advance paid to the contractor under the above provisions shall be affected from the monthly payments on actual consumption basis, but not later than period more than three months (even if unutilized).

Clause –19: Recovery as arrears of Land Revenue.

Any sum due to the Government by the contractor shall be liable for recovery as arrears of Land Revenue.

Clause –20: Refund of Security Deposit/Retention Money.

On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurements are checked by a competent authority, if such check is necessary otherwise from the last date of recording the final measurements), the defects notice period has also passed and the Engineer has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor (in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

Contractor

Chief Municipal Officer
Municipal Committee Shahdadpur

Assistant Executive Engineer
Municipal Committee Shahdadpur

ABC Certified
The Largest Circulated Sindhi Daily of Pakistan
هڪ ئي وقت ڪراچي، حيدرآباد ۽ سکر مان شايع ٿيندڙ پهرين سنڌي اخبار
DAILY KAWISH
روزانه ڪاوش
(جلد 37) چنڇر 17 آڪٽوبر 2026ع بمطابق 05 جمادي الاول 1448ھ (شمارو 75) قيمت 40 رپيا

آفس آف دي ميونسپل ڪميٽي
شهدادپور، ڊسٽرڪٽ سانگهڙ

No.MC/EB/SHD/295/2026

شهدادپور، تاريخ: 15-10-2026

ٽينڊر گهرائڻ لاءِ نوٽيس

ميونسپل ڪميٽي شهدادپور، SPPRA جي "EPADS" ويب سائيٽ فريعي، SPPRA رولز 2010 (هيل ٽائين ترميم ٽيل) جي رول (1) 17 ۽ رولز (1) 46 تحت، هيٺ ڏنل ڪمن لاءِ آنهن سموري اهل ٽيڪيدارن/فرمن/ڪمپنين کان اليڪٽرانڪ بولين طلب ڪري ٿي. جن وٽ لاڳاپيل شعبي ۾ مناسب درجي موجود هجي.

ايس نمبر	ڪم جو نالو	ڪميل لاڳت (ايم) ۾	سيڪيورٽي رقم	بولي/ ٽينڊر فيس
01	وارد نمبر 03 ڪاڻ 04، شهدادپور ۾ پيور/سي سي بلاڪ فلورنگ، 12 ۽ 18 انچ قطر واري سيوريج لائن جنهن ۾ نالين جي سطح مٿي ڪرڻ ۽ آر سي سي سليبس جي تعمير	10.0	2٪	3000/-
02	وارد نمبر 05 ڪاڻ 06، شهدادپور ۾ پيور/سي سي بلاڪ فلورنگ، 12 ۽ 18 انچ قطر واري سيوريج لائن جنهن ۾ نالين جي سطح مٿي ڪرڻ ۽ آر سي سي سليبس جي تعمير	10.0	2٪	3000/-
03	وارد نمبر 08 ڪاڻ 07، شهدادپور ۾ پيور/سي سي بلاڪ فلورنگ، 12 ۽ 18 انچ قطر واري سيوريج لائن جنهن ۾ نالين جي سطح مٿي ڪرڻ ۽ آر سي سي سليبس جي تعمير	10.0	2٪	3000/-
04	وارد نمبر 09 ڪاڻ 10، شهدادپور ۾ پيور/سي سي بلاڪ فلورنگ، 12 ۽ 18 انچ قطر واري سيوريج لائن جنهن ۾ نالين جي سطح مٿي ڪرڻ ۽ آر سي سي سليبس جي تعمير	10.0	2٪	3000/-
05	وارد نمبر 11 ڪاڻ 12، شهدادپور ۾ پيور/سي سي بلاڪ فلورنگ، 12 ۽ 18 انچ قطر واري سيوريج لائن جنهن ۾ نالين جي سطح مٿي ڪرڻ ۽ آر سي سي سليبس جي تعمير	10.0	2٪	3000/-
06	شهدادپور ۾ مين روڊ فلائي اوور ڪان ٽين ٽلوار تائين، پيور/سي سي بلاڪ فلورنگ ۽ 12 ڪاڻ 18 انچ قطر وارين نالين جي سطح مٿي ڪرڻ، آر سي سي مين هولز جي تعمير/مرمت	10.0	2٪	3000/-
07	ميونسپل ڪميٽي شهدادپور: باهرين لينڊ اسڪيپنگ ۽ پارڪن جي تعمير، سامان جي فراهمي ۽ پوٽا لڳائڻ	20.0	2٪	3000/-
08	ميونسپل ڪميٽي شهدادپور جي جنرل اسٽاف ۽ صفائي عملي لاءِ ايس۔01 ڪاڻ 04 ۾ 2 عدد يونيفارم (ڪپڙو، سلائي ۽ جينز) جي فراهمي.	ڪليل اڪائونٽ	2٪	3000/-

ٽينڊر جي عمل جو شيڊول

ايس نمبر	شيڊول	تاريخ ۽ وقت	هدايت
1.	بڊنگ/ٽينڊر دستاويزن جي دستيابي	21.10.2026 کان 04.11.2026	پرائيويٽ/ٽينڊر جا دستاويز "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA سنڌ جي ويب سائيٽ تان ڊائون لوڊ ڪيا ويندا.
	پرائيويٽ/ٽينڊر جمع ڪرائڻ ۽ آخري تاريخ	05.11.2026 تي 03:00 وڳي	پرائيويٽ/ٽينڊر "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA سنڌ جي ويب سائيٽ تي اپلوڊ ڪيا ويندا.
	پرائيويٽ/ٽينڊر جي جڳهه جو اعلان	05.11.2026 تي 04:00 وڳي	ٽينڊر کولڻ واري ڪميٽي، چيف ميونسپل آفيسر، ميونسپل ڪميٽي شهدادپور جي آفيس ۾.

موت نه ملڻ جي صورت ۾ پين ڪوشش

ايس نمبر	شيڊيول	تاريخ ۽ وقت	هدايت
2.	بڊنگ/ٽينڊر دستاويزن جي دستيابي	06.11.2026 کان 20.11.2026	پرائيويٽ/ٽينڊر جا دستاويز "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA سنڌ جي ويب سائيٽ تان ڊائون لوڊ ڪيا ويندا.
	پرائيويٽ/ٽينڊر جمع ڪرائڻ ۽ آخري تاريخ	23.11.2026 تي 03:00 وڳي	پرائيويٽ/ٽينڊر "EPADS" (http://portalsindh.eprocurement.govt.pk) SPPRA سنڌ جي ويب سائيٽ تي اپلوڊ ڪيا ويندا.
	پرائيويٽ/ٽينڊر جي جڳهه جو اعلان	23.11.2026 تي 04:00 وڳي	ٽينڊر کولڻ واري ڪميٽي، چيف ميونسپل آفيسر، ميونسپل ڪميٽي شهدادپور جي آفيس ۾.

3. پرائي ڊينڈ ڪي گهرجي ته هر ٽينڈر کولڻ کان اڳ، ڪنهن به شيڊول بئنڪ مان ميونسپل ڪميٽي شهدادپور جي نالي تي پي آرڊر/ ڊرافٽ جي ٽينڈر فيس جي رقم ناقابل واپسي جمع ڪرائي، ٽينڈر فيس جي رقم جو ذڪر لاڳاپيل ڪم جي تفصيلن ۾ ڏيڻ هوندو.

4. ٽينڈر جا دستاويز SPPRA سنڌ جي "EPADS" ويب سائيٽ (http://portalsindh.eprocurement.govt.pk) تان ڊائون لوڊ ڪرڻا پوندا.

5. ڪم لاءِ مقرر ڪيل رقم جي 5 سيڪڙو جي برابر بڊ سيڪيورٽي جيڪا ميونسپل ڪميٽي شهدادپور جي نالي تي پي آرڊر يا بئنڪ ڊرافٽ جي صورت ۾ هجي، ٽينڈر سان گڏ اپلوڊ ڪرڻ لازمي آهي. ان کان علاوه، بڊ سيڪيورٽي جي اصل ڪاپي هڪ بند لفافي ۾، جنهن تي فرم جو نالو ۽ ڪم جو نالو لکيل هجي، ٽينڈر کولڻ واري ڪميٽي جي آفيس ۾ ٽينڈر کولڻ کان اڳ جمع ڪرائڻي پوندي، ٻي صورت ۾ ٽينڈر/بولي رد ڪئي ويندي.

6. ٽيڪيدارن کي گهرجي ته هر ٽينڈر دستاويزن ۾ ڏنلهنجو مڪمل ۽ صحيح موجوده/پرسنل پروفائل ۽ آفيشل ڊوزي انگن ۾ بيان ڪن. انڪمبرن يا شرطن وارا ٽينڈر/بولين قبول نه ڪيون ويندبون.

7. جيڪڏهن ڪنهي به جملي دستاويز ملايا، ته ٽينڈر/بولي بغير ڪنهن معاوضي جي رد يا منسوخ ڪئي ويندي ۽ ضابطن مطابق ڊنڊ پڻ لاڳو ڪيو ويندو.

8. ڊائون لوڊ ڪيل ٽينڈر/بولين، پروڪيورمينٽ ڪميٽي پاران، چيف ميونسپل آفيسر ميونسپل ڪميٽي شهدادپور جي آفيس ۾، مقرر ڪيل تاريخ، وقت ۽ هنڌ تي، انهن ٽيڪيدارن/پارٽنين/فرمن/پرائي ڊينڈن جي موجودگي ۾ کوليون ويندين جيڪي اڃي موجود هجڻ چاهين ٿا.

9. جيڪڏهن ٽينڈر کولڻ واري ڊينهن حڪومت پاران عام موڪل جو اعلان ڪيو ڇي يا ڪنهن ٻئي سبب ڪري اهو ڊينهن ڪم واري ڊينهن نه هجي، ته ان صورت ۾ آيندڙ سرڪاري ڪم واري ڊينهن کي ٽينڈر جمع ڪرائڻ ۽ کولڻ لاءِ مقرر ڊينهن سمجهيو ويندو. جڏهن ته وقت اهوئي رهندو جيڪو اڳ ۾ چاڻايو ويو هو.

10. پروڪيورنگ ايجنسي، SPPRA رولز 2010 جي لاڳاپيل شقن تحت، بولي يا تجويز قبول ڪرڻ کان اڳ ڪنهن به وقت ٽينڈر/بولي کي رد ڪري سگهي ٿي.

11. مقرر وقت گذرڻ کان پوءِ ڪو به ٽينڈر/بولي وصول نه ڪئي ويندي.
ڪامياب بولي ڏينڈرسان معاهدو ٿيڻ کان پوءِ، ناڪام بولي ڏينڊرن کي سندن بڊ سيڪيورٽي واپس ڪئي ويندي.

12. جيڪڏهن اي۔بڊنگ بابت ڪا به سوال گهريل هجي ته مهرباني ڪري رابطو ڪرين: "EPADS" هيلپ لائن UAN# 051-111-137-237.

13. ميونسپل ڪميٽي شهدادپور جي اختيارن، SPPRA رولز۔2010 (هيل ٽائين ترميم ٽيل) جي شرط سان مشروط طور تي ٽينڈر/بولي قبول يا رد ڪري سگهي ٿي.

اهليت جا معيار / قابليت جا معيار:-

14.
- NTN سرٽيفڪيٽ
- ڪارگر P.E.C ڪيٽيگري (جتي درخواست) لاڳاپيل فيلڊ اسپيشلائيزيشن جي.
- سنڌ ريونيو بورڊ سان رجسٽريشن
- 05 سالن جو لاڳاپيل تجربو (ڪم جي آرڊر ۽ ساڳئي نوعيت جي ڪم جي مڪمل ٿيڻ جو سرٽيفڪيٽ)
- گهٽ ۾ گهٽ 5 سالن جو ٽرن اوور (02 ڪاڻ 04 ملين).
- اليڪٽريڪل ۽ ميڪيڪل ڪمن جي حوالي سان ساڳئي علاقائي جي اليڪٽريڪل لائسنس اٿارٽي سنڌ ڪان جاري ڪيل صحيح لائسنس (جيڪڏهن لاڳو هجي).
- اسٽيپ پيپر تي ڪر ڪندي فرم، ڪنهن به مقدمي، ڪاتي جي رٽ، چڪيل يا سرڪاري ڪاتي ۾ ڪنهن به ڪم جي مڪمل ٿيڻ ۾ غير ضروري دير ۾ ملوث ناهي.
- حلف نامو ته سڀئي دستاويز / تفصيل / پيش ڪيل معلومات سڄي ۽ صحيح آهن.
- گذريل 3 سالن ۾ ڪم جي برابر قيمت يا ان کان وڌيڪ جي دستاويزي دستاويز ۽ آجر کان شروعات ۽ مڪمل ٿيڻ جي ڏيتا ڏيڪارينڈڙ اطمينان بخش مڪمل ٿيڻ جو سرٽيفڪيٽ.
- مشينري ۽ سامان جي فهرست موجود آهي جنهن ۾ ان جي ملڪيت جي دستاويزي ثبوت شامل آهن.
- ڪنهن به پروڪيورنگ ايجنسي طرفان فرم کي بليڪ لسٽ / منع ته ڪيو ويو آهي يي صورت ۾ ميونسپل ڪميٽي ايس ايڇ ڊي فرم کي ايس پي پي آر اي رولز ۔ 2010 جي رول ۔ 30 (ترميم ٽيل) جي تابع نااهل قرار ڏيندو حلف نامو ته فرم بليڪ لسٽ نه آهي گهربل آهي.
- ميونسپل ڪميٽي شهدادپور پاران ايس پي پي آر اي رولز ۔ 44 جي شق جي تابع لاڳاپيل سمجهيو ويندڙ ڪو به پيو عنصر

چيف ميونسپل آفيسر
ميونسپل ڪميٽي
شهدادپور

INF-KRY 4563/2026
I WORK FOR SINDH
www.iwork4sindh.com
JOB PORTAL BY INFORMATION DEPARTMENT

Quantity of Bill

Name of Work	CONSTRUCTION OF OUTDOOR LANDSCAPING & PARKS MUNICIPAL COMMITTEE SHAHDADPUR			
Name of Agency				
S.NO	Qty	Items	Rate	Unit	Amount
1	4800	Excavation in Foundation of building bridges and other structure i/c Dag belling dressing refilling around structure with excavated earth watering and ramming lead upto 5 F. (In Ordinary Soil) (G.S.I.No.18 ,(b) P-17)	11.88	P-Cft.	57024
2	1500.00	Dismantling cement concrete Plain 1:2:4 (GSI No. 19 (c) P-20)	133.08	P-Cft.	199620
3	5400	Pacca brick work in foundation & plinth in cement sand mortar ratio (1:6) (GSI No. 4e P-29)	359.20	P.Cft:	1939680
4	800	Kerb Stone: P/F precast edge block 3750 PSI industrial made size 6" thick x 12" long x 18" high i/c the cost of cartage excavation from work for haunching 1450 PSI lean concrete 2250 PSI concrete for haunching 1:4 cement sand mortar. (highway SI No. 14 P-221).	678.38	P-Rft.	542704
5	900	Erection and removal of centring for reinforced or plain cement concrete works of partal wood (2nd class). Vertical .(S.I No.19 (b) P-13)	298.15	P-Sft.	268335
6	400.000	Cement concrete plain i/c placing compacting finishing and curing and curing complete i/c screening and washing of stone aggregate Without shuttering ration 1:2:4. (GSI No. 5 (f) P-25)	443.54	P-Cft.	177416
7	528	Cement Concrete brickor stone ballast 1 1/2" 2" gauge in ratio (1:4:8) etc complete (G.S.I.No. 4, P-24)	296.69	P-Cft.	156652
8	7200.00	Cement plaster 1:6 upto 12' height 3/8" thick (G.S.I. No. 13 (a) P/52).	35.87	P-Sft	258264
9	7200.00	Cement Plaster 1/2" thick (1:4) (G.S.I.No. 11 (B) P/52)	39.83	P-Sft.	286776
10	900.00	Reinforced cement concrete work i/c all labour & material except the cost of steel reinforce & its labour for bending & binding which will be paid saparately this rate also i/c all kinds of forms moulds lifting shuttering curing rendering & finishing the exposed surface i/c screening & washing of shingle .(a) R.C work in roof slab, beams columns rafts lintels & other structural members laid in situ or pre -cast laid in position compited in all respects ratio (1:2:4) 90 lbs cement 2 Cft sand 4 cft shingle 1/8" to 1/4" gauge. (G.S.I.No.6, P-25)	717.59	P-Cft.	645831
11	32.14	Fabrication of mild steel reinforced for cement concrete i/c cutting bending, laying, in position making joints & fastening i/c cost of rust from bars (G.S.I.No. 8 (b), P-26)	17936.09	P.Cwt	576517
12	3600.00	Providing and fixing iron steel grill using solid square bars of size ½" x ½" placed at 4" i/c and frame of flat iron patti of ¾" x ¾" i/c cicle shape at 1.0 apart of equivalent fitted with screws are pins i/c painting three coats with first coat of red oxide paint etc. (GSI No. 30 P-76)	833.27	P-Sft.	2999772
13	45000.00	Filling Watering and ramming earth under floor with new earth (excavated from out side) lift upto 5, ft and lead upto 10 miles i/c cost of earth (GSI No. 22 P-17)	47.02	P-Cft.	2115900
14	45000.00	Laying earth in 6" layer & levelling dressing & watering for compection etc complete (GSI No. 13 (b) P-16)	1.58	P-Cft.	71100



15	1000.00	Supplying and plantation of avenue trees complete composite rate inclusive of supply of nursery stock, 7-12 ft height in 18" grow bag or pot ; transport and loading to site, handling & holding setting out and traffic barricading (M.R)	5000.00	Each	5000000
16	28750.00	Supplying grass Trufing slobs of banks or lawns with grass sids l/c ploughing laying manuring, setting and watering (truf got from within a distance of 5 miles and	60.50	P-Sft.	1739375
17	3600.00	Coloured Cement tiles (8"x8"x3/4") of approved dark shade laid flat in 1:2 cement mortar over 3/4" bedding mortar of 1:2 (GSI No. 15 P-45)	188.39	P-Sft:	678204
18	210.00	Supplying and fixing special heavy type steel doors for look - ups withn angle iron frame of 2-1/2" to 2- 1/2" x 3/8" size and shutter of 2" x 2"x 3/8" with 1" diameter M.S bars placed @ 4" center to center with asepaRate locking box having size of 12" x 12" of M. steel sheet embeded in masonary with proper locking arrangement as per approved design including cost of erection of steel gate and jfixing in masonry wallin cement concrete 1: 2: 4 etc. complete, as per instructions of Engineer Incharge. (GSI No. 27 P/560)	4300.68	P-Sft:	903143
19	3600.00	Preparing surface and painting guard bars gates, iron bars gratting, railling (l/c standard braces etc) and smillor open work. (GSI No. 5 (d) P-63)	9.76	P-Sft.	35136
	3600.00	each subsequent coat.	7.12	P-Sft.	25632
			Total		**18677081**

MUNICIPAL COMMITTEE SHAHDADPUR

ASSISTANT EXECUTIVE ENGINEER
MUNICIPAL COMMITTEE SHAHDADPUR

I am agreed for execution of above said work/Job at the _____ % above/below of S.R.

Contractor

ASSISTANT EXECUTIVE ENGINEER
MUNICIPAL COMMITTEE SHAHDADPUR