



**TEHSIL MUNICIPAL ADMINISTRATION
THALL**

BIDDING DOCUMENTS

TEHSIL MUNICIPAL ADMINISTRATION THALL

TEHSIL MUNICIPAL ADMINISTRATION THALL



BID SOLICITATION DOCUMENTS FOR

NOTICE INVITING TENDER EPADS

Sealed tenders based on MRS-2025 (1" Bi Annual) / Non MRS-items for the below mentioned works are hereby invited on the basis of Single Stage Single Envelope Procedure through EPADS from the government contractors registered with PEC, enlisted with C&W Department as per Centralized Enlistment Policy of the Government of Khyber Pakhtunkhwa for the current financial year (2025-26) Accelerated Sustainable Development Initiative (ASDI).

S#	Scheme Name	Amount in Million	2% Earnest Money in Rs	Last Date / Time of Submission of Tender of Forms	Date / Time of Tender Opening
1	Construction of streets and drains at Tehsil Thall (Naryab-I, Naryab-II, Torawari, Dallan)PK-93	17.50	350000/-	13/01/2026 12:00 PM	13/01/2026 02:00 PM

Terms and Conditions:

1. Bidding Documents can be downloaded from the official EPADS website i.e (eprocure.gov.pk) after publishing NIT on Daily Newspaper and KPPRA Website. The BSD will be filled neatly and a clear scan copy of the same will be uploaded at the time of apply (bid submission) through EPADS.
2. The bid documents along with original bid securities and detail rate analysis (if applicable) complete in all respect must be delivered through courier to the Office of Tehsil Municipal Administration TMA Thall before closing time of bid.
3. Cutting/overwriting/manipulation in the bid solicitation documents will not be acceptable. Any mismatching among the scanned copies submitted through EPADS and that submitted in hard will leads into his disqualification and the same contractor will be considered as non-responsive.
4. The rates may be offered as % age above or % age below or at-par on engineer estimate.
6. The securities shall be in shape of call deposit in favor of the TMO TMA Thall.
7. The eligible contractors/firms must have relevant codes of Pakistan Engineering Council (PEC).
8. The contractors quoting their bids up to a limit of 10% below Engineer Estimate shall submit bid security @ 2% only of Engineer Estimate.
9. The contractors quoting their bids more than 10% below up to 20% below on Engineers' Estimate shall submit along with their bids 8% Additional Security of Engineer's Estimated cost in addition to 2% bid security. If the bid is not accompanied with the required amount of additional security, then it will be considered as non-responsive and the 2% bid security shall be forfeited in favor of Government TMA and the second lowest bidder and so on will be considered accordingly.
10. Similarly, a contractor, quoting bid more than 20% below shall submit with his bid an additional security on Engineer's estimated cost equal to the differential amount of submitted bid and Engineers' Estimate along with detailed rate analysis. In case of more than 20% below bids, if the bid is not accompanied by the detailed rate analysis and/ or required amount of additional security, then said bid shall be considered as non- responsive. All the securities submitted along with such non-responsive bid shall be forfeited in favor of Government and the 2nd lowest bidder and so on will be considered accordingly. It is to clarify that additional security will be provided in shape of call deposit in name of TMO TMA Thall.
11. In case detailed rate analysis submitted with the bids is, in view of the Procuring Entity, not convincing, the Head of the Procuring Entity may declare such bid as non-responsive without any forfeiture of bid securities and record reasons thereof.

12. The call deposits i.e. bid security for the work / contract must be prepared after publishing of NIT and before the closing time of the bid.

13. In case of tie / draw amongst the responsive bidders, the bid may be decided through free toss which shall be considered as final.

14. Any electronic bidder who provides false, or materially inaccurate or incomplete or do not send information in hard form will be disqualified as per KPPRA Act Section 29 (1) read with KPPRA Rule (43). Furthermore, the Procuring Entity/Executing Agency will recommend and sent cases for debarring/Blacklisting and will initiate/ take action in light of approved procedure / mechanism as per KPPRA Act section 29 (2) read with KPPRA Rule (44).

15. The firms/contractors who wants to participate in tendering process may registered themselves with the EPADS for gaining their unique username and password.

16. The PEC and KPPRA registration (Active Tax Payer) must be valid for current Financial Year and attached with the Bids.

17. The Procuring Entity can cancel all or any tender with cogent reason.

18. The work can be increase/decrease as per site requirement and availability of fund.

19. Any addition made in the terms & conditions in NIT advertised shall be implemented as per KPPRA Act & Rules.

Note: Work orders of the aforementioned schemes will be issued to the contractor subject to release /availability of fund.

Tehsil Officer (I&S)
TMA Thall

Tehsil Municipal Officer
TMA Thall

**OFFICE OF THE TEHSIL MUNICIPAL
ADMINISTRATION THALL**

CORRIGENDUM

**REFERENCE NOTICE INVITING TENDER THROUGH
EPADS IN RESPECT OF TMA THALL REGARDING
VARIOUS DEVELOPMENT SCHEMES PUBLISHED IN
DAILIES NEWS ISLAMABAD DATED 14/12/2025 VIDE
INF (P) 5293/25, THE CORRIGENDUM IS HEREBY
ISSUED AS UNDER:-**



"Enlisted with **C&W Department**" may be read and write
as (Enlisted with "**Local Council Board Peshawar
Khyber Pakhtunkhwa, KPPRA & PEC**").

**Tehsil Municipal Officer,
TMA Thall.**

**TO(I&S),
TMA Thall.**

ZERO TOLERANCE TO CORRUPTION **INF(P) 5351/25**

BILL OF QUANTITIES

Construction of streets and drains at Tehsil Thall (Naryab-I, Naryab-II, Torawari, Dallah)PK-93	
1	Construction of Street and Drain at Gandheri Behram Shee Sultan Ayaz Korona at Dallah
2	Construction of Street & Drain Qadri Banda Musarat Korona at Dallah
3	Construction of Street and Drain at Qadri Banda Zakir Korona at Dallah
4	Construction of Street and Drain at Tora Ghundi Ismail Chairman Korona at Tora Wari
5	Construction of Street and Drain at Shna Wari Qomi Qabristan at Naryab-2
6	Construction of Street and Drain at Shna Wari Shahab udin Korona at Naryab-2
7	Construction of Street and Drain at Sara Zamaka Sangirh Rehmat Abad at Naryab-I
8	Construction of Street and Drain at Sangirh Rehmat Abad Shahabu din Korona at Naryab-I
9	Construction of Street and Drain at Mianjikhel Usman Udin Korona at Dallah
10	Construction of Street and Drain at Mohallah Gajirio Kaly Naryab-I
11	Construction of Street and Drain at Haji Risham Badshah satar dallah
12	Construction of Street and Drain at Malak Azmat mainoor Khel Dallah at Dallah
13	Construction of Street and Drain at Orakzai road zarin kalony zargiri at Naryab-2
14	Construction of Street and Drain at said Shah Korona Zargiri at Naryab-2

Item Code	Description Of Item	Quantity	Unit	Rate	Amount
(03-21-b)	leveling & Dressing earth to designed section ordinary or Hard Soil upto cut or fill 6"	529.45	m ³	27.70	14666
(06-05-i)	PCC 1:4:8 as specified	349.43	m ³	12340.56	4312208
(06-05-f)	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4),	349.43	m ³	17035.28	5952702
(03-07-b)	earth excavation in open cut upto 1.5m depth for drain etc & disposal in hard soil	397.08	m ³	410.99	163197
(06-05-i)	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:4:8)	132.36	m ³	12340.56	1633412
(06-05-f)	Plain Cement Concrete including placing, compacting, finishing & curing (Ratio 1:2:4),	158.83	m ³	17035.25	2705774
(06-46-a)	E removing foam work to concrete in any shape,	1390.33	M2	736.33	1023745
(06-07-a-03)	RCC (1:2:4) as in slab beam etc as specified,	11.33	m ³	19446.34	220230
(06-08-c)	Fabrication of M/Steel as specified Grade 40,	0.89	ton	303009	269463
(23-02-c)	Providing and laying non-reinforced concrete pipe moulded with cement concrete 1:1-1/2:3 conforming to ASTM Specification C-14-73, Class-2, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing, cutting pipe where necessary, finishing and testing, etc. complete:- 9" i/d wall thickness 1".	49.38	m	1847.87	91239

(23-03-a-01)	Providing & laying R.C.C. pipe sewers, moulded with cement concrete 1:1-1/2:3 conforming to ASTM specification C-76-79, Class II, Wall B, including carriage, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc. complete:-12" i/d, wall thickness 2".	45.72	m	2759.96	126179
	Add 1.05% area cost factor				825641
	Add 1% TS charges				165128
					17503584
				Total Rs	17500000
				Say Rs (M)	17.500

I hereby coated rates as:

% age Above

% age Below

At-Par

Certification

Certified that I M/S _____ Govt Contractor have thoroughly read and understand the entire attached bd and accepting and is agreed with each and every page of the entire BSD without any ambiguity or objection

Signature of Contractor

Seal of Contractor