

SCOPE OF WORK REPAIR OF PMM MAIN BUILDING ROOF WALL

S.NO.		DESCRIPTION	QTY UNIT
1.	CIVIL WORK	Scaffolding	17850 Sft
2.	CIVIL WORK	Dismantling of RCC Roof Top	1530 Sft
3.	CIVIL WORK	Dismantling of Projection RCC Slab	510 Sft
4.	CIVIL WORK	Dismantling of Projection RCC Slab Walls	2550 Sft
5.	CIVIL WORK	Shuttering	2040 Sft
6.	CIVIL WORK	Shuttering RCC Beam	1147 Sft
7.	CIVIL WORK	Shuttering RCC Jacks Beam to Roof	360 Sft
8.	CIVIL WORK	RCC Projection Slab	510 Sft
9.	CIVIL WORK	Projection Walls PCC Block	2550 Sft
10.	CIVIL WORK	Sheet 5/8 – 1/2 – 3/8	6.9 Ton
11.	CIVIL WORK	RCC 1:2:4 Concrete	1075 Cft
12.	CIVIL WORK	PCC Plaster Walls	2550 Sft
13.	CIVIL WORK	Supply and Placement Precast/Concrete Slab	1530 Sft
14.	CIVIL WORK	Laying of RCC Flooring Precast/Concrete Slab	1530 Sft
15.	SAFETY	Scaffolding Safety Green Net	17850 Sft
16.	CIVIL WORK	Installation of New Storm Pipe to provide Rainwater Disposal	APR
17.	CIVIL WORK	Repair of Damaged Sections using Rock Wall for Structure	APR
18.	CIVIL WORK	Site Cleaning and Removal of Demolition Debris	APR