



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	5
RFQ No	AM19498SIR	
DATE	09.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
 SAP No.6100016392

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	23.04.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Rehabilitation of electric system at PSO Aviation Facility Peshawar Airport

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<b><u>Rehabilitation of electric system</u></b>	<b><u>Peshawar (Aviation)</u></b>				
1.01	<b><u>Fixing of electric connection</u></b> =====		<b><u>JOB</u></b>	4		
	Insulation resistance testing =====					
	Insulation resistance testing of cables as per site requirements for following equipments Receipt motor, delivery motor, firefighting water motor and pole lights.					
	Cable testing of each equipment will be considered as one job.					
1.02	<b><u>Fixing of electric connection</u></b> =====		<b><u>JOB</u></b>	1		
	Inspection of grounding and earthing =====					
	Inspection/ testing of electric system grounding, bonding of earth pits, panel and tanks.					
1.03	<b><u>Fixing of electric connection</u></b> =====		<b><u>JOB</u></b>	3		
	Development of line diagram =====					
	Development of line diagram for the electric panels. Soft copy to be shared in printable and editable AutoCAD 2007 format.					
	This work is required for 3 different electric panels (1, 3 & 4) whose images are attached.					
	Each panel will be considered as one job.					
1.04	<b><u>Fixing of electric connection</u></b> =====		<b><u>JOB</u></b>	1		
	Development of electric layout =====					
	Development of electric layout of the facility, mentioning all the details like cables and electric equipment. Soft copy to be shared in printable and editable AutoCAD 2007 format. Signed and stamped 3 hard copies on A1 size to be provided by vendor.					



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	5
RFQ No	AM19498SIR	
DATE	09.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
 SAP No.6100016392

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	23.04.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Rehabilitation of electric system at PSO Aviation Facility Peshawar Airport

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	<p><b><u>Fixing of electric connection</u></b>            =====            Dressing &amp; Tagging            =====            Proper dressing, tagging and identification of all cables, breakers , connectors etc inside the panel.            This work is required for 4 different electric panels (1, 3, 4, 7) whose images are attached.</p> <p>Each panel will be considered as one job.</p>		<b>JOB</b>	4		
1.06	<p><b><u>Fixing of electric connection</u></b>            =====            Electric protective cover            =====            Fabrication and installation of protective cover/ acrylic shield for bus bars, bare cables, connectors etc for main electric panel# 1 whose image is attached.</p>		<b>JOB</b>	1		
1.07	<p><b><u>Fixing of electric connection</u></b>            =====            Removal of unused cables            =====            Safe removal of unused cables, breakers and fitting etc from main electric panel# 1 whose image is attached.</p>		<b>JOB</b>	1		
1.08	<p><b><u>Fixing of electric connection</u></b>            =====            Termination of cables            =====            Proper termination of cables and fixing with cable lugs for safe connections in panels This work is required for 5 different electric panels (1, 3, 4, 6, 7) whose images are attached.</p> <p>Each panel will be considered as one job.</p>		<b>JOB</b>	5		
1.09	<p><b><u>Fixing of electric connection</u></b>            =====            Fabrication of bottom metal plate</p>		<b>JOB</b>	1		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	5
RFQ No	AM19498SIR	
DATE	09.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
 SAP No.6100016392

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	23.04.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Rehabilitation of electric system at PSO Aviation Facility Peshawar Airport

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.10	===== Fabrication and installation of bottom metal plate for electric panel# 1 whose image is attached. <b>Fixing of electric connection</b> =====		<b>JOB</b>	6		
1.11	Providing and installation of glands ===== Providing and installation of cable glands for all the cables of 6 electric panels. This work is required for 6 different electric panels(1 to 6) whose images are attached.  Each panel will be considered as one job. <b>Fixing of electric connection</b> =====		<b>JOB</b>	20		
1.12	Providing and installation of volt meter ===== Providing and installation of digital voltage LED indicators (indicators should have black background display) on panels having feature to display voltage reading on individual phase. <b>Fixing of electric connection</b> =====		<b>JOB</b>	3		
1.13	Providing and installation of amp meter ===== Providing and installation of digital amp meter on panel having feature to display readings in different phases at a time. <b>Fixing of electric connection</b> =====		<b>JOB</b>	3		
1.14	Providing and installation of volt meter ===== Providing and installation of digital volt meter on panel having feature to display readings in different phases at a time. <b>Fixing of electric connection</b> =====		<b>JOB</b>	1		
	Fixing of energy meter =====					



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	5
RFQ No	AM19498SIR	
DATE	09.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
 SAP No.6100016392

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	23.04.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Rehabilitation of electric system at PSO Aviation Facility Peshawar Airport

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.15	<p>Proper fixing of energy meter in panel with conduits and cable glands.</p> <p><b>Fixing of electric connection</b></p> <p>=====</p> <p>Providing and installation of residual current device</p> <p>=====</p> <p>Providing and installation of residual current devices and earth leakage circuit breakers as per site conditions.</p>		<b>JOB</b>	4		
1.16	<p><b>Fixing of electric connection</b></p> <p>=====</p> <p>Providing and installation of hour meter</p> <p>=====</p> <p>Providing and installation of hour meter for motors of receipt&lt;(&gt;,&lt;(&gt;)&gt; delivery, air compressor and fire fighting pumps.</p> <p>=====</p> <p>Terms and conditions</p> <p>=====</p> <p>1. Rates are inclusive of all types of applicable taxes and transportation charges.</p> <p>2. The electric servicing is a complete 'TURN -KEY' job. All the required labor, tools, materials etc. are to be arranged by the vendor.</p> <p>3. PSO representative shall accompany the contractor during job. Contractor and his staff to follow all safety and HSE procedures as per PSO policy.</p> <p>4. Acceptance of the job is subject to the inspection and verification by relevant Station In-charge or his authorized representative.</p> <p>5. Vendor must complete the job within 60 days after issuance of service order.</p> <p>6. Part payment is not allowed. If the vendor fails to complete the service within time stipulated, PSO will be entitled to impose to him 0.1% penalty amount of the total amount of Service Order per day as liquidated damages for the period with a maximum of 10% deductions. Qty may vary as per site conditions &lt;(&gt;,&lt;(&gt;)&gt; payment will be made as per actual work done.</p> <p>7. Contractor will be responsible for any damage to PSO property after</p>		<b>JOB</b>	4		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	5
RFQ No	AM19498SIR	
DATE	09.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016392

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON (Date)	23.04.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Rehabilitation of electric system at PSO Aviation Facility Peshawar Airport

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>handing over by the Station incharge. If any damage found after completion of required job, it will be repaired by vendor without any additional cost to PSO.</p> <p>8. All the relevant documents (CNIC, Company card, valid police verification etc) as required by ASF will be arranged by vendor.</p> <p>9. Vendor will provide 12 months warranty of workmanship and materials for date of commissioning. Incase if any defect observed during this period, it will be rectified by vendor free of cost.</p> <p>Rehabilitation of electric system at Peshawar Aviation facility as per below mentioned scope.</p> <p>Scope of work:</p> <ol style="list-style-type: none"> <li>Vendor to conduct pre mobilization meeting to have an understanding of site requirements and work required.</li> <li>All relevant documents (CNIC, valid police verifictaion from all addresses as per cnic and employee card) will be provided atleast 2 working days prior to visit.</li> <li>Vendor will perform the jobs as described in below line items. Vendor will share if there is any other mandatory work required on site and is not mentioned in issued service order. Approval to be taken for such jobs before performing.</li> <li>This is a turn-key project, all the required equipment, tools, material and labour etc will be arranged by vendor.</li> <li>Vendor and his employees will follow all the HSE requirements as per company policy.</li> <li>Since the facility is live and operting 24/7 basis. PSO has backup generator for alternate power supply. Incase if vendor need to isolate electric equipment such as pumps for more than 1 hour than alternate arrangement will be provided to keep the facility running.</li> <li>Vendor will depute atleast 1 electric supervisor having qualification of electric diploma or engineering with atleast 1 year work experience.</li> </ol>					