



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	4
RFQ No	RF19652SI	
DATE	29.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016575

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON (Date)	20.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets <(>&<)> False Ceiling replacement works at M/s BISMILLAH TRADES-1 (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<b><u>Canopy Repair - Bismillah Trades-1</u></b>	<b>PSO House</b>				
1.01	<b><u>Providing and Laying of GI sheet</u></b> Replacement of Canopy Top Sheets: Job includes removal of old canopy top GI Sheets and providing, fabrication and fixing of corrugated G.I. continuous sheet, 22 SWG (atleast 30 micron powder coated) including overlaps, crown and edge elements, expansion joints and making openings. Also included are fixings such as glavanized steel J-bolts, nuts and washer. Unit of Measurement: SQFT Note: 1- Contractor will be responsible for the removal/disposal of debris outside retail outlet premises 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Bending sheering of sheet should be as per automatic machine. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.Ft 3- Cost of Item = Cost of new material - Cost of old scrapped/removed material		<b>M2</b>	1,900		
1.02	<b><u>GI corrugated sheet</u></b> Providing Fabricating and fixing in position on existing structure, 16 SWG plain GI Sheet dain water channel including self tapping screw or galvanized M S J-Bolts, Rubber washer<(>,<)> Cup washer and Nuts etc. Joining each other rivet and Silicon filing in joins, making opening for drainage and fixing UPVC drain cover.  Unit of Measurement: SQFT  Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises.		<b>M2</b>	250		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	4
RFQ No	RF19652SI	
DATE	29.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016575

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON (Date)	20.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets <(>&<)> False Ceiling replacement works at M/s BISMILLAH TRADES-1 (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	<p>2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Will be measured with roof sheeting in Sq.ft</p> <p>3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.</p> <p><b>Installation of UPVC Pipe Class D 4"</b></p> <p>Providing and Instaling 4" Dia, local made UPVC drain pipe complete with all fitting as per site requirements hanged with MS hanger/support for drainage of Rain water, job also includes complete with cutting, jointing, &amp; wastage etc. Complete in all respect. Unit of Measurement = RFT</p>		<b>M</b>	120		
1.04	<p><b>Provid Erectng.Fixng. of GI drain ridge</b></p> <p>Providing and Laying of 26 Swg(atleast 30 micron powder coated) Plain top sheet on fascia complete in all respects.</p> <p>Unit of Measurement: SQFT</p> <p>Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises. 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.</p>		<b>M2</b>	350		
1.05	<p><b>Civil Miscellaneous</b></p> <p>Providing services for high elastomeric water proofing of canopy top</p>		<b>SET</b>	1,900		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	4
RFQ No	RF19652SI	
DATE	29.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016575

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	20.05.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets <(>&<) False Ceiling replacement works at M/s BISMILLAH TRADES-1 (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	<p>sheet and drain channels after complete replacement. Providing and applying of two coat of sealing flex after complete cleaning and removal of dust from the sheet and apply two coats. Sealing flex is water based modified acrylic/synthetic rubber emulsion.</p> <p>Job also includes complete sealing of the holes and openings and ensure proper workmanship with approved sealant and silicone packing where required.</p> <p>Brand: Ultra Seal flex or approved equivalent.</p> <p><b>Miscellaneous</b></p> <p>Providing Material and Service, for proper arrangement of loose Electric wires in proper conduit (flexible wiring, channel patti and taping) lying at top of canopy, Tank area, DB room and office area, Complete in all respect. Job also includes removal/redirectioning of electric/other wiring passing over or attached with Canopy.</p> <p>Providing services for replacement/repair of Fascia LED lights, Signage items, if found fused with proper connector arrangements and wiring, where necessary.</p>		EA	1		
1.07	<p><b>False Ceiling (Canopy)</b></p> <p>Providing and fixing of new false ceiling under canopy with 4" wide 26 SWG pre-painted (white color) steel sheet strips with no perforations and maximum length of 12 ft. hinges, bolts and all necessary fittings including soffit return of 22 swg for false ceiling finish of approved shades to be suspended with metal adjustable suspension system as per standard. Complete in all respect as per direction of engineer incharge.</p> <p>Job also includes safe removal and reinstallation of LED Canopy lights, and any additional Canopy light to be installed at site, inclusive of additional wiring and light frame, as and where required at site.</p> <p>Job means Square Foot; i.e. unit of measurement for this item.</p> <p>Terms &amp; Conditions: 1.,,The rates of items are inclusive of all taxes or any other tax</p>		EA	2,000		



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	4
RFQ No	RF19652SI	
DATE	29.04.2026	

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)  
SAP No.6100016575

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

20.05.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. \_\_\_\_\_ PO/DD NO. \_\_\_\_\_

**Title:** Providing Services For Replacement of Canopy Top Sheets <(>< False Ceiling replacement works at M/s BISMILLAH TRADES-1 (CF) - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>applicable and contractor is required to submit GST/SST invoice at the time of invoice.</p> <p>2.,,Contractor will arrange testing of equipment at his own cost, if required.</p> <p>3.,,Quality of work is the prime concern of PSO. The contractor will be required to produce best quality work.</p> <p>4.,,Work must be completed within 120 days after site handed over to contractor, subject to DHA approval.</p> <p>5.,,Contractor has to comply with all HSE procedures and policies during execution of the work.</p> <p>6.,,Contractor should strictly follow the safety and security rules of PSO. Contractor's team has to follow Company's rules and procedures as well as HSE guidelines and safety procedures.</p> <p>7.,,All labour, tools, materials and transportation to be provided by contractor.</p> <p>8.,,Payment will be made as per actual quantity of Work Done.</p> <p>9.,,If the Contractor fails to complete the work within time stipulated, the Engineer Incharge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of SO.</p> <p>10.,,Contractor should maintain housekeeping of the workplace during progress of work and shall clear and remove all surplus materials and rubbish from workplace after completion of job as per instruction of Incharge.</p> <p>11.,,The work will only be accepted after inspection and approval by the DE.</p> <p>12.,,Bidder must visit the site before quoting for the job to properly asses the scope of work.</p> <p>13.,,Damage to the False Ceiling during replacement of sheets is to be born by contractor himself.</p> <p>14.,,Rates are inclusive of scrap materials</p> <p>15.,,Work will be performed using proper PPEs like, harness, safety helmets, Shoes etc complete in all respect.</p>					