



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016585

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

19.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Services for Installation of Safety Rail</u>	Faqirabad (Depot)				
1.01	<u>Instalation & Removal</u> Dismantling of 12-inch diameter breather valve from Tank 2606 and installation of the same breather valve on Tank 2602<(>,<)> Scope of Work / Job Details: Dismantling, shifting and reinstallation of 12-inch Breather Valve currently installed on Tank 2606. The job includes safe dismantling and unbolting of the 12-inch breather valve and shifting through a 20-ton crane to Tank 2602. Scope of work also includes unbolting and removal of the 24-inch manhole cover installed on Tank 2602. The manhole cover shall be lowered and taken outside the tank zone for required cutting, welding, and fabrication works to accommodate installation of the 12-inch breather valve. After completion of all fabrication and modification works, the manhole cover shall be reinstalled on Tank 2602 with proper alignment and bolting. The job includes complete installation, refitting, and tightening of all bolts to ensure safe and proper commissioning		EA	1		
1.02	<u>Installation of Nozzle</u> Service for blinding of removed breather valve connection after shifting from TK# 2606 to TK#2602 by installation and bolting of blind flange using 12 inch Dia spiral wound gasket.		EA	1		
1.03	<u>Fabrication of Miscellaneous Items.</u> Fabrication and installation of 12-inch diameter goose neck on the manhole cover of Tank 2603 roof for safe venting and operational requirements. Scope of Work: Preparation of the tank roof manhole cover for installation Fabrication and positioning of 12-inch goose neck Proper attachment and welding as per site requirements Ensuring functional alignment and sealing of the goose neck Compliance with all relevant safety and operational standards API 650 Compliance: Installation of the goose neck shall be carried out in accordance with		EA	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
 SAP No.6100016585

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	19.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	<p>API 650 # Welded Tanks for Oil Storage, covering: Requirements for tank roof attachments and openings Welding and fixing practices to maintain tank roof integrity Structural and mechanical integrity of tank remains uncompromised</p> <p><u>Fabrication of Miscellaneous Items.</u> Fabrication, supply and installation of 10-inch diameter goose neck on the manhole cover of 24 inch Dia of Tank 2604 roof for safe venting and operational requirements.</p> <p>Scope of Work: Preparation of the tank roof manhole cover for installation Fabrication and positioning of 10-inch goose neck Proper attachment and welding as per site requirements Ensuring functional alignment and sealing of the goose neck Compliance with all relevant safety and operational standards</p> <p>API 650 Compliance: Installation of the goose neck shall be carried out in accordance with API 650 # Welded Tanks for Oil Storage, covering: Requirements for tank roof attachments and openings Welding and fixing practices to maintain tank roof integrity Structural and mechanical integrity of tank remains uncompromised</p>		EA	1		
1.05	<p><u>Fabrication of Miscellaneous Items.</u> Fabrication, installation of 12-inch and 10-inch-Dia goose neck on the manhole covers of Tank 2605 roof for safe venting and operational requirements.</p> <p>Scope of Work: Preparation of the tank roof manhole covers of 24-inch Dia for installation Fabrication and positioning of 12-inch & 10-inch-Dia goose neck Proper attachment and welding as per site requirements Ensuring</p>		EA	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016585

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

19.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ PO/DD NO. _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	<p>functional alignment and sealing of the goose neck Compliance with all relevant safety and operational standards</p> <p>API 650 Compliance: Installation of the goose neck shall be carried out in accordance with API 650 # Welded Tanks for Oil Storage, covering: Requirements for tank roof attachments and openings Welding and fixing practices to maintain tank roof integrity Structural and mechanical integrity of tank remains uncompromised.</p> <p>Painting Works</p> <p>Paint Job for Safety Railing, Splash Plates, and Goose Necks</p> <p>Description: Mechanical cleaning, surface preparation, and painting of all MS safety railings and splash plates, and all goose necks installed on Tank 2603, 2604, 2605, and 2606.</p> <p>Product Specifications: Aliphatic Acrylic Polyurethane Coating Property Test Standard Description Solids by volume ISO 3233 63+-2% Gloss level (GU 60°) ISO 2813 Gloss (70-85) Flash point ISO 3679 Method 1 30°C Density calculated 1.4 kg/l Dry film thickness 50-100 microns Wet film thickness 80-160 microns Theoretical spreading rate 12.6-6.3 sqm/l Color: Clifton Sand</p> <p>Scope of Work: Mechanical cleaning of surfaces using power brush to remove rust, dirt, and loose material Ensure uniform coating, coverage, and smooth finish on all exposed surfaces All works to be carried out safely without damaging the installed structures</p>		M2	110		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016585

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

19.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.07	<u>Fabrication of Miscellaneous Items.</u> Arrangements, handling and utilization of 12 inch and 10 Inch Dia MS Elbow 90 degree as part of the service scope for modification works-<> ,<-> including vendor responsibility for availability during execution.		EA	4		
1.08	<u>Fabrication of Miscellaneous Items.</u> Arrangements, handling and utilization of 12-inch MS Bling Flange class 150 as part of the service scope for modification works, including vendor responsibility for availability during execution.		EA	1		
1.09	<u>Fabrication of Miscellaneous Items.</u> Arrangements, handling and utilization of 12-inch MS Flange Sorf class 150 as part of the service scope for modification works, including vendor responsibility for availability during execution.		EA	3		
2	<u>Miscellaneous Steel structure</u> Fabrication, supply and installation of MS safety railing on the roof of Tank 2602 for safe access during inspection, operation and maintenance activities. Technical Details: Main posts and handrail made of MS square section 50 x 50 mm Toe guard / intermediate members made of MS flat bar (50 mm to 100 mm width) Layout and spacing as per site requirement and safety practices API 650 Compliance: All welding, fixing and attachment of safety railing to the tank roof shall be carried out in accordance with API 650 # Welded Tanks for Oil Storage, ensuring: No adverse impact on tank roof structural integrity Compliance with API 650 requirements for attachments, welding and workmanship Tank tightness and mechanical integrity remain uncompromised	Faqirabad (Depot)	KG	1,000.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016585

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	19.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
3	<p>Miscellaneous Steel structure</p> <p>Fabrication, supply and installation of MS splash plates for Tank 2602 to minimize product splashing during tank filling operations and to protect the tank shell and internals.</p> <p>Technical Details: Splash plates to be fabricated from mild steel, 6 mm thickness Size and shape to suit tank nozzle arrangement and site conditions Proper positioning to effectively control product splash without obstructing normal tank operation or inspection access API 650 Compliance: All design, fabrication, welding and installation of splash plates shall be carried out in accordance with API 650 # Welded Tanks for Oil Storage, ensuring: Compliance with API 650 requirements for tank attachments and appurtenances Welding and fixing practices do not adversely affect tank shell / roof integrity Tank tightness and mechanical integrity of Tank 2602 remain uncompromised</p> <p>Terms & Conditions</p> <ol style="list-style-type: none"> Contractor shall execute all works strictly as per the Job Description, Technical Specifications, and API / PSO standards. Any deviation from approved drawings, specifications or scope must be approved in writing by PSO Engineer. All works to comply with API, OSHA, ISO, and PSO HSE standards. Material, welding, scaffolding, and installation to follow PSO approved procedures. Contractor must provide personal protective equipment (PPE) to all personnel. Scaffolding, lifting, and working at height must comply with PSO HSE and local regulations. Contractor shall ensure zero compromise on safety, including safe access, fall protection, and fire prevention measures. All work shall be inspected and approved by PSO Quality Engineer / 	Faqirabad (Depot)	KG	1,500.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016585

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	19.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>Supervisor.</p> <p>9.,Contractor to maintain records, inspection reports, and certifications of materials and work. Any defective work shall be rectified at contractor#s cost.</p> <p>10.,Contractor shall coordinate with PSO Operations Team to schedule work without disrupting tank operations. Access to site, tanks, and facilities is controlled by PSO Permit to Work (PTW) system.</p> <p>11.,All materials, tools, and equipment shall be as per PSO approved specifications. Contractor is responsible for safe handling and storage of materials on site.</p> <p>12.,Payment will be made after completion of work and PSO inspection.</p> <p>13.,Any penalties or deductions due to delay, non-compliance, or safety incidents will apply as per contract.</p> <p>14.,Contractor shall dispose of waste, debris, and hazardous material as per PSO rules and environmental regulations. Work area shall be cleaned and restored after completion.</p> <p>15.,Contractor shall maintain insurance for personnel, equipment, and third-party liability during execution. Any damage to PSO property due to contractor negligence shall be repaired or compensated by contractor.</p> <p>Documentation & Reporting</p> <p>16.,Contractor shall submit daily progress reports, material usage, inspection records, and HSE compliance certificates.</p> <p>17.,All work completion must be signed off by PSO Engineer / In-charge Depot before release of payment.</p> <p>18.,The job includes labor, transportation and all material charges.</p> <p>19.,All Govt. taxes and GST are included in the above-mentioned rates.</p> <p>20.,PENALTY: In the event of Contractor's/Supplier failure to deliver the Services/Goods within the time mentioned in purchase order/service order, PSO shall be entitled to deduct from his bills/outstanding payments or other works done by him for PSO or from any amount due to him by PSO a sum of Rs. 0.1% of Purchase Order/Service Order value per day as liquidated damages for the period which the said services/material remains incomplete or fails to pass the quality tests subject to a maximum 10% of work order amount to be recovered from the contract on his default.</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	7
RFQ No	OP19650SI	
DATE	30.04.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016585

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	19.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provision of Hand/ Safety Railing on Roof Top of Vertical Storage Tank # 2602 and Modification of Venting Equipments on Tanks # 2602,2603,2604 ,2605,2606 at Faqirabad Depot North

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.