



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016820

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	20.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Deboxing of 5m dia 35m len Tank</u>	<u>New Faisalabad (Depot)</u>				
1.01	<u>Bolting/Unbolting of pipe joints</u> Unbolting of Tank Roof Manholes Job includes Unbolting of 24" dia Manholes of Tank Roof. Scope of Work: ----- Job includes application of anti-rust spray before unbolting activity and use of non-ferrous tools for unbolting activity. Contractor to arrange non-ferrous tools such as brass tools, etc. The job also includes the lifting of man hole and removing it from tank and placing it nearby.		EA	6		
1.02	<u>Bolting/Unbolting of pipe joints</u> Removal of sump line valve includes Unbolting of 4" dia line of Tank. Scope of Work: ----- Removal of sump line valve after unbolting it. The job includes the unbolting of both valve flanges. Job includes application of anti-rust spray before unbolting activity and use of non-ferrous tools for unbolting activity. Contractor to arrange non-ferrous tools such as brass tools, etc.		EA	3		
2	<u>Installation of Blind Plates</u>	<u>New Faisalabad (Depot)</u>				
2.01	<u>Tank Capacity Plates</u> Positive Isolation of Tank Pipelines Providing and installation of Spectacle Blinds on Tank's 1 nos x 10" dia Delivery Pipelines.		EA	3		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016820

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	20.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.02	<p>Job to be done prior to degassing and opening of manholes.</p> <p>Scope of Work (for item 2.001 to 2.002):</p> <p>Unbolting of connecting flange joint. Scope of work also includes providing and installation of spectacle blinds, and application of anti-rust spray before unbolting activity and use of non-ferrous tools for unbolting activity.</p> <p><u>Tank Capacity Plates</u></p> <p>Positive Isolation of Tank Pipelines Providing and installation of Spectacle Blind on Tank's 1 no. x 4" dia Return Pipeline. Job to be done prior to degassing and opening of manholes. Scope of work as given in item 2.001.</p>		EA	3		
3	<u>Lighting and Ventilation</u>	<u>New Faisalabad (Depot)</u>				
3.01	<p><u>Installation of LED Lights</u></p> <p>**EA = Days**</p> <p>Explosion Proof Lights in Tank</p> <p>Installation of explosion proof LED Lights (at least 3 Nos) to obtain total 1000 LUX. Vendor will also arrange all the cables, pipes, explosion proof D.B, earthing of DB, lights required for job completion.</p> <p>NOTE: Payment is subject to number of days lights are used inside tank.</p>		EA	18		
3.02	<p><u>24 Inch dia Industrial Exhaust Fans</u></p> <p>*EA = Days**</p> <p>Degassing of Tank Job includes degassing of tank of diameter 63.5m with one explosion proof exhaust fans/blowers. 1 No. x 24" explosion proof exhaust fan to be installed on roof manhole.</p> <p>NOTE: Payment is subject to number of days explosion proof fans are</p>		EA	18		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016820

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

20.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
4	used. <u>Retrieval of Product</u>	<u>New Faisalabad (Depot)</u>				
4.01	<u>Product Transfer Operation</u> **MTO = JOB** Retrieval of product from bottom and centre sump with minimum 1" dia Ex-proof pump. Product will be retrieved by suction end of pump into the centre sump line and pump outlet to be connected to Receipt pipeline of another tank or tank lorry.		<u>MTO</u>	3.000		
5	<u>Removal of Sludge</u>	<u>New Faisalabad (Depot)</u>				
5.01	<u>Supply and Installation of Pump.</u> Retrieval of product and sludge removal from bottom and centre sump with minimum 1" dia ex-proof Pump. Sludge will be removed from tank and shifted to metallic drums (upto15 Drums) and if quantity exceeds or not manageable by Drums then contractor will excavate the pit as per requirement and will install and lay two layers of polyethene to prevent contamination of soil.		<u>EA</u>	15		
5.02	<u>Providing and replacing miscellaneous pa</u> Supply of 15 nos. metallic drums for storage of sludge. NOTE: Payment is subject to the number of drums filled. In case of excavation of pit, the total item amount will be paid.		<u>EA</u>	15		
5.03	<u>Shifting & stacking of filled drums</u> Job includes shifting of sludge filled drums within the terminal as per the specification of terminal engineer / terminal in charge. NOTE: Payment is subject to the quantity of drums needed for sludge storage to be shifted.		<u>EA</u>	15		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016820

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	20.05.2026	BY (Time)	
--------------	------------	--------------	--

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
6	<u>Internal Cleaning of Tank</u>	<u>New Faisalabad (Depot)</u>				
6.01	<u>Mechanical Cleaning tank</u> Manual cleaning to be done using labour and high-pressure water-jet nozzle with independent of source of water and relevant attachments, as needed to remove contaminants. Job is subject to the approval of terminal engineer. Note: Since tank are semi buried and in cylindrical shape Internal Area for cleaning will be including complete Bottom and max accessible height of shell.		EA	1,800		
7	<u>Box-up of Tank</u>	<u>New Faisalabad (Depot)</u>				
7.01	<u>Bolting/Unbolting of pipe joints</u> Bolting of Tank Roof Manholes Job includes Bolting of all 24" dia Manholes of Tank Roof after placing them in their original position and after completion of integrity of tank. Job also includes supply and installation of non-asbestos gasket sheet 2mm thick. Scope of Work (for Item 7.001 to 7.003): Job includes application of anti-rust spray before bolting activity and use of non-ferrous tools for bolting activity. Contractor to arrange nonferrous tools such as brass tools, etc.		EA	6		
7.02	<u>Bolting/Unbolting of pipe joints</u> Bolting of Tank pipeline Job includes Bolting of 4" dia return pipeline and sump pipeline after		EA	6		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
 Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
 SAP No.6100016820

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	20.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
7.03	<p>placing of valve to its original place and removal of blind from return pipeline.</p> <p>Job also includes supply and installation of non-asbestos gasket sheet 2mm thick. Scope of Work as given in item no. 7.001</p> <p><u>Bolting/Unbolting of pipe joints</u></p> <p>Bolting of Tank delivery pipeline</p> <p>Job includes Bolting of 10" dia pipeline of delivery valve after removal of blind, the job should be done after the completion of tank integrity.</p>		EA	3		
8	<p>Job also includes supply and installation of non-asbestos gasket sheet 2mm thick. Scope of Work as given in item no. 7.001</p> <p><u>Mobilization and Demobilization</u></p>	<u>New Faisalabad (Depot)</u>				
8.01	<p><u>Transportation / Labour Charges</u></p> <p>Job includes Mobilization and Demobilization of equipment and personnel to site as per requirement of job / instructions of terminal engineer or in charge.</p> <p>TERMS and CONDITIONS: =====</p> <ol style="list-style-type: none"> All services, tools, materials to be provided by the contractor. Non-Ferrous tools to be used for bolting and unbolting works. All the transportation, accommodation is responsibility of contractor paid by the contractor and rates will be inclusive of all taxes. Tank will be handed over to vendor upon its availability. Tank will be handed over to contractor after product level is reached to dead stock(>,<) and operations department will confirm it. Contractor will ensure the positive isolation is done before unboxing of tank. Contractor will be providing detailed Work Method Statement, Emergency Response Plan, Risk assessment. Relevant Permit to works will be obtained before start of work. WMS (Work Method Statement should be 		JOB	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016820

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

20.05.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>included but not limited to the following)</p> <p>i. Ventilation Requirements for Confined Spaces: Ventilation is a way of making sure employees have access to enough breathable air. Any obstruction to the flow of oxygen could impact the health of persons inside the confined space in a matter of minutes or less. It may cause dizziness, shortness of breath, increased heart rate, headaches, or restlessness.</p> <p>ii. Under OSHA regulations, you must provide the following safety measures:</p> <p>"Oxygen (O2) levels need to stay between 19.5% and 22%."</p> <p>"Gases and flammable vapours must be kept below 10% of their lower explosive limit (LEL)"</p> <p>"Potentially toxic materials must stay below their personal exposure limit (PEL) levels, or immediate danger to life and health (IDLH) levels if you're using anything less than supplied air respirator protection.</p> <p>Monitoring Workplace Workspace needs to be continuously monitored in order to find out if additional ventilation is needed or if the levels become a hazard. A quality Gas Monitor must be used to test the air at all levels, including at the bottom, middle, and top of the space.</p> <p>Use a 4-Gas Monitor that can measure hydrogen sulphide, carbon monoxide, oxygen, and the lower explosive levels of combustible gases. The attendant / buddy system has specific responsibilities during a confined space entry.</p> <p>These includes:</p> <p>"Attendant should remain outside the space during entry operations - Do Not Leave the space unattended."</p> <p>"The Attendant should have a clear knowledge of hazards-existing & potential and able to use air monitoring equipment to keep a close watch on the atmospheric conditions inside the confined space and communicate changes."</p> <p>"Maintain communications with the entrant"</p> <p>7. Contractor will ensure availability of PPEs as per Job Hazard Analysis including Third Party Inspected SCBA, Gas Masks, Nitrile and Cotton</p>					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	7
RFQ No	OP19575AAR	
DATE	20.05.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016820

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	20.05.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Tank Cleaning for Internal Inspection as per API 653

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	<p>Gloves, Long Rubber Boots, Safety Shoes, Googles etc.</p> <p>8. Contractor will depute skilled and qualified Site Supervisor (B.E / D.A.E), HSE Supervisor with HSE certifications (IOSH/NEBOSH), and Confined space entry attendant with specialized certification for each tank. All deputed staff must have experience in relevant job and Oil & Gas industry.</p> <p>9. Contractor will provide third party certification of equipment to be used where applicable.</p> <p>10. Contractor will ensure earthing of equipment to be installed. Earthing test will also be carried out for equipment installed and storage tank as well. Work will be carried out if results are satisfactory as per PSO Policy.</p> <p>11. Contractor will arrange enough F.Es to be placed at site. 12. The contractor will arrange all accessories required for proper cleaning of the tank including saw dust, wipers etc.</p> <p>13. Any product losses/ contamination due to improper collection pit / polythene sheet shall be borne by the contractor as appropriated by Location In charge.</p> <p>14. Contractor should maintain housekeeping of the worksite during progress of work and shall clear and remove all surplus materials and rubbish from site after completion of job as per instruction of Engineer In charge.</p> <p>15. Project delivery date is of 1 year from PO issuance date due to uncertainty of tank availability. After intimation from terminal engineer, vendor is to mobilize within 2 day and completion time for all activities will be 12 days after handing over of tanks.</p> <p>16. If the Contractor fails to complete the work within time stipulated, the Engineer In charge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Work Order per day per the time delayed and subject to maximum 10% Value of P.O.</p> <p>17. For all explosion proof and intrinsically safe items and also any other safety items, vendor will be required to submit valid certificates.</p>					