



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RC-19695AS	
DATE	01.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100016877

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	16.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ **PO/DD NO.** _____

Title: Provision, Installation, Testing <(>&<) Commissioning of Fire Hydrant <(>&<) Foam System at Capri FS, F-7 Markaz, Islamabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Fire Fighting System at Capri FS,</u>	<u>PSO House</u>				
1.01	<u>SUPPLY OF FIRE FIGHTING EQUIPMENTS SYS.</u> Fire Fighting System (Complete) All works shall be executed strictly in accordance with CDA approved drawings including Fire Fighting Layout Drawings (CAPRI REVISED FF PLOT NO.1, F-7 PSO PUMP # Nov 27, 2024) and BOQ (CGS Fire Fighting BOQ). Description: Supply, installation, testing & commissioning of complete fire fighting system as per approved CDA drawing, CDA approved brand and CDA approved BOQ: System includes but is not limited to: 1.,,Fire hydrant and sprinkler system complete in all respect 2.,,Fire alarm system 3.,,Fire Safety equipment Scope includes piping network, valves, hydrants, hose systems, foam system, pumps, accessories, and all allied works. Testing & Commissioning Testing shall be performed as per NFPA standards and consultant-approved drawings and BOQ documents. 1.,,Hydrostatic testing 2.,,Pump performance test 3.,,Flow & pressure test 4.,,Foam discharge test 5.,,Final commissioning Final completion from CDA against CDA letter # CDA- Dir (E<(>&<)DM)/EAP (C-203/2025/60 dated 21-02-2025 is included in scope of contractor).		<u>JOB</u>	1		
1.02	<u>UNDER GROUNG WATER TANK</u> Underground Water Tank (20800 US Gallons UGWT) Execution shall be as per approved structural drawings (SA-PSO Capri UGWT OHWT # Drawings) and Bar Bending Schedule (SA-PSO Capri UGWT OHWT #		<u>EA</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RC-19695AS	
DATE	01.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100016877

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED		
	ON (Date)	16.06.2026	BY (Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %** Rs. _____ PO/DD NO. _____

Title: Provision, Installation, Testing <(>&<)> Commissioning of Fire Hydrant <(>&<)> Foam System at Capri FS, F-7 Markaz, Islamabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	<p>BBS).</p> <p>Description: Construction of RCC Underground Water Tank including excavation, PCC<(>,<)> RCC works, reinforcement, waterproofing, piping connections, and all associated works including electrical plumbing work. Execution shall be as per approved structural drawings (SA-PSO Capri UGWT OHWT # Drawings) and Bar Bending Schedule (SA-PSO Capri UGWT OHWT # BBS). Job also include removal of existing pavers and relaying of the same as per PSO approved drawings and standards.</p> <p>Scope Clause: Execution shall be as per approved structural drawings, Bar Bending Schedule (BBS), and consultant specifications. All necessary materials and activities required for complete functionality are deemed included.</p> <p>1 EA = 1 JOB</p> <p>Overhead water tank Overhead Water Tank (OHWT)</p> <p>All works shall be carried out as per approved structural drawings (SA-PSO Capri UGWT OHWT # Drawings) and design notes.</p> <p>Description: Demolishing of Existing Structure Construction of RCC Overhead Water Tank including staging, structural works, internal coating, piping connections, and all associated works. All works shall be carried out as per approved structural drawings (SA-PSO Capri UGWT OHWT # Drawings) and design notes. Construction of Outside Walls (brick work + Plastering work), complete in all respect as per direction of Engineer In charge (approx. size 29'x 10' x 15')</p> <p>Scope Clause:</p>		JOB	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RC-19695AS	
DATE	01.06.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100016877

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.06.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provision, Installation, Testing (>&<) Commissioning of Fire Hydrant (>&<) Foam System at Capri FS, F-7 Markaz, Islamabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	<p>All works shall be carried out as per approved design drawings and structural specifications provided by the consultant.</p> <p><u>Refurbishment of Pump Room</u> Design and Construction of Pump room</p> <p>Design and fabrication of temporary structure for firefighting room complete in all respect up to satisfaction of Engineer In charge.</p> <p>----- NOTES:</p> <p>1. All work to be completed as per the guidelines of PSO Engineer and provided drawings. 2. The project to be completed within 90 days after the issuance of work order/site handover.</p>		<u>JOB</u>	1		