



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	5
RFQ No	RF19788SI	
DATE	11.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017369

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

28.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet and False Ceiling at Razi SS(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>M&R Works at NVR0s</u>	<u>PSO House</u>				
1.01	<u>22 SWG CGI SHEET FOR CANOPY ROOF</u> Replacement of Canopy Top Sheets Job includes removal of old canopy top GI Sheets and providing, fabrication and fixing of corrugated G.I. continuous sheet, 22 SWG (at least 30-micron powder coated) including overlaps, crown and edge elements, expansion joints and making openings. Also included are fixings such as galvanized steel J -bolts, nuts and washer or self-screw as per site requirement. Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Bending sharing of sheet should be as per automatic machine. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft. 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.		<u>SET</u>	3,600		
1.02	<u>16 SWG GI SHEET, GUTTER & CLADDING</u> Providing Fabricating and fixing in position on existing structure, 16 SWG plain GI Sheet drain water channel including self-tapping screw or galvanized M S J-Bolts, Rubber washer(>,<)> Cup washer and Nuts etc. Joining each other rivet and Silicon filing in joins, making opening for drainage and fixing UPVC drain cover. Note:		<u>SET</u>	600		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	5
RFQ No	RF19788SI	
DATE	11.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017369

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

28.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet and False Ceiling at Razi SS(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises. 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft. 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material. 22 SWG CGI SHEET FOR CANOPY ROOF		SET	600		
1.04	Providing and Laying of 22 Swg(at least 30 micron powder coated) Plain top sheet on fascia complete in all respects. Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises. 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material. P/L UPVC PIPE 4" DIA, CLASS-D		RET	800		
1.05	Providing and Installing 4" Dia<(>,<,>) local made UPVC drain pipe complete with all fitting as per site requirements hanged with MS hanger/support for drainage of Rain water, job also includes complete with cutting, jointing, <(>&<) wastage etc. Complete in all respect. Water Proofing		SET	3,600		
	Providing services for high elastomeric water proofing of canopy top sheet after complete replacement. providing and applying of two coats of sealing flex after complete cleaning and removal of dust from the sheet and apply two coats. Sealing flex is water based modified acrylic / synthetic rubber emulsion.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	5
RFQ No	RF19788SI	
DATE	11.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017369

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

28.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet and False Ceiling at Razi SS(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	Job also includes complete sealing of the holes and opening and ensure proper workmanship. Brand: Ultra Seal flex or approved equivalent. Unit of measurement is SFT. <u>INSTALLATION FALSE CEILING</u> "Replacement of False Ceiling Providing and fixing false ceiling under canopy with 4" wide 26 SWG pre-painted (white color) steel sheet strips with no perforations and maximum length of 12 ft. hinges, bolts and all necessary fittings including soffit return of 14 swg for false ceiling finish of approved shades to be suspended with metal adjustable suspension system as per standard. Complete In all respect as per direction of engineer incharge. Dismantling and stacking of old False Ceiling at site is also included in the give rates. Job also includes removal and re-installation of canopy lights with wiring including installation of additional canopy lights. Additional canopy Lights to be provided by PSO. Job further includes removal and installation of canopy fascia (If required) blue bars, rewiring of blue bars arrangement, etc. complete in all respect while execution of work." UNit: SFT TERMS AND CONDITIONS: 1., Contractor will be responsible for the removal / disposal Of debris outside retail outlet premises as per the instruction of the engineer incharge 2.<(>,<)>Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. 3.<(>,<)>The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment<(>,<)> undertake steps to mitigate risk and work planning for the high		SET	3,600		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	5
RFQ No	RF19788SI	
DATE	11.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017369

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

28.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet and False Ceiling at Razi SS(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves<(>,<)> Helmets, Goggles, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. 4.<(>,<)>The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 5.<(>,<)>All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 6.<(>,<)>Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. 7.<(>,<)>Wherever applicable, contractor is bound to engage certified / licensed electrician for electrical works. 8.<(>,<)>Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall<(>,<)> thunderstorm, etc.). For any special case, approval from DE will be required and work will be performed under supervision of DE. 9.<(>,<)>The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 10.<(>,<)>The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in #no smoking# area, etc) during work.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	5
RFQ No	RF19788SI	
DATE	11.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017369

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

28.07.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet and False Ceiling at Razi SS(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Contractors will also ensure proper work planning and risk assessment prior to start of work. 11.<(>,<)>The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 12.<(>,<)>The contractor shall indemnify PSO, its offices<(>,<)> employees, agents and representatives from and against all losses, costs, penalties, fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by this contract. 13.<(>,<)>Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO. 14.<(>,<)> All material, tools, labor, etc. to be provided by the Contractor. 15.<(>,<)>Quoted rates are inclusive scrap materials. 16.All material, tools, labor, etc to be provided by the Contractor. 17.The rates are inclusive of all Govt. taxes, transportation<(>,<)> loading/unloading, labor, etc 18.The payment is subject to inspection / satisfaction of Engineer Incharge. 19.Work completion time is 45 days after site handed over to vendor 20. It is mandatory that the Contractor must visit the Site in order to understand / ascertain scope of work and site conditions prior to quoting rates in Tender. 21. Quantity may be use in other outlets as per instruction of divisional engineer. 22- All scrap material old GI sheet, drain channel etc, debris to shift/dispose off from outlets is contractor responsibility.					