



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	2
RFQ No	OP19615SIR	
DATE	20.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017476

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

04.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Supply and Installation of Terminal Signage at Machike Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>SIGNAGE FOR DEPT/ INSTALLATION</u>	<u>Machike</u>				
1.01	<u>Signage Miscellaneous</u> Raised Building Facia raised Signage Providing services with materials for provision and installation of 30 ft x 5 ft ACM sheet signage with 5 mm,, thick acrylic-moulded weather proof blue light for front-lit 3D acrylic moulded letters, the top of signage will be,, 7 feet high form roof level, it also includes provision of moveable hinge type assemblies for maintenance,, purposes i-e provision of windows/doors for maintenance etc with 18 SWG GI Sheet) & suitable steel to withstand,, with heavy storms considering the area requirements. LED back-lit modules (40 lumen light source). Lighting,, philips or equivalent. Rear support with tubular structure and sheet backing. Detachable for maintenance LED,, back lit modules source light 40 Lumen. Back to be supported Tubular structure and sheet. ,,	<u>(Inst.)</u>	<u>JOB</u>	1		
1.02	<u>Signage Miscellaneous</u> 6 feet dia Vinyl PSO logo Providing services with Flex with laminated text of 6 feet dia vinyl PSO logo with vinyl back weather proof LED. lighting Modules. Back-lit with Weather proof LED modules. Outer ring: FRP round circle Thickness 6mm with mild steel support structure etc		<u>JOB</u>	1		
1.03	<u>HOARDING SIGNAGE</u> Supply of HSE signage in various sizes as required by the Terminal Engineer. Material: PVC vinyl stickers with high-intensity prismatic reflective sheeting. The scope includes letters, pictograms, and symbols in all required colors as per HSE standards and site requirements.,,		<u>M2</u>	60		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	2
RFQ No	OP19615SIR	
DATE	20.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017476

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

04.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Supply and Installation of Terminal Signage at Machike Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2	Supply, fabrication, and installation of terminal signage including building fascia signage, PSO logo signage, and HSE safety signage in various sizes. The work includes provision of reflective PVC vinyl stickers, LED back-lit modules, acrylic letters, and fabrication/installation of required steel support structures complete with painting and fixing as per site requirements and instructions of the Terminal Engineer. Miscellaneous Steel structure Steel Structure for Supporting Signage Providing services with material for fabrication, cutting, grinding, bending, welding, (>&<) erection as per site requirement (>&<) size of signs with steel structural members like consisting of hollow pipes, solid/round bars, MS Plate/Angle/Channels etc including any modification required for fixing on gantry with rawal bolts, U-Clamps etc. The job also includes surface preparation with mechanical tools, application of red oxide primer (50 micron, two coats), enamel paint (50 micron, two coats). Complete in all respects as per site conditions and instructions of site incharge. Providing services with material for fabrication, cutting, grinding, bending, welding, (>&<) erection as per site requirement (>&<) size of signs with steel structural members like consisting of hollow pipes, solid/round bars, MS Plate/Angle/Channels etc including any modification required for fixing on gantry with rawal bolts, U-Clamps etc. The job also includes surface preparation with mechanical tools, application of red oxide primer (50 micron, two coats), enamel paint (50 micron, two coats). Complete in all respects as per site conditions and instructions of site incharge.	Machike (Inst.)	KG	300.000		