



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	1
RFQ No	RC-19804AS	
DATE	22.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017480

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

06.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repairing <(&<) Maintenance work of Driveway at Nisar F/s DFA BWP Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Driveway Repairing at Nisar F/s DFA</u>	<u>PSO House</u>				
1.01	<u>Asphalt Concrete Carpeting</u> Removal of existing bitumen(asphalt)road surface from the sides of the petrol pump area, including safe cutting<(>,<)> dismantling, loading<(>,<)> and disposal through mechanical means. The removed material shall be transported and dumped at an approved waste disposal site outside the petrol pump premises<(>,<)> strictly in accordance with safety regulations and government guidelines.		<u>FT2</u>	12,000		
1.02	<u>Installation of 80 MM Pavers</u> Providing and laying/fixing of new 80mm thick paver blocks (PSO standard), including submission and approval of sample from the Engineer prior to installation. Work includes proper surface preparation, excavation to required depth, laying of compacted sub-base with approved mixed material, two layers of sand filling, leveling, and mechanical compaction. Pavers shall be properly aligned, joint-filled, and compacted to achieve a firm and even finish as per PSO company standards. Terms & Conditions: Please note that all the work done and task completed within 90 days, after the issuance of Service Order**		<u>M2</u>	11,250		