



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	2
RFQ No	OP-19858AM	
DATE	27.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017601

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provide Service for Laying of 80 mm thick CC pavers in front Lube Ware House at Quetta Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Services for laying of Pavers</u>	<u>Quetta</u>				
		<u>(Depot)</u>				
1.01	<u>Pavers</u> Providing services for Dismantle, Cutting, removing of existing cc/gravel/stone as per required in front of Lube ware house area for laying of pavers.		<u>M2</u>	370		
1.02	<u>Pavers</u> P/L OF 80 MM THICK PAVER WITH SUBBASE Providing and Laying Precast Concrete Pavers of size 200 mm x 100 mm x 80 mm (as per site requirement): Providing and laying precast concrete pavers of size 200 mm x 100 mm x 80mm thick (as per site requirement) having a minimum compressive strength of 7000 psi, including all necessary materials, labor, tools, and equipment to complete the work as specified and directed by the Engineer In-Charge. Scope of Work Includes; - Preparation of Base/Sub-base: Laying of river sand or khaka up to the required level; compaction of the base/sub-base using a minimum 10-ton roller or plate compactor to achieve proper surface stability and levelling. - Bonding Layer: Provision and spreading of fine sand or other approved bonding materials for levelling and bedding purposes. - Laying of Pavers: Proper laying of paver blocks in the required pattern, ensuring tight joints and uniform alignment. - Joint Filling and Finishing: Filling of joints with fine river sand/khaka and finishing of the surface to achieve a neat, level, and		<u>M2</u>	370		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	2
RFQ No	OP-19858AM	
DATE	27.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017601

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

11.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provide Service for Laying of 80 mm thick CC pavers in front Lube Ware House at Quetta Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	compact appearance Pavers Providing and laying lean concrete 1:2:4 mix ratio using S.R. Cement, approved quality 3/4" max: size graded crush and fine aggregate (Hill sand) of required properties including form work installation & removal, mixing, transporting, placing, compacting, finishing and curing etc. Complete in all respects total(1.5 m3)=(60 m2)with 50 to 70 mm thickness, the specified area is separate from laying of pavers. TERMS AND CONDITIONS: 1) All labor, tools, material, transportation to be provided by the contractor. 2) All HSE standards to be followed by the contractor 3) PSO reserve right to impose penalty on late execution of job. 4) The Contractor and his staff will strictly abide by the HSE/security rules of the company & it is the responsibility of the contractor to provide his staff PSO approved PPEs and while working inside the depot they are bound to use it as no worker will be allowed to work without the use of PPEs. 5) Work completion time will be 30 days after issuance of work order. 6)Quantities against various items are estimated and may increase or decrease, however payment shall be made as per actual verified quantities. 7)If the Contractor fails to complete the work within time stipulated, the Engineer In charge will be entitled to deduct from his bills for a value of .10% of work order per day and subject to maximum 10% value of P.O. 8)Job is subject to inspection of In charge Engineer. 9) All the Govt: Taxes are included in above rates. **All the work done and task completed within 30 days, after the issuance of Service Order**		M2	60		