



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Remodelling of Masjid E Khizra Fs, Khi</u>	<u>PSO House</u>				
1.01	<u>STEEL CANOPY CONVERSION</u> SCOPE OF WORK Remodeling / Renovation of existing building including and allied civil and electrical and drainage works. Remodeling / Modification of existing canopy including raising/ increase the height of canopy along with all associated steel structural works<(> ,<)> electrical, false ceiling and top sheets as per approved drawings and direction of Engineer Incharge. Allied electrical works complete in all respect<(>,<)> including dismantling, shifting, reinstallation, testing and commissioning as per site requirements. Removal of Existing tank and Installation of new UGFST with allied decantation, venting, UPP pipeline etc, complete in all respect. Upgradation of driveway including paver replacement, construction of island, cutoff drain and approaches to connect with main road for entry and exit of vehicles. Repairing and shifting of Existing tyre shop with allied electrical works. Repairing of Existing Boundary Wall. MODIFICATION & RAISING THE HEIGHT OF EXISTING STEEL STRUCTURE CANOPY: Services required for modification & increasing / raising the height of	<u>SFT</u>	1,200			



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Existing Canopy upto 20ft and provision of solar system. Supply & Installation of False ceiling, top sheets, drain channel for rain water, fabrication and installation of steel structure and allied work for proposed canopy upgradation project mentioned in RFQ<(>,<)> layout and detail drawings, site requirements complete in all respect. This job also includes the following scope but not limited to: 1- Removal of Existing false ceiling, drain channel, pipes & Top sheets <(>,<)> water proofing, or any other material completely required for proposed upgradation of canopy as per site requirement, revised drawings based on design vetting and directed by Engineer Incharge. Scope also includes Removal of existing signage, blue bars, ACM<(>,<)> spreaders, electrical wiring, and LED lights completely and stacking safely and shifting of all material in PSO depot/ terminal as directed by Engineer Incharge as part of item scope without any additional cost. Installation of Signage which includes blue bars, ACM, spreaders, safety signage will be installed by separate contractor (Signage contractor). 2- Vetting of the existing canopy structure which includes the assessment of existing canopy steel structure and foundation for the raising the height of existing canopy upto 20ft and provision of solar system. The vetting part will be covered/done through a sperate line item mentioned in RFQ. The execution of canopy will be carried out as per consultant revised drawings and report. 3- For modification of existing canopy existing steel structure will be used after repair, fabrication, rectification/ modification and cleaning, painting as per consultant report and revised drawings.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	New bolts/ anchor bolts will be used in entire canopy. Old or damaged will be replaced completely as part of item scope without any additional payment. In case of any additional steel structure requirement the work will be carried out by the contractor accordingly and the new / additional material will be paid through a separate line item in Kgs mentioned in RFQ subject to the prior approval from PSO Site Incharge. Modification of existing canopy which includes lifting / increasing the height of existing canopy as per revised drawings (with increased height upto 20ft and provision of solar) based on drawings approved by consultant after vetting the design. INSTALLATION OF STEEL STRUCTURE CANOPY: Fabrication, Installation & Erection of Steel Structure Canopy members as per Layout, drawing and in accordance with approved shop drawings<(> ,<)> including all trusses, purlins, runner, columns, studs and anchor bolts. All steel sections and plates etc. shall confirm to ASTM A-36 steel. All bolts should confirm to ASTM-A 307- "Low Carbon Steel" or to ASTM-325 -High Strength Bolt shall be used for structural steel joints <(>,<)> including suitable nuts and plain hardened washer. The length of bolts shall be in 1/4 of an inch variation. In structure the bolt shall extend 1/4 of an inch beyond the nuts. All welding electrodes shall confirm to the latest edition of American Welding Society and ASTM A233. The electrodes should have a minimum yield strength of 60,000PSI and ultimate strength of 73,000 psi. The job including mechanical cleaning of all steel structure members by using hand tools up to the standard of SSPC-SP10 and supply and application of red oxide primer to a dry film thickness of 50microns in minimum of two coats. Surfaces to be cleaned with non-fluffy rags before applying primer followed by two coats of					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	industrial enamel paint of the same make to a DFT of 50 microns in a minimum of two coats complete in all respect as per drawing specification and instruction of Engineer Incharge. Note: Enamel paint shall be used/ applied and for color and shade contractor will take prior approval. All structure members shall be painted before erection and finally touched after erection for required finishing. FALSE CEILING: Providing and fixing false ceiling under canopy with 4" wide 26SWG pre-painted steel sheet strips with no perforations and maximum length of 4 ft. hinges, bolts and all necessary fittings I/C soffit return of 16SWG for false ceiling finish of approved shades to be suspended with metal adjustable suspension system as per standard, complete in all respect as per direction of Engineer Incharge. GI CORRUGATED SHEETS: Providing, Fabrication and fixing of corrugated powder coated (minimum 30 micron) G.I. continuous sheet 22SWG including overlaps, crown and edge elements, expansion joints and making openings. Also included are fixings such as galvanized steel J-bolts, nuts and washer. Complete as per drawing and specifications Minimum Overlapping of sheets will be approximately 6-inches on all side of sheeting. Crown will be of plain G.I. Continuous sheet, 16 SWG including overlaps minimum 6-inches or as per drawings, for rain water gutter laid over purlins, Fascia sheets fixed properly in a slope making openings for rain water disposal. Also included are fittings such as galvanized steel J bolts, nuts and washer etc. Complete as per drawing and specification. PLUMBING WORK: Providing, fabrication and installation of 4" dia UPVC rain water drainage pipe and 2.5" dia UPVC pipe for electrical cable fixed inside steel columns with 3"Dia flexible spiral wound rubber pipe, including all types of bends and other fixing arrangements etc. complete as per					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.02	drawings and specification and as directed by the Engineer Incharge. Note: All dismantled / un-used material Steel structure, wiring, LED lights, signage, sheets will be stacked at site safely and further shift in PSO depot/ terminal as directed by Engineer Incharge. <u>PUMP ISLAND</u> CONSTRUCTION OF PUMP ISLAND: Construction of Pump Island as per drawings, site complete in all respect and as directed by Engineer Incharge. This job includes the following scope Providing and laying Plain cement concrete (PCC) where required using approved quality 3/4" maximum size graded crushed aggregate, stone or gravel with approved quality hill sand including all formwork, rodding, vibrating, levelling and curing etc. -,3"thick Lean concrete 1:4:8 -,PCC 1:3:6 in required width and height as per drawings. Providing opening/ pocket for product pipeline (UPP 54mm dia)<(>,<)> electrical cables and drain pipe as per drawing and site requirements. Providing and Installing in place Porcelain Tiles of PSO approved shade and colour i.e. grey in colour over 1:3 cement mortar, grouting the joints, including all beds and anchoring tiles to be laid in approved pattern as per instruction of Engineer Incharge and PSO standard. Providing, Fabrication, Installation, of MS-Angle 1 1/2" x 1 1/2" x 1/4"tk around the island with red oxide primer 50 microns (DFT) and finally enamel paint 50 microns (DFT) complete as per drawings & PSO specification and Standards.		<u>RFT</u>	36		
1.03	<u>CONST. RCC PIT & INSTL UGFS TANK 15/25KL</u> CONSTRUCTION OF UGFS TANK PIT & INSTALLATION OF 25KLs:		<u>EA</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Services required for Construction of RCC Pit and Installation of UGFS Tank 25 KLS as per attached layout, detail drawings, site requirements and as directed by Engineer Incharge. The scope includes the following but not limited to: -Construction of RCC Pit -Installation of UGFS Tank -Supply & Installation of Vent Pipe lines with allied fittings, valves <(>,<)> flanges or any other material complete in all respect. -Separate Earthing of Tanks as per attached drawing. Note: UGFS Tanks (15/25/50 KLS) and Quick Couplings will be provided by PSO. All other material (pipe lines, fittings, flanges, gas kits or any other will be the part of Contractor scope). A-., Civil Works for Tank Pit 1-.,EXCAVATION: Excavation in any kind of soil (dry or wet, hard or soft) including removing of existing flooring /asphalt pavement or any other structure encountered during excavation to a varying depth as required including levelling, dressing, dewatering, shoring (if required) and compaction of subgrade with plate/ roller compactor as to achieve 95% AASHTO modified dry density according to the drawing and as directed by Engineer Incharge. The job includes disposal of surplus material outside of depot/ site upto sites allocated by Municipality/city authorities for this purpose and housekeeping of the site complete in all respect. 2-.,BACK FILLING: Backfilling with excavated earth including breaking clods, dressing, watering and consolidating by ramming in layers not exceeding 150mm/6-inches depth to obtain 95% AASHTO modified dry density by mechanical means with plate/ roller compactor including all lift <(>&<)> leads with testing according to the drawing, specification and as directed by Engineer Incharge.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	3-.,STONE SOLING: Providing and laying stone soling 9" thick of approved quality under the base of the tank pit, including hand packing vertically and filling voids with stone dust (Khaka), consolidating and compacting with mechanical means to achieve compaction as per drawings and instructions of the Engineer In-Charge. 4-.,P/L LEAN CONCRETE (1:4:8): Providing and laying lean concrete 1:4:8 mix ratio using S.R. Cement, approved quality 3/4" max. size graded crush and fine aggregate (hill sand) of required properties, including formwork installation and removal, mixing, transporting, placing<(>,<)> compacting, finishing, and curing, complete in all respects and as directed by the Engineer In-Charge. 5-.,P/L LEAN CONCRETE (1:3:6): Providing and laying cement concrete 1:3:6 mix ratio using S.R. Cement, approved quality 3/4" max. size graded crush and fine aggregate (hill sand) of required properties<(>,<)> including formwork installation and removal, mixing, transporting <(>,<)> placing, compacting, finishing, and curing, complete in all respects and as directed by the Engineer In-Charge. 6-.,INDUSTRIAL POLYTHENE SHEET: Providing and placing in position industrial polythene sheet on the lean concrete. 7-.,P/L CONCRETE (1:2:4) # Base, Walls, Tank Foundations/Pedestals, Roof Slab, etc.: .,Providing and laying 1:2:4 concrete with S.R. Cement of specified strength, approved quality 3/4" max. size graded crushed stone and fine aggregate (hill sand) of required properties, including formwork(installation and removal), mixing, transporting, placing, compacting,finishing, and curing, complete in all respects as specified. .,Construction of Pre-Cast / Cast-in-Situ slab of UGFS Tank Pits as per drawings and as directed by the Engineer In-Charge. .,Providing and fixing galvanized anchor bolts (J-Type) with double nuts and washers (4 Nos. Anchor Bolts # 1" dia x 12" long) in tank foundation/saddles for anchoring, as per required level, spacing, and alignment for the anchoring of tanks. .,Chamfer/gola 75mm x 75mm (or as shown in drawing) to be provided at all corners of walls and base with reinforcement.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Note: To confirm the desired cube strength (minimum 3000 psi at 28 days), cube tests (3 + 3 = 6 Nos.) for 7 & 28 days will be carried out by the contractor from a company-approved laboratory at his own cost. No extra payment will be made to the contractor. 8-.,WATER STOPPER: 225mm wide and 5mm thick water stopper of approved make or equivalent to be used in joints as mentioned in the drawings and as directed by the Engineer In-Charge. 9-.,SUPPLY & INSTALLATION OF DEFORMED STEEL BARS (Grade-60): Supply and installation of deformed steel reinforcement bars as per drawings and specifications. Includes all wastage, cuttings, overlaps (shown or not shown in the drawings, according to the formula $48 \times \text{diameter}$), cost of straightening, cutting, bending, binding, placing in position on cement concrete precast spacers or M.S. chairs, and tying with binding wire (18SWG), complete in all respects as directed by the Engineer In-Charge. Note: Mill Test Certificate from the manufacturer will be provided by the contractor. Deformed steel of yield strength 60,000 psi to be used. Any further testing required by the client shall be arranged by the contractor at his own cost without any additional payment. 10-.,P/A INTERNAL PLASTER (1/2" Thick): Providing and applying cement plaster 1/2" thick in 1:4 cement sand mortar to beams, columns,ceilings, and walls at any height, including all corners, recesses,jambs, and joints of masonry, roughening of surfaces, cement slurry backing, and scaffolding. Includes a 6" wide heavy-duty metal lath strip nailed at the joints of masonry and concrete structure, and curing<(>,<(> complete in all respects as directed by the Engineer In-Charge. .,Pudlo plaster with 5 lbs. of Pudlo per bag of cement (50 kg) will be used for inside floors and walls. 11-.,BITUMEN COATING (for External Concrete): Providing and laying two coats of PB-4 hot bitumen or approved make imported waterproofing chemical to the substructure in contact with the ground, including the					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	cost of all materials, labor, and equipment, complete as per drawings ,specifications, and as directed by the Engineer In-Charge. Here's your section properly formatted clean, consistent, and professional while keeping all original content unchanged and engineering-style formatting aligned with your previous section: B-,,INSTALLATION OF UGFS TANK 12-,,INSTALLATION OF UGFS TANK (15/25/50 KL): Installation of UGFS Tank(provided by PSO) on foundation at proper level and alignment as per attached drawings. 13-,,LOWERING OF UGFS TANK: Lowering the UGFS Tank into the pit with the help of a crane and placing it so that the tank is in perfect line<(> ,<(> level, and alignment as per attached drawings. Note: Third-party certified crane, all lifting devices, rigger, and crane operator shall be used as per HSE requirements. The contractor will submit the report and certificates prior to execution. 14-,,SECURING OF TANK: Securing the tank in the pit with the help of two(2) Nos. M.S. straps made from flat M.S. bar size 1-1/2" wide and 3/16" thick, fixed with foundation bolts. Refer to detail for bolts (Sr.#7-c). 15-,, M.S. SUMP COVER WITH FRAME: Providing and fixing M.S. sump cover with frame as per drawings, positioned 2" above tank platform. Job includes providing and fixing sump cover with frame, including scraping <(>,<(> cleaning, and applying two (2) coats of red oxide primer over three (3) coats of approved colour synthetic enamel paint. Also includes providing and grouting 4 Nos. M.S. hooks for frame and 1 No. heavy-duty manhole cover on RCC manholes in the pit as per drawing. 16-,,SHEET GASKET: Providing, fitting, and jointing 5mm thick sheet gasket for the manhole flange and tightening all nuts and bolts to make it watertight. 17-,, VENT PIPE: Providing and fixing 1-1/2" dia. M.S. vent pipe, 12 ft high from tank platform level/finished paver level, rising vertically and in perfect plumb, including providing and fixing 'T'-type air vent					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY % PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	with elbows and wire mesh cap. The pipe shall be cleaned and applied with two (2) coats of red oxide primer and three (3) coats of approved colour synthetic enamel paint. 18-,, SAND FILL: Providing and laying sand fill of approved quality and origin in the tank pit and pipeline trench, including consolidating by ramming in layers not exceeding 6" depth to attain 95% modified AASHTO density, including all lead and lift. Note: -The tanks shall be finally cleaned at the time of product filling. -For tank pits sharing boundary wall, payment will be made accordingly. 19-,, EARTHING OF UGFS TANKS: Providing and fixing 20 mm dia 99% copper earthing electrode 10ft Length upto underground water level for achieving desired result i.e. less than 5 ohms. This job also includes earthing leads upto earth connecting point and inspection chamber. as per attached reference Drawings. 54 mm dia. UPP FUEL PIPE UPP FUEL PIPE: PROVIDING AND LAYING CO-AXIAL SUCTION PIPELINE Services Required for Providing and laying co-axial Suction Pipeline using ultra polythene pipe (UPP 54mm diameter) of approved make or approved equivalent from UGFS Tank to Dispensing Units (DU's) with all fittings and fixtures. Job includes the UPP pipeline shall be laid 18" below the NGL with a fine sand cushion around the pipe as per attached drawing complete in all respect and as directed by Engineer Incharge.		<u>M</u>	300		
1.05	DECANTING GI PIPE 3 1.01,,DECANTING GI PIPE 3" dia: Providing and laying G.I. Decantation pipeline 3-inches dia., 8 SWG thick, in such a way that couplings (provided by PSO) are properly fitted at the decanting points. The line is to be linked with the fill		<u>RFT</u>	30		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	line of the tank with tee having a reducer 3" x 1½" dia. pipe, 2 feet long, complete in all respect including excavation, laying, backfilling, compaction with all materials, fittings, foot valve or any other valve, flanges, studs, gaskets, etc. Job also includes providing and applying a prime coat of red oxide DFT 50 microns and enamel coats of DFT 50 microns as per instructions of Engineer Incharge. Note: Quick coupling will be provided by PSO, and the installation will be done by the contractor. <u>GUARD RAIL FILL PT.</u> 1.01., GUARD RAIL FILL PT: Guard Rail: Services required for Providing and Fixing of Guard Rail at Fill Point. Scope includes providing, fixing & fabricating 4" dia MS-pipe for Guard rail at Fill point including foundation as per attached drawing, mechanical cleaning, antirust paint/ primer red oxide minimum DFT 50microns and enamel paint to a DFT of 50 microns of same make as per attached layout, detail drawings, site requirements complete in all respect and as directed by Engineer Incharge.		<u>RFT</u>	25		
1.07	<u>P/L 60 MM PAVER EXIST. PAVEMENT</u> PROVIDING & LAYING 60MM THICK PRECAST CONCRETE PAVER WITH BASE MATERIAL Providing and laying of Precast Concrete Pavers 60mm thick of approved make or approved equivalent complete in all respect, as per drawing and as directed by Engineer Incharge. Existing Pavers level will be raised and maintained as per PSO standards which is 6-inches down from existing office finished floor level. All required material (base, pavers, sand or any other including equipment, manpower, tools will be part of contractor scope). This job includes the following but not limited to: Removal & Stacking of Existing Pavers: Removal of all existing pavers and stacking at site for re-use or final disposal / shifting to PSO depot / terminal / outlet as directed by Engineer Incharge. Levelling and Compaction of Subgrade: Levelling, dressing, cutting to		<u>SFT</u>	5,500		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

12	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.08	maintain the required slope/level, and compaction of subgrade/subsurface with Road Roller 10 to 12 ton. Providing and Laying Base material (6" to 9" Thick) to raise the driveway level 6-inches down from existing office floor: - Providing and laying 6" to 9" thick base material (compacted thickness) to be laid in one layer 6" to 9" (compacted thickness) to raise the existing pavers level. This work shall consist of furnishing, spreading <(>,<)> and compacting according to the specifications and drawings. Levelling<(>,<)> dressing, watering, and compaction by using Road Roller 10-12 ton complete in all respect and as directed by Engineer Incharge. Note: For sub-base and base material, NHA Specifications (attached) will be followed. Material samples for approval will be submitted to the Engineer Incharge for prior approval. Providing and Laying of Precast Concrete Pavers (60mmtk) of approved make or approved equivalent: Providing and laying of Precast Concrete Pavers of approved make or approved equivalent make and city type of size 200mm x 100mm x 60mm thick, laid in pattern (as per site) and should have minimum compressive strength of 49 N/mm² (7100 Psi), to be laid over 2" thick compacted sand graded to BS-882 and voids to be filled by sand/Khaka and finally pavers to be compacted with plate compactors. Red colour pavers shall be used to demarcate the borders or pattern flooring if required. Note: Compressive strength test, tensile splitting test and Abrasion Resistance along with certificates that pavers supplied to PSO are from the test batch as per report from manufacturer, are to be provided by the contractor. If the client requires further testing, it will be arranged by the contractor at his own cost according to BS 6717:1993 <(>&<)> 2001 to ensure quality requirements. P/L CURB STONE P/L CURB STONE:		RFT	200		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

13	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.09	PROVIDING AND FIXING OF CEMENT CONCRETE FAIR FACE CURB STONES Providing and fixing of cement concrete fair face Kerb Stones of approved make or approved equivalent of size 450mm x 300mm x 150mm at the edge of driveway on either side, at the toe/ ends of pavers and any other area including excavation, jointing and pointing in cement sand mortar 1:4 with S.R. cement, curing, and backfilling. Finally, painting on Kerb Stones (Yellow & Black) with enamel paint two coats and one prime coat complete in all respect and as directed by Engineer Incharge. This job also includes the excavation, backfilling, provision of 3" thick lean concrete 1:4:8, for the placement of Kerb Stones. <u>P/L CUT OFF DRAIN</u> Construction of Cut-off drain fair face with uniform slope towards the main sewerage covered with RCC concrete slab and MS grating complete in all respect, as per attached layout, detailed drawings and as directed by Engineer Incharge. Job includes excavation, lean concrete, deformed steel bars, RCC 1:2:4, plaster 1/2"tk internal, bitumen coating on external surface in contact with soil, steel formwork/wooden ply to be used for fair face<(>,<)> steel rating, painting of grating with one prime coat DFT 50 microns and two enamel coats DFT 50 microns coat complete in all respect and as directed by Engineer Incharge.		<u>RFT</u>	130		
1.10	<u>Excavation</u> 1.01,,EXCAVATION: Excavation and backfilling in any kind of soil (dry or wet, hard or soft) including removing of existing flooring /asphalt pavement or any other structure encountered during excavation to a varying depth as required including levelling, dressing, dewatering, shoring (if required) and compaction of subgrade with plate/ roller compactor as to achieve 95% AASHTO modified dry density according to the drawing and as directed by Engineer Incharge. This job also includes the backfilling of		<u>M3</u>	2.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

14	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.11	area with existing / excavated soil and in layers 6" each and compaction to achieve the 95% modified ASHTO dry density complete in all respect. The job includes disposal of surplus material out side of depot/ site upto sites allocated by Municipality/city authorities for this purpose and house keeping of the site complete in all respect. <u>Earth/Back filling</u> 1.01,,EARTH/BACK FILLING: Earth filling of specified area with approved earth fill material obtained from outside approved source and to maintain the required level and slope of site or and as per site requirement subject to the prior approval from Site Engineer i/c breaking clods, dressing, watering<(>,<)> ramming in layers not exceeding 6-inches thk in depth compaction of soil with 10 to 12 ton roller as to achieve 95% AASHTO modified dry density i/c all lead and lift as per drawings and instructions of Engineer Incharge. Note: Actual compacted depth shall be considered for measurement /payment		<u>M3</u>	2.000		
1.12	<u>1:4:8 CONCRETE</u> 1.01,,1:4:8 CONCRETE: Providing and laying lean concrete 1:4:8 mix ratio using S.R. Cement<(>,<)> approved quality 3/4" max: size graded crush and fine aggregate (hill sand) of required properties including form work installation & removal<(>,<)> mixing, transporting, placing, compacting, finishing and curing etc.<(>,<)> complete in all respects and as directed by Engineer Incharge.		<u>M3</u>	2.000		
1.13	<u>Laying of R.C.C 1:2:4</u> 1.01,,Laying of R.C.C 1:2:4: Providing and laying 1:2:4 with S.R Cement specified strength approved quality 3/4" max: size graded crushed stone and fine aggregate (hill		<u>M3</u>	15.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

15	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.14	sand) of required properties including form work (installation <(>&<)> removal) mixing, transporting, placing, compacting, finishing and curing etc., complete in all respects as specified. Note: To confirm the desired cube strength minimum 3000Psi at 28days the cube tests (3+3=6No's) for 7<(>&<)>28days will be carried out by contractor from Company approved laboratory at his own cost and no extra payment will be made to contractor SUPPLY & INSTALLATION OF DEFORMED STEEL 1.01.,SUPPLY & INSTALLATION OF DEFORMED STEEL BARS: Note: Due to SAP System Limitations code of deformed steel is not exist which has been covered in text. Supply of deformed steel reinforcement bars as per drawings <(>&<)> specifications. All wastage, cuttings, overlaps and chairs are included in the cost and no extra payment will be made in this regard. This item also includes the Installation of all reinforcement bars including the cost of straightening, cutting, bending, binding, wastage, and such overlaps as are not shown in the drawings, placing in position on cement Concrete precast spacer or M.S. chairs and tying with galvanized binding wire 18SWG etc. complete in all respects as per drawings as directed by Engineer Incharge. Note: Mill test Certificate from the manufacturer will be provided by the contractor. Deformed steel of yield strength 60 ,000Psi to be used. Any further testing required by the client the contractor will arrange at his own cost without any additional payment.		KG	300.000		
1.15	Plain Plaster ½" thick PLAIN PLASTER ½" THICK: Providing and applying cement plaster 1/2" thick in 1:4 cement sand mortar to beams, columns, ceiling, walls at any height i/c all corners <(>&<)> recesses, jams and joints of masonry, roughing the surfaces and cement slurry backing to all surfaces i/c and scaffolding. This job also includes 6" wide heavy-duty metal lath strip nailed at the joints of masonry and concrete structure and curing complete in all respect and as directed by Engineer Incharge.		M2	170		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

16	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.16	<u>Plain Plaster 3/4" thick</u> 1.01,,PLAIN PLASTER ¾" THICK: Providing and applying cement plaster 3/4" thick in 1:4 cement sand mortar to beams, columns, ceiling, walls at any height i/c all corners, recesses, jams and joints of masonry, roughing the surfaces and cement slurry backing to all surfaces i/c and scaffolding. This job also includes 6" wide heavy-duty metal lath strip nailed at the joints of masonry and concrete structure and curing complete in all respect and as directed by Engineer Incharge.		<u>M2</u>	60		
1.17	<u>BRICK / BLOCK MASONARY</u> Providing and laying best quality machine made block masonry of specified thickness set in 1:6 cements and mortar i/c required scaffolding, racking out and cleaning of joints and curing of masonry i/c 18 gauge G.I. sheet dovetail anchors at 2'-0" c/c vertically at joints of RCC columns and masonry. Complete as per specification and direction of engineer incharge		<u>M3</u>	25.000		
1.18	<u>Plastic Emulsion Paint</u> PAINT WORKS: Painting works (Complete building includes ceiling, walls, doors ,windows, steel gates etc.) includes the following work: 1.,Plastic Emulsion Paint (Internal Paint) Providing and applying three (3) coats of Plastic Emulsion paint of PSO approved color and shade on plastered surfaces including preparation of base, rubbing the surface with carborundum stone, applying primer coat of Sealer of approved quality on the entire surface, filling the depressions with putty, cutting the surface and rubbing smooth finally with sand paper complete as per specifications and drawings. The job also includes scaffolding, all tools, material and manpower.		<u>M2</u>	180		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

17	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.19	<u>Weather Shield Paint</u> WEATHER SHIELD PAINT: Providing and applying 3 coats of WEATHER SHIELD paint from ICI/Berger/equivalent of required colour and shade job includes preparation of the base by rubbing the surface with carborundum stone filling the depressions with putty, cutting the surface and rubbing smooth finally with sand paper complete as per specifications and directions of the site engineer. Weather Shield Paint (External Paint where required): Providing and applying three (3) coats of WEATHER SHIELD paint of required colour and shade job includes preparation of the base by rubbing the surface with carborundum stone filling the depressions with putty, cutting the surface and rubbing smooth finally with sand paper complete as per specifications and directions of the site engineer. Note: ACM Sheets will be installed on outside of building at front and all remaining sides to be painted subject to site requirements. The job also includes scaffolding, all tools, material and manpower.		<u>M2</u>	160		
1.20	<u>WIRING FOR SPREADER</u> Providing, laying, testing and termination of multi core cable 3 x 2.5sq.mm PVC/PVC of 450/750V from distribution board to Spreader run in PVC pipe complete in all respect as per specifications, drawing and directions of the site Engineer. Cables are to be of High conductivity Copper to meet the requirements of BS EN 60228 "Conductor of insulated cables". PVC insulation material to conform to BS7566/BSEN 50363.		<u>RFT</u>	250		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

18	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.21	<u>WIRING FOR DU & MOTOR</u> Providing, laying, testing and termination of cable from pump panel board to dispensing pump and dispenser, independent circuits and separate PVC Pipes shall be used for motor and dispenser and motor shall be connected to the junction box of the pump with the help of 3/4 inch dia Union as per drawing or Engineer's instruction the size of the cables and other details are as follows. Dispenser section wiring with 4 x 2.5 sq.mm (multicore cable PVC/PVC of 450/750V)+ 1 x 2.5 sq.mm for earthing run in 3/4 inch dia PVC Pipe. Pump motor circuit cable 3 x 4 sq.mm (multicore cable PVC/PVC of 450/750V) run in 1 inch dia PVC Pipe.		<u>RFT</u>	300		
1.22	<u>S/I 1-HP CENTFUGAL PUMP</u> Supply & Installation of Centrifugal Horizontal pumping set motor 1 HP complete with installation and necessary piping works for connection with Underground water tank and overhead water tank of KIOSK as per PSo standards and Enginer Incharge.		<u>EA</u>	1		
1.23	<u>P/L UPVC 8" DIA, CLASS-B FOR DRAIN LINES</u> Proving and laying UPVC pipe of 8 inch dia Class B to be installed in fine grade river sand of 6" layer on each side of pipe and as directed by Engineer Incharge. Job also includes excavation of trench 600mm wide upto the required depth and backfilling with compaction as per attached drawing.		<u>RFT</u>	100		
1.24	<u>P/L UPVC PIPE 6" CLASS-B FOR CABLE SLEE</u>		<u>RFT</u>	20		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

19	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.25	Proving and laying UPVC pipe of 6 inch dia Class B to be installed in fine grade river sand of 6" layer on each side of pipe and as directed by Engineer Incharge. Job also includes excavation of trench 600mm wide upto the required depth and backfilling with compaction as per attached drawing. <u>Supply and Installation of 4" UPVC Pipe</u> Proving and laying UPVC pipe of 4-inch dia Class D to be installed in fine grade river sand of 6" layer on each side of pipe and as directed by Engineer Incharge. Job also includes excavation of trench 600mm wide upto the required depth and backfilling with compaction as per attached drawing.		<u>M</u>	50		
1.26	<u>P/L UPVC PIPE 2" CLASS-B FOR CABLE SLEE</u> Proving and laying UPVC pipe of 2 inch dia Class B to be installed in fine grade river sand of 6" layer on each side of pipe and as directed by Engineer Incharge. Job also includes excavation of trench 600mm wide upto the required depth and backfilling with compaction as per attached drawing.		<u>RFT</u>	25		
1.27	<u>ASPHALT</u> Services required for Providing, laying and compacting Asphalt Wearing Course 67mm thick complete in all resepct, as per drawing and as directed by Engineer Incharge. This job includes the following but not limited to: 1- Levelling , dressing , cutting to maintain the required slope/ level and Compaction of subgrade. Compaction test to achieve 95% result a		<u>SFT</u>	1,000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

20	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.28	minimum of one in-place density test shall be performed. 2- Providing and laying 9"tk sub-base laid and compacted in two layers of (4 1/2"tk each) compacted thickness. This work shall consist of furnishing, spreading and compacting granular sub-base according to the specifications and PSO drawings. Granular sub-base shall consist of natural or process aggregates such as gravel, sand, Khaka in required slope, levels and compaction with Road Rollar 10 to 12 ton. 3- Providing and laying basecourse material laid and compacted in layers of 6" thick compacted thickness as per drawing in required slope, levels and compaction with Road Rollar 10 to 12 ton. 4- Providing, laying and compacting asphalt concrete wearing course 67mm thick conforming to PSO's Specification including prime coat. Note: For subbase, basecourse and Asphalt wearing course NHA Specifications(attached) will be followed. Material Sample for approval will be submitted to the PSO Site Engineer for prior approval. <u>Installation of LED Lights</u> Fixing of LED Canopy lights (provided by PSO) Scope includes fixing/ installation of under canopy LED lights as per PSO approved specifications. Job includes cutting of false ceiling<(> ,<(> hanging arrangements of light & providing and installation of necessary wiring from DB to Circuit with 3Cx4Sqmm cable & point to point with 3Cx2.5Sqmm cable complete in all respect and as directed by Engineer Incharge. Note: LED Canopy Lights will be provided by PSO. All other materials for wiring and installation will be part of this item scope.		EA	15		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

21	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.29	<u>INSTALLATION OF ALUMINIUM COMPOSITE MATE</u> Supply and Installation of ACM sheets at front and side elevation of building block at Retail Outlets as per following details and attached reference drawing and as per site requirements directed by PSO site Incharge. Job includes cutting, bending, routing, transportation and installation of ACM sheets as per the requirements at Retail Outlets. Job also includes installation of Aluminium C-channels of size 1.75" x 0.5" approx. at equal intervals for holding ACM sheets using Aluminium angle strips of size 0.5"x 0.5" approx. using appropriate riveting and screwing system.		<u>SFT</u>	1,600		
1.30	<u>P/L LUBE BAY DRAIN</u> Providing & Laying of lube bay Drain as per attached layout and detail drawings and as directed by Engineer Incharge.		<u>RFT</u>	26		
1.31	<u>C/O GREASE PIT</u> Construction of Grease Pit as per layout and detail drawing and as directed by Engineer Incharge.		<u>EA</u>	1		
1.32	<u>HOIST INSTALLATION</u> Installation of Hoist in Car Wash as per Drawings and instruction of Engineer incharge.		<u>EA</u>	2		
1.33	<u>Steel structure fabrication</u> Supply , Installation, Fabrication , welding of Steel Structure angles <> beams , girders, C/U channels, square pipes, flat bars, galvanized anchor bolts or any other steel member as per site requirement of any size in accordance with drawings in proper alignment and levels horizontally and vertically including fabrication, cutting, making holes for anchor bolts including fixing in concrete as per		<u>KG</u>	500.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

22	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.34	alignment and levels, structure welding, mechanical cleaning of steel section by using hand tools and supply and application of red lead primer (approved make) to a dry film thickness of 50 microns in minimum of two followed by two coats of industrial enamel paint of the same make to a DFT of 50 microns in a minimum of two coats complete in all respect as per drawing and directed by Engineer Incharge. <u>Design Consultancy</u> Design Vetting for Steel Structure Canopy: PSO intends to increase the height of existing canopy and to install the Solar Panel on the existing canopy and the existing canopy has no option to sustain the additional load for proposed solar system. In view of that vetting of the existing canopy structure & is required from a reputed consultant firm PEC approved having relevant design experience of minimum 5 years. Scope includes the following: a- As-building of existing canopy, Vetting of Existing canopy and proposed the upgradation in existing design for raising of height and addition of solar system with complete revised execution drawings (IFC) <> design calculations, MTO, Difference sheet showing the of weight of existing canopy structure and addition weight (if required) and for the reinforcement of canopy as per proposed scope. For design vetting the wind pressure 120miles per hour and seismic zone 2B to be referred as per UBC, Pakistan Building & AISC-16 Code along with other international codes & standards, as per best engineering practices etc. The tentative load of solar system is 1.5Kg per sft and it will be further confirmed at time of execution. Contractor will follow the		EA	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

23 OF 39

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

RFQ No RC-19847SR

DATE 29.07.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	parameters accordingly for further detailed design. - PSO Canopy design is based on 100mph wind velocity and it further to be vet for 120miles per hour. However, localized average wind speed data should also be reviewed to support assumptions wherever higher to be used for design vetting. - Consultant will prepare the as-built of existing canopy, study existing structure and check the structural and design as per proposed requirement for the installation of solar system and increasing the height of canopy upto 20ft. -Consultant shall prepare and submit all drawings and calculations to the client for review and approval and will incorporate all changes suggested by client. Deliverables: Consultant shall provide Layout Plans, all detail drawings for canopy structure and with allied detailed works, execution drawings (IFC), design calculations, report, MTO, Weight Difference sheet showing the of weight of existing canopy structure and addition weight (if required) and for the reinforcement of canopy as per proposed scope. - Consultant shall provide soft copies and Two SETs (IFC) of hard copies of all the all deliverables. Soft Copy of drawings to be provided in Editable AutoCAD Format). Separate copies of design and vetting document to be submitted as per mentioned scope of work. Consultant shall provide clarifications, guidance and technical assistance whenever required by PSO without any additional cost and as part of this item.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

24	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.35	<u>RELAYING PAVERS</u> RE-LAYING OF PRE-CAST CONCRETE PAVERS Laying of Precast Concrete Pavers in pattern (as per site) over 2" thick compacted sand graded to BS-882 and voids to be filled by sand / Khaka and finally pavers to be compacted with plate compactors. Red colour pavers shall be used to demarcate the borders or pattern flooring if required. Complete in all respect and as directed by Engineer Incharge.		<u>SFT</u>	100		
1.36	<u>2"X2"X2.5" CONCRETE MANHOLE</u> Construction of Manholes (2ft x 2ft x 2ft). Construction of Manholes includes following scope of work - Excavation & backfilling in all kind of soil and any structure which encountered during excavation, backfilling with suitable earth(>,<)> dewatering (if required), disposal of surplus material from outside of depot premises. - Internal size 2ft x2ft upto 2 to 2.5ft in depth (depth will be adjusted as per site requirements to maintain invert levels and as directed by Engineer Incharge) - Lean concrete (1:4:8),3-inches thick and 3-inches projected from base area - PCC Concrete (1:2:4) base 4-inches thick and additional for pipe fixing as per drawing. - Block/ Brick masonry 8"thick with block masonry approved by the Engineer Incharge - PCC Concrete (1:2:4) border 4-inches thick on wall for fixing of Manhole cover - Inside & outside Plaster 3/4"tk with 1:4 cement sand mortar		<u>EA</u>	8		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

25	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.37	- Providing & fixing of Cast Iron Manhole cover of approved make or approved equivalent heavy duty as per size of Manhole with angle frame complete in all respect and as directed by Engineer Incharge. <u>Construction of Manholes</u> Construction of Manholes (1.5ft x 1.5ft x 1.5ft) Construction of Manholes includes following scope of work - Excavation & backfilling in all kind of soil and any structure which encountered during excavation, backfilling with suitable earth(>,<)> dewatering (if required), disposal of surplus material from outside of depot premises. - Internal size 1.5ft x 1.5ft x 1.5ft in depth (depth will be adjusted as per site requirements and as directed by Engineer Incharge) - Lean concrete (1:4:8),3-inches thick and 3-inches projected from base area - PCC Concrete (1:2:4) base 4-inches thick and additional for pipe fixing as per drawing. - Block/ Brick masonry 8"thick with block masonry approved by the Engineer Incharge - PCC Concrete (1:2:4) border 4-inches thick on wall for fixing of Manhole cover - Inside & outside Plaster 3/4"tk with 1:4 cement sand mortar - Providing & fixing of Cast Iron Manhole cover of approved		<u>EA</u>	6		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

26	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.38	make or approved equivalent heavy duty as per size of Manhole with angle frame complete in all respect and as directed by Engineer Incharge. Renovation / Rehabilitation REMOVING, SHIFTING, REPAIRING & RE-INSTALLATION OF EXISTING TYRE SHOP Repairing and shifting of Existing tyre shop with allied electrical works. This job includes removing, repairing of steel structure, painting<(>,<,> shifting/Installation and CC flooring inside the tyre shop with PCC 1:2:4 & 9" stone soling of existing tyre shop as per attached drawings <(>,<,> site requirements and directed by Engineer Incharge.		JOB	1		
1.39	Porcelain Tile Works (Sft) Tile Works: .,Removal of existing tiles and debris outside of premises. .,Providing and fixing of new Porcelain Tiles for building floor with skirting (6" height). .,Providing and fixing of new Porcelain Tiles for Washrooms includes flooring and walls height upto false ceiling. .,Providing and fixing of new Porcelain Tiles for Plinth protection outside of building. Size of existing building plinth will be referred and for existing building 3ft wide to be constructed as per site		SFT	3,000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

27	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.40	requirement. Job includes careful dismantling of existing floor/wall tiles, removal of bedding mortar/adhesive, disposal of debris outside site, cleaning and preparation of the base surface, levelling and making good the substrate, providing and applying cement mortar/tile adhesive, laying and fixing of new tiles true to line, level and plumb, cutting and fitting around edges, corners and services, grouting of joints with approved grout, final cleaning, and protection of finished surfaces<(> ,<)> complete in all respects as per drawings and specifications. Providing and laying Porcelain Tiles includes cutting of tiles, 1" thick/ required thickness cement mortar 1:3 / bond of approved make or approved equivalent over a bed including filling joints with neat slurry of white, pigmented grout cement, levelling curing, cleaning etc. Note: .,,PSO approved tiles shade, colour and size will be used. .,,Size of tiles can be changed/ adjusted as per PSO requirement. .,,For Office, shop stop and plinth Protection of building, Wash Rooms (Public / Executive) separate Tiles shades, colors and sizes have been mentioned in attached Material Specification/ Compliance Sheet. Contractor will submit the sample of tiles of approved make or approved equivalent to the PSO Site Incharge for approval prior procurement and execution at site. Electrical Works ELECTRIC WORKS Removal of existing DB's, wiring completely and providing and laying new DB's/Panel with complete wiring (Concealed/ open as per site requirements), earthing of DB's, connections as per provided building		EA	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

28	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	layout and site requirement. WIRING: (Completely new wiring with all material, fixtures and services) Supply, Installation testing and commissioning of following items including all materials, fixtures, switch boards, power plugs, A/C points, SMD LED Tube lights, SMD Down Lights complete in all respect including labour, tools and accessories as per specifications, drawings and instruction of the Engineer Incharge. -WIRING FROM DB TO SWITCH BOARD: Circuit wiring from distribution board (DB) to switch board in appropriate/ specified size of pvc conduit on surface / concealed with 2x2.5 sq.mm +ECC 1x2.5 sq.mm 1-core pvc insulated wires, including any wiring between switch boards on the same circuit. -WIRING OF LIGHT POINT TO SWITCH BOARD & POINT TO POINT: Wiring of lighting point to switch Board with 1.5 sq.mm 1-core wires for ECC green in colour and 2- 2.5 sq.mm common neutral, & live including 16 SWG sheet steel back boxes. Same as above item but wiring from light point to point. Wiring with 3x2.5 sq.mm for 5A, switch socket connected with any nearest light circuit. -WIRING OF POWER SOCKET: Wiring for 15A switch socket unit / AC unit from distribution board with 3 X 4 SQ.MM multi core cable in PVC conduit or metallic conduit. Switches socket light fixtures and fans to be provided as per site requirements in required quantities complete in all respect and as per approval of engineer incharge. - LIGHTS: (as per attached layout and site requirements) -Providing and fixing LED SMD Lights 12 to 14 watt - Providing and fixing wall LED light of 18 to 20 watt - Providing and fixing LED SMD Ceiling Lights 10 to 12 watt - Providing and fixing LED SMD Down Lights 14 to 18 watt covered with					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

29	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	glass - Switches of 5A with 10swg steel back box or pvc from one gang to six gang connecting LED SMD Tube Lights for front punch section (Elevation). Work also includes the connection with multi core cable from point to light fixtures as per attached plan of lights. DB's for building, canopy, DUs, tyre shop etc. will be provided as per provided details and specifications of components and the Contractor will submit the Shop drawings, SLD's for review and approval by PSO and for any suggested change will be updated and incorporated by the contractor accordingly without any additional cost. Providing and fixing of all electrical fixtures, switch boards <(>,<)> power plugs, A/C points, stabilizer racks in DB room, ceiling fans/ bracket fans/ louvered fans to be fixed in false ceiling, exhaust fans with louvered for washrooms, removal and reinstallation of existing A/C after complete maintenance and service and incase of any changes in parts will be replaced by the contractor, A/C gas filling, installation / outdoor and indoor units as per site requirement. -Distribution/Panel Board (DB): Providing, Installation, testing and commissioning of Distribution Board with all material and accessories, factory assembled and tested. It shall consist of following components. Note: Contractor should submit the shop drawing of Panel before fabrication for approval. Main Distribution panel Type:., Floor mounted/Wall Mounted (Compartment Wise/As per site requirement) Size: ,As per site requirement IP: ,43 Colour:.,Smoke grey (Powder coated) Circuit Breaker: ,As per site requirement					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

30	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Incoming: 1 x 100A, TP MCCB ICU-15 KA. 1 x,80A, TP MCCB ICU-15 KA. 3 x Control Fuses 3 x Indication Lamps 1 x Volt Meter with Selector Switch 1 x Ammeter with Selector Switch 3 x CTs (As per main incoming breaker 100/ 5A) Incoming (Solar & Generator): 1 x 80A, TP MCCB ICU-15 KA (Future Provision for Solar System) 1 x 63A, TP MCCB ICU-15 KA. (For DG Set) 3 x Indication Lamps (Both MCCB's Main Breaker & DG set should be electrically and mechanically interlocked) Outgoing: 1 x 32A, TP MCB ICU - 10 KA (Main Breaker for DU's) 1 x 32A, TP MCB ICU - 10 KA (Main Breaker for Canopy) 2 x 32A, TP MCB ICU - 10 KA (Main Breaker Spare) 18 x 10A SP 12 x 6A SP 3 x 15A SP 3 x 20A SP 1 x 20A TP MCB (Water Pump) 1 x 20A TP MCB (Compressor) 2 x 20A TP MCB (Spare) 1 x 50A Contactor at AC-1 Sub Incoming (Emergency Circuit) 1 x 50A, TP MCCB ICU-10 KA. 1 x 50A TP Contactor at AC-1 Outgoing 6 x 10A SP 1,,x 20A SP					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

31	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY % PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Note: Contractor provides 3 nos. Relay shunt trip coil 220 V AC connected with main breaker, solar breaker and DG set breaker in MDB with 2x 1.5 mm cable for emergency stop complete in all respect as per directions of the site engineer. Compartment for (3 DU's): All material and accessories, factory assembled and tested. It shall consist of following components. Incoming 1 x 32A, TP MCB ICU - 10 KA Outgoing 8 x 6 Amp SP 8 x 10 Amp SP 6 x 15 Amp SP Compartment For Canopy Incoming 1 x 32A, TP MCCB 10 KA. Outgoing 6 x 10 A SP 10 x 6 A SP Sub-Incoming (Circuit to cut off in case of Power Failure) 1 - 32 A, TP MCB 10 KA 1 - 32 A Contractor AC-1 Note: The work include supply, installation, termination and testing of all incoming and outgoing cables with allied accessories required for Installation, fixing, connecting and commissioning of Distribution board, complete in all respect to the entire satisfaction of engineer incharge. -EARTHING: (All DUS, Monolith Tower, Canopy, All DBs,light poles etc as per site requirement)					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

32	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.41	Providing and fixing 20 mm dia 99% copper earthing electrode 10ft Length upto underground water level for achieving desired result i.e. less than 5 ohms. This job also includes earthing leads upto earth connecting point and DB and inspection chamber. as per attached reference Drawings. Earthing of all DB's in the Kiosk, canopy, light poles, monolith <u>Supply and Installation of False Ceiling</u> Plaster of Paris (POP) False Ceiling Removing of Existing False Ceiling, apply plaster, clearing the surface and preparing the roof for installation of False Ceiling. The work includes providing and applying a suspended false ceiling system made of Plaster of Paris (POP) with galvanized iron wire, screws <(>,<)> jute tape over joints to prevent cracking and all other materials<(>,<)> tools, manpower as per site requirement, complete in all respects, as per drawings and the direction of the Engineer. Material & Surface Finish: A 12#15 mm thick POP layer applied, Surface levelled Smooth, seamless <(>,<)> free from cracks, waviness, or unevenness, all corners and edges sharp and true, finished and even plane, Primer and two coats of plastic emulsion to be applied. Final coat of primer and paint applied only after complete drying. Cut-outs: Openings for light fixtures, diffusers, and other fittings provided as per electrical/mechanical layout. False Ceiling to be installed as per provided layout and site engineer approval.		<u>FT2</u>	250		
1.42	<u>Miscellaneous services</u> 1 - Synthetic Enamel Paint (Wooden Doors, steel gates, steel Structure): Providing and applying application of red lead primer (approved make) to		<u>JOB</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

33	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	a dry film thickness of 50 microns and two coats of super gloss Synthetic enamel paint of the same make to a DFT of 50 microns in a minimum of two coats of PSO approved color and shade. This job also includes cleaning the surface preparation as per manufacturer specifications at any height complete in all respect and as directed by Engineer Incharge. 2- Doors & Windows work includes the following: ·,,Wooden Doors: Providing and fixing 1-1/2-inch-thick solid core hydraulically pressed commercial veneer flush door shutters made from batten board conforming to B.S.S 3444 with door frame of size 6" x 2.5" solid deodar wood including iron lugs for fixing frame G.I hinges, cost includes approved door locking system polishing or painting with three coats of Super Gloss Synthetic Enamel of approved shade as per drawings and specifications. ·,,Providing and fixing Door frames in seasoned deodar wood with moisture content 10 to 12% free from whirling grains and Knots. ·,,Providing beading on both sides of the door frame. The door to be treated with door preservative. 3- Providing and fixing aluminum Kick plate 12" high for all wash room doors (existing doors and new doors). 4- Aluminum Door & Windows: Providing and fixing fully glazed Hinged/Sliding/Fixed Doors, Windows and ventilators of blue powder coated aluminum extruded section (as per PSO standards) using specified thickness, PSO standard color clear float glass of fitted with PVC gasket including all hardware and caulking all joints with silicone sealant complete as per specification and drawing. Providing wood packing in entire length of aluminum section. ·,,Aluminum section with 12mm glass (all front doors and glazing walls). ·,,Aluminum section with 5mm glass (for ventilators only). ·,,Aluminum Section thickness 2mm					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

34	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	„Providing and fixing Door Closers as per attached material specification / compliance sheet. 5-„Providing and fixing floor mounted door closers heavy duty for aluminum/ glazed doors as per attached material specification / compliance sheet. Note: Existing aluminum doors and windows will be replaced with new material and existing will be removed completely and to be shifted to PSO designated place (depots / terminal) as directed by Engineer Incharge. complete in all respect and site requirements. 6- Repairing & Painting of Existing Steel Louvers Door (Double Leaf) for DB Room: Job includes anti rust paint and three coats of enamel paint necessary fittings and fixtures including approved locking system complete in all respect. Note: Existing DB room gate will be used and incase of any repair will be part of item with complete cleaning and painting of gate. 7-„Supply & Installation of New Fiber # OH Water Tank (500 Gallons): Providing and Installation of Fiber - OH Water Tanks 500Gallons which includes providing and installation of centrifugal Pump, allied plumbing, piping (PPRC to be used in required length and diameter), all fitting and fixtures required to connect the underground water tank with inflow, outflow all connections with Underground water tank & overhead water tanks, carwash area complete in all respect.					
1.43	<u>BUILDING ROOF WATER PROOFING</u> Roof Treatment includes the following:		M2	100		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

35	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.44	„Removal of existing roof screeding, OH water tanks and all other materials including water pipes etc. „Roof screeding: Providing and laying roof screeding 1:2:4 average 2 1/2" thick at any height in proper slop (1-inch in 10ft) using approved quality crushed stone 1/2" down and fine aggregate (hill sand) of required properties. This job also includes the chamfering border/ gola (150mm by 150mm) along the wall and using welded wire mesh 10 SWG (75mm by 75mm) of Al-Burhan Steel (Pvt) Ltd or approved equivalent to be used with concrete steel nails, including form work (installation & removal) mixing, transporting, placing, compacting, finishing and curing etc. complete in all respect and as directed by Incharge.# „Adequate no's of drain pipes (4" dia uPVC pipe of approved make) to be fixed with hooks and other requirements with wall and dropped in drain pit/ manhole) „Providing & Laying Bitumen coating on roof slab using bitumen 10/20 Grade at 20/25 lb/10m² complete in all respect and as directed by the Engineer Incharge. „Providing & Laying Pea size gravel @ 0.1m³/ 10m² on roof slab complete in all respect as per drawing and specification and as directed by the Engineer Incharge. Plumbing Services PLUMBING WORKS: „Dismantling of Existing wash basin, commode and all plumbing works and debris should be removed by contractor directed by engineer incharge. Supply & Installation of Wash basin of approved make or approved equivalent size 24" x 18" including C.P. waste fitting. plastic waste pipe steel brackets, C.P. mixture, C.P. tee stop cock flexible pipe etc. complete in all respect. „Supply & Installation of Hanging Commode (English Water Closet) with concealed flush Tank, of approved make or approved equivalent includes			1		

JOB



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

36	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	shower arrangements for office wash room all fittings, accessories, C.P. tee stop cock flexible pipe etc. complete in all respect. ·,,Supply & Installation of Asian water closet of approved make or approved equivalent of vitreous china with virtuous china concealed flush tank including includes shower arrangements, C.P. tee stop cock flexible plastic pipe etc. complete in all respect. ·,,Supply & Installation of 1/2" dia. C.P. Stopcock & Bibcock. ·,,Supply & Installation of 4" dia pvc floor trap of C. with minimum 1" water seal. Supply & Installation of UPVC pipe of approved make in following diameters i),,dia 4", 3", 2" or any other requirement of site. ·,,Supply & Installation of PPRC pipe of following diameters for water supply (hot & Cold) lines as per manufacturer specifications and recommendations: i),,dia 1/2" ii),,dia 3/4" iii),,dia 1" iv),,dia 1-1/4" ·,,Supply & Installation of Gate Valve for PPRC Pipeline of following diameters. i),,dia 1/2" ii),,dia 3/4" iii),,dia 1" iv),,dia 1-1/2" ·,, Toilet Accessories: ·,,Toilet paper holder in PSO chrome plated ·,,Soap dish in chrome plated					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

37	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	• „Towel Bar chrome plated • „Cloth Hook chrome plated • „Muslim Shower along with stop cock chrome plated • „Providing and fixing 3 feet x 2 feet clear float mirror with hard board backing and clip fixed to wall with C.P. brass screws etc. complete. Note: Two Bathrooms are to be rehabilitated as per the drawings and layout provided by engineer incharge. ----- ----- General Notes: 1- The contractor must visit the site before quoting. 2- Contractor should submit the document along with bid Material Procurement Schedule, Project Schedule inclusive of mobilization, Site Organogram, list of equipments & manpower to be deployed at site during execution. 3- Contractor will depute Site Engineer (BE Civil/Mechanical) 5 years minimum relevant work experience for the execution of job. Contractor will submit CV along with experience details. 4-Contractor will depute HSE Supervisor with necessary trainings and minimum three (3) years of relevant work experience. Contractor will submit CV of HSE Supervisors along with training certificates. 5-The contractor will obtain prior written approval of PSO site Incharge before starting any major construction activities at site.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

38	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017543

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

13.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	6-The contractor will submit the Fortnight Progress Report inclusive of manpower & equipments details with next 15 days plan. The Fortnight Report will also be submitted with the percentage of completed work against the schedule/ planned till date. 7-Contractor will endeavor to supply the material/equipment as per attached material sheet mentioned in the attached specifications/compliance sheet. If the contractor wants to offer/use material/equipment other than specified, he will clearly mention in his bid which he wants to offer as equivalent. He will submit all technical and commercial details, test reports/FAT's reports/data sheets and other necessary details of the offered material/equipment along with the samples. PSO may ask the bidder to carry out testing, inspections for the offered material/equipments. PSO reserves the right to approve or disapprove the offered item/material as equivalent and will not have an obligation to assign any reason thereof. All such inspections and testings cost are to be borne by the bidder. 8-Bidder would extend his bid validity period if evaluation of equivalent is delayed due to poor response of the bidder. 9-The contractor must clear the site from debris/surplus material on regular/ daily basis. 10-The contractor will adopt special care as per PSO HSE requirements for the dismantling should proceed from top to bottom. 11-Rates are inclusive of all types of taxes e.g SST/PST and GST. 12-The total project duration shall be 110 calendar days, which					



39	OF	39
RFQ No	RC-19847SR	
DATE	29.07.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017543

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	13.08.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: Remodeling of Masjid-e-Khizra fs, Khi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	includes 10 calendar days for mobilization and 100 calendar days for construction. Terms & Conditions: Note: All the work done and task completed within 110 days, after the issuance of Service Order**					