



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	OP-19875NZ	
DATE	03.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017663

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

19.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Installation of RTG on TK-801 and dismantling of RTG from TK-809 at MHK Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Installation of RTG on TK-801</u>	<u>Mehmood</u> <u>Kot (Inst.)</u>				
1.01	<u>Radar Gauging System</u> Installation, testing, Commissioning & Calibration Of: 1. Flex line 990 Radar 2. Vito Temperature 3. Pressure Transmitter Note: Manufacture of RTG Honey well Scope of Work: 1. Installation of given above Instruments 2. Power-up and functional testing of Flex line 990 Radar, Vito Temperature & Pressure Transmitter 3. Configuration of instrument parameters as per approved datasheets. 4. Troubleshooting and correction of configuration-related issues. 5. Wireless communication of radar with WDM & CIU88. CIU888 new backup load into Experion HS & communication. 6. Tank strapping/chart update and verification within the tank gauging system. 7. Validation of level, temperature, and pressure measurements against reference values. 8. Functional testing under operating conditions. 9.Existing wireless network should not be disturbed while carrying out job activity 10.Vendor will ensure wireless communication signal strength to avoid any loss of data 11.vendor will ensure re-establishing of wireless mesh network and point to point wireless communication with the clear of line sight. 12.During this activity, if any fault/damage to existing system occur<(> ,<)> vendor will responsible to rectify without any cost. Note: Installation required on TK-801(HSD), and on 809 after integrity testing/rehabilitation. Also 02 Nos visit & transportation charges included in this line item		<u>JOB</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	OP-19875NZ	
DATE	03.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017663

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

19.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Installation of RTG on TK-801 and dismantling of RTG from TK-809 at MHK Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.02	<u>Radar Gauging System</u> Dismantling of Radar of TK-809 and isolation from main system at MHK 1. Flex line 990 Radar 2. Vito Temperature 3. Pressure Transmitter Note: Vendor will responsible for same dismantling of complete radar system or disconnection from software backend. Terms& Conditions: 1)All Services, tools, material and transportation(>,<)> scaffolding required to be provided by the contractor. 2)Payment will be made as per actual work done. 3)All HSE standards to be followed by the contractor. 4)All contractor staff must wear proper PPEs during work execution. The contractor would have to follow all safety and HSE standards at site with mandatory PPEs (Safety Helmet, Safety Shoes, Cover all or Trouser with T-Shirt as the loose clothes are not allowed) 5)Contractor will ensure proper housekeeping and cleaning of the area during and after completion of work. 6)Job is subject to inspection and verification of Terminal Engineer/Location In charge. 7)Vendor will complete the job within 20 days after email confirmation from location engineer. 8)If the Contractor fails to complete the work within time stipulated (>,<)> the Engineer In charge will be entitled to deduct from his bills a value of 0.10% of total work order amount per day upto maximum		<u>JOB</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	OP-19875NZ	
DATE	03.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100017663

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

19.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Installation of RTG on TK-801 and dismantling of RTG from TK-809 at MHK Terminal.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	10%value of P.O. 9)All materials and items are to be provided and installed subject to approval from location in charge/engineer and to their satisfaction. 10) Visit and transportation charges included in above rate. 2 to 3 visit may required for this jobs 11)Rates are inclusive of all types of taxes. g.PST, GST, etc 12)Payment will be done against actual work done. Partial payments are allowed as per work done. 13) This work order will be valid for 1.5 years and can be extend as per location demand.					