



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	6
RFQ No	IP-198841A	
DATE	09.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017759

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

2:15 PM

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY Fix %
PO/DD NO. _____

Title: Supply, Installation, Testing and Commissioning of PFI Panel at PSO EJHD, Karachi Aviation Station.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	Power Factor Improvement Panel Supply of one no. 150 KVAR, Floor-mounted, indoor-type automatic Power Factor Improvement (PFI) panel. The panel shall be powder-coated 14 SWG sheet steel enclosure. Incoming: - 1 x 400 A TP MCCB 25 KA (adj). - 1 x 12 Stage PFI Relay. - 3 x Current Transformer. - 3 x Exhaust Fan. - 8 X Branded Filter. - 2 X Thermostat Relay. - 4 X Control Fuse. PFI Capacitor: - 1 X 50 KVAR Power Capacitor. - 3 X 25 KVAR Power Capacitor. - 1 X 12.5 KVAR Power Capacitor. - 1 X 7.5 KVAR Power Capacitor. - 1 X 5 KVAR Power Capacitor. - 1 X 50 KVAR TP Magnetic Contactor. - 3 X 25 KVAR TP Magnetic Contactor. - 1 X 12.5 KVAR TP Magnetic Contactor. - 1 X 7.5 KVAR TP Magnetic Contactor. - 1 X 5 KVAR TP Magnetic Contactor. - 7 X 32 A HRC Fuses with Base. - 7 X On/Off Indication Lights (Green/Red). - 7 X On/Off Push Button (Green/Red). - 7 X 16A M-O-A Selector Switch. The Panel Manufacturer Shall: - Provide all necessary supporting switchgear, including MCBs/MCCBs<(> ,<(> contactors, protection components, wiring terminals, and busbar capacity.	EJHD	EA	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	6
RFQ No	IP-198841A	
DATE	09.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017759

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

2:15 PM

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY Fix %
PO/DD NO. _____

Title: Supply, Installation, Testing and Commissioning of PFI Panel at PSO EJHD, Karachi Aviation Station.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	- Ensure space allocation, segregation, and labeling are done accordingly. - Only capacitor units will be required to be procured and added later <(>,<)> all other provisions must be pre-installed. - Any additional switchgear requirement at the time of drawing finalization is also included in this item without any additional cost. - The drawing must be finalized after the satisfaction and approval of PSO Head office team. Note: - Contractor to provide Shop drawing, SLD & Components list prior fabrication for PSO Approval.					
2	Conduit GI 2"dia (M.G.) Supply of 2 inches dia GI Conduit (Medium Gauge) including all bends, tees, sockets, union etc.	EJHD	M	30		
3	Cable 3% C-95 sq.mm PVC/PVC/SWA/PVC Supply of 600 / 1000 V 3.5 core 95 sq.mm Cu/PVC/PVC grade copper conductor cable.	EJHD	M	40		
4	Services EJHD - PFI Panel	PSO House				
4.01	Installation of PFI panel - Supply, installation, testing, and commissioning of a floor-mounted indoor PFI panel, along with all associated works, as per the following scope: 1) Supply of one no. 150 KVAR, wall-mounted, indoor-type Power Factor Improvement (PFI) panel. 2) Installation of PFI Panel and integration & Commissioning with existing main panel. 3) Allied cabling & conduiting works. - Installation of the PFI panel including physical mounting, alignment <(>,<)> and anchoring to the floor. Integration with the existing LT panel / main distribution system. - Work includes all required terminations of all incoming and outgoing		JOB	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	6
RFQ No	IP-19884IA	
DATE	09.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017759

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

2:15 PM

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY Fix %
PO/DD NO. _____

Title: Supply, Installation, Testing and Commissioning of PFI Panel at PSO EJHD, Karachi Aviation Station.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	cables, earth connections and all accessories for installation such as nut, bolts, lugs, cable ties and angle iron frame etc required for installation complete in all respect and to the entire satisfaction of Head office team.					
4.02	6 mm Thick Rubber Mat - Functional testing and commissioning of the system, ensuring stable power factor performance complete in all respect and to the entire satisfaction of PSO Head Office Team. - Supply of 6 mm Thick (1 meter X 1 meter) rubber mat placed in front of Panel.		EA	1		
4.03	G.I. Conduit 2" - Installation of 2 inch dia GI conduit (Medium gauge) Including all bends, tees, sockets, unions etc. complete in all respect to the entire satisfaction of Engineer Incharge.		M	20		
4.04	Cables 3½ C-95 sq.mm PVC/PVC/SWA/PVC - Laying, handling, testing and termination of copper conductor 3.5-Core 95 sq. mm Cu/ PVC/SWA/PVC Cable (from LT room to the room behind HT room) complete in all respect and to the entire satisfaction of Engineer Incharge.		M	30		
4.05	Note: - Proper size tinned copper Lugs and brass glands would be provided by the contractor. - The cables would be laid in the cable tray as per site requirements. Cable Tray (200 x 100mm) - Supply, fixing and installation of Cable Tray of size 200 mm x 100 mm with fixing brackets, covers, nuts, bolts, bends, channels, bracket supports etc. and all accessories required complete in all respect. - Supply of Cable Tray 200 mm x 100 mm, 2 mm thick GI cable tray made from galvanized sheet, not perforated in explosion proof area. Perforated in non-explosion proof area with top cover screwed with SS. The scope of this item includes:		M	30		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	6
RFQ No	IP-198841A	
DATE	09.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017759

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

2:15 PM

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY Fix %
PO/DD NO. _____

Title: Supply, Installation, Testing and Commissioning of PFI Panel at PSO EJHD, Karachi Aviation Station.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	1) Supply and installation of supporting structure (brackets, angles, or channels) for the cable tray. 2) Support spacing to be calculated based on cable weight and tray load-carrying capacity. 3) Contractor shall submit detailed drawing indicating the layout of the cable tray and the proposed supports, with spacing and anchoring methodology. Installation shall only begin after drawing approval. 4) All trays shall be installed level and aligned, with uniform spacing maintained between tray supports. 5) Cable needs to be taken out mid-way along the tray run, the contractor must terminate the cable using brass glands through cut holes with proper bushings. ===== NOTE: 01) Actual installed material will be used for calculation of weight. 02) All equipment to be checked and inspected by PSO HO team. 03) Any site office, store, utility supplies (Electricity, Water etc.) required at site during the execution of works shall have to be arranged by the contractor. 04) Contractor will follow all quality standards given time to time. M <(>&<)>R Engineer along with Contractor must maintain the log book at Site and any changes or observations to be recorded and signed by the HO Engineer. 05) Contractor will utilize skilled manpower for the execution of the project. 06) providing all tools and equipment required for execution of complete job / project is the sole responsibility of the contractor. 07) Contractor will provide activity based schedule after issuance of work order. 08) All rates shall be inclusive of all duties, taxes (GST/SST/PST etc.), levies and transportation charges. 09) All type of consumables, arrangement etc. required for complete scope of work shall be provided by the contractor without any additional					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	6
RFQ No	IP-198841A	
DATE	09.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017759

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

2:15 PM

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY Fix %
PO/DD NO. _____

Title: Supply, Installation, Testing and Commissioning of PFI Panel at PSO EJHD, Karachi Aviation Station.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	cost. 10) All installation shall be done as per satisfaction of PSO HO team. 11) Contractor shall provide 1 year warranty of the supplied material. 12) All field test, megger, continuity test shall be performed during installation in the presence of HO Engineer. 13) Contractor shall restore the site at its original condition after completion of respective jobs. Clearing of debris would also be the responsibility of contractor. 14) Contractor shall strictly adhere and comply with the HSE policy. No compromise would be allowed on HSE during construction works. Contractor shall arrange PPEs (Personal Protective Equipment) and ensure that staff wear the PPEs during execution of work. 15) Prior Approval must be taken for all material to be supplied before commencement of works. Sample to be provided if required / asked by the HO Engineer. 16) The quantities of items may increase or decrease at site. Payment would be made on the basis of actual work done. 17) Prior approval must be taken for all material to be supplied before commencement of works. Sample to be provided if require / asked by the HO engineer. 18) Project completion time is 120 calendar days. Sundays and gazette holidays are non-working days and included in calendar days. 19) Contractor will follow the Plant timings. Plant timings are from Monday to Friday (8:00 A.M to 05:00 PM) <(>&<)> Saturday (8:00 AM to 1:00 PM). 20) Contractor will provide activity based schedule after issuance of work order. 21) Contractor shall restore the site at its original condition after completion of respective jobs. Clearing of derbies would also be the responsibility of contractor. 22) If the Contractor fails to complete the work within time stipulated in the Purchase Order (Without any genuine reason or creditable justifications), the Engineer/Incharge will be entitled to deduct from his due amounts or bills for the job awarded through this order or other monies due to him by PSO, a value of 0.1% of service order per day and					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	6
RFQ No	IP-19884IA	
DATE	09.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017759

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

2:15 PM

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY Fix %
PO/DD NO. _____

Title: Supply, Installation, Testing and Commissioning of PFI Panel at PSO EJHD, Karachi Aviation Station.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	subject to maximum 10% of the service order. AMOUNT OF BID SECURITY: - RS. 50,000/-.					