



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RC-19879SJ	
DATE	06.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017739

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Canopy Fascia Signage Works at NVROs, South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Canopy Fascia Signage Works</u>	<u>PSO House</u>				
1.01	<u>Dismant. & removal of steel struc./sheds</u> Job includes dismantling and removal of existing Panaflex /ACM Fascia Signage including old blue bars, frames, angles, wiring etc complete in all respect JOB-EA (EA is equivalent to one NVRO station). Means Quantity of this item represent number of site(s)		<u>JOB</u>	8		
1.02	<u>Dismant. & removal of steel struc./sheds</u> Providing and installation of new MS structure 18 SWG 3/4" square pipe with red oxide primer (Two coats) along with finish paint White oil (two coats) ICI/Burger for proper fixing of ACM sheets as per PSO approved design. Job further includes Routing, cutting, bending and installation of old ACM sheets new top sheet with as per PSO approved design. ACM will be provided by PSO. The job also includes transportation of ACM Material provided by PSO to proposed site. Installation of new holder sheet is also included in this item. Job is in RFT		<u>JOB</u>	1,400		
1.03	<u>WIRING CANOPY FACIA</u> Providing and laying of new wiring 2x 1.5 mm Sq: PVC Insulated of approved PSO brand.job includes installation of old LED rods will be provided by PSO.		<u>RFT</u>	1,400		
1.04	<u>Fabrication of Miscellaneous Items.</u> Providing and Fixing new aluminium 'Z' channel (2mm thick) in canopy fascia with alignment for the fixing of blue bars. EA-RFT		<u>EA</u>	1,400		
1.05	<u>Fabrication of Miscellaneous Items.</u> Providing and Fixing new aluminium 'L' channel (2mm thick) in canopy fascia with alignment for the fixing of blue bars. EA-RFT		<u>EA</u>	1,400		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RC-19879SJ	
DATE	06.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017739

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Canopy Fascia Signage Works at NVROs, South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	Installation of LED Lights Supply, Installation, Testing and Commissioning of LED Tube Rod, 4 feet at NVROs. Job includes: Removal of existing tube rods from the fixture. Installation of new LED rods in the fixture. Electrical Rewiring for the rod (if required) with 3/0.029 gauge wire of Pakistan cables or approved brand. Body: Plastic Length: 4-feet Diode: LED Body thickness: 1200mm or above Intensity: 1600 lumens or above Power Rating: 10.5W-16W max. Color: 5000K-6000K (White) Color Rendering Index: 70 or above Life Span: 15000 Hours or greater Lux Level: Minimum of 2000 Lux (avg) Operating Temp (degree): -10C to 60C Terms & Conditions: ===== 1. The rates of items are inclusive of all taxes or any other tax applicable and contractor is required to submit GST/ SST invoice at the time of invoice. 2. Contractor will arrange testing of equipment at his own cost, if required. 3. Quality of work is the prime concern of PSO. The contractor will be required to produce best quality work. 4. Work must be completed within 180 days after site handed over to contractor. 5. Contractor has to comply with all HSE procedures and policies during execution of the work.		EA	170		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RC-19879SJ	
DATE	06.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017739

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

25.08.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Canopy Fascia Signage Works at NVROs, South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	6. Contractor should strictly follow the safety and security rules of PSO. Contractor's team has to follow Company's rules and procedures as well as HSE guidelines and safety procedures. 7. All labour, tools, materials and transportation to be provided by contractor. 8. Payment will be made as per actual quantity of Work Done. 9. If the Contractor fails to complete the work with in time stipulated, the Engineer Incharge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of SO. 10. Contractor should maintain housekeeping of the workplace during progress of work and shall clear and remove all surplus materials and rubbish from workplace after completion of job as per instruction of Incharge. 11. The work will only be accepted after inspection and approval by the DE. 12. Bidder must visit the site before quoting for the job to properly asses the scope of work. 13. Damage to the False Ceiling during replacement of sheets is to be born by contractor himself. 14. Rates are inclusive of scrap materials 15. Work will be performed using proper PPEs like, harness<(>,<)> safety helmets, Shoes etc complete in all respect.					