



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	4
RFQ No	OP-19859AM	
DATE	17.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017814

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

01.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Supply, Installation, Testing <(>&<) Commissioning of 11kV Incoming MV Panel at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>MV Panel for Solar Net Metering KTA</u>	<u>Keamari</u>				
1.01	<u>Installation of MV Switchboard</u> Supply, Installation, Testing and Commissioning of MV Incoming panel at KTA Gasoline The job includes: A. Supply of factory-built, metal-clad, indoor type MV Incoming panel rated 630 Amps, 25kA suitable for 11kV, 3-phase, 50Hz system, complete with vacuum circuit breaker and all standard accessories as per specification sheet attached with tender documents. The COMPONENTS DESCRIPTION and quantity required areas follows: · Sheet Metal Cubicle with 630AMBB, 25kA of make Schneider/Arson and the required quantity is 1. · VCB-630A, D/O with Tulip Contact, 25kA/3Sec. (motorized operation with Shunt trip & UVT) of make Schneider and the required quantity is 1. · Relay with O/C, S/C, Earth Fault Protection of make P123/P115/Schneider/Equivalent and the required quantity is 1. · Digital Energy Analyzer of make Schneider and the required quantity is 1. · Insulator 175 of make METELX/FICO and the required quantity is 3. · PTs 11kV/#3/110/#3, Class 0.5, 100VA (Rating shall be as per requirement) of make METELX/FICO and the required quantity is 3. · CTs 100/5/5A, 5P20 15VA, 0.5M 510VA (Rating shall be as per requirement) of make METELX/FICO and the required quantity is 3. · Analogue Ammeter (0-200A) of make Schneider and the required quantity is 1. · Ammeter Selector Switch (4-Position) of make Schneider and the required quantity is 1. · Analogue Voltmeter (0-11KV) of make Schneider and the required quantity is 1. · Voltmeter Selector Switch (4-Position) of make Schneider and the required quantity is 1. · Indication Lamp 'CBON'RED, 110VAC of make Schneider and the required quantity is 1.	<u>Terminal</u>	<u>JOB</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	4
RFQ No	OP-19859AM	
DATE	17.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017814

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

01.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Supply, Installation, Testing <(>&<)> Commissioning of 11kV Incoming MV Panel at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	· Indication Lamp 'CBOFF' GREEN, 110VAC of make Schneider and the required quantity is 1. · Indication Lamp 'TRIP' YELLOW, 110VAC of make Schneider and the required quantity is 1. · Indication Lamp 'TRAFOALARM' WHITE, 220VAC of make Schneider and the required quantity is 1. · Indication Lamp 'SERVICE and TEST POSITION' of make Schneider and the required quantity is 1. · Push Button 'CBON', RED-1NO of make Schneider and the required quantity is 1. · Push Button 'CBOFF', GREEN-1NO of make Schneider and the required quantity is 1. · Push Button 'HOOTERMUTE', BLACK- 1NO of make Schneider and the required quantity is 1. · Push Button 'LOCKOUTRESET', BLACK-1NC of make Schneider and the required quantity is 1. · Fluorescent Light 220VAC of make Local and the required quantity is 1. · Door limit switch with 1NC of make Schneider and the required quantity is 1. · Anti Condensation Heater 60W, 220VAC of make E Logics and the required quantity is 1. · Humidity Sensor 220VAC of make E Logics and the required quantity is 1. · Capacitor Trip Unit of make E Logics and the required quantity is 1. · Status Indication Relay (04 Window) of make ELAB and the required quantity is 1. · Selector Switch of make Schneider and the required quantity is 1. · Selector Switch for LOR of make Schneider and the required quantity is 1. · Control Relay 14 Pin, 220VAC with Base, 4C/O of make PHEONIX and the required quantity is 1. · Control Relay 14 Pin, 110VDC with Base, 4C/O of make PHEONIX and the required quantity is 1. · 3-Pole, 6A-6KA <(>&<)> ACMCB 110VAC of make Schneider and the required quantity is 1.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	4
RFQ No	OP-19859AM	
DATE	17.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017814

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

01.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Supply, Installation, Testing <(>,<)> Commissioning of 11kV Incoming MV Panel at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	· 2-Pole,6A-6KA<(>,<)> ACMCB110 VAC of make Schneider and the required quantity is 1. · 2-Pole,4A-6KA<(>,<)> ACMCB 110VDC of make Schneider and the required quantity is 1. · 2-Pole,6A-6KA<(>,<)> ACMCB 220VAC of make Schneider and the required quantity is 1. · 1-Pole,2A-6KA,ACMCB220VAC of make Schneider and the required quantity is 4. · CT Terminal 6sqmm of make Phoenix and the required quantity is 10. · Shorting Link/End Plate for CT Terminal of make Phoenix and the required quantity is 12. · Terminal Block 4sqmm of make Phoenix and the required quantity is 80. · End Plate / End Stopper for Terminal Block of make Phoenix and the required quantity is 60. · Hooter, 220VACofmakeCAMSCO/Equivalent and the required quantity is 1. · Earthing Switch of make Schneider/Equivalent and the required quantity is 1. · Surge Arresters of make Schneider/Equivalent and the required quantity is 1Set. B. Installation, Testing and Commissioning of MV Incoming panel Scope includes the following activities for the above 11kVMV Panel: 1. Shifting of panel to installation location Positioning, leveling<(>,<)> alignment,anchoring 2. Busbar coupling with existing panel (as per PELGA drawings) 3.CT/PT secondary wiring<(>,<)> control wiring terminations 4. Verification of all interlocks, limit switches, space heaters<(>,<)> auxiliaries 5.Relay configuration<(>,<)> protection settings<(>,<)> scheme testing 6.Functional testing of VCB(manual+motoroperated) 7.Meggertests<(>,<)> continuity tests and control circuit checks 8.Pre-commissioningchecksaspermanufacturerguidelines 9.Energization support and final commissioning					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	4
RFQ No	OP-19859AM	
DATE	17.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017814

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

01.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Supply, Installation, Testing <(><)> Commissioning of 11kV Incoming MV Panel at PSO Keamari Terminal A.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	C. TRANSPORTATION OF 11KV MV PANEL FROM MANUFACTURER TO PSO-KTA SITE Transportation scope includes: 1. Loading of panel from manufacturer's facility 2.Safe transport to PSO KTA site 3.All handling equipment <(><)> Labor <(><)> and logistics 4.Protection against vibration ,moisture<(><)> and impact during transit Panel to arrive damage-free for installation at site. Terms and Conditions: 1)All type of taxes are included in the above rates. 2)Contractor should strictly follow the Safety and Security Rules of PSO. 3)Safety of Vehicle Shall been sured by contractor. Any damage during transportation shall be bear by the contractor. 4)All Labor, tools,materials and transportation to be provided by contractor. 5)Payment will be made after completion of job as per Directions/satisfactions of Engineer and actual quantity of work done. The contractor shall provide six months warranty for the material and services provided. 6)The contractor must complete the job within 12 weeks after the issuance of PO. If the Contractor fails to complete the job within stipulated time<(><)> PSO will be entitled to deduct an amount equivalent to 0.1% of the Purchase Order value per day as liquidated damages for the period upto maximumof10%of the value of PO. 7)The contractor will be responsible for any sort of damage to the material/items during transportation. 8)The Services will be provided at PSO Keamari Terminal A Gasoline Section.					