



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	2
RFQ No	RC-19892AM	
DATE	17.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

01.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Pavers at PSO S/S 02 ,CORO site,lsb Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Replacement of Pavers at PSO S/S 02</u>	<u>PSO House</u>				
1.01	<u>P/L 80 MM PAVER EXIST. PAVEMENT</u> Providing and Laying Precast Concrete Pavers of size 200 mm x 100 mm x 80mm: Providing and laying precast concrete pavers of size 200 mm x 100 mm x 80mm thick having a minimum compressive strength of 7000 psi, including all necessary materials, labor, tools, and equipment to complete the work as specified and directed by the Engineer In-Charge. Scope of Work Includes: - Removal of Existing Pavers: Removal of old pavers and stacking of old removed pavers properly at site as per instructions of Engineer in-charge, including excavation of all kinds of existing strata as required. - Preparation of Base/Sub-base: Laying of river sand or khaka up to the required level; compaction of the base/sub-base using a minimum 10-ton roller or plate compactor to achieve proper surface stability and levelling. - Bonding Layer: Provision and spreading of fine sand or other approved bonding materials for leveling and bedding purposes. - Laying of Pavers: Proper laying of paver blocks in the required pattern, ensuring tight joints and uniform alignment. - Joint Filling and Finishing: Filling of joints with fine river sand/khaka and finishing of the surface to achieve a neat, level, and compact appearance. Note The timeline of work is 30 days from issuance of PO or handing of site TERMS AND CONDITIONS: 1) All applicable Govt taxes are included in the given rates. 2) Parts / services provided are subject to inspection and satisfaction of the location engineer.		<u>SFT</u>	13,500		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	2
RFQ No	RC-19892AM	
DATE	17.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017839

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

01.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Replacement of Pavers at PSO S/S 02 ,CORO site,lsb Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	3) Job completion time = 30 days. 4) Quantities may vary. However, payment will be made as per actual quantity of work done. 5) All tools, equipments and consumables required for the job will be arranged by the contractor at his own cost. 6) Disposal of scrapped / removed material is the responsibility of the contractor. 7) Strict HSE compliance must be ensured. All HSE measures will be adopted in accordance with PSO safety guidelines,DEs instructions and standard safety procedures for such works must be ensured. No compromise whatsoever shall be made on this, and if no-compliance is found at any site, work shall be stopped immediately. delay penalty in such case shall be on vendor's part. **All the work done and task completed within 30 days, after the issuance of Service Order**					