



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	5
RFQ No	OP-19887AS	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017910

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation for Tank 5904 at Kotlajam Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Rehab work of tank 5904</u>	<u>Kotlajam</u>				
		<u>(Depot)</u>				
1.01	<u>"Supply & fabrication of steel structure</u>		<u>KG</u>	1,200.000		
	Rehabilitation for Tank 5904 at Kotlajam Depot Job Include :					
	1.Supply and Installation of Safety Railing on the top of Tank 2.Bottom build-up					
	3.Repainting of Tank (sand blasting ,grid blasting , painting of all supplied material , tank Bottom , Tank sheet ,Roof stairs, hand rials all are the part of painting work)					
	4.Repairing of Tank Pad Scope of work:					
	Sr no 1. Supply and Installation of Safety Railing on the top of Tank					
	Supply of Miscellaneous Steel for columns, beams, pipe supports, bolts, walkways platforms, staircase, Manholes, Covers, stud bolts and nuts, Grating and frame for valve pit, shed, grating and cut-off drain for gantry etc. Rates will be applied all type of steel sections / plates to be used in fabricating the structure as per drawings & specifications including but not limited to channels, beams, chequered plates, plain plates, pipes, flat bars, angle irons, bolts, j-bolts,					
	Note: Supply of deformed steel reinforcement bars. All wastage, cuttings, overlaps and chairs are included in the cost and no extra payment will be made in this regard. Only actual laid quantities will be considered for payment. Mill test Certificate from the manufacturer will be provided by the contractor . Deformed steel of yield strengt 60,000 psi. (as PSO Approved)					
1.02	<u>Fabrication welding and installation of</u>		<u>JOB</u>	1		
	Sr no 02. Bottom build-up Minimum 04 and as per requirement					
	All required inspections, UT mapping(>,<) thickness measurements, and assessment activities have already been completed prior to execution of repair work. The identified pitted areas of tank bottom plates having remaining thickness shall be repaired through weld build-up method in accordance with approved procedure and applicable requirements of					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	5
RFQ No	OP-19887AS	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017910

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation for Tank 5904 at Kotlajam Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	American Petroleum Institute API 653. After completion of build-up welding, the repaired areas shall be dressed and subjected to applicable Non- Destructive Testing (NDT) including DPI/DPT, UT, and any other inspection requirement as advised by inspection department to verify weld soundness, thickness restoration, and integrity of repaired sections prior to acceptance and commissioning. (Required testing as per standard is included in the scope , report of the same will also be shared with facility engineer) Paint Works (Sft) Sr no 03. Paint work Tank Repainting of Tank (sand blasting ,grid blasting , painting of all supplied material, tank Bottom , Tank first shell internal Tank shell outer ,Roof stairs, hand rials all are the part of painting work as PSO Approved) Preparation of steel structure surface as per PSO Approved Maintenance Coating system. CONCATENATE ("Application of base coat Polyamine cured epoxy mastic (surface tolerant epoxy) min thickness ", Sheet1!H3, " microns as per PSO Maintenance coating system standard.") Application of top coat Polyurethane minimum thickness 60 microns as per PSO Maintenance coating system standard. Preperation of surface, application of Base coat and application of top coat as per Maintenance coating system on Product pumps complete in all respect. Provision of steel scaffolding as per site requirement. The payment will be made based on the surface area coated above the height of 3 ft from ground for structures where scaffolding is used. The usage of scaffolding is to be approved by PSO Location Engineer beforehand. After installation of scaffolding it is to be checked and verified by PSO Approved third party inspector. Stencilling/Labelling /marking/flow direction and colour coding on product pipelines as per attached Annexure F on entire length of product pipelines, including previously painted pipelines as well. using polyurethane coating as per specs. sand blasting ,grid blasting ,i.e all are the part of paint PSO Approved. Term& Condition All tools, materials, labour, inspection tools, transportation, handling, handling, lifting equipment ladders, stairs to be provided by the contractor. 2) All inspection tools to be provided by the contractor.		SFT	1,105		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	5
RFQ No	OP-19887AS	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017910

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation for Tank 5904 at Kotlajam Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	3) The inspection tools are to calibrated by approved third party lab. 4) Any Paint manufacturer requirement for paint application to be carried out by the contractor in addition to PSO Maintenance Coating System after approval from PSO. 5) Colour shades to be as per PSO Specifications. 6).The rates are inclusive of all Govt. taxes, transportation, Note: App specs are attached Foundation Sr no 04. Repairing of Tank Pad The civil repair work of tank foundation shall be carried out to rectify damaged, settled, or deteriorated portions of the foundation to ensure proper structural support and uniform load distribution beneath the tank bottom. The scope includes foundation repair, re-leveling, concrete restoration, gap rectification, and strengthening of affected areas as required. After completion of civil works, final inspection and level verification shall be performed to ensure the foundation condition is suitable for safe operation and compliance with applicable standards. Terms and Conditions: 1.Rates should be inclusive of all types of taxes. 2. Contractor to provide third party fitness certificate for all the equipment's to be used for execution of work including but not limited to welding machines, cranes, compressors, safety harness / equipments etc complete in all respects - Sample formats are attached with the bid documents. 3. Contractor will provide Sales & Service Tax Invoice along with the bill. 4. Acceptance of the equipments / materials is subjected to inspection of PSO representatives. 5. Contractor will provide fire fighting equipments, PPE's and fulfill all HSE requirement and measure during the execution of works. PSO's Safety Booklet Construction, Electrical, PPE's etc) should be referred		JOB	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	5
RFQ No	OP-19887AS	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017910

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation for Tank 5904 at Kotlajam Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	in this regard. 6. All supplied materials and accessories should be brand new and from fresh stock. Contractor will submit the MTC's of the material wherever required. Contractor will arrange inspection / testing of all supplies / materials that will be provided / supplied by the Contractor. All cost pertaining to this inspection / testing shall be borne by the Contractor. 7. Contractor shall responsible/rectify any damage occurred to PSO property during execution of work without charging any cost to PSO. 8. Contractor will jointly visit with Site Engineer to ascertain the actual quantities of material required for the job before delivery of material at the site. 9. Contractor will depute Site Engineer BE (Engineering) atleast 5 years minimum work experience for the execution of job & HSE Supervisor atleast 3 years minimum work experience (as mentioned in Technical Evaluation). 10. Existing material (pipes and other structure etc) may be utilized depending upon the usability of the material on sole discretion of PSO and as per instruction of PSO engineer. 11. Providing all Tools & Equipments required to execute the complete Job / Project is the sole responsibility of the Contractor. 12. Contractor / Supplier to provide welder procedure specification and qualification record. Contractor will carry out Welding Qualification Procedure Test, Welder Qualification Test for all welders in the presence of M<(>&<)>R / Project Engineer and all related NDT and mechanical test as per applicable codes / standards at their own cost 13. For Supply item, Payment to be made according to actual dimensions. 14. Gaskets to be provided & installed by Contractor, for all the Nozzles, Manholes etc. Contractor will provide Gaskets for Hydrotesting, and for Box- up for Commissioning of pipeline , without charging any additional cost to PSO. 15. Unbolting, Rebolting (for Hydrotesting, for Box-up etc.) of all Nozzles and Manholes is included in Contractor overall scope. Contractor will not charge any additional cost to PSO for these activities. 16. All Hot Work activities must be performed in purely isolated (Fire					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	5
RFQ No	OP-19887AS	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017910

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation for Tank 5904 at Kotlajam Depot

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	retardant fully protected shed) IT IS ADVISABLE FOR ALL BIDDER TO VISIT PSO KOTLAJAM OIL DEPOT PRIOR TO SUBMIT THE TENDER, IN ORDER TO ASCERTAIN THE ACTUAL WORK SCOPE CLEARLY & COMPLETELY, AND TO UNDERSTAND THE SITE CONDITION **All the work done and task completed within 120 days after the issuance of Service Order**					