



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	2
RFQ No	OP-19520AM	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017919

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Installation of Pvers over Old water pond at PSO Depot Faqeerabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Pavers work Installation for water Pond</u>	<u>Faqirabad (Depot)</u>				
1.01	<u>EXCAVATION</u> Excavation in all kind of strata/ soil (dry or wet etc. Including clearing and grubbing of site complete in all respects, including all operation, complete with breaking clods, levelling, dewatering, shoring and compacting.		<u>CFT</u>	2,016		
1.02	<u>"Exca/BackFilling, of Surplus earth."</u> Backfilling of approved earth (Sweet)obtained from outside source and filling pond soil, remaining in layer not exceeding 150mm in depth compaction of soil as to achieve 95 % AASHTO modified dry density and approval & instruction of PSO Engineer/ In charge. Note: - Actual compacted depth shall be considered for measurement/payment. Cost includes compaction test and other related test shall be carried out to find stability of soil through approved laboratory to be arranged and paid by the contractor. No extra charges will be paid to contractor.		<u>M3</u>	28.550		
1.03	<u>Laying sub-base</u> Laying of 2inch sand i-e fine river/ sand / Lawrencepure shall be utilized for this purpose. Material must be layered in layer and compaction to achieve compaction strength of 95% AASHTO.		<u>M3</u>	9.120		
1.04	<u>Providing and laying pavers</u> Supply and laying of precast concrete pavers of type of size 200x40x80 mm thick laid in herringbone pattern and should have minimum compressive strength of 42/mm2 (7000 PSI) to be laid over 2-inch-thick compacted sand graded to BS-882 and avoid to be filled by SAND and finally pavers to be compacted with pate compactor. Job to be completed as per the instruction of Depot In-charge/ Engineer. Terms and Conditions: 01) The job includes Labour, transportation and all material charges. 02)All Govt. taxes and SST is included in the above-mentioned rates. 03)All services, tools, tackles, material, transportation to be arranged by the Contractor.		<u>M2</u>	187.360		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	2
RFQ No	OP-19520AM	
DATE	19.08.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100017919

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Installation of Pvers over Old water pond at PSO Depot Faqeerabad

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	04) Quality is the prime concern of PSO, no compromise shall be made in this regard. Only first class approved quality material, workmanship and supervision will be utilized by the contractor which shall strictly conform to the WO/PO specification. 05) Contractor should strictly follow the safety and security rules of PSO. Contractor to follow Company's rules and procedures as well as HSE guidelines and safety procedures. 06) Payment after completion of the job on submission of the bill, duly verified by the concerned officials. 07) Payment will be made against the vendor invoices after completion of specific job(s) and inspection by the PSO designated official within 30 days. 08) The Contractor will visit the Depot after the Issuance of Service Order, coordinate with the Depot team and as per the availability of the designated area, the contractor will carry out the task within 25 days after the signing of service order.					