



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	6
RFQ No	RF19667SZ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018134

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services Required for M<(>&<)>R Works for PSO Zoom Tower Installed Across South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Rehabilitation of Zoom Towers South</u>	PSO House				
1.01	<u>Preparatory works</u> Preliminary work arrangements / resources: (For 04 nos. Zoom Signs installed all across the South Zone- List attached) Necessary work arrangement for 'work at height'- 120FT (Approximate) Preparatory works includes (but not limited to) following activities: A. Development of Project management and safety risk plan. B. Based on the safety requirements, arrange suitable crane as per requirement (at least 45 Tonne, minimum 130ft boom length and 3rd party certified crane). Job also includes development of safe temporary work platforms. C. Cordoning off the work area in the vicinity. NOTES: ----- 1. Contractor to provide third party fitness certificate for all the equipment to be used for execution of work included but not limited to Cranes, welding machines, safety harness / equipment, etc. complete in all respects. 2. The work area should be properly cordoned off with the barricading sheets, tapes, stop and warning signs for ingress of un-authorized personnel. 3. Necessary arrangements such as Green Net etc. to avoid/restrict any falling objects, Staff, Material, Transportation , Camping/residence, Mess, TA/DA and Engineering and HSE staff and tools expenses. 4. Deployment of experienced Site Engineer / Site Supervisor. 5. Deployment of HSE officer having NEBOSH/IOSH certification. 6. HSE officer will not allow any work after the sunset and will strictly adhere to PTWs/safety certificates.		EA	4		
1.02	<u>Miscellaneous</u> Fabrication of Steel Structure (Unit: Kg)		EA	100		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	6
RFQ No	RF19667SZ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018134

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services Required for M(>&<)R Works for PSO Zoom Tower Installed Across South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	(As per requirement and for 04 nos. Zoom Signs installed all across the South Zone- List attached) Supply and Installation of new Steel Structure including L Angle, Bracings, Plain Plates, U Bolts, Nut Bolts, washers, studs etc. The Job includes making weld joints as per API 1104 standard and using E70XX Electrodes. The Job also includes using Die Penetration Testing (DPT) for testing the quality of Weld Joints in rectangular and circular portion of Zoom Tower. Scope of Work Includes the following: 1- Safe removal of loose/damaged structure. 2- Deployment of experienced welder (Valid certificate required) for fabrication work. 3- Providing the Third party certified welding plant. 4- Providing & installation of required & relevant material for welding. 5- Steel Structure Iron Angle L 2"x2"x1/4" as per recommendation of consultant. 6-Use of Welding protection sheet is mandatory. 7- The Contractor will submit Welding Procedure Specification (WPS), Procedure Qualification Record (PQR) and Welder Qualification Test Record (WQTR) prior to start of the job. 8- Paint of New structure: scope includes, preparation of surface and application of paint on new steel structure which includes but not limited to 2 coats of primer minimum DFT 50 microns followed by 2 coats of enamel paint to a minimum DFT of 50 microns compatible to be done. Note: 1- Any minor/major damage to existing PSO Signage flex/structure after the site handover from respective Divisional Engineer will result in replacement of complete PSO Signage flex by the contractor at his own expense. 2- As per site requirement, area will be cordoned off properly by using scaffolding and GI sheet (before any hot work). 3- Fabrication, Welding shall be done as per relevant					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	6
RFQ No	RF19667SZ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018134

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services Required for M<(>&<)>R Works for PSO Zoom Tower Installed Across South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	standard and cost of any additional welding qualification procedure tests (if required), welder test (if required) and all sorts of testing shall be borne by the contractor. Further, this extra cutting and fabrication shall be borne by the Contractor. 4- All types of consumables (welding electrodes, gas etc.) <(>&<)> scaffoldings required for the fabrication, erection, installation <(>&<)> welding job shall be provided by Contractor, without any additional cost. All tools, equipment, cranes, scaffoldings, strings etc. are to be arranged by Contractor to carry out above defined work i.e. Contractor will not charge any additional cost to PSO for this. 5- Unit: Kg <u>Repair of weld seam</u> (As per requirement and for 04 nos. Zoom Signs installed all across the south Zone- List attached) Making Weld Joints, in existing installed structure for further strengthening the already present weld joints, as per AWS D1.1 and API 1104 standards. The Job also includes using Die Penetration Testing (DPT) for testing the quality of Weld Joints. Job further includes Paint of weld joints including surface preparation and application of paint which includes but not limited to 2 coats of primer minimum DFT 50 microns followed by 2 coats of enamel paint to a minimum DFT of 50 microns compatible to be done. Note: 1. Only One Welding Joint will be considered when the existing welding joint of two different Steel Mechanical plates is rewelded/ strengthened. 2. Unit: M = One Weld Joint between two Steel Plates 3. Weld to be mostly performed at joint between base plate and stiffener plate and at joint between circular pole and stiffener plate. 4. The Contractor will submit Welding Procedure Specification (WPS), Procedure Qualification Record (PQR) and Welder Qualification Test Record (WQTR) prior to start of the job.		M	300		
1.04	<u>Zoom Signage</u>		EA	4		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	6
RFQ No	RF19667SZ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018134

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services Required for M(>&<)>R Works for PSO Zoom Tower Installed Across South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	Tightening of Nuts/Bolts (As per requirement and for 04 nos. Zoom Signs installed all across the South Zone- List attached) 1- Proper cleaning of nuts/bolts. 2- Tightening of nuts/bolts through nut tightening machine in order to ensure proper tightening. -During tightening of nuts, if any nut got damaged/cracked(>,<)> the replacement cost will be borne by vendor. Cleaning Miscellaneous Cleaning of Internal Steel Structure and Logo Skin (As per requirement and for 04 nos. Zoom Signs installed all across the South Zone- List attached) 1- Cleaning of internal steel structure of circular logo and rectangular portions. 2- Cleaning of PSO Logo skin where applicable (both circular and rectangular) with glitter as per signage cleaning scope. -During cleaning, if skin got damaged/cracked, the replacement cost will be borne by vendor.		EA	4		
1.06	Paint Miscellaneous Paint work at Steel Structure (As per requirement and for 04 nos. Zoom Signs installed all across the South Zone- List attached) 1- Providing & application of one coat of brilliant white colored enamel paint at steel structure. 2- Paint of ICI or equivalent is required. 3- Unit of measurement is Each (mentioned for each zoom sign, i.e. 04 Nos)		EA	4		
1.07	Providing/fixing tube light. Providing / Installation of LED Tube Rods (As per requirement and for 04 nos. Zoom Signs installed all across the South Zone- List attached) 1- Providing & Installation of new LED tube rods of PHILIPS or equivalent 14 W and 4 ft long polycarbonated-plastic body (along with connectors) and making necessary electrical connections. (specifications sheet attached)		EA	1,000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	6
RFQ No	RF19667SZ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018134

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services Required for M<(>&<)>R Works for PSO Zoom Tower Installed Across South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	2- Providing the 1.5mm electrical cable of Pakistan Cables or equivalent for LED tube rods as per site requirement. TERMS AND CONDITIONS: 1.<(>,<)>Contractor will be responsible for the removal / disposal of debris outside retail outlet premises as per the instruction of the engineer incharge 2.<(>,<)>Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. 3.<(>,<)>The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment, undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes <(>,<)> Gloves, Helmets, Googles, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. 4.<(>,<)>The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 5.<(>,<)>All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 6.<(>,<)>Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. 7.<(>,<)>Wherever applicable, contractor is bound to engage certified / licensed electrician for electrical works. 8.<(>,<)>Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	6
RFQ No	RF19667SZ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018134

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Services Required for M<(>&<)>R Works for PSO Zoom Tower Installed Across South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	, etc.). For any special case, approval from DE will be required and work will be performed under supervision of DE. 9.<(>,<)>The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines , overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 10.<(>,<)>The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs <(>,<)> smoking in #no smoking# area, etc) during work. Contractors will also ensure proper work planning and risk assessment prior to start of work. 11.<(>,<)>The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 12.<(>,<)>The contractor shall indemnify PSO, its offices<(>,<)> employees, agents and representatives from and against all losses, costs , penalties, fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by this contract. 13.<(>,<)>Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO. 14.<(>,<)>All Government taxes are included in these rates. 15. All prices for services of third party certified crane are included in it. 16. job to be completed within 300 days after handing over the site					