



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Cleaning & De-gassing of Tank-307 at KTB</u>	<u>Keamari Terminal</u>				
1.01	<u>Bolting/Unbolting of pipe joints</u> Unbolting & Bolting of 16" Dia Flange Joints: Scope Includes: Application of suitable anti-rust/penetrating spray on the bolts and nuts prior to commencement of unbolting activity. The contractor shall carefully unbolt and dismantle 02 Nos. existing 16-inch diameter flange joints using appropriate non-ferrous/non-sparking tools. After completion of the required tank cleaning and degassing activities <(>,<)> the contractor shall reassemble and properly bolt 01 No. 16-inch diameter blind flange, including installation of the required gasket and tightening of bolts/nuts uniformly and adequately to ensure a leak-tight joint. All required workers, non-ferrous tools, anti-rust spray, consumables, and other accessories necessary for satisfactory completion of the work shall be arranged by the contractor.		<u>EA</u>	3		
1.02	<u>Installation of Valve 16" dia</u> Dismantling of 16" Dia Gate Valve (Delivery Side of Tank): Scope of Work: Includes the safe dismantling and removal of 01 No. 16-inch diameter gate valve installed on the delivery line. The valve shall be carefully disconnected and removed using suitable chain blocks/lifting arrangements and appropriate non-sparking/non-ferrous tools, as applicable, ensuring safe handling without damage to the valve, pipeline, or associated components. After removal, the dismantled valve shall be safely shifted and placed at the location designated by the M<(>&<)>R Engineer/PSO Representative. Following removal of the valve, the contractor shall install 01 No. 16-inch diameter blind flange on the open pipeline side, including the required gasket, bolts, nuts<(>,<)> and proper tightening to ensure a secure and leak-tight connection. All required labor, tools, lifting equipment, tackles, and consumables necessary for satisfactory completion of the work shall be arranged by the contractor.		<u>EA</u>	1		
1.03	<u>Degassing of Vessels</u> De-Gassing of Tank with Explosion Proof Fans and Installation of		<u>JOB</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Explosion Proof LED Lights inside tank: Scope of work: The scope of work includes complete de-gassing/gas-freeing of Tank-307, having approximately 16 m diameter and 14.5 m height, using suitable explosion-proof exhaust fans/blowers to achieve a safe and gas-free condition for subsequent tank cleaning activities. 1. The contractor shall arrange, supply, install, operate and remove 02 Nos. 24-inch diameter explosion-proof exhaust fans/blowers, duly ATEX-approved/certified, with 01 No. installed at the shell manhole and 01 No. installed at the roof manhole. The exhaust arrangement shall be suitably positioned and operated to facilitate effective removal of hydrocarbon vapours from the tank and achieve the required gas-free condition. 2. Upon completion of de-gassing, the contractor shall arrange and install suitable ATEX-approved explosion-proof LED lighting inside the tank to facilitate safe execution of internal cleaning activities. A minimum of 03 Nos. explosion-proof LED lights shall be provided inside the tank, with adequate positioning/illumination to achieve an overall illumination level of approximately 1000 Lux at the required work areas. (Vendor will arrange lux Meter to verify the reading) 3. The contractor shall arrange all necessary ATEX-approved/explosion-proof electrical accessories and temporary installations, including power cables, cable protection/conduits/pipes <(>,<)> explosion-proof distribution board (DB), earthing arrangement for the DB, lighting fixtures, connectors, plugs, glands and all other accessories required for safe and satisfactory completion of the job. 4. All explosion-proof/ATEX equipment and instruments proposed for use shall be supported by valid OEM/manufacture certificates, ATEX certification, technical datasheets and other relevant compliance					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	documents. The contractor shall submit the required documents to the M <(>&<)>R Engineer/PSO Representative for verification and approval prior to mobilization/use of the respective equipment. No explosion-proof equipment or instrument shall be permitted for use inside/around the tank until its compliance has been verified and accepted by the M <(>&<)>R Engineer. In case any equipment/instrument is found non-compliant, defective, unsuitable or not meeting the required safety standards, the contractor shall immediately replace it with an acceptable and duly certified alternative at no additional cost to PSO. 5. All installation, operation, shifting, dismantling and removal of temporary de-gassing and lighting arrangements, including required labor, tools, tackles, electrical accessories and consumables, shall be in the contractor's scope. The contractor shall ensure that all equipment and temporary electrical installations are properly earthed and maintained in safe operating condition throughout the work. 6. The de-gassing activity shall be carried out under the applicable PSO HSE requirements, approved Permit-to-Work system, confined-space entry requirements and gas-testing requirements. The tank shall only be declared safe for subsequent entry/cleaning activities after satisfactory gas testing (by PSO Approved 3rd Party representative) and confirmation by the authorized PSO/HSE representative. Cleaning and Sludge Removal Internal Cleaning of Tank Bottom, Shell and Roof & Removal of Sludge/Contaminated Water: Scope of work: 1. The scope of work includes complete internal cleaning of Tank-307 (16 m diameter × 14 m height), previously in HSFO service, including removal of accumulated/deposited HSFO residues from the tank bottom, complete internal shell surface and roof. Since HSFO deposits may be firmly adhered to the tank surfaces, the cleaning shall be carried out manually using suitable methods and tools, including brass/non-sparking scrapers <(>,<)>					
			JOB	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	wherever required, to loosen and remove the deposited material without damaging the tank plates or coating. 2. Prior to commencement of shell and roof cleaning, the contractor shall arrange and erect suitable mobile scaffolding inside the tank<(>,<)> complete with proper castor wheels, locking arrangements, working platforms, guardrails and other necessary safety accessories. (Safe for Use certified of scaffolding will be required from Authorized Scaffolding Inspector after erection). The scaffolding shall be of adequate height and capacity to provide safe access to the required areas of the tank shell and roof. The contractor shall progressively shift the mobile scaffolding as required to facilitate complete access and cleaning of the internal shell and roof surfaces. The entire first shell course and accessible internal roof surfaces shall be manually cleaned, including removal of all adhered HSFO deposits and residues. Upon completion of the shell and roof cleaning, the scaffolding shall be safely dismantled and removed from inside the tank. 3. Before/alongside the shell and roof cleaning activity, the tank bottom and sump area shall be thoroughly cleaned, and all accumulated HSFO residues and debris shall be collected and removed. The sludge removed from the tank shell, roof and bottom shall be collected by the contractor and safely transferred outside the tank using suitable ATEX-approved/explosion-proof equipment and arrangements. The contractor shall make all necessary arrangements for collection, handling and removal of the sludge and sludge-contaminated water from the tank area. The contaminated water shall be pumped out using a suitable ATEX-approved/explosion-proof pump and transferred into an appropriate bowser/tanker, carrying vehicle or suitable drums/containers arranged by the contractor. The contractor shall be fully responsible for the safe transportation and final disposal of sludge and contaminated water outside the PSO facility at an authorized disposal facility, in accordance with all applicable Sindh Environmental Protection Agency (SEPA)/EPA requirements, environmental laws and regulations. All					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	permits, approvals, transportation arrangements and disposal-related documentation, where applicable, shall be the sole responsibility of the contractor, and no contaminated water or sludge shall be discharged<(>,<)> dumped or disposed of within the PSO facility or at any unauthorized location. The contractor shall ensure that no sludge or contaminated material is allowed to contaminate the surrounding tank area or soil. 4. After mechanical/manual removal of sludge and residues, the contractor shall carry out complete internal washing of the tank<(>,<)> including bottom, shell and roof surfaces, using suitable high-pressure/jet spray nozzles and arrangements. Water required for washing shall be provided by PSO; however, all necessary pumps, hoses<(>,<)> spray nozzles, fittings, temporary piping and other accessories required for carrying out the washing operation shall be arranged by the contractor. 5. The contractor shall make complete arrangements for collection<(>,<)> pumping, removal and safe handling of the sludge-contaminated wash water generated during the cleaning activity. The contaminated water shall not be discharged onto the ground, drainage system or any other area without prior authorization. The contractor shall arrange suitable tankers/bowsers, vacuum tankers, containers or other approved means, as required, for safe collection and transportation/disposal of the contaminated water at the location designated/approved by PSO. Any disposal shall be carried out strictly as per PSO/HSE instructions and applicable environmental requirements. 6. The contractor shall leave the internal surfaces of the tank in a clean condition, free from loose HSFO sludge, residues and debris, to the satisfaction of the PSO M<(>,<)>R/Operations Representative and HSE requirements. Any remaining localized deposits identified during inspection shall be further removed by the contractor without additional cost.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.05	7. All labor, mobile scaffolding, brass/non-sparking scrapers, hand tools, sludge collection containers/drums, pumps, hoses, jet spray arrangements, lifting/handling arrangements, internal transportation and all other equipment, tools and consumables required for satisfactory completion of the cleaning work shall be arranged by the contractor<(>,<)> except for the washing water specifically stated to be provided by PSO. 8. The completed work shall be subject to inspection and acceptance by the PSO M<(>&<)>R/Operations Representative, and any area found inadequately cleaned shall be re-cleaned by the contractor at no additional cost to PSO. <u>Inspection of Scaffolding</u> Arrangement and Erection of Mobile Tower Scaffolding Inside Tank: Scope of work: 1. The scope of work includes the arrangement, erection, shifting and dismantling of suitable mobile tower scaffolding inside Tank-307 to facilitate safe access for manual scraping and cleaning of all internal shell course plates. 2. The contractor shall provide mobile tower scaffolding of suitable design, height, load-bearing capacity and configuration, complete with proper castor wheels with locking arrangements, working platforms<(>,<)> guardrails, mid-rails, toe boards, access ladders and other required safety accessories. The scaffolding shall be suitable for use inside the tank and shall allow safe access to all required shell courses for removal of adhered HSFO deposits. 3. The scaffolding shall be erected, modified, shifted and dismantled only by trained and competent/certified scaffolders in accordance with applicable safety requirements. After erection and before commencement of any work-at-height activity, the complete scaffolding arrangement		<u>JOB</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	shall be inspected by a competent/authorized Third-Party Scaffolding Inspector. The contractor shall submit the relevant inspection/certification record to the PSO M<(>&<)>R/HSE Representative for verification prior to use. 4. The scaffolding shall be inspected/re-certified after any major modification, relocation or alteration, and whenever required by the applicable safety requirements. The contractor shall ensure that all castor wheels are properly locked while the scaffolding is occupied and that the tower remains stable during use. Movement/relocation of the mobile tower shall only be carried out when no person is on the scaffold. 5. The contractor shall progressively shift the mobile tower scaffolding as required to provide access to the complete internal shell surface and shall ensure that all areas requiring scraping are safely accessible. Upon completion of the scraping/cleaning activity, the contractor shall safely dismantle and remove the complete scaffolding arrangement from inside the tank. 6. All scaffolding material, certified scaffolders, inspection by the authorized Third-Party Scaffolding Inspector, shifting/relocation<(>,<)> dismantling, labor, tools, transportation and other accessories required for satisfactory completion of the work shall be arranged by the contractor and deemed included in the quoted price. 7. No work at height shall be permitted from the scaffolding until the required inspection and certification has been completed and the scaffolding has been declared safe for use by the competent/authorized inspector and accepted by the PSO Representative. <u>Delivery / transportation charges</u> Delivery/Transportation, Mobilization & Demobilization Charges: 1. The scope of work includes all delivery and transportation charges<(>,<)>		EU	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.07	including mobilization of the contractor's labor, equipment, tools<(>,<)> scaffolding, machinery, accessories and other materials required for execution of the subject job at Tank-307, KTB. 2. The contractor shall arrange transportation and mobilization/demobilization of all required resources to and from the site as per the job requirements and instructions of the Terminal Engineer/PSO Representative/Terminal In-Charge. The contractor shall also be responsible for shifting and transportation of its equipment and materials within the terminal premises as required for satisfactory execution of the work. 3. The quoted amount shall be considered as one-time lump-sum charges<(>,<)> irrespective of the number of trips required for mobilization<(>,<)> demobilization, delivery, collection or shifting of labor, equipment<(>,<)> tools and materials during execution of the job. No additional transportation, mobilization or demobilization charges shall be payable for multiple trips required to complete the job. 4. All vehicles and transportation arrangements used by the contractor shall comply with applicable PSO site entry, HSE and vehicle safety requirements. Supply and inst of flange 8 inch Supply & Installation of 16" Dia Blind Flange (CLASS 150# RF): Scope: 1. The scope of work includes the supply, installation and proper tightening of 01 No. 16-inch diameter blind flange on the designated 16-inch pipeline connection, complete with all required nuts, bolts<(>,<)> suitable gasket and other necessary accessories for making a secure and leak-tight joint.		JOB	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	2. The contractor shall ensure that the blind flange, gasket, nuts and bolts are of suitable size, rating, material and specifications compatible with the existing pipeline/flange arrangement. Installation shall be carried out properly and uniformly to ensure a secure and leak-tight connection, as per applicable engineering practices and instructions of the PSO M-><>R Engineer/Representative. 3. The supplied 16-inch blind flange shall become the property of PSO upon delivery/installation and shall not be removed, retained or returned to the contractor after completion of the job. The cost of the blind flange, nuts, bolts, gasket, transportation, labor, tools and all other accessories required for satisfactory completion of the work shall be deemed included in the quoted rate. ===== TERMS & CONDITIONS ===== 1. The job includes labor, transportation and all material charges. 2. The above item/job is subjected to entire satisfaction and inspection/ acceptance by engineer/PSO representative. 3. Payment against the Job(s) will be made against the vendor invoice after completion of work and passing quality /quantity of goods /works and services including all verifications /inspections by the PSO designated official in-charge within 30 days. 4. The contractor/ supplier will submit his bill to concern official in-charge, at Keamari Terminal B and get it signed by the Location Engineer and Location Incharge. The invoice will then be collected from the Terminal and Submitted to VIMs Section and obtain the DP Number. 5. All Government taxes and GST/SST is included in the above mentioned rates. 6. If the Contractor fails to complete the work within time stipulated in the Service Order (Without any genuine reason or creditable justifications), the Engineer/Incharge will be entitled to deduct from					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	11
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	his due amounts or bills for the job awarded through this order or other monies due to him by PSO, a value of 0.1% of service order per day and subject to maximum 10% of the service order. 7. The contractor must follow the HSE standards, security and other requirements to work at PSO location. 8. Vendor will provide the services within 21 days after issuance of PO. 9. All personnel deployed by the contractor for tank cleaning<(>,<)> confined-space entry, scaffolding, lifting, electrical and other specialized activities shall be trained, competent and appropriately certified/qualified for the respective work. The contractor shall provide valid competency/certification documents whenever required by PSO. 10. All temporary electrical equipment, lighting, pumps, exhaust fans/blowers and other equipment used inside or in the vicinity of the tank shall be suitable for hazardous-area service and duly ATEX-approved/certified or otherwise accepted by PSO. Relevant certification/documents shall be submitted for verification prior to use. Any equipment found unsuitable or non-compliant shall be replaced by the contractor at no additional cost to PSO. 11. The contractor shall be fully responsible for the safe collection<(>,<)> removal, transportation and disposal of HSFO residues and contaminated water generated during the cleaning activity. No residue, contaminated water or other waste shall be discharged or disposed of within the PSO premises or at any unauthorized location. Disposal outside the facility shall be carried out in accordance with all applicable EPA/SEPA environmental requirements and regulations, and all associated arrangements, approvals, transportation and disposal costs shall be borne by the contractor. 12. Required third-party inspection/certification of scaffolding and other applicable equipment shall be arranged by the contractor prior to use. 13. The contractor shall ensure that the work area and surrounding PSO premises are kept clean and free from spilled sludge, contaminated water, debris and other waste generated during the job. Any damage					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	11
RFQ No	OP-19983NZ	
DATE	04.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018114

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

23.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Service Required For Complete Internal Cleaning & De-Gassing of Tank-307 (HSFO Service) at Keamari Terminal-B.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	caused to PSO property, equipment, tank, pipeline or other facilities due to the contractor's activities shall be rectified by the contractor at its own cost, to the satisfaction of PSO. 14. Any work/activity shall be carried out only after obtaining the required PSO Permit-to-Work and authorization from the designated PSO Engineer/Terminal In-Charge. The contractor shall immediately stop work if instructed by the PSO Representative/HSE Representative due to any unsafe condition or violation of HSE requirements. 15. The contractor shall comply with all applicable environmental<(>,<)> safety, statutory and regulatory requirements during execution of the work and shall be solely responsible for any non-compliance attributable to its activities.					