



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RC-19977SJ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018148

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: PAINT AND GRAPHICS OF LUBRICANT RACKS WITH ALLIED REPAIR WORKS AT NVROS IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>LUBE RACK REPAIR</u>	<u>PSO House</u>				
1.01	<u>STEEL LUBE RACK</u> LUBE RACK REPAIR WORKS Job includes: 1-Isolation of Lube racks from DU-island by dismantling raval bolts. 2-Tranportation of the lube rack to the workshop. 3-Scrapping complete lube rack for actual sheet strength. 4- Complete replacement of Side glass 8mm (plain imported). 5- Complete replacement of front shelve glass 06 NOs each rack 5mm (plain imported). 6-Replacement of broken hinges and pipe. 7- Complete replacement of all locks and installation of magnetic catcher both along with door locks (12 Nos each rack). 8-Preparation of lube rack for paint by applying steel putting where required to fill up the gaps/cavities to ensure smooth surface. 9. Providing and applying fresh spray auto paint on Lube Racks with PSO scheme by means of 5HP Compressor maintaining 2 bar pressure. 12. Providing and Pasting PSO graphics (3M or equivalent) on Lube Racks as per PSO approved artwork. (design to be provided by PSO). 14. Cover each lube rack with polyethene wraps of approved specs complete in all respects. 14. Transportation of prepared lube rack from workshop to designated NVRO in Faisalabad Division. 15. Refixing of finished/prepared lube rack on DU-island with raval bolts of approved size and specifications. (04 NOs on each rack). Note: The outlet could be any NVRO in Faisalabad Division. Minor repairs i.e. lock hook, glass frame hooks<(>,<(> necessary welding	<u>EA</u>	199			



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RC-19977SJ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018148

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

22.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: PAINT AND GRAPHICS OF LUBRICANT RACKS WITH ALLIED REPAIR WORKS AT NVROS IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	works, denting, screws and others required in repair of lube rack complete in all respects are included in the scope. TERMS AND CONDITIONS: 1. All material tools and labors charges are the part of the scope. 2. NO on-site job is allowed. all lube rack to be shifted to vendors workshop for repair and paint works. If at any instance on-site job activity witnessed by any official/dealer/team mate. A straight penalty amounting Rs. 100000/- be applicable for the instance and repeat of the instance may lead to the cancellation of PO without any claim by vendor. 3. All transportation charges at the part of the scope. 4. Job completion time is 180 Days after the PO issuance to contractor via email/SAP Ariba. 0.1% to 10% of the bill to charged as per day penalty in case of delay by the contractor. 5. Thickness of applied paint must not be less than 150 microns. Arrangement of Calibrated (Validity Expiration not less than 4months). Alcometer for paint thickness inspection is the sole responsibility of the contractor. For each thickness observed less than 150 microns, the contractor will be liable to rectify the job without any extra charges. 6. The PSO approved latest artwork to be pasted on lube racks. contractor to obtain latest art work design and specs from concerned DE. 7. The Contractor is required to get the paint approved from the concerned Engineer before the start of the work. Only brands of company approved specs are applicable. 8. The contractor will share step by step pictures of the works with Concerned Engineer after: 1. Surface preparation, 2. Applying putty, 3. Applying Single coat, 4. Applying double coat. The engineer will allow the contractor for proceeding in the next step after verifying the pictures. 9. Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety.					



3	OF	3
RFQ No	RC-19977SJ	
DATE	07.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018148

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	22.09.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: PAINT AND GRAPHICS OF LUBRICANT RACKS WITH ALLIED REPAIR WORKS AT NVROS IN FAISALABAD DIVISION

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	All material, tools and labor charges are included in the scope. 10. All govt taxes and rates are included in the scope.					