



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Autocare Facility at Al-Askar, Karachi</u>	<u>PSO House</u>				
1.01	<u>Preparatory works</u> Dismantling, Maintenance, and Site Clearance Dismantling of ceiling, pelmets, MDF partition walls, electrical wiring <(>,<)> along with all appliances and lighting fixtures. Removal of tiles, plinth protection work, glass partition, restoration works, and all other necessary works as per site requirements and the instructions of the PSO Engineer. Complete area cleaning and site clearance in all respects. 1 EA = 1 JOB		<u>EA</u>	1		
1.02	<u>Cement Board Partition Work (Sft)</u> Partitioning wall Providing and installation of 16 SWG MS frame 3" x 1.5" pipe for partitioning wall with 12 mm cement board sheet covering on both side of structure as per approved design. Application of Red oxide paint on pipe Scope of work includes installation of wire-mesh at joints of cement board with proper filling		<u>SFT</u>	500		
1.03	<u>Inspection Pit (Oil Change)</u> A) Construction of Inspection Pit: drawing complete in all respect and as directed by Engineer Incharge. This job includes the following scope but not limited to following a- Construction of foundation for Shutter / Railing in lean concrete ,2000 psi cylinder strength, 1:3:6 ratio, Construction of PCC Floor (1:2:4) b-Construction of Steel plates for trolley (Outer), complete in all respects. c-Construction of Angle 1.5"x1.5"x3/16" for trolley (Bottom)<(>,<)> complete in all respects. d-Construction of Angle 1.5x1.5x3/16" for trolley (For covers)<(>,<)>		<u>JOB</u>	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	complete in all respects. e-Providing & Installation of Drain Lube Oil Trolley, complete in all respects f-Installation of MS Plates for ladder steps, (corrugated / antiskid finish or wire gauze patterned stairs), grey color, with yellow painted front edges g-Installation of high quality non-skid Floor tiles at the base of pit <(>,<) as per approved sample. White tile 12 x 12 h-Providing & Installation of high quality glazed tiles on side walls of pit, as per approved sample. White tile 12 x 12 i-Providing & Installation of pit cover with 12 swg sheet, powder coated colour, complete in all respects. j-Providing & Installation of pit Cover with meshed grating, powder coated, complete in all respects. k-Providing & Installation of Tube light, complete fixture, along with transparent acrylic cover in front of recessed brick enclosure. l-Installation of Guard Rail, pipe dia 2", placed around the pit<(>,<) painted, fixed, complete in all respects.					
1.04	<u>AIR LINE GI PIPE 1/2</u> Providing and installation of 1/2" dia. GI pipe from the compressor to the designated point, including bends, unions, tee elbows, and end valve, complete in all respects.		<u>RFT</u>	100		
1.05	<u>Miscellaneous</u> Providing & Fixing Rubber Car Wheel Stopper		<u>EA</u>	4		
1.06	<u>Application of Epoxy</u> Service Area Floor Epoxy Flooring in AutoCare Service Area. Supply and applying of industrial grade epoxy on floor as per approved specs on the floor of auto care including. surface preparation: surface to be free from any dust, crack, moisture etc. Applying of solid epoxy primer, base coat and finish coat in approved colour/shade as per satisfaction of PSO Engineer/ Architect.		<u>M2</u>	19		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.07	<u>Supply and Installation of False Ceiling</u> Aluminium C-Channel Ceiling: Supply and installation of Aluminum C Channel of 2in x 4in of Powder coating of the frame components in approved color RAL 7013 (Dulux 10YY 08/093 Pebble Mosaic), All exposed edges must be chamfered or safely covered with appropriate protective materials to prevent injury from sharp edges. - Drilling and fixing of frames with appropriate anchors and fasteners to existing walls and ceiling ensuring even and durable finish resistant to corrosion and environmental conditions, ensuring proper support and level alignment. This also include concealed wiring of the lighting system as per requirement. 1 FT2 = 1 RFT		<u>FT2</u>	240		
1.08	<u>Supply and installation of LED lights</u> Waterproof Lights: Supply and Installation of IP65 Waterproof LED Lights in service area as per drawing. Specifications: Power consumption 40W Color: 4000K, CRI>80, Luminous efficacy: 140 lm/Watt Beam Angle: 120 degree, Power Factor: Greater than 0.95. Protection Class: Compliance to IEC 62031, EN IEC 620301-2-1, IEC 622778. Safety Class I Certification: CB, IECEE Housing Material: Polycarbonate Surface Mounted: Dimensions (LxWxH)(typ.): 40W (1221x74x60.5) and 20W (659x74x60.5) Warranty: Up to 5 years Placement of Lights on C channel with required spacing.		<u>EA</u>	24		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.09	LED lighting system inside the tyre shop, waiting and Auto care as per PSO specification, design and drawing complete in all respect. <u>Signage and Graphics work</u> Graphical Elements at Back Wall: Supply and installation of 10mm foam board with printable Vinyl with waterproof lamination of approved artwork on back wall of Lube bay as per requirement. All work to be completed as per the PSO representative instruction. 1 AU = 1 SFT		<u>AU</u>	144		
1.10	<u>Gypsum Ceiling Works (Sft)</u> WAITING AREA: Ceiling made with 2x2 gypsum ceiling complete with all required accessory		<u>SFT</u>	80		
1.11	<u>Paint Works (Sft)</u> Paint of Auto care Ceiling with matt black paint with water matt making the surface smooth, putting filler where required		<u>SFT</u>	336		
1.12	<u>Paint Works (Sft)</u> Paint of Auto care wall<(>,<(> Internal with oil base paint as per approved color, making the surface smooth, putting filler where required		<u>SFT</u>	800		
1.13	<u>12 mm Glass Plain (Imported)</u> 12mm tempered glass with aluminum fitting including all wastage and transportation		<u>FT2</u>	80		
1.14	<u>12 mm Glass Plain (Imported)</u> Single leaf Glass door Providing & fixing single leaf tempered glass door with all required accessories, door closer, handles, locks etc. Size, 7 x 3		<u>FT2</u>	21		
1.15	<u>Provid.&Fixing of Solid Flush door</u> Provision and fixation of WPC flush doors for store, with 16 swg GI		<u>JOB</u>	2		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.16	door framing complete with all required accessory Size: 2.5 x 7 1 JOB = 1 NO <u>MS Sliding Gate (Main)</u> Providing, Fabrication, Supply and Fixation of MS Sliding Grill Door at the Front Side of the Main Entrance, complete in all respects, including frame, guide channels, rollers, locking arrangement, handles, welding<(>,<)> anchoring and all necessary hardware/accessories. The door shall be properly aligned, smoothly operable, and finished with approved anti-rust treatment and paint/coating as per site requirements and the instructions of the PSO Engineer.		<u>EA</u>	100		
1.17	1 EA = 1 SFT <u>Installation of Electrical Wiring</u> Wiring from DB to board Wiring of lighting circuits from distribution board to lighting control switch board & board to board with 2x2.5 sq.mm single core PVC insulated wire 300/500 volts grade single core stranded copper conductor wire in 1" PVC conduit, including all wiring accessories recessed in wall<(>,<)> column, ceiling etc., including 2.5 sq.mm single core PVC insulated(Green) wire as ECC, complete as per specifications and drawing.		<u>JOB</u>	4		
1.18	1 JOB = 1 Point <u>Installation of Electrical Wiring</u> Wiring of light and fan point from point to switch with 1.5 sq.mm single core PVC insulated copper conductor wire in 1" dia PVC conduit<(>,<)> including all wiring accessories, recessed in the wall, column<(>,<)> roof including ECC single core (Green) wire, complete as per specification and drawing. 1 JOB = 1 Point		<u>JOB</u>	8		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.19	<u>Switch (4 gang)</u> 4 Gang Switch		<u>EA</u>	2		
1.20	<u>Switch (6 gang)</u> 6 Gang Switch		<u>EA</u>	1		
1.21	<u>Installation of LED Lights</u> b) Ceiling mounting (2 x 2) 40W LED Down light, color White, aluminum made with reflector and built in driver, complete in all respect		<u>EA</u>	8		
1.22	<u>Distribution Board</u> Distribution Board (DB): Supply, installation, connecting, testing, and commissioning of following wall mounted DB for lighting and power that should be factory assembled ready wired and complete. Type: Wall mounted Size: 300 x 225 x 125 mm IP Rating: 43 or above Colour: Pearl Light Grey RAL 9022 Incoming: -3 Indication Lamp -01 x 32 Amp TP MCB Outgoing: -01 x 20 Amp TP MCB (For Compressor) -05 x 10 Amp SP MCB Earthing: 20 mm diameter 99% copper earthing electrode (10 ft. Length) directly driven in ground including earthing leads up to earth connecting point/ DB and inspection chamber. To be done as per drawing and instruction of Engineer including earthing leads up to earth connection point/DB.		<u>JOB</u>	1		
1.23	<u>PVC Conduit 2"</u> Supply and installation of 2" dia PVC conduit surface/ recessed in wall <(>,<)> beam etc., including all installation accessories as required for power cabling, complete as per specification and drawing.		<u>M</u>	11		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.24	<u>PVC Conduit 1-1/2"</u> Supply and installation of 2" dia PVC conduit surface/ recessed in wall <(>,<)> beam etc., including all installation accessories as required for power cabling, complete as per specification and drawing.		<u>M</u>	9		
1.25	<u>Miscellaneous</u> Supply & Installation of 4" Dia MS Bollard - 3' height painted, 16 SWG U-bend pipe, complete in all respects. 1 EA = 1 JOB		<u>EA</u>	1		
1.26	<u>PCC (1:2:4)</u> - Providing and laying plain cement concrete of mix 1:2:4 for blinding/binding under pile cap and associated foundation elements. - Item includes supply, mixing, placing, compacting, curing, and removal of formwork, complete in accordance with specifications and Consultant's instructions. - Concrete shall be prepared using approved quality 3/4 in. maximum size graded crushed aggregate and fine aggregate. - Scope of work include 3-4 inch stone soling.		<u>FT2</u>	4		
1.27	<u>Block Masonry Work</u> Providing and laying best quality burnt brick (2000Psi)/solid block masonry (1200Psi) of specified thickness set in 1:4 cement sand mortar including required scaffolding racking out and cleaning of joints and curing of masonry complete as per drawing and specifications & instructions of site Incharge vertically at joints of RCC columns and masonry, complete as per specification and direction of Engineer Incharge.		<u>M3</u>	2.000		
1.28	<u>Plain Plaster 3/4" thick</u> Providing and applying cement plaster 3/4" thick in 1:4 cement sand mortar to beams, columns, ceiling, walls at any height i/c all corners <(>,<)> recesses, jams and joints of masonry, roughing the surfaces and cement slurry backing to all surfaces i/c and scaffolding.		<u>M2</u>	10		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018180

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.29	This job also includes 6" wide heavy duty metal lath strip nailed at the joints of masonry and concrete structure and curing complete in all respect and as directed by Engineer Incharge. <u>Porcelain Tile Works (Sft)</u> Providing, laying and Fixing of Terrazo Textured Porcelain tiles on already laid CC rough floor (tiles to be fixed with dry bond) including dry bond, approved unsanded grout, spacers in required size, cutting(>,<)> curing, cleaning, hacking / chipping of existing surface for bonding where necessary, wastage, all fixing accessories and arrangements, etc. Complete in all respects and as per drawing, patterns and directions of the Architect / Engineer. (Brands; S Abdullah, Kale, Abu-Yousuf, Hidayat & co or Equivalent) (for reference see product # PORCELAIN TILE (2FT X4FT) (REF. AIVE TILE CODE # LC 55-AVGN 03-155-24X48-SB TERRAZZIO LIGHT GREY POLISHED of Kale or equivalent as per directives of PSO representative. Job also includes provision and installation of 4" high Porcelain Tile skirting (matching the flooring) with approved adhesive, cutting(>,<)> wastage, etc. complete in all respect as per the instructions PSO Engineer.		<u>SFT</u>	240		
1.30	<u>Clearance / NOC</u> The contractor shall obtain all necessary approvals, NOCs, permits, and clearances from the relevant authorities at its own cost and responsibility. ----- Note: - All the work done and task completed within 30 days, after the issuance of Service Order.		<u>JOB</u>	1		



9	OF	9
RFQ No	RC-20003AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018180

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	29.09.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: Construction of AutoCare Facility at Al-Askar FS, Karachi

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	- All work shall be completed in all respects as per site requirements and the instructions of PSO engineer. Auto Care Facility is to be constructed at Al-Askar FS, Karachi.					