

Standard Bidding Document

NCB-289 Procurement of 132KV Lightning Arrester with Supported Steel
Structure (SSS)
(Goods)

National

Single Stage-One Envelope



September 16, 2026

*IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director
Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory
Phone: +92-319-599-2205, Email: iescopmu@iesco.com.pk*

Table of Contents

REQUEST FOR BIDS	1
Instructions to Bidders	3
Bid Data Sheet	23
Bids Data Sheet (BDS)	24
Eligibility Criteria	28
Evaluation Criteria	30
Items/Lots	32
Related Services of Goods:	33
Items/Lot Specification	34
Price Schedule	35
General Conditions of Contract	37
Special Conditions of Contract	47
Bid Securing Declaration	54
Contract Form	56
Integrity Pact	59
Performance Guarantee Form	61
Annexure	64
Manufacturer experience annex	65
Production capacity annex	65
Bidder information form	65
Bidder JV form	65

Deviation from contractual provision	65
Deviation technical provision	65
Qualification information	66
Manufacturer authorization	66
Manufacturer information form	66
Production capacity of manufacturer	66
Letter of bid technical	66
IESCO blacklisting policy	67
Correction of defect in warranty period	67
type test requirements	67
price schedule EXW	67
Price schedule DDP	67
specification	68
payment terms	68
Procurement Forms	69
Past Experience and Completed Contracts	1
Historical Contract Non-Performance, and Pending Litigation and Litigation History	1
Current Contracts and Their Progress	1
Financial Capacity and Net Worth Evaluation Form	1
Average Annual Turnover	1
Additional Forms and Documents	73

REQUEST FOR BIDS

PROCUREMENT OF GOODS

1. The **IESCO-PMU (Islamabad Electric Supply Company (IESCO))** has reserved Funds for the procurement planned for FY **2026-27**. The **IESCO-PMU (Islamabad Electric Supply Company (IESCO))** intends to apply part of the proceeds of this Fund to cover eligible payments under the contract for the "**NCB-289 Procurement of 132KV Lightning Arrester with Supported Steel Structure (SSS)**" with the reference of "**P35663**"
2. The **IESCO-PMU (Islamabad Electric Supply Company (IESCO))** invites sealed Bids from eligible Bidders for procurement of goods described in the bidding documents on **EPADS v2.0**.
3. **Single Stage-One Envelope** will be used by adopting **Least Cost Based Selection (LCBS)** Technique for the subject procurement, in line with the Public Procurement Rules, 2004 and any Regulations, Regulatory Guides, Procurement Guidelines or Instructions issued by the Authority from time to time.
4. All Bids must be accompanied by a Bid Security amounting described in Bid Security Section in Bidding Document in the form of or all bids must be accompanied by bid securing declaration in the format specified in the Bidding documents
5. E-Bidding documents, containing detailed terms & conditions, specifications and requirements etc. are available on **e-Pak Acquisition and Disposal System (EPADS)** at **<https://epads.gov.pk/opportunities/federal/procurements/35663>** for all the interested bidders registered on **EPADS v2.0**. Bidders are required to get themselves registered on **EPADS v2.0** to participate in Bidding process.
6. The e-bids, prepared in accordance with the instructions in the e-Bidding Documents, must be submitted through **EPADS v2.0** on or before **Friday, October 2, 2026 11:00 AM**. E-bids will be opened using **EPADS v2.0** on the same day at **Friday, October 2, 2026 11:30 AM**. Manual submission of Bids shall not be entertained. Those vendors who have not yet registered on the

new version of **EPADS v2.0**, may register themselves on <https://vendors.epads.gov.pk/>. A tutorial to explain the registration process is available at <https://www.youtube.com/watch?v=MNW6T38v7tc>

In terms of Rule 48 of Public Procurement Rules, 2004 Grievance Redressal Committee (GRC) is notified for the subject procurement and notification copy is available on the procuring agency's website and on Authority's website at (www.ppra.org.pk).

IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director
Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory
+92-319-599-2205
iescopmu@iesco.com.pk





Instructions to Bidders

A. Introduction

1.Scope of Bids

1.1 The Procuring Agency (PA), as indicated in the **Bids Data Sheet (BDS)** invites Bids **through EPADS v2.0** for the provision of Goods for as specified in the BDS and **in Section V - Evaluation Criteria, Specifications & Schedule of Requirements**. The name, identification, and number of items/deliverables are provided in the **BDS**. The successful Bidders will be expected to provide the goods within the specified period and timeline(s) as stated in the **BDS**.

2. Source of Funds

2.1 Source of funds is referred in Clause-1 of Invitation for Bids.

3. Eligible Bidders

3.1 A Bidder may be natural person, company or firm or public or semi-public agency of Pakistan or any foreign country, or any combination of them with a formal existing agreement (on Judicial Papers) in the form of a joint venture, consortium, or association. In the case of a joint venture, consortium, or association, all members shall be jointly and severally liable for the execution of the Contract in accordance with the terms and conditions of the Contract. The joint venture, consortium, or association shall nominate a Lead Member as nominated in the BDS, who shall have the authority to conduct all business for and on behalf of any and all the members of the joint venture, consortium, or association during the Bidding process, and in case of award of contract, during the execution of the contract.

3.2 Verifiable copy of the agreement that forms a joint venture, consortium or association shall be required to be submitted as part of the Bid.

3.3 The appointment of Lead Member in the joint venture, consortium, or association shall be confirmed by submission of a valid Power of Attorney to the Procuring Agency.

3.4 Any bid submitted by the joint venture, consortium or association shall indicate the part of proposed contract to be performed by each party and each party shall be evaluated (or post qualified if required) with respect to its contribution only, and the responsibilities of each party shall not be substantially altered without prior written approval of the Procuring Agency and in line with

any instructions issued by the Authority.

(The limit on the number of members of JV or Consortium or Association may be prescribed in BDS, in accordance with the guidelines issued by the PPRA).

3.5 The invitation for Bids is open to all prospective suppliers, manufacturers, or authorized agents / dealers subject to any provisions of incorporation or licensing by the respective national incorporating agency or statutory body established for that particular trade or business. Procuring agencies shall specify the registration/licensing requirements for the foreign bidders keeping in view the requirement of that business.

3.6 A Bidder shall not have a conflict of interest. All Bidders found to have a conflict of interest shall be disqualified. A Bidder may be considered to have a conflict of interest with one or more parties in this Bidding process, if they:

1. are associated or have been associated in the past, directly or indirectly with a firm or any of its affiliates which have been engaged by the Procuring Agency to provide consulting services for the preparation of the design, specifications and other documents to be used for the procurement of the Goods to be purchased under this Invitation for Bids.
2. have controlling shareholders in common; or
3. receive or have received any direct or indirect subsidy from any of them; or
4. have the same legal representative for purposes of this Bid; or
5. have a relationship with each other, directly or through common third parties, that puts them in a position to have access to information about or influence on the Bids of another Bidder, or influence the decisions of the Procuring Agency regarding this Bidding process; or
6. Submit more than one Bid in this Bidding process.

3.7 A Bidder may be ineligible if –

1. he is declared bankrupt or, in the case of company or firm, insolvent;
2. payments in favor of the Bidder is suspended in accordance with the judgment of a court of law other than a judgment declaring bankruptcy and resulting (in accordance with the national laws) in the total or partial loss of the right to administer and dispose of its property;

3. the Bidder is convicted, by a final judgment, of any offence involving professional conduct;

4. the Bidder is blacklisted locally or by international organizations and hence debarred due to involvement in corrupt and fraudulent practices, or performance failure or due to breach of Bid securing declaration.

3.8 As and when required, bidders shall provide to the Procuring Agency evidence of their eligibility, proof of compliance with the necessary legal requirements to carry out the contract effectively.

3.9 Bidders shall submit Bids relating to the nature, conditions and modalities of sub-contracting wherever the sub-contracting of any elements of the contract amounting to more than ten (10) percent of the Bid price is envisaged.

4. Eligible Goods and Related Services

4.1 All goods and related services to be supplied under the contract shall have their origin in eligible source countries, and all expenditures made under the contract will be limited to such goods and services. For purpose of this Bid, ineligible countries are the countries declared ineligible by the Federal Government.

5. One Bid per Bidder

5.1 A bidder shall submit only one Bid, in the same bidding process, either individually as a Bidder or as a member in a joint venture or any similar arrangement.

5.2 The Bidder shall not engage a subcontractor for any portion of the contract if the value of such subcontracting exceeds thirty percent (30%) of the total contract amount.

6. Cost of Bidding

6.1 Any cost incurred by the bidder relating to the preparation and submission of its Bid shall be borne by the bidder, and the Procuring Agency shall in no case be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

B. Bidding Documents

7. Contents of Bidding Document

7.1 The Goods required, Bidding procedures, and terms and conditions of the contract are prescribed in the Bidding Documents. In addition to the Invitation for Bids, the Bidding documents which should be read in conjunction with any addenda issued in accordance with **ITB 9.1** include:

Section I -Invitation to Bids

Section II Instructions to Bidders (ITB)

Section III Bid Data Sheet (BDS)

Section IV Evaluation Criteria, Specifications, Schedule of Requirements

Section V Bid Forms

Section VI General Conditions of Contract (GCC)

Section VII Special Conditions of Contract (SCC)

Section VIII Contract Forms

7.2 The Bidder is expected to examine all instructions, forms, terms and specifications in the Bidding documents. Failure to furnish all the information required in the Bidding documents through **EPADS v2.0** will be at the Bidder's risk and may result in the rejection of his Bids.

8. Clarification of Bidding documents

8.1 A prospective Bidder requiring any clarification of the Bidding documents may notify the Procuring Agency through **EPADS v2.0**.

8.2 The Procuring Agency will within three (3) working days after receiving the request for clarification, respond to any request for clarification through **EPADS v2.0** provided that such request is received not later than three (03) days prior to the deadline for the submission of Bids as prescribed in **ITB 22**

8.3 Copies of the Procuring Agency's response will be forwarded to all identified Prospective Bidders through **EPADS v2.0**, including a description of the inquiry, but without identifying its source.

8.4 Should the Procuring Agency deem it necessary to amend the Bidding document as a result of a clarification, it shall do so following the procedure under **ITB 9**.

8.5 If indicated **in the BDS**, the Bidder's designated representative is invited at the Bidder's cost to attend a pre-Bid meeting at the place, date and time mentioned **in the BDS**. During this pre-Bid meeting, prospective Bidders may request clarification of the schedule of requirement, the Evaluation Criteria or any other aspects of the Bidding document.

8.6 Minutes of the pre-Bid meeting, if applicable, including the text of the questions asked by Bidders, including those during the meeting (without identifying the source) and the responses given, together with any responses prepared after the meeting will be uploaded on **EPADS v2.0**. Any modification to the Bidding documents that may become necessary as a result of the pre-Bid meeting shall be made by the Procuring Agency exclusively through the use of an Addendum pursuant to **ITB 9**. Non-attendance at the pre-Bid meeting will not be a cause for disqualification of a Bidder.

9. Amendment of Bidding documents

9.1 Before the deadline for submission of Bids, the Procuring Agency for any reason, whether at its own initiative or in response to a clarification requested by a prospective Bidder or Pre-Bid meeting may modify the Bidding documents by issuing addenda through **EPADS v2.0**.

9.2 The Procuring Agency shall promptly publish the addendum through **EPADS v2.0**.

9.3 Any addendum issued including the notice of any extension of the deadline shall also be communicated through EPADS v2.0 to all the bidders who have already submitted their bids. Such bidders shall have the right to withdraw their already submitted bid and re-submit the revised bid prior to the original or extended bid submission deadline.

9.4 To give prospective Bidders reasonable time in which to take an addendum/corrigendum into account in preparing their Bids, the Procuring Agency may, at its discretion, extend the deadline for the submission of Bids through **EPADS v2.0**:

Provided that the Procuring Agency shall extend the deadline for submission of Bids, if such an addendum is issued within last three (03) days of the Bids submission deadline.

C. Preparation of Bids

10. Language of Bid

10.1 The Bid prepared by the bidder, as well as all correspondence and documents relating to the Bids exchanged by the Bidder and the Procuring Agency shall be written in the English language unless otherwise specified in the BDS. Supporting documents and printed literature furnished by the Bidder may be in another language provided they are accompanied by an accurate translation of the relevant pages in the English language unless otherwise specified in the **BDS**, in which case, for purposes of interpretation of the Bidder, the translation shall govern.

11. Documents and samples Constituting the Bid

11.1 The Bid prepared by the Bidder shall constitute the documents required in the **BDS**.

Details of sample(s) where applicable and requested in the BDS.

1. Documentary evidence established in accordance with ITB that the Bidder is eligible and/or qualified for the subject bidding process;
2. Documentary evidence establish that the Bidder has been authorized by the manufacturer to deliver the goods into Pakistan, where required and where the supplier is not the manufacturer of those goods;
3. Documentary evidence establish that the goods and related services to be supplied by the Bidder are eligible goods and services, and conform to the Bidding Documents;
4. Bid security or Bid Securing Declaration furnished in accordance with **ITB 18**.

12. Documents Establishing Eligibility of the Goods and Conformity to Bidding documents

12.1 To establish the conformity of the bidder to the Bidding document, the Bidder shall furnish as part of its Bids the documentary evidence that Goods provided conform to the technical specifications and standards.

13. Documents Establishing Eligibility and Qualification of the Bidder

13.1 The Bidder shall furnish, as part of its Bid, all those documents establishing the Bidder's eligibility to participate in the Bidding process and/or its qualification to perform the contract if its Bid is accepted.

14. Form of Bids

14.1 The Bidder shall fill the Form of Bid furnished in the Bidding documents. The Bids Form must be completed without any alterations to its format and no substitute shall be accepted.

15. Bids Prices

15.1 The Bids Prices quoted by the Bidder in the Form of Bid and in the Price Schedules shall conform to the requirements specified below or exclusively mentioned hereafter in the Bidding documents.

15.2 All items in the Schedule of Requirement must be listed and priced separately in the Price Schedule(s). If a Price Schedule shows items listed but not priced and neither explicitly denied, their prices shall be construed to be included in the prices of other items.

15.3 Items not listed in the Price Schedule shall be assumed not to be included in the Bid, and provided that the Bid is still substantially responsive in their absence or due to their nominal nature, the corresponding average price of the respective item(s) of the remaining substantially responsive Bidder(s) shall be construed to be the price of those missing item(s).

15.4 The Bid price to be quoted in the Form of Bid in accordance with **ITB 14.1** shall be the total price of the Bid.

15.5 The Bidder shall indicate on the appropriate Price Schedule, the unit prices (where applicable) and total Bid price of the Goods it proposes to provide under the contract.

15.6 Prices quoted by the Bidder shall be fixed during the Bidder's performance of the contract and not subject to variation on any account. A Bid submitted with an adjustable price will be treated as non-responsive and shall be rejected.

16. Bids Currencies

16.1 Prices shall be quoted in Pakistani Rupees unless otherwise specified in the BDS in accordance with Rule 30 (2) of the Public Procurement Rules, 2004.

17. Bids Validity Period

17.1 Bids shall remain valid for the period specified in the **BDS** after the Bid submission deadline prescribed by the Procuring Agency. A Bid valid for a shorter period shall be rejected by the Procuring Agency as non-responsive. The period of Bid validity will be determined from the complementary Bid securing instrument, i.e. the expiry period of Bid Security or Bids Securing Declaration as the case may be.

17.2 The procuring agency shall ordinarily be under an obligation to process and evaluate the bid and to issue letter of award within the stipulated bid validity period.

17.3 Under exceptional circumstances, prior to the expiration of the initial Bid validity period, the Procuring Agency may request the Bidders' consent to an extension of the period of validity of their Bids only once through **EPADS v2.0**, for the period not more than the period of initial bid validity. The Bid Security provided under **ITB 18** shall also be suitably extended. A Bidder may refuse the request without forfeiting its Bid security or causing to be executed its Bid Securing Declaration. A Bidder agreeing to the request will not be required nor permitted to modify its Bid, but will be required to extend the validity of its Bid Security or Bid Securing Declaration for the period of the extension.

18. Bid Security or Bid Securing Declaration

18.1 The Bidder shall furnish as part of its Bid, a Bid Security in accordance with Rule 25 of the Public Procurement Rules, 2004.

18.2 The original Bid Security shall be enclosed within the sealed envelope and to be submitted physically before closing time for submission of bids. Whereas, scanned copy of bid security shall be uploaded electronically through EPADS v2.0 before closing hours for submission of bids.

18.3 The Bidder who failed to submit the original Bids security before the submission deadline shall be disqualified straightaway.

18.4 The Bid Security or Bid Securing Declaration is required to protect the Procuring Agency against the risk of Bidder's conduct which would warrant the security's forfeiture, pursuant to **ITB 18.7**.

18.5 The Bid Security shall be denominated in the local currency, and it shall be a Bank Draft in the name of the Procuring Agency and valid for twenty-eight (28) days beyond the end of the validity of the Bid. This shall also apply if the period

for Bids/Bid Validity is extended. In either case, the form must include the complete name of the Bidder.

18.6 The Bid Security shall be payable promptly upon written demand by the Procuring Agency in case any of the conditions listed in **ITB 18** are invoked.

18.7 Unsuccessful Bidders' Bid Security will be discharged or returned as promptly as possible, however in no case later than thirty (30) days after the expiration of the period of Bids Validity prescribed by the Procuring Agency pursuant to **ITB 17**. The Procuring Agency shall make no claim to the amount of the Bid Security, and shall promptly return the Bid Security document, after whichever of the following that occurs earliest:

- a. the expiry of the Bid Security;
- b. the entry into force of a procurement contract and the provision of a Performance Guarantee, for the performance of the contract if such a guarantee, is required by the Bid documents;
- c. the rejection by the Procuring Agency of all Bids;
- d. the withdrawal of the Bids prior to the deadline for the submission of Bids, unless the Bids documents stipulate that no such withdrawal is permitted.

18.8 The successful Bidder's Bids Security will be discharged upon the Bidder signing the contract, or furnishing the Performance Guarantee.

18.9 The Bid Security may be forfeited or the Bid Securing Declaration executed:

- a. if a Bidder:
- b. withdraws its Bid during the period of Bid Validity as specified by the Procuring Agency, and referred by the Bidder on the Form of Bids except as provided for in **ITB 17.2**; or
- c. does not accept the correction of errors; or
- d. in the case of a successful Bidder, if the Bidder fails:
- e. to sign the contract; or
- f. to furnish Performance Guarantee.

19. Withdrawal, Substitution, and Modification of Bid

19.1 Before Bid submission deadline, any Bidder may withdraw, substitute, or modify its Bid after it has been submitted through EPADS v2.0. Bids requested to be withdrawn, shall be returned unopened to the Bidders through **EPADS v2.0**.

20. Format and Signing of Bid

20.1 The Bidder shall prepare and submit Bids with due diligence after carefully reading all the terms and condition **before bid submission deadline** through EPADS v2.0.

D. Submission of Bids

21. Submission of Bids through EPADS v2.0

21.1 The Technical and Financial Bids if required to submitted, shall be submitted on **EPADS v2.0**.

22. Deadline for Submission of Bids

22.1 Bids shall be received by the Procuring Agency through **EPADS v2.0** before bid submission deadline.

22.2 The Procuring Agency may, under exceptional circumstances, extend the deadline for the submission of Bids, after recording reasons in writing and in an equal opportunity manner.

In such case, all rights and obligations of the Procuring Agency and the Bidders that were previously governed by the original deadline shall thereafter be subject to the revised deadline.

E. Opening and Evaluation of Bids

23. Opening of Bids

23.1 The Bid Evaluation Committee of the Procuring Agency shall open all Bids through the EPADS v2.0, on the date and time specified in the Bid Data Sheet (BDS).

23.2 The Bid Evaluation Committee **shall generate minutes through EPADS v2.0 containing brief details of bid opening process.** The record of the Bid opening shall include, as a minimum: the name of the Bidder, the Bid price if applicable, and the presence or absence of a Bid Security or Bid Securing Declaration.

23.3 The procuring agency shall live broadcast the opening of bids on national media or on their website or digital channels, if the volume of procurement exceeds five hundred million rupees in case of goods and services and one thousand million rupees in case of works.

23.4 In case the date of opening of bid has been declared as public holiday or the procuring agency fail to open bid due to any EPADS v2.0 related issues, the submission and opening of bids shall be shifted to the next working day on the same time.

23.5 In case of Single Stage One Envelope Procedure, the Bidders names, the Bid prices, the total amount of each Bid and, the presence or absence of Bid Security, Bid Securing Declaration and such other details as the Procuring Agency may consider appropriate, will be announced by the Bid Evaluation Committee.

24. Clarification of Bids

24.1 To assist in the examination, evaluation and comparison of Bids of the Bidders, the Procuring Agency may, ask any Bidder for a clarification of its Bid including breakdown of prices.

24.2 The request for clarification and the response shall be sought through EPADS v2.0 **before three days prior to the deadline for submission of bids.** No change in the prices or substance of the Bids shall be sought, offered, or permitted.

24.3 The alteration or modification in the BIDS which in any way affect the following parameters will be considered as a change in the substance of a Bids:

1. evaluation & qualification criteria;
2. required scope of work or specifications;
3. all securities requirements;
4. tax requirements;

5. terms and conditions of Bidding documents.

6. change in the ranking of the Bidder

24.4 From the time of Bids opening to the time of Contract award if any Bidder wishes to contact the Procuring Agency on any matter related to the Bids it should do so through **EPADS v2.0**.

25. Preliminary Examination of Bids

25.1 Prior to the detailed evaluation of Bids, the Procuring Agency will determine whether each Bid:

1. meets the eligibility criteria defined in **ITB 3**;
2. has been prepared as per the format and contents defined by the Procuring Agency in the Bidding documents;
3. is accompanied by the required securities; and
4. is substantially responsive to the requirements of the Bidding documents.

25.2 The Procuring Agency's determination of a Bid's responsiveness will be based on the contents of the Bid itself.

25.3 A substantially responsive Bid is one which conforms to all the terms, conditions, and specifications of the Bidding documents, without material deviation or reservation. A material deviation or reservation is one that: -

1. affects in any substantial way the scope, quality, or performance of the Goods;
2. limits in any substantial way, inconsistent with the Bidding documents, the Procuring Agency's rights or the Bidders obligations under the Contract; or
3. if rectified, would affect unfairly the competitive position of other Bidders presenting substantially responsive Bids.

25.3 If a Bids is not substantially responsive, it will be rejected by the Procuring Agency and may not subsequently be evaluated for complete technical responsiveness.

26. Examination of Terms and Conditions; Technical Evaluation

26.1 The Procuring Agency shall examine the Bids to confirm that all terms and conditions specified in the **GCC** and the **SCC** have been accepted by the Bidder without any material deviation or reservation.

26.2 The Procuring Agency shall evaluate the technical aspects of the Bids submitted, to confirm that all requirements specified in Schedule of Requirements and Technical Specifications of the Bidding documents have been met without material deviation or reservation.

26.3 If after the examination of the terms and conditions and the technical evaluation, the Procuring Agency determines that the Bid is not substantially responsive in accordance with **ITB 25.2**, it shall reject the Bid.

27. Correction of Errors

27.1 Bids determined to be substantially responsive will be checked for any arithmetic errors. Errors will be corrected as follows: -

1. if there is a discrepancy between unit prices and the total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail, and the total price shall be corrected, unless in the opinion of the Procuring Agency there is an obvious misplacement of the decimal point in the unit price, in which the total price as quoted shall govern and the unit price shall be corrected;
2. if there is an error in a total corresponding to the addition or subtraction of sub-totals, the sub-totals shall prevail and the total shall be corrected; and
3. where there is a discrepancy between the amounts in figures and in words, the amount in words will govern.
4. Where there is discrepancy between grand total of price schedule and amount mentioned on the Form of Bids, the amount referred in Price Schedule shall be treated as correct subject to elimination of other errors.

27.2 The amount stated in the Bid will, be adjusted by the Procuring Agency in accordance with the above procedure for the correction of errors and, with the concurrence of the Bidder, shall be considered as binding upon the Bidder. If the Bidder does not accept the corrected amount, its Bid will then be rejected, and the Bid Security may be forfeited or the Bids Securing Declaration may be executed.

28. Conversion to Single Currency

28.1 To facilitate evaluation and comparison, the Procuring Agency will convert all Bids prices expressed in the amounts in various currencies in which the Bids prices are payable. For the purposes of comparison of bids quoted in different currencies, the price shall be converted into a single currency specified in the bidding documents. The rate of exchange shall be the selling rate prevailing on the date of opening of financial bids specified in the bidding documents, in accordance with weighted average customer exchange rates list issued by the State Bank of Pakistan on that day.

29. Evaluation of Bids

29.1 The Bids, quotations, or proposals shall be evaluated by the respective evaluation committees as per evaluation criteria described in the Bidding Documents in accordance with Rule 29 and 30 of the Public Procurement Rules, 2004.

1. Least Cost Based Selection (LCBS)

After meeting the requirements of eligibility, qualification and substantial responsiveness, the bid in compliance with all the mandatory (technical) specifications/requirements and/or requisite quality threshold (if any), and having lowest evaluated cost (or financial proposal) shall be considered Successful Bid.

2. Quality and Cost Based Selection (QCBS)

In such combination, there shall be some specific weightage of both the technical features and financial aspects of the proposal. The financial marks shall be awarded on the basis of inverse proportion calculations. The successful bid shall be declared, on the basis of combined evaluation.

3. Quality Based Selection (QBS)

After meeting the requirements of eligibility, qualification and substantial responsiveness the bid in compliance with all the mandatory (technical) specifications/requirements and attaining highest marks in the Technical Evaluation considering all other qualitative and/or quantitative parameters (or point rated criteria) for technical proposal(s) such as working methodology, implementation plan, resource allocation, additional functionalities, risk management approach, knowledge transfer techniques, post implementation methodology etc. shall be treated as highest ranked bid. Later on, the financial proposal of highest ranked bidder shall be opened, however, in case of failure to proceed further with such a bidder, the procuring agency may resort to second

highest bidder and so on.

29.2 In case of tie of bids, the bidders shall be provided an opportunity to offer their best and final monetary offer through EPADS v2.0. However, in no case the rates shall be higher than the original financial bids.

30. Domestic Preference

30.1 The procuring agency shall evaluate and compare bids, allow for preference to domestic bidders, while competing with the international bidders in accordance with the policies of Federal Government.

The percentage of preference, to be accorded shall be clearly mentioned in the bidding documents under the bid evaluation criteria.

31. Determination of Successful Bid

31.1 Selection technique will be adopted for determining the Successful Bid in accordance with the criteria referred in the BDS or prescribed in the separate section titled as Evaluation Criteria.

31.2 In case where the Procuring Agency adopts the Cost Based Evaluation Technique and, the Bid with the lowest evaluated price from amongst those which are eligible, compliant and substantially responsive shall be the Successful Bid.

31.3 The Procuring Agency may adopt the Quality & Cost Based Selection Technique due to the following two reasons:

1. Where the Procuring Agency knows about the main features, usage and output of the products; however not clear about the complete features, technical specifications and functionalities of the goods to be procured and requires the bidders to submit their proposals defining those features, specifications and functionalities; or
2. Where the Procuring Agency, in addition to the mandatory requirements and mandatory technical specifications, requires parameters specified in Evaluation Criteria to be evaluated while determining the quality of the goods.

31.4 In such cases, the Procuring Agency may allocate certain weightage to these factors as a part of Evaluation Criteria, and may determine the ranking of the bidders on the basis of combined evaluation in accordance with provisions of Rule 2(1)(h) of the Public Procurement Rules, 2004.

32. Abnormally Low Financial Bids

32.1 Where the Bid price is considered to be abnormally low, the Procuring Agency shall perform price analysis either during determination of Successful Bids or as a part of the post-qualification process.

32.2 The Procuring Agency may reject an Abnormally low financial bids.

32.3 In order to identify the Abnormally Low Bids (ALB) following approaches can be considered to minimize the scope of subjectivity:

1. Comparing the Bids price with the cost estimate;
2. Comparing the Bids price with the Bids offered by other Bidders submitting substantially responsive Bids; and
3. Comparing the Bids price with prices paid in similar contracts in the recent past either government- or development partner-funded.

32.4 The Procuring Agency will determine to its satisfaction whether the Bidder that is selected as having submitted the successful bid is qualified to perform the contract satisfactorily.

32.5 The determination will take into account the Bidder's financial, technical, and production capabilities. It will be based upon an examination of the documentary evidence of the Bidder's qualifications submitted by the Bidder, as well as such other information as the Procuring Agency deems necessary and appropriate. Factors not included in these Bidding documents shall not be used in the evaluation of the Bidders' qualifications.

32.6 Procuring Agency may seek "Certificate for Independent Price Determination" from the Bidder and the results of reference checks may be used in determining an award of contract.

Explanation: The Certificate shall be furnished by the Bidder. The Bidder shall certify that the price is determined keeping in view of all the essential aspects such as raw material, its processing, value addition, optimization of resources due to economy of scale, transportation, insurance and margin of profit etc.

32.7 An affirmative determination will be a prerequisite for award of the contract to the Bidder. A negative determination will result in rejection of the Bidder's Bids, in which event the Procuring Agency will proceed to the next ranked Bidder to make a similar determination of that Bidder's capabilities to

perform satisfactorily.

F. Award of Contract

33. Criteria of Award

33.1 The Procuring Agency will award the Contract to the Bidder whose Bids has been determined to be substantially responsive to the Bidding documents and who has been declared as Most Advantageous Bidder.

34. Negotiations

34.1 The procuring agency shall not engage in negotiations with respect to scope and price with the bidder except when the procuring agency conducts a procurement using direct **or negotiated** contracting or a request for proposals with evaluation based on quality alone.

34.2 The procuring agency may negotiate with the most advantageous bid with a view to streamline the work or task execution, at the time of contract finalization on methodology, work plan, staffing, finalizing payment arrangements, delivery arrangements, minor amendments to the special conditions of the contract.

35. Procuring Agency Right to reject all bids

35.1 The Procuring Agency reserves the right to reject all bids or proposals at any time prior to the issuance of the Letter of Award, without incurring any liability, in accordance with Rule 33 of the Public Procurement Rules, 2004.

36. Procuring Agency's Right to Vary Quantities at the Time of Award

36.1 The Procuring Agency reserves the right at the time of contract award to increase or decrease the **quantity of** Goods originally specified in these Bidding documents provided this does not exceed **by** 15%, without any change in unit price or other terms and conditions of the Bids and Bidding documents.

37. Notification of Award

37.1 Prior to the award of contract, the procuring agency shall announce and publish the result of bid evaluation on **EPADS v2.0** in accordance with Rule 35

of the Public Procurement Rules, 2004.

37.2 The Bidder whose Bids has been accepted will be notified of the award by the Procuring Agency prior to expiration of the Bids/Bid Validity period. The Letter of Award will state the sum that the Procuring Agency will pay the successful Bidder in consideration for the delivery of Goods as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price).

37.3 The Letter of award will constitute the formation of the Contract, subject to the Bidder furnishing the Performance Guarantee and signing of the contract.

38. Signing of Contract

38.1 Promptly after issuance of Letter of award, Procuring Agency shall send the successful Bidder the draft Contract, incorporating all terms and conditions as agreed by the parties to the contract.

38.2 Immediately after the Redressal of grievance by the GRC (if any), mandatory standstill period in accordance with Rule 35 of the Public Procurement Rules, 2004 and **after fulfillment of all condition's precedent** of the Contract Form, the successful Bidder and the Procuring Agency shall sign the Contract.

39. Corrupt & Fraudulent Practices

39.1 Procuring Agencies (including beneficiaries of Government funded projects and procurement) as well as Bidders/Contractors under Government financed contracts, observe the highest standard of ethics during the procurement and execution of such contracts, and will avoid to engage in any corrupt and fraudulent practices.

F. Grievance Redressal & Complaint Review Mechanism

40. Constitution of Grievance Redressal

40.1 The Grievance Redressal Committee shall address the grievance, if any submitted by any party, including the bidder, in accordance with Rule 48 of the Public Procurement Rules, 2004 to be read with Redressal of Grievances Regulations, 2021.

40.2 In case if any party or the bidder is not satisfied with the decision of the GRC or if it fails to decide within ten days, the bidder or the party may file an appeal before the Appellate Committee of the Authority in accordance with Rule 48 of the Public Procurement Rules, 2004 to be read with Redressal of Grievances Regulations, 2021.

G. Mechanism of Blacklisting

41. Mechanism of Blacklisting

41.1 The Procuring Agency shall initiate blacklisting proceedings against any bidder, supplier, or contractor in accordance with the Mechanism for Blacklisting Regulations, 2024, read with Rule 19 of the Public Procurement Rules, 2004.

41.2 The blacklisted/debarred bidder may file the review petition before the Authority in accordance with Rule 19 of the Public Procurement Rules, 2004 to be read with Procedure of filing and disposal of Review Petitions Regulations, 2021.





Bid Data Sheet

Bids Data Sheet (BDS)

The following specific data for the procurement of Goods to be procured shall complement, supplement, or amend the provisions in the Instructions to Bidders (ITB). Whenever there is a conflict, the provisions herein shall prevail over those in ITB.

BDS Clause Number

ITB Number

Amendments of, and Supplements to, Clauses in the Instruction to Bidders

A. Introduction

BDS Clause Number 1

ITB Number 1.1

Name of Procuring Agency: **IESCO-PMU (Islamabad Electric Supply Company (IESCO))**

The subject of procurement is: **NCB-289 Procurement of 132KV Lightening Arrester with Supported Steel Structure (SSS)**

Expected commencement date: **Friday, October 30, 2026**

BDS Clause Number 2

ITB Number 2.1

Financial year for the operations of the Procuring Agency: **2026-27**

Name and identification number of the Contract: **P35663**

BDS Clause Number 3

ITB Clause Number 3.1

JV/Consortium or Association Allowed: **Yes**

Number of JV/Consortium Members: **2**

see section of eligibility criteria.

B. Bidding Documents

BDS Clause Number 4

ITB Number 8.1

The Bidders may seek clarifications through **EPADS v2.0** : Clarification Date: Monday, September 28, 2026
Pre-Bid Meeting: Wednesday, September 23, 2026 11:00 AM
Venue: Office Of Chief Engineer (Development) IESCO Adjacent to the 132KV Rawal Grid Station Club Road Islamabad.

C. Preparation of Bids

BDS Clause Number 5

ITB Number 10.1

The Language of all correspondences and documents related to the Bids shall be in: **English**

List of documents required along with the bid:

1. i. Joint venture Agreement if any on non-judicial stamp paper for particular tender ii. No Deviation certificates from Commercial terms and technical specification iii. Firms Engineers and professionals Information iv. Income tax returns for last three years v. Audited Financial Reports of last three years vi. Confirm and valid Bank Credit line (latest) (if any) required to establish cash flow or financial resources.

BDS Clause Number 6

ITB Number 11.1

Items/Lots and there related documents:

See section items and Lots

BDS Clause Number 7

ITB Number 12.1

Items / Lots Specifications:

see section of items specifications.

BDS Clause Number 8

ITB Number 15.6

The price shall be **Fixed**.

BDS Clause Number 9

ITB Number 16.1

Currency of the Bids shall be : **PKR**

BDS Clause Number 10

ITB Number 17.1

The Bids/Bid Validity period shall be: **90 Days**

BDS Clause Number 11

ITB Number 18.1

The amount of Bid Security shall be as defined in Bid Security Section for items and lots given in **BDS 6**

The Bid Security shall be in the form of:

D. Submission of Bids

BDS Clause Number 12

ITB Number 20.1

Bid shall be submitted online on EPADS v2.0 whereas hard copy of the bid security should be submitted to the following;

Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory
before bid submission deadline.

Bids that are not submitted on EPADS v2.0 shall be disqualified.

The deadline for Bids submission is: **Friday, October 2, 2026 11:00 AM**

E. Opening and Evaluation of Bids

BDS Clause Number 13

ITB Number 23.1

The Bids opening shall take place on **EPADS v2.0.**

Day : **Friday**

Date: **Friday, October 2, 2026**

Time : **11:30 AM**

BDS Clause Number 14

ITB Number 31.1

Selection technique adopted will be: **Least Cost Based Selection (LCBS)**
see Evaluation Criteria

F. Review of Procurement Decisions

BDS Clause Number 15

ITB Number 41.1

Grievance against this procurement shall be submitted online on EPADS v2.0.

Arbitrator shall be appointed by mutual consent of the both parties.




Eligibility Criteria

Bidder's Type	Required Registration
Sole Proprietorship	NADRA CITIZENSHIP (CNIC/NICOP)
Partnership Firm	FBR (NTN)
Company (Private Limited)	FBR (GSTN)
Company (Public Limited)	
Company (Holding Company)	
Company (Limited by Guarantee)	
State Owned Enterprise (Private Limited)	
State Owned Enterprise (Public Limited)	

Eligibility Criteria	Document
The amount of performance security (or guarantee), as a percentage of the Contract Price, shall be Ten (10%) percent of the Contract Price in favor of chief engineer (Development) IESCO from Schedule Bank of Pakistan having rating A+ in shape of Bank Guarantee. Contractor will provide performance Guarantee at time of acceptance of Notification of Award	Yes
Bid Declaration Form not applicable	No

Bid security must be submitted in an acceptable form in the amount fixed in PKR valid for 28 days beyond bid validity period in favor of Chief Engineer (Development), IESCO, Islamabad.	Yes
The bidder shall include all applicable taxes, duties, levies and GST etc. as per PPRA EPADS v2.0 in the bid price. Any applicable tax or duty not included in the quoted price shall be deducted from the bidder's payments as per applicable Government rules and SOPs. No additional payment shall be made on this account. Moreover, any excuse of bidder for not adding the taxes amount in the bid price shall not be accepted.	Yes
Price schedule attached as annexure shall be considered for bid price being mandatory to be filled for responsiveness.	Yes



Evaluation Criteria

Eligible bidder(s) with substantially responsive bid(s) offering **Least Cost Based Selection (LCBS)** shall be consider for the award of contract(s).

Least Cost Based Selection (LCBS)

Weightage

Technical Evaluation %	
100	

Technical Marks	100
Passing Marks	100
Technical Evaluation Criteria	
Bidder or its manufacturer or Joint Venture (JV) must have successfully completed at least two (02) contracts of similar complexity involving same or higher-rated material/equipment during the last ten (10) years. The aggregate value of both contracts shall be equal to or greater thanRs. 50M butnone of the contract value should be less than 30% of aggregate value.(Rs. 15M) (Quantitative)(Doc Required)	30
Manufacturer shall demonstrate at least five years experience in designing and manufacturing of similar nature/complex involving same or higher rated equipment/material. Two (02) years satisfactory operation performance of same or high rated equipment. (Quantitative)(Doc Required)	30

Manufacturer will indicate its manufacturing / production capacity which shall be double the total sum of orders already in hand, expected orders in pipe line and this order (if placed by the bidder) (Quantitative)(Doc Required)	10
Bidder's Net Worth for last year calculated as difference b/w total assets & total liabilities should be positive. however bidder's net worth shall be equal to or greater than 40% of Rs. 50 M (20 M) (Quantitative)(Doc Required)	10
Minimum average annual turnover of PKR calculated as total revenue of the Bidder over the last three Years shall be equal to or greater than Rs. 76 M (Quantitative)(Doc Required)	10
Specify proposed sources of financing, working capital and lines of credit available to meet the cash flow demands shall be equal to or greater than Rs.50 M (Quantitative)(Doc Required)	10



Items/Lots

Items Without Lots :

Item	UNSPSC	Delivery Schedule	Quantity	Bid Security	Manufacturer / Dealer Authorization	Warranty
Procurement of 132KV Lightning Arrester with Supported Steel Structure (SSS)	Switchgear systems	Address: IESCO Regional store new wah Schedule: (120 Days (EXW Basis) for local / 210 Days (DDP Basis) for foreign) After signing of contract Quantity: 65/Qty	65/Qty	1794113 PKR	Manufacturer Authorization form	730 Days

Related Services of Goods:

No



Items/Lot Specification


Items Without Lots :

Item: Procurement of 132KV Lightning Arrester with Supported Steel Structure (SSS)

UNSPSC: Switchgear systems

Specifications / Requirementss:

P-181:2012



Price Schedule

For Individual Items

#	Item Title	Quantity	Unit Price (PKR)	Total Price (PKR)	Delivery Location	Delivery Period / Year	Country of Origin
1							
2							

For Lots

#	Lot Title	Total Lot Price (PKR)	Country of Origin
1	[Lot 1 Title]		





General Conditions of Contract

A. General

1. Definitions

1.1 Unless the context otherwise requires, the following terms whenever used in this Contract shall have the same meaning and shall be interpreted as indicated

- a. "Applicable Law" means the laws and any other instruments having the force of law in the Government's Country, or in such other country as may be specified in the Special Conditions of the Contract (SC), as they may be issued and in force from time to time;
- b. "Procuring Agency" means:-
 - a. any Ministry, Division, Department or any Office of the Government;
 - b. any authority, corporation, body or organization established by or under a Law or which is owned or controlled by the Government;
- c. "The Contract" means an agreement enforceable by law;
- d. "The Contract Price" means the price payable to the Bidder under the Contract for the full and proper performance of its contractual obligations;
- e. "Ancillary Services" means those services ancillary to the provision of Goods, such as transportation and insurance, and any other incidental services, such as installation, commissioning, provision of technical assistance, training, and other such obligations of the Bidder covered under the Contract;
- f. "GCC" means the General Conditions of Contract contained in this section;
- g. "SCC" means the Special Conditions of Contract by which the GCC may be amended or supplemented;
- h. "Day" means calendar day unless indicated otherwise.
- i. "Effective Date" means the date on which this Contract comes into force and effect.
- j. "The Bidder" means the individual or corporate body whose Bids to provide the Goods has been accepted by the Procuring Agency;
- k. "The Project Site," where applicable, means the place or places named in Bids Data Sheet and technical Specifications;
- l. "Government" means the Government of Pakistan;
- m. "Subcontractor" means any entity to which the Bidder subcontracts any part of the Goods.
- n. "Service" means any object of procurement other than goods or works;
- o. "Party" means the Procuring Agency or the Bidder, as the case may be, and "Parties" means both of them;
- p. "Foreign Currency" means any currency other than the currency of the country of the Procuring Agency;

q. "Completion Date" means the date of completion of the contract by the Bidder as certified by the Procuring Agency;

r. "In Writing" means communicated in written form with proof of receipt;

s. "Local Currency" means the currency of Pakistan;

2. Application and Interpretation

2.1 These General Conditions shall apply to the extent that they are not superseded by provisions of other parts of the Contract.

2.2 In interpreting these Conditions of Contract headings and marginal notes are used for convenience only and shall not affect their interpretations unless specifically stated; references to singular include the plural and vice versa; and masculine include the feminine. Words have their ordinary meaning under the language of the Contract unless specifically defined.

3. Applicable Law

3.1 The contract shall be governed and interpreted in accordance with the laws of Pakistan, unless otherwise specified in SCC.

4. Governing Language

4.1 The Contract as well as all correspondence and documents relating to the Contract exchanged between the Bidder and the Procuring Agency, shall be written in the **English language** unless otherwise stated in the SCC. Supporting documents and printed literature that are part of the Contract may be in another language provided these are accompanied by an accurate translation of the relevant passages in English, in which case, for purposes of interpretation of the Contract, this translation shall govern.

5. Notices

5.1 Any notice, request, or consent made pursuant to this Contract shall be in writing and shall be deemed to have been made when delivered in person to an authorized representative of the Party to whom the communication is addressed, or when sent by registered mail, telex, telegram, or facsimile to such Party at the address specified in the SCC.

6. Delivery/Location

6.1 The Goods shall be delivered to such locations as the Procuring Agency may approve and as specified in SCC.

7. Authorized Representatives / Authority of Member in charge

7.1 Any action required or permitted to be taken, and any document required or permitted to be executed, under this Contract by the Procuring Agency or the Bidder may be taken or executed by the officials specified in the SCC.

B. Commencement, Completion, Modification, and Termination of Contract

8. Effectiveness of Contract

8.1 This Contract shall come into effect on the date the Contract is signed by both parties and such other later date as may be stated in the SCC.

9. Commencement of Services

9.1 The Bidder shall confirm availability of Key Experts and begin carrying out the Services not later than the number of days after the Effective Date specified in the SCC.

10. Program

10.1 Before commencement of the Services, the Bidder shall submit to the Procuring Agency for approval a Program showing the general methods, arrangements, order and timing for all activities. The Services shall be carried out in accordance with the approved Program as updated.

11. Starting Date/Expiration Date

11.1 The Bidder shall start carrying out the Services Five (05) days after the date the Contract becomes effective, or at such other date as may be specified in the SCC.

11.2 Unless terminated earlier pursuant to Clause **GCC 15** hereof, this Contract shall expire at the end of such time period after the Effective Date as specified in the SCC.

12. Entire Agreement

12.1 This Contract contains all covenants, stipulations and provisions agreed by the Parties. No agent or representative of either Party has authority to make, and the Parties shall not be bound by or be liable for, any statement, representation, promise or agreement not set forth herein.

13. Modification

13.1 Any modification or variation of the terms and conditions of this Contract, including any modification or variation of the scope of the Services, may only be made by written agreement between the Parties. However, each Party shall give due consideration to any Bids for modification or variation made by the other Party.

13.2 In cases of any modifications or variations, the prior written consent of the Procuring Agency is required.

14. Force Majeure

14.1 Definition

For the purposes of this Contract, “Force Majeure” means an event which is beyond the reasonable control of a Party and which makes a Party’s performance of its obligations under the Contract impossible or so impractical as to be considered impossible under the circumstances.

14.2 No Breach of Contract

The failure of a Party to fulfill any of its obligations under the contract shall not be considered to be a breach of, or default under, this Contract in so far as such inability arises from an event of Force Majeure, provided that the Party affected by such an event (a) has taken all reasonable precautions, due care and reasonable alternative measures in order to carry out the terms and conditions of this Contract, and (b) has informed the other Party as soon as possible about the occurrence of such an event.

14.3 Extension of Time

Any period within which a Party shall, pursuant to this Contract, complete any action or task, shall be extended for a period equal to the time during which such Party was unable to perform such action as a result

of Force Majeure.

14.4 Payments

During the period of their inability to perform the Services as a result of an event of Force Majeure, the Bidder shall be entitled to continue to be paid under the terms of this Contract, as well as to be reimbursed for additional costs reasonably and necessarily incurred by them during such period for the purposes of the Services and in reactivating the Service after the end of such period.

15. Termination

15.1 By the Procuring Agency

The Procuring Agency may terminate this Contract in case of the occurrence of any of the events specified in paragraphs (a) through (e) of this Clause. In such an occurrence the Procuring Agency shall give at least thirty (30) calendar days' written notice of termination to the Bidder in case of the events referred to in (a) through (d); at least sixty (60) calendar days' written notice in case of the event referred to in (e);

- a. If the Bidder fails to remedy a failure in the performance of its obligations hereunder, as specified in a notice of suspension;
- b. If the Bidder becomes (or, if the Bidder consists of more than one entity, if any of its members becomes) insolvent or bankrupt or enter into any agreements with their creditors for relief of debt or take advantage of any law for the benefit of debtors or go into liquidation or receivership whether compulsory or voluntary;
- c. If the Bidder fails to comply with any final decision reached as a result of arbitration proceedings;
- d. If, as the result of Force Majeure, the Bidder is unable to perform a material portion of the Services for a period of not less than sixty (60) calendar days;
- e. If the Procuring Agency, in its sole discretion and for any reason whatsoever, decides to terminate this Contract;

15.2 By the Bidder

The Bidder may terminate this Contract, by not less than thirty (30) calendar days' written notice to the Procuring Agency, in case of the occurrence of any of the events specified in paragraphs (a) through (d) of this Clause.

- a. If the Procuring Agency fails to pay any money due to the Bidder pursuant to this Contract and not subject to dispute within forty-five (45) calendar days after receiving written notice from the Bidder that such payment is overdue.
- b. If, as the result of Force Majeure, the Bidder is unable to perform a material portion of the Services for a period of not less than sixty (60) calendar days.
- c. If the Procuring Agency fails to comply with any final decision reached as a result of arbitration.
- d. If the Procuring Agency is in material breach of its obligations pursuant to this Contract and has not remedied the same within forty-five (45) days (or such longer period as the Bidder may have subsequently approved in writing) following the receipt by the Procuring Agency of the Bidder's notice specifying such breach.

C. Obligations of the Bidder

16. General

16.1 Standard of Performance

1. The Bidder shall deliver the product and carry out the Services with all due diligence, efficiency and economy, in accordance with generally accepted professional standards and practices, and shall observe sound management practices, and employ appropriate technology and safe and effective equipment, machinery, materials and methods. The Bidder shall always act, in respect of any matter relating to this Contract or to the Services, as a faithful adviser to the Procuring Agency, and shall at all times support and safeguard the Procuring Agency's legitimate interests in any dealings with the third parties.

16.2 Law Applicable to Goods

The Bidder shall deliver the goods in accordance with the Contract and in accordance with the Law of Pakistan and shall take all practicable steps to ensure that any of its Experts and Sub-Bidders, comply with the Applicable Law.

17. Conflict of Interests

17.1 Bidder Not to Benefit from Commissions and Discounts.

The remuneration of the Bidder shall constitute the Bidder's sole remuneration in connection with this Contract or the Services, and the Bidder shall not accept for their own benefit any trade commission, discount, or similar payment in connection with activities pursuant to this Contract or to the Services or in the discharge of their obligations under the Contract, and the Bidder shall use their best efforts to ensure that the Personnel, any Subcontractors, and agents of either of them similarly shall not receive any such additional remuneration.

17.2 Bidder and Affiliates Not to be Otherwise Interested in Project

The Bidder agree that, during the term of this Contract and after its termination, the Bidder and its affiliates, as well as any Subcontractor and any of its affiliates, shall be disqualified from providing Goods for any project resulting from or closely related to the Services.

17.3 Prohibition of Conflicting Activities

Neither the Bidder nor its Subcontractors nor the Personnel shall engage, either directly or indirectly, in any of the following activities:

- a. during the term of this Contract, any business or professional activities in the Government's country which would conflict with the activities assigned to them under this Contract;
- b. during the term of this Contract, neither the Bidder nor their Subcontractors shall hire public employees in active duty or on any type of leave, to perform any activity under this Contract;

18. Confidentiality

18.1 Except with the prior written consent of the Procuring Agency, the Bidder and the Experts shall not at any time communicate to any person or entity any confidential information acquired in the course of the contract.

19. Insurance to be Taken Out by the Bidder

19.1 The Bidder(a) shall take out and maintain, and shall cause any Subcontractors to take out and maintain, at its (or the Subcontractors', as the case may be) own cost but on terms and conditions approved by the Procuring Agency, insurance against the risks, loss or damage, and for the coverage, as shall be specified in the SCC; and (b) at the Procuring Agency's request, shall provide evidence to the Procuring Agency showing that such insurance has been taken out and maintained and that the current premiums have been paid.

20. Bidder's Actions Requiring Procuring Agency's Prior Approval

20.1 The Bidder shall obtain the Procuring Agency's prior approval in writing before taking any of the following actions:

- (a) appointing such members of the Personnel not provided by the Bidder;
- (b) changing the Program of activities; and
- (c) any other action that may be specified in the SCC.

21. Reporting Obligations

21.1 The Bidder shall submit to the Procuring Agency the reports and documents in the numbers, and within the periods as prescribed by the Procuring Agency.

22. Liquidated Damages

22.1 If the Supplier fails to deliver any or all of the Goods or to perform the Services within the period(s) specified in the Contract, the Procuring Agency shall, without prejudice to its other remedies under the Contract, deduct from the Contract Price, as liquidated damages, a sum equivalent to the percentage specified in SCC of the delivered price of the delayed Goods or unperformed Services for each week or part thereof of delay until actual delivery or performance, up to a maximum deduction of the performance security (or guarantee) specified in SCC. Once the said maximum is reached, the Procuring Agency may consider termination of the Contract pursuant to **GCC Clause 15**.

22.2 Correction for Over-payment

If the Intended Completion Date is extended after liquidated damages have been paid, the Procuring Agency shall correct any overpayment of liquidated damages by the Bidder by adjusting the next payment certificate. The Bidder shall be paid interest on the overpayment, calculated from the date of payment to the date of repayment, at the rates specified in SCC.

22.3 Lack of performance penalty

If the Bidder has not corrected a Defect within the time specified in the Procuring Agency's notice, a penalty for Lack of performance will be paid by the Bidder. The amount to be paid will be calculated as a percentage of the cost of having the Defect corrected, assessed as specified in the SCC.

23. Performance Guarantee

23.1 Within Seven (07) days from the issuance of acceptance letter from the Procuring Agency, the successful Bidder shall furnish the Performance Guarantee in shape of ----- at the discretion of the PA in the amount **specified in SCC**. In case the amount of Bids security is equal or greater than

23.2 The proceeds of the Performance Guarantee shall be payable to the Procuring agency as compensation for any loss resulting from the Supplier's failure to complete its obligations under the Contract.

23.3 The Performance Guarantee shall be denominated in the currency of the Contract, or in a freely convertible currency acceptable to the Procuring agency and shall be in the acceptable form as specified in SCC.

23.4 The Performance Guarantee will be discharged by the Procuring agency and returned to the Supplier not later than thirty (30) days following the date of completion of the Supplier's performance obligations under the Contract, including any warranty obligations, unless otherwise **specified in SCC**.

24. Fraud and Corruption

24.1 The Procuring Agency requires the Supplier to disclose any commissions or fees that may have been paid or are to be paid to agents or any other party with respect to the Bidding process or execution of the Contract. The information disclosed must include at least the name and address of the agent or other party, the amount and currency, and the purpose of the commission, gratuity or fee.

25. Sustainable Procurement

25.1 The Bidder shall conform to the sustainable procurement contractual provisions, if and as specified in the SCC.

D. Bidder's Personnel

26. Description of Personnel

26.1 The titles, agreed job descriptions, minimum qualifications, and estimated periods of engagement in the carrying out of the Services of the Bidder's Key Personnel. The Key Personnel listed by title as well as by name are hereby approved by the Procuring Agency.

27. Removal and/or Replacement of Personnel

27.1 Except as the Procuring Agency may otherwise agree, no changes shall be made in the Key Personnel. If, for any reason beyond the reasonable control of the Bidder, it becomes necessary to replace any of the Key Personnel, the Bidder shall provide as a replacement a person of equivalent or better qualifications.

27.2 If the Procuring Agency finds that any of the Personnel have (i) committed serious misconduct or have been charged with having committed a criminal action, or (ii) have reasonable cause to be dissatisfied with the performance of any of the Personnel, then the Bidder shall, at the Procuring Agency's written request specifying the grounds thereof, provide as a replacement a person with qualifications and experience acceptable to the Procuring Agency.

27.3 The Bidder shall have no claim for additional costs arising out of or incidental to any removal and/or replacement of Personnel.

E. Obligations of the Procuring Agency

28. Assistance and Exemptions

28.1 The Procuring Agency shall use its best efforts to ensure that the Government shall provide the Bidder such assistance and exemptions as specified in the SCC.

29. Change in the Applicable Law

29.1 If, after the date of this Contract, there is any change in the Applicable Law with respect to taxes and duties which increases or decreases the cost of the related Services rendered by the Bidder, then the remuneration and reimbursable expenses otherwise payable to the Bidder under this Contract shall be increased or decreased accordingly by agreement between the Parties, and corresponding adjustments shall be made to the amounts referred in the SCC.

30. Services and Facilities

30.1 The Procuring Agency shall make available to the Bidder and the Experts, for the purposes of the Services and free of any charge, the services, facilities and property described , at the times and in the manner specified in the SCC or terms of reference.

30.2 In case that such services, facilities and property shall not be made available to the Bidder, the Parties shall agree on (i) any time extension that it may be appropriate to grant to the Bidder for the performance of the Services, (ii) the manner in which the Bidder shall procure any such services, facilities and property from other sources, and (iii) the additional payments, if any, to be made to the Bidder as a result thereof.

F. Payments to the Bidder

31. Contract Price

31.1 The price payable shall be in Pakistani Rupees unless otherwise specified in the SCC. Prices charged by the Supplier for Goods delivered under the Contract shall not vary from the prices quoted by the Supplier in its Bid.

32. Terms and Conditions of Payment

32.1 Payments will be made to the Bidder according to the payment schedule stated in the SCC and as per actual invoice submitted by the Bidder.

32.2 Unless otherwise stated in the SCC, the advance payment shall be made against the provision by the Bidder of a bank guarantee for the same amount, and shall be valid for the period stated in the SCC. Any other payment shall be made after the conditions listed in the SCC for such payment have been met, and the Bidder have submitted an invoice to the Procuring Agency specifying the amount due.

33. Currency of Payment

33.1 Any payment under this Contract shall be made in the currency(ies) specified in the SCC.

G. Quality Control

34. Identifying Defects

34.1 The principle and modalities of Inspection of the Goods by the Procuring Agency shall be as indicated in the SCC. The Procuring Agency shall check the Bidder's performance and notify him of any Defects that are found. Such checking shall not affect the Bidder's responsibilities. The Procuring Agency may instruct the Bidder to search for a Defect and to uncover and test any service that the Procuring Agency considers may have a Defect. Defect Liability Period is as defined in the SCC.

35. Correction of Defects, and

Lack of Performance Penalty

35.1 The Procuring Agency shall give notice to the Bidder of any Defects before the end of the Contract. The Defects liability period shall be extended for as long as Defects remain to be corrected.

35.2 Every time notice a Defect is given, the Bidder shall correct the notified Defect within the length of time specified by the Procuring Agency's notice.

35.3 If the Bidder has not corrected a Defect within the time specified in the Procuring Agency's notice, the Procuring Agency will assess the cost of having the Defect corrected, the Bidder will pay this amount, and a Penalty for Lack of Performance.

36. Taxes and Duties

36.1 A Supplier shall be entirely responsible for all taxes, duties, fees, etc., incurred until delivery of the contracted Goods to the Procuring Agency.

H. Settlement of Disputes

37. Alternate Dispute Resolution

37.1 The disputes between the parties to the contract may be settled in accordance with Public Procurement Rules, 2004.

37.2 The procuring agency shall refer the matter to the Chief Justice Islamabad High Court or Managing Director PPRA or the Secretary Ministry of Law & Justice for appointment of Arbitrator.

37.3 The fee for the Arbitrator shall be specified in Pak Rupees as determined by the appointing authority which shall be borne and shared equally by the contracting parties.



Special Conditions of Contract

SECTION VIII. SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions of Contract shall supplement the General Conditions of Contract. Whenever there is a conflict, the provisions herein shall prevail over those in the Conditions of Contract. The corresponding clause number of the GCC is indicated in parentheses.

Number of GC Clause

Amendments of, and Supplements to, Clauses in the General Conditions of Contract

Number of GC Clause 1

Definitions

The Procuring Agency is: IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory

The Supplier is:

The title of the subject procurement is: NCB-289 Procurement of 132KV Lightning Arrester with Supported Steel Structure (SSS)

Number of GC Clause 3

Applicable/Governing Law:

The Contract shall be interpreted in accordance with the laws of Islamic Republic of Pakistan

Number of GC Clause 4

Language:

The language of the Contract, all correspondence and communications to be given, and all other documentation to be prepared and supplied under the Contract shall be in **English**.

Number of GC Clause 5

Notices:

The addresses for the notices are:

Procuring Agency:

IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director
Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory
+92-319-599-2205
iescopmu@iesco.com.pk

Contractor/ Bidder:

[Name, address and telephone number].

The Contractor/ Bidder's Representative(s)

[Name, address, telephone number and e-mail address]

Number of GC Clause 7.1

The Authorized Representatives are:

For the Procuring Agency:

IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director
Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory
+92-319-599-2205
iescopmu@iesco.com.pk

For the Bidder:

Name:

Designation:

Address:

Number of GC Clause 8

Effectiveness of the contract

Number of GC Clause 9

Commencement of Contract:

Number of GC Clause 11.2

Expiration of Contract:

Number of GC Clause 15

Termination

In the event of termination of the contract due to any reason as already defined in the General Conditions of Contract, the Bidder shall be responsible for providing to the Authority the Goods till the time of alternate arrangements.

Number of GC Clause 17

Conflict of Interest:

The Procuring Agency reserves the right to determine on a case-by-case basis whether the Bidder should be disqualified from providing goods or services due to a conflict of a nature described in Clause GCC 17.

Number of GC Clause 22

Liquidated Damages

If the Bidder fails to provide services as required under the contract or in case of any data loss/data breach or any incident compromising the data security or other such failures related to any services, the Bidder shall pay to the Procuring Agency as Liquidated Damages at a rate of **0.05%** to **10.00%** of the Contract value, in accordance with the extent of performance failure & the cost of investigating such incidents as judged by the

Authority.

Number of GC Clause 23

Performance Guarantee:

The amount of performance guarantee shall be **10.00%** of the contract price in acceptable form of **Bank Guarantee**

Number of GC Clause 32

Payment terms:

Payment will be made to the Bidder against the procured Goods and services according to the actual invoice or running bills submitted by the Bidder against the services provided within the time given in the conditions of the contract.

Number of GC Clause 33

Currency of Payment:

All the payment to be released to the contractor/Bidder shall be in Pakistani Rupees.

Number of GC Clause 34

Identifying Defects:

The Authority reserves the right at any time to inspect the premises of the provider to inspect the goods and monitor the goods being provided.

Inspections & Tests Requirements

Quality and quantity inspection shall be carried out prior to shipment of Goods by the manufacturer(s) at the supplier's own expense and responsibility in terms of the items specified in the specifications. The supplier shall submit the inspection certificate issued by him which should be attached with the certificate(s) of the manufacturer(s) to the Procuring Agency in order to ensure that the goods are manufactured in compliance with the contract

Factory Acceptance Tests (FAT) shall be carried out at the premises of Manufacturer jointly witnessed with IESCO Engineers. The Contractor shall keep the Engineer informed of the progress of manufacture and notify the Engineer approximately six (6) weeks in advance, in writing as to when the Goods or any part thereof will be ready for inspection and for shipping to wharf at the port of entry/disembarkation.

Following the receipt of such notice, the Engineer shall nominate to arrange pre-shipment inspection of the Goods or any part thereof including the packing at the Contractor's premises and will issue a pre-shipment Inspection Report or waiver to pre-shipment inspection. The Goods or any part thereof shall be shipped or delivered only upon issuance of pre-shipment inspection report. The Goods/material shall be subject to the type, sample and routine tests as described in the Specifications.

The contractor shall provide free of charge all such assistance, instruments, machines, labor and materials as are normally required for carrying out such tests. In case a part or whole of the equipment being supplied at the project by the contractor is from within the country (Pakistan) or outside country, the cost of performing as well as witnessing any test by the Inspectors during pre-shipment local inspection shall be borne by the

contractor if such tests are clearly intended by or provided

for in the specifications or as agreed between IESCO and the contractor. Two (2) number authorized Engineers from IESCO will carry out inspection of the material at manufacturer's works. A notice of at least six (6) weeks advance, in writing shall have to be given to the IESCO by the Supplier when the stores against the order are ready for Inspection. Manufacturer will provide facilities for tests as per tender specifications free of cost.

All reasonable facilities as provided in the specifications or followed by Trade & Industry in general shall have to be offered to the Inspecting officers, by the Supplier at their expense for carrying out Testing and Inspection. If Goods are being manufactured on other premises, the Contractor shall obtain permission of the Engineer/IESCO to carry out such inspection, examinations and testing at those premises.

For such purpose, the Supplier shall provide free access at all times during manufacture, assembly and testing to the premises in which the work is being carried out. The contractor will cover all the expenses in context of witnessing of the tests by the Inspectors including 1st class traveling (by air or by road depending on the distance from Islamabad Pakistan to the place or places of inspections), boarding & lodging in any A class accommodation, local transportation and daily allowance

As per prevailing rules per inspector to meet other expenses. Abroad Testing witnessing @ 250 USD and 15% incidental charges per inspector. Local Testing Witnessing as per prevailing rules and regulation of TA/DA. The supplier shall submit the inspection certificate issued by him which should be attached with the certificate(s) of the manufacturer(s) to the Procuring Agency in order to ensure that the goods are manufactured in compliance with the contract.

In case the Goods fail to withstand any test, the cost of repeating such test and the cost of witnessing such test by the authorized Engineer/ Inspectors of IESCO shall be borne by the contractor and the equipment released or modified to the satisfaction of the Engineer without any additional cost to the IESCO.

Any inspection and /or witnessing of tests or the waiving of such tests and /or surveillance by the IESCO/Engineer or their two Nos. representatives / Inspectors shall not relieve the Supplier of its obligations and responsibilities under the Contract regardless of any approval or consent given by the IESCO/Engineer or their two Nos. Representatives Inspector. Two copies of all the Inspection and Tests Reports and certificates including that for-quality control shall be supplied to IESCO

The IESCO/Consultant or his two Nos. representatives/Inspector shall countersign the reports and certificates of such tests as have been witnessed. The Purchaser may reject any Goods or any part thereof that fail to pass any test and/or inspection or do not conform to the specifications. The Supplier shall either rectify or replace such rejected Goods or parts thereof or make alterations necessary to meet the specifications at no cost to the Purchaser, and shall repeat the test and/or inspection,

at no cost to the Purchaser, upon giving a notice. The Purchaser may require the Supplier to carry out any test and /or inspection not required by the Contract but deemed necessary to verify that the characteristics and performance of the Goods comply with the technical specifications, codes and standards under the Contract, the costs and expenses incurred in the carrying out of such test and/or inspection shall be borne by the Contractor / Supplier.

Further, if such test and /or inspection impede the progress of manufacturing and/or the Supplier's performance of its other obligations under the Contract, due allowance will be made in respect of the Delivery Dates and Completion Dates and the other obligations so affected. The Supplier shall obtain from any relevant third party or manufacturer any necessary permission or consent to enable the Purchaser or its designated representative to attend the test and/or inspection.

In case, due to any Pandemic/ urgency of material etc. where witnessing of factory acceptance testing/ foreign Inspection (if involved) may not be possible considering travels restrictions, requirement of material then third-party inspection will be opted through signing of Addendum after approval of Competent Authority. In such cases contractor will provide 03-year additional extended Warranty in lieu of waiver of physical inspection.

The third-party inspection will be carried out after obtaining approval of Credible Testing laboratory from IESCO conducted by third party inspector witnessed by two No. IESCO Engineers on line through Zoom/ skype. The charges of testing/ witnessing of type tests will be borne by Supplier. The material will be delivered after approval of inspection certificate & test reports of approved inspectors from IESCO.

Delivery & Documents

For Goods supplied from abroad: (Outside purchaser's country on DDP) Upon shipment, the Supplier shall notify the Procuring Agency and the Insurance Company by cable the full details of the shipment, including Contract number, description of Goods, quantity, the vessel, the bill of lading number and date, port of loading, date of shipment, port of discharge, etc

The Supplier shall mail the documents (but not limited to the following papers) to the Procuring Agency, with a copy to the Insurance Company: (i) One original plus four copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount; (ii) original and four copies of the negotiable, clean, on-board bill of lading marked "freight prepaid" and four copies of nonnegotiable bill of lading

(iii) One original plus four copies of the packing list identifying contents of each package, (iv.) Insurance Certificate, (v.)Manufacturers or Supplier's warranty certificate, (vi.)inspection certificate, issued by the nominated inspection agency, and the Supplier's factory inspection report; and

(vii.) Certificate of country of origin issued by the chamber of commerce and industry or equivalent authority in the country of origin in duplicate. The above documents shall be received by the Procuring Agency at least one week before arrival of the Goods at the port or place of arrival and, if not received, the Supplier will be responsible for any consequent expenses

For Goods from within Pakistan: (within purchaser's country on EXW) Upon delivery of the Goods to the transporter, the Supplier shall notify the Procuring Agency and mail the following but not limited documents to the Procuring Agency:(i.)one original plus four copies of the Supplier's invoice showing Goods' description, quantity, unit price, and total amount;

(ii.)delivery note, railway receipt, or truck receipt; (iii.)Manufacturers or Supplier's warranty certificate (iv.)inspection certificate issued by the nominated inspection agency, and the Supplier's factory inspection report; and

(v.)Certificate of country of origin issued by Pakistan Chamber of Commerce and Industry or equivalent authority in the country of origin in duplicate. The above documents shall be received by the Procuring Agency before arrival of the Goods and, if not received, the Supplier will be responsible for any consequent expenses

Number of GC Clause 37

Following is the guidance for Dispute Resolution

i. If any dispute of any kind whatsoever shall arise between the Authority and the Bidder in connection with or arising out of the Contract, including without prejudice to the generality of foregoing, any question regarding its existence, validity, termination and the execution of the Contract – whether during developing phase or after their completion and whether before or after the termination, abandonment or breach of the Contract – the parties shall seek to resolve any such dispute or difference by mutual diligent negotiations in good faith within 14 (fourteen) days following a notice sent by one Party to the other Party in this regard.

ii. At future of negotiation the dispute shall be resolved through mediation and mediator shall be appointed with the mutual consent of the both parties.

iii. At the event of failure of mediation to resolve the dispute relating to this contract such dispute shall finally be resolved through binding Arbitration by sole arbitrator in accordance with Arbitration Act 1940. The arbitrator shall be appointed by mutual consent of the both parties. The Arbitration shall take place in Islamabad, Pakistan and proceedings will be conducted in English language.

iv. The cost of the mediation and arbitration shall be shared by the parties in equal proportion however the both parties shall bear their own costs and lawyer's fees regarding their own participation in the mediation and arbitration. However, the Arbitrator may make an award of costs upon the conclusion of the arbitration making any party to the dispute liable to pay the costs of another party to the dispute.

v. Arbitration proceedings as mentioned in the above clause regarding resolution of disputes may be commenced prior to, during or after completion of the contract.

Notwithstanding any reference to the arbitration herein, the parties shall continue to perform their respective obligations under the Contract unless they otherwise agree that the Authority shall pay the Bidder any monies due to the Bidder.

Rules of procedure for arbitration proceedings:

Any dispute between the Authority and a Bidder who is a national of the Islamic Republic of Pakistan arising in connection with the present Contract shall be referred to adjudication or arbitration in accordance with the laws of the Islamic Republic of Pakistan including Arbitration Act 1940, however above provision shall prevail in referring the case to the Arbitrator.

Place of Arbitration and Award:

The arbitration shall be conducted in English language and place of arbitration shall be at Islamabad. The award of the arbitrator shall be final and shall be binding on the parties.



Bid Securing Declaration

Form 9: Bid Securing Declaration

Date: *[insert date (as day, month and year)]*

Bid No.: **P35663**

To: **IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory**

We, the undersigned, declare that:

We understand that, according to your conditions, Bids must be supported by a Bid Securing Declaration.

We accept that we will be blacklisted and henceforth cross debarred for participating in respective category of public procurement proceedings for a period of (not more than) six months, if fail to abide with a bid securing declaration, however without indulging in corrupt and fraudulent practices, if we are in breach of our obligation(s) under the Bid conditions, because we:

1. have withdrawn or modified our Bid during the period of Bid Validity specified in the Form of Bid;
2. Disagreement to arithmetical correction made to the Bid price; or
3. having been notified of the acceptance of our Bid by the Procuring Agency during the period of Bid Validity, (i) failure to sign the contract if required by Procuring Agency to do so or (ii) fail or refuse to furnish the Performance Security or to comply with any other condition precedent to signing the contract specified in the Bidding Documents.

We understand this Bid Securing Declaration shall expire if we are not the successful

Bidder, upon the earlier of (i) our receipt of your notification to us of the name of the successful Bidder; or (ii) twenty-eight (28) days after the expiration of our Bid.



Contract Form

SECTION IX: CONTRACT FORMS

THIS AGREEMENT made the ____ day of _____ 20____ between **IESCO-PMU (Islamabad Electric Supply Company (IESCO))**, Director Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory

(hereinafter called “the Procuring Agency”) of the one part and [name of Bidder] of [city and country of Bidder] (hereinafter called “the Bidder”) of the other part:

WHEREAS the Procuring Agency invited Bids for provision of goods, viz., **NCB-289 Procurement of 132KV Lightning Arrester with Supported Steel Structure (SSS) (P35663)** and has accepted a Bids by the Bidder for the provision of Goods in the sum of [contract price in words and figures] (hereinafter called “the Contract Price”).

NOW THIS CONTRACT WITNESSETH AS FOLLOWS:

1. In this Contract words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract referred to.

2. The following documents shall be deemed to form and be read and construed as part of this Contract, In the event of any ambiguity or conflict between the Contract Documents listed below, the order of precedence shall be the order in which the Contract Documents are listed below:-

1. This form of Contract;
2. the Form of Bids and the Price Schedule submitted by the Bidder;
3. the Schedule of Requirements;
4. the Technical Specifications;
5. the Special Conditions of Contract;
6. the General Conditions of the Contract;
7. the Procuring Agency’s Letter of Acceptance; and
8. [add here: any other documents]

3. In consideration of the payments to be made by the Procuring Agency to the Bidder as hereinafter mentioned, the Bidder hereby covenants with the Procuring Agency to provide the Goods related services and to remedy defects therein in conformity in all respects with the provisions of the Contract.

4. The Procuring Agency hereby covenants to pay the Bidder in consideration of the provision of Goods and the remedying of defects therein, the Contract Price or such other sum as may become payable under the

provisions of the contract at the times and in the manner prescribed by the contract.

IN WITNESS whereof the parties hereto have caused this Contract to be executed in accordance with their respective laws the day and year first above written.


Signed, sealed, delivered by _____ the _____ (for the Procuring Agency)

Witness to the signatures of the Procuring Agency:

.....

Signed, sealed, delivered by _____ the _____ (for the Procuring Agency)

Witness to the signatures of the Bidder:





Integrity Pact

Integrity Pact

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC. PAYABLE BY THE SUPPLIERS OF GOODS, SERVICES & WORKS IN CONTRACTS WORTH RS.10.00 MILLION OR MORE

Contract

Number: Contract

Value: Contract Title:

Dated:

[Name of Supplier] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Pakistan or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoP) through any corrupt business practice.

Without limiting the generality of the foregoing [Name of Supplier] represents and warrants that it has fully declared the brokerage, commission, fee etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultations fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP, except that which has been expressly declared pursuant hereto.

[Name of Supplier] certifies that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with GoP and has not taken any action or will not take any action to circumvent the above declaration, representative or warranty.

[Name of Supplier] accepts full responsibility and strict liability for making and false declaration, not making full disclosure, misrepresenting fact or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other right and remedies available to GoP under any law, contract or other instrument, be voidable at the option of GoP.

Notwithstanding any rights and remedies exercised by GoP in this regard, [Name of Supplier] agrees to indemnify GoP for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to GoP in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [Name of Supplier] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from GoP.



Performance Guarantee Form

Performance Guarantee Form

To: **IESCO-PMU (Islamabad Electric Supply Company (IESCO)), Director Head Office, Street # 40, Sector G-7/4., Islamabad Capital Territory**

WHEREAS *[name of Bidder]* (hereinafter called “the Bidder”) has undertaken, in pursuance of Contract No. *[reference number of the contract]* dated *[insert date]* for provision of Goods(hereinafter called “the Contract”).

AND WHEREAS it has been stipulated by you in the said Contract that the Bidder shall furnish you with a Bank Guarantee by a reputable bank for the sum specified therein as security for compliance with the Bidder’s performance obligations in accordance with the Contract.

AND WHEREAS we have agreed to give the Bidders guarantee:

THEREFORE, WE hereby affirm that we are Guarantors and responsible to you, on behalf of the Bidder, up to a total of *[amount of the guarantee in words and figures]*, and we undertake to pay you, upon your first written demand declaring the Bidder to be in default under the Contract and without cavil or argument, any sum or sums within the limits of *[amount of guarantee]* as aforesaid, without your needing to prove or to show grounds or reasons for your demand or the sum specified therein.

This guarantee is valid until the: *[insert date]*

Signature and seal of the Guarantors

[name of bank or financial institution]

[address]

[date]





Annexure

Manufacturer experience annex

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Manufacturer experience annex** (page number: 74)

Production capacity annex

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Production capacity annex** (page number: 75)

Bidder information form

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Bidder information form** (page number: 76)

Bidder JV form

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Bidder JV form** (page number: 77)

Deviation from contractual provision

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Deviation from contractual provision** (page number: 78)

Deviation technical provision

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Deviation technical provision** (page number: 79)

Qualification information

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Qualification information** (page number: 80)

Manufacturer authorization

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Manufacturer authorization** (page number: 83)

Manufacturer information form

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Manufacturer information form** (page number: 84)

Production capacity of manufacturer

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Production capacity of manufacturer** (page number: 85)

Letter of bid technical

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Letter of bid technical** (page number: 86)

IESCO blacklisting policy

Information (Read-Only)

See Form Under Additional Forms and Documents: **IESCO blacklisting policy** (page number: 88)

Correction of defect in warranty period

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Correction of defect in warranty period** (page number: 117)

type test requirements

Technical Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **type test requirements** (page number: 118)

price schedule EXW

Financial Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **price schedule EXW** (page number: 119)

Price schedule DDP

Financial Submission (Vendor)

Document Required

See Form Under Additional Forms and Documents: **Price schedule DDP** (page number: 120)

specification

Technical Submission (Vendor)


Document Required

See Form Under Additional Forms and Documents: **specification** (page number: 121)

payment terms

Information (Read-Only)

See Form Under Additional Forms and Documents: **payment terms** (page number: 164)





Procurement Forms

Past Experience and Completed Contracts

Bidder or its manufacturer or Joint Venture (JV) must have successfully completed at least two (02) contracts of similar complexity involving same or higher-rated material/equipment during the last Ten (10) years. The aggregate value of both contracts shall be equal to or greater than Rs. 50M but none of the contract value should be less than 30% of aggregate value. (Rs. 15M)

To substantiate compliance with this requirement, the Bidder/JV shall submit copies of relevant Purchase Orders / Contract Agreements along with Completion Certificates/GRN/Delivery Challan etc issued by the concerned client.

The manufacturer shall demonstrate at least five (05) years' experience in designing and manufacturing of similar nature/complex involving same or higher rated equipment/material. Two (02) years satisfactory operation performance of same or high rated equipment /material. For the ease of evaluation, related form are enclosed in annexure and the same will be considered during evaluation.

See Form Under Additional Forms and Documents: **Past Experience and Completed Contracts** (page number: 167)

Historical Contract Non-Performance, and Pending Litigation and Litigation History

History of Non-performing Contracts

Non-performance of a contract did not occur as a result of contractor default since 1st January 2025.

a Non-performance, as decided by the Purchaser, shall include all contracts where (a) nonperformance was not challenged by the contractor, including through referral to the dispute resolution mechanism under the respective contract, and (b) contracts that were so challenged but fully settled against the contractor. Nonperformance shall not include contracts where Purchaser's decision was overruled by the dispute resolution mechanism. Nonperformance must be based on all information on fully settled disputes or litigation, i.e. dispute or litigation that has been resolved in accordance with the dispute resolution mechanism under the respective contract and where all appeal instances available to the Bidder have been exhausted.

b This requirement also applies to contracts executed by the Bidder as Joint Venture partner.

pending litigation

All pending litigation, arbitration, Grievance Redressal committee (GRC) and Appellate GRC or other material events impacting the net worth and/or liquidity of the bidder, if any, shall be treated as resolved against the Bidder and so shall in total not represent more than 25% (twenty five percent) of the Bidder's last year net worth calculated as the difference between total assets and total liabilities.

See Form Under Additional Forms and Documents: **Historical Contract Non-Performance, and Pending Litigation and Litigation History** (page number: 168)

Current Contracts and Their Progress

Financial Resources shall be determined as per following :

Financial Resources = working capital + credit line from sheduled bank - current commitment as per attached proforma

See Form Under Additional Forms and Documents: **Current Contracts and Their Progress** (page number: 170)

Financial Capacity and Net Worth Evaluation Form

Financial Capability of Bidder

a. Submission of audited financial statements for the last three years to demonstrate the current soundness of the Bidder's financial position. Bidder's Net Worth for the last year calculated as difference between total assets and total liabilities should be positive. However, bidder's networth shall be equal to or greater than 40% of Rs. 50 M (20M)

incase of

1 Single entity = 100% comply

2 incase of JV lead partner 100% and member 100%

b. Specify proposed sources of financing, working capital, lines of credit, and other financial means, available to meet the cash flow demands shall be equal to or greater than Rs.50 M.

incase of

1 single entity = 100% comply

2 incase of JV lead partner 60% and member 40%

See Form Under Additional Forms and Documents: **Financial Capacity and Net Worth Evaluation Form** (page number: 171)

Average Annual Turnover

Minimum average annual turnover of PKR calculated as total revenue of the Bidder over the last three Years shall be equal to or greater than Rs. 76 M.

incase of

1 single entity = 100% comply

2 incase of JV lead partner 60% and member 40%

See Form Under Additional Forms and Documents: **Average Annual Turnover** (page number: 173)





Additional Forms and Documents

Manufacturing Experience

Criteria		Compliance Requirements			Documents
Requirement	Single Entity	Joint Venture			Submission Requirements
		All Partners Combined	Each Partner	One Partner	
- The manufacturer shall demonstrate at least five (05) years' experience in designing and manufacturing of similar nature/complex involving same or higher rated equipment/material. - Two (02) years satisfactory operation performance of same or high rated equipment /material.	Must meet requirement	Not applicable	Not applicable	Manufacturer must meet	Manufacturer Will provide the Detailed supply Record of similar or higher rated equipment. Satisfactory performance Of similar equipment for Two years.

Criteria	Compliance Requirements			Documents	
Requirement	Single Entity	Joint Venture			Submission Requirements
		All Partners Combined	Each Partner	One Partner	
In order to ensure the smooth and timely execution of order, the manufacturer will indicate its manufacturing / production capacity which shall be double the total sum of orders already in hand, expected orders in pipe line and this order (if placed on the bidder). The manufacturer shall provide the information with the bid to establish its capacity / capability to execute the order for which necessary documentary evidence may be attached related for the above mentioned requirements. In this context the manufacturer is required to fill in the relevant forms given in Forms of this tender document and submit the same with the bid. The purchaser may visit the site of supplier at any time during evaluation at the cost of supplier.	Must meet requirement	Not applicable	Not applicable	Manufacturer must meet	Forms

**A Bidder or Manufacturer shall provide evidence of production output.*

Bidder Information Form

Date of Bid Submission: _____

Request for Bid No.: NCB _____

Page _____ of _____ pages

1. Bidder's Name: _____
2. In case of JV, legal name of each member: _____
3. Bidder's actual or intended country of registration: _____
4. Bidder's year of registration: _____
5. Bidder's Address in country of registration: _____
6. Bidder's Authorized Representative Information Name: _____ CNIC No. _____ Address: _____ Telephone/Fax numbers: _____ Email Address: _____
7. Attached are copies of original documents of [please check the box(es) of the attached original documents] ☐ Articles of Incorporation (or equivalent documents of constitution or association), and/or documents of registration of the legal entity named above. ☐ In case of JV, letter of intent to form JV or JV agreement, in accordance with ITB 3.4. ☐ Establishing that the Bidder is not under the supervision of the Procuring Agency
8. Included are the organizational chart, a list of Board of Directors, and the beneficial ownership.

Bidder's JV Members Information Form

Date of Bid Submission: _____

Request for Bid No.: NCB _____

Page____of _____pages

1. Bidder's Name: _____
2. Bidder's JV Member's name: _____
3. Bidder's JV Member's country of registration: _____
4. Bidder's JV Member's year of registration: _____
5. Bidder's JV Member's legal address in country of registration: _____ _____
6. Bidder's JV Member's authorized representative information Name: _____ Address: _____ Telephone/Fax numbers: _____ Email Address: _____
7. Attached are copies of original documents of [please check the box(es) of the attached original documents] ☐ Articles of Incorporation (or equivalent documents of constitution or association), and/or registration documents of the legal entity named above, in accordance with ITB 4.4.
8. Included are the organizational chart, a list of Board of Directors, and the beneficial ownership.

Deviation from Contractual/Commercial Provision

It is presumed that bidder shall not take any deviation. However, if he intends to take deviation to specified contractual/commercial conditions, those must be listed in the space provided below.

Sr #	Section No	Clause No	Deviation	Clarifications

Sign & Stamped by bidders

Deviation from Technical Provision

It is presumed that bidder shall not take any deviation. However, if he intends to take deviation to specified terms, those must be listed in the space provided below:

Sr #	Section No.	Clause No	Deviation	Clarifications

Sign & Stamped by bidders

Form of Qualification Information

1. Individual Bidders or Individual Members of Joint Ventures

1.1 Constitution or legal status of Bidder:

(Attach copy)

Place of registration: _____

Principal place of business: _____

Power of attorney of signatory of Bid: _____

1.2 Total annual volume of Services performed in _____ years, in the internationally traded currency specified in the Bid Data Sheet: _____

1.3 Services performed as prime Supplier on the provision of Services of a similar nature and volume over the last _____ years. The values should be indicated in the same currency used for Item 1.2 above. Also list details of work under way or committed, including expected completion date.

Project name and country	Name of Procuring Agency (PA) and contact person	Type of Services provided and year of completion

1.4 Major items of Supplier's Equipment proposed for carrying out the Services. List all information requested below. Refer also to ITB 13.3(c).

Item of equipment	Description, make, and age (years)	Condition (new, good, poor) and number available	Owned, leased (from whom?), or to be purchased (from whom?)
(a)			
(b)			

1.5 Qualifications and experience of key personnel proposed for administration and execution of the Contract. Attach biographical data. Refer also to ITB 13.4(d).

Position	Name	Years of experience (general)	Years of experience in proposed position
(a)			
(b)			

1.6 Proposed sub-contracts and firms involved. Refer to GCC 24.

Sections of the Services	Value of Sub-contract	Sub-contractor (Name and address)	Experience in providing similar Services
(a)			
(b)			

1.7 Financial reports for the last (*insert period*) years: balance sheets, profit and loss statements, auditors' reports, etc. List below and attach copies.

1.8 Evidence of access to financial resources to meet the qualification requirements: cash in hand, lines of credit, etc. List below and attach copies of support documents mentioning that We certify/confirm that we comply with eligibility requirements as per ITB 3 of the bidding documents.

1.9 Name, address, and telephone, telex, and facsimile numbers of banks that may provide references if contacted by the Procuring Agency.

1.10 Information regarding any litigation, current or within the last (*insert period*) years, in which the Bidder is or has been involved.

Other party(ies)	Cause of dispute	Details of litigation award	Amount involved
(a)			
(b)			

1.11 Information regarding Occupation Health and Safety Policy and Safety

Records of the Bidder.

1.12 Statement of compliance with the requirements of ITB 3.4.

1.13 Proposed Program (service work method and schedule). Descriptions, drawings, and charts, as necessary, to comply with the requirements of the bidding documents.

2. Joint Ventures

2.1 The information listed in 1.11 - 1.12 above shall be provided for each member of the joint venture.

2.2 The information in 1.13 above shall be provided for the joint venture.

2.3 Attach the power of attorney of the signatory (ies) of the Bid authorizing signature of the Bid on behalf of the joint venture.

2.4 Attach the Contract among all members of the joint venture (and which is legally binding on all members), which shows that

- (a) all members shall be jointly and severally liable for the execution of the Contract in accordance with the Contract terms;
- (b) one of the members will be nominated as being in-charge, authorized to incur liabilities, and receive instructions for and on behalf of any and all members of the joint venture; and
- (c) the execution of the entire Contract, including payment, shall be done exclusively with the member in charge.

3. Additional Requirements

3.1 Bidders should provide any additional information required in the Bid Data Sheet and to fulfill the requirements of ITB 12.1, if applicable.

We, the undersigned declare that

- (a) The information contained in and attached to this form is true and accurate as of the date of bid submission

Or [delete] statement which does not apply]

- (b) The originally submitted pre-qualification information remains essentially correct as of date of submission

Authorized Signature: _____

Name and Title of Signatory: _____

Name of Bidder: _____

Address: _____

Manufacturer's Authorization

No. _____

Dated _____

Date of Bid Submission:

____/____/2025

Request for Bid No.:

NCB _____

To:

WHEREAS

We _____, who are official
manufacturers of _____,
having factories at _____, do
hereby authorize M/s _____ to
submit a Bid the purpose of which is to provide the following Goods, manufactured
by us _____
and to subsequently negotiate and sign the Contract.

We hereby extend our full guarantee and warranty in accordance clause-18 of General
Conditions of Contract, with respect to the Goods offered by the above firm.

Signed: _____

Name: _____

Title: _____

Date signed _____ day of _____ Month, _____ Year

Manufacturer's Information Form

Date of Bid Submission: _____

Request for Bid No.: NCB _____

Page ____ of ____ pages

1. Manufacturer's Name: _____
3. Manufacturer Country of Registration: _____
4. Manufacturer year of Registration: _____
5. Manufacturer's legal address of Head Office and Production sites in Country of Registration: _____
6. Manufacturer's Authorized Representative Information Name: _____ Address: _____ Telephone/Mob/Fax numbers: _____ Email Address: _____
1 Attached are copies of original documents of [please check the box(es) of the attached original documents] from concern chamber of commerce manufacturing country or Pakistani Embassy in manufacturing country ☐ Articles of Incorporation (or equivalent documents of Constitution or Association), and/or registration documents of the legal entity named above, in accordance with ITB 4.4. 2. Included are the organizational chart, a list of Board of Directors, and the Beneficial Ownership.

Production Capacity of Manufacturer

Sr #		Factory Capacity in unit as mentioned in Price schedule
A	Total Factory Production Capacity (No. or Sets or other unit)/Year	
B	Order in Hand (No. or Sets or other unit)	
C	Expected order during execution of this contract if awarded (No. or Sets or other unit)	
D	Quantity of this order	
E	Remaining Capacity of Factory (No. or Sets or other unit) E= (A-B-C-D)	
$A \geq 2xE$		

Signed & Stamped by Manufacture

Letter of Bid – Technical Proposal

No. _____

Dated _____

Date of Bid submission: _____

Request for Bid No.: (NCB) _____

Description of Bid: _____

To:

We, the undersigned Bidder, hereby submit our Bid, in two parts, namely:

- (a) the Technical Proposal, and
- (b) the Financial Proposal.

In submitting our Bid we make the following declarations:

- (a) **No reservations:** We have examined and have no reservations to the bidding document, including addenda as well as blacklisting mechanism issued in accordance with Instructions to Bidders (ITB 9);
- (b) **Eligibility:** We meet the eligibility requirements and have no conflict of interest in accordance with ITB 3;
- (c) **Bid/Proposal-Securing Declaration:** We have not been suspended nor declared ineligible by the Procuring Agency based on execution of a Bid Securing Declaration or Proposal Securing Declaration in the Procuring Agency's country in accordance with ITB 4;
- (d) **Conformity:** We offer to supply in conformity with the bidding document and in accordance with the Delivery Schedules specified in the Schedule of Requirements the following Goods: *[insert a brief description of the Goods and Related Services]*-----

-----];
- (e) **Bid Validity Period:** Our Bid shall be valid for the period ----- specified in BDS 17.1 (as amended, if applicable) from the date fixed for the Bid submission deadline specified in BDS 23.1 (as amended, if applicable), and it shall remain binding upon us, and may be accepted at any time before the expiration of that period;
- (f) **Performance Security:** If our Bid is accepted, we commit to obtain a performance security in accordance with the bidding document;
- (g) **One Bid per Bidder:** We are not submitting any other Bid(s) as an individual Bidder, and we are not participating in any other bid(s) as a Joint Venture member or as a subcontractor, and meet the requirements, other than Alternative Bids submitted in accordance with ITB 19;
- (h) **Suspension and Debarment:** We, along with any of our

subcontractors, suppliers, consultants, manufacturers, or service providers for any part of the contract, are not subject to, and not controlled by any entity or individual that is subject to, a temporary suspension or a debarment imposed by the Procuring Agency. Further, we are not ineligible under Pakistan laws;

- (j) **State-owned enterprise or institution:** (check appropriate box)
i. We are not a state-owned enterprise or institution ☐
ii. We are a state-owned enterprise or institution but meet the requirements of this tender. ☐
- (k) **Binding Contract:** We understand that this Bid, together with your written acceptance thereof included in your Letter of Acceptance, shall constitute a binding contract between us, until a formal contract is prepared and executed;
- (l) **Not Bound to Accept:** We understand that you are not bound to accept the Most Advantageous Bid or any other Bid that you may receive; and
- (m) **Fraud and Corruption:** We hereby certify that we have taken steps to ensure that no person acting for us, or on our behalf, engages in any type of Fraud and Corruption.
- (n) **Commissions, gratuities and fees:** We have paid, or will pay the following commissions, gratuities, or fees with respect to the bidding process or execution of the Contract:

Name of Recipient	Address	Reason	Amount

Complete Name of the Bidder: * _____

Name of the person duly authorized as per PoA to sign the Bid on behalf of the Bidder: ** _____

Title of the person signing the Bid: _____

Signature of the person named above: _____

Date signed _____ **day of** _____ **Month** _____ **Year** _____

*: In the case of the Bid submitted by a Joint Venture specify the name of the Joint Venture as Bidder.

**: Person signing the Bid shall have the power of attorney given by the Bidder. The power of attorney shall be attached with the Bid Schedules.


MECHANISM FOR BLACKLISTING OF CONTRACTORS / CONSULTANTS / MANUFACTURERS



**Approved by IESCO Board of Directors (BoD) in its
178th Meeting held on 23rd August 2019.**

ISLAMABAD ELECTRIC SUPPLY COMPANY (IESCO)

28th October, 2019



DISCLAIMER

If any clause of this policy afterwards develops contradiction with PPRA Rules, then PPRA Rules will supersede the relevant clause of IESCO Mechanism for Blacklisting of Contractors / Consultants / Manufacturers.

TABLE OF CONTENTS

PREFACE	1
DEFINITIONS	2
Chapter No.1	
1.1 Introduction	4
1.2 Extent of Application	4
1.3 Basic Principles of Blacklisting Mechanism	5
Chapter No.2	
Grounds for Blacklisting	
2.1 General Grounds	6
2.2 Grounds at Competitive Bidding Stage	6
2.3 Grounds at Contract Implementation Stage	8
2.4 Blacklisted Person / Entity etc.	10
Chapter No.3	
Formulation of “IESCO Standing Committee for Blacklisting”	
3.1 Defining Structure of Committee	11
3.2 Provision of Additional Member	11
3.3 Timeline for Finalization of Recommendations	11
Chapter No.4	
Procedure for Suspension and Blacklisting.	12
4.1 The Competitive Bidding Stage	12
4.1.1 Initiation of Action	12
4.1.2 Notification	12
4.1.3 Hearings	13
4.1.4 Decision	13
4.1.5 Notice of Decision	13
4.2 Contract Implementation Stage	14
4.2.1 Initiation of Action	14
4.2.2 Notification	14
4.2.3 Hearings	14
4.2.4 Decision	15
4.2.5 Notice of Decision	15
4.3 Blacklisted Person / Entity etc.	15
Chapter No.5	
Review against Decision of the Procuring Agency	16
5.1 Filing an appeal for Review against decision	16
5.2 Constituting Decision Review Committee	16
5.3 Timeline for deciding the Appeal	16
5.4 Finalization of the Decision	16
Chapter No.6	
Appeal	
6.1 Filing an Appeal with the Authority	17
Chapter No.7	
Period of Debarment	
7.1 Period of Debarment for Blacklisted Firms	18

	Chapter No.8	
	Appraisal to Procurement Committee/Board of Directors	
8.1	Appraisal of Blacklisted Firms to Procurement Committee / Board of Directors (BoD)	19
	Chapter No.9	
	Communication of Notification to Authority	
9.1	Methodology for Communication of Notification of the PPRA / NTDC / WAPDA /DISCOs Delisting	20
9.2	Effectiveness	21
9.3	Amendments	21
9.4	Delisting	21
	Appendix-1 - Process to deal with Complaints	22
	Appendix-2 - Guidelines for Evaluation of Performances of Contractors	24
	Form for Hearing	25



PREFACE

This mechanism of blacklisting has been drafted in the light of Rule-19 “Blacklisting of suppliers and contractors” of the Public Procurement Rules, 2004 “PPRA Rules”. This Mechanism has been developed to mitigate the possibilities of corrupt practices and ensure the transparent and corruption free public procurement in the organization. The blacklisting policies of various procurement agencies have also been consulted. The policy was placed on IESCO website for more than 03 months & all the stake holders were invited to furnish their comments so that no one may have any objection after its implementation. This mechanism consists of 09 chapters containing Grounds for Blacklisting, Procedure for Suspension and Blacklisting, Formulation of “IESCO Standing Committee for Blacklisting”, Review against Decision of the Procuring Agency, Period of Debarment, Process to deal with Complaints & Guidelines for Evaluation of Performances of Contractors. The procedure has been developed for both of the procurement stages including competitive bidding stage and contract implementation stage. A disclaimer Clause has also been added so that Authority’s instructions could prevail. This document shall be considered an integral part of IESCO Bidding Documents / Tender Documents/ RFPs as well as contract agreements / purchase orders etc. The bidders shall have to submit an undertaking along with their bid that they have read all the contents of this blacklisting mechanism and they accept all the provisions of this document.

DEFINITIONS

In addition to definitions mentioned in bidding document, following definitions are also applicable:

- (i) **Authority:** The Public Procurement Regulatory Authority.
- (ii) **Appeal:** Right of firm/individual to bring its / his grievance against the issuance of Blacklisting Order at the appropriate legal forum.
- (iii) **Appellate Authority:** The department, office or government unit exercising general and/or administrative supervision/control over the blacklisting agency. Department level agencies shall exercise appellate authority over offices, agencies, under their jurisdiction. *Provided, further,* that blacklisting decisions of government agencies that are not subject to general and/or administrative supervision/control of any department, office or government unit shall be final and executor.
- (iv) **Award:** A written notice from the procuring entity accepting a bid or proposal.
- (v) **Blacklisting:** An administrative penalty disqualifying a person or an entity from participating in any government procurement for a given period.
- (vi) **Blacklisting Mechanism:** A mechanism adopted by IESCO as a procuring agency/entity for Blacklisting supplier(s), manufacturer(s), distributor(s), contractor(s) or Experts/consultants/consulting firm(s) etc.
- (vii) **Blacklisted Person/Entity.** A person/entity that was disqualified by an agency and/or is included in the PPRA/ADB/World Bank/Donor Agencies' (working with Government of Pakistan) Consolidated Blacklisting Report/sanctioning list.
- (viii) **Contractor** includes-suppliers, contractors and consultants
- (ix) **Consolidated Blacklisting Report:** The report prepared by the NTDC/WAPDA/DISCOs/PPRA/ADB/World Bank/Donor Agency working with Government of Pakistan containing the list of supplier(s), manufacturer(s), distributor(s), contractor(s) or Experts/ consultants/ consulting firm(s) blacklisted by procuring entities/agencies.
- (x) **Debarment:** state of being legally excluded from participating in all types of procurement proceedings of the procuring department for a given period.
- (xi) **Delist.** Removal of a person/entity from the Consolidated Blacklisting Report.
- (xii) **Procuring Agency:** Any department, attached department or any office of the Islamabad Electric Supply Company;

- (xiii) **Suspension.** Administrative action taken for infractions committed by a contractor during the competitive bidding stage, whereby such contractor is prohibited from further participation in the bidding process of an agency.
- (xiv) **Termination of Contract-** Extinction of contract by reason or resolution or rescission under applicable rules/regulations/laws arising from the default of the firms/individuals.



Chapter No.1

1.1 Introduction

Blacklisting is one of the effective tools used in the struggle against the corruption in connection with public procurement. The main objectives of any procurement process are transparency, economy, fairness and efficiency so that public money is spent on welfare of the public. Hence, blacklisting is an instrument, which may lead to the decrease of the potential corruption risks and also inculcate protection of public means and increase of effectiveness of allocation of the limited resources.

Rule-19 “Blacklisting of suppliers and contractors” of the Public Procurement Rules, 2004 (hereinafter “**PPRA Rules**”) stipulates that;

*“The procuring agencies shall specify a mechanism and manner to permanently or temporarily bar, from participating in their respective procurement proceedings, suppliers and contractors who either consistently fail to provide satisfactory performances or are found to be indulging in corrupt or fraudulent practices. Such barring action shall be duly publicized and communicated to the Authority:
Provided that any supplier or contractor who is to be blacklisted shall be accorded adequate opportunity of being heard.”*

In the light of the above said Clause, Blacklisting Mechanism (hereinafter **the Mechanism**) has been specified for all procurements made by IESCO. This policy shall govern the blacklisting of manufacturers, suppliers, distributors, contractors, consultants and consulting firms (“contractors” for brevity) involved in government procurement for offenses or violations committed during competitive bidding and contract implementation

Any capitalized terms and abbreviations used in this mechanism which are not defined herein shall have the meanings given to them in Public Procurement Regulatory Authority Ordinance, 2002 (hereinafter “**PPRA Ordinance**”) and PPRA Rules amended upto date.

1.2 Extent of Application

- i. The Mechanism shall be applicable and remain in force, along with any amendments thereto, within IESCO until any clear instructions or guidelines are imparted by the Government through PPRA, PEC, or any other competent forum.
- ii. The Mechanism shall also be applicable on the pre-qualified firms.
- iii. The Mechanism shall be applicable for suppliers / bidders / contractors / local agents / representatives / consultants / firms / individuals / distributors / Manufacturers / organization transacting business with IESCO.

- iv. Wherever any provision of this mechanism shall be in conflict with provisions of any applicable guidelines of donor agencies, or any other applicable Statute / Law or Rule enforced at the time in Pakistan, the provisions of the Statute / Law or rule shall prevail.
- v. After Approval of this mechanism by the competent Authority, it shall be considered an integral part of bidding document/tender document/RFP as well contract agreement/Purchase Order, unless otherwise specified PPRA rule-5. The bidder will submit an Undertaking along-with their bid that they have read and accept the provisions of this Mechanism. Non-submission of an Undertaking may result in rejection of their bid. The said Undertaking will subsequently become part of the Contract Agreement as well.

1.3 Basic Principles of Blacklisting Mechanism

Following are the important basic principles of Blacklisting Mechanism::

- i. To lay down effective mechanism for disciplining deviant Contractors against whom, misconduct has been established;
- ii. An opportunity will be provided to any contractor alleged to have committed an act of misconduct, to defend himself;
- iii. The formal hearing be conducted by a Committee/Committees.
- iv. The presenter has the sole responsibility for deciding the terms of suspension.
- v. Blacklisting is a temporary action and not permanent measure.
- vi. The period of blacklisting / suspension would invariably depend upon the seriousness / nature of offence committed by the erring contractor.
- vii. Blacklisting Mechanism is applicable for all type of national or international contractors, manufacturers, consultants, pre-qualified contractors /manufacturers, local agents, distributors and suppliers.

CHAPTER NO. 2

GROUND S FOR BLACKLISTING

2.1 General Grounds

The following shall comprise the broad multilateral grounds for blacklisting:

- i. **Corrupt Practice**" the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence the action of a public official in the procurement process or in contract execution;
- ii. **Fraudulent Practice**" a misrepresentation or omission of facts in order to influence a procurement process or the execution of a contract
- iii. **Collusive Practice**" a scheme of arrangement between two or more bidders, with or without the knowledge of the Purchaser, designed to establish bid price at artificial, non-competitive levels, and
- iv. **Coercive Practice**" harming or threatening to directly or indirectly, persons or their property to influence their participation in the procurement process or affect the execution of a contract.

In addition to above, blacklisting of firms/individuals may be resorted to when the charges are of serious nature, which include but are not limited to the following:

2.2 Grounds at Competitive Bidding Stage

The procuring Agency shall impose on bidder(s)/JV/Entities/Consulting firm(s) or prospective bidders the penalty of suspension or blacklist them for a specific period for the offense from participating in the public bidding process, without prejudice to the imposition of additional administrative sanctions as the internal rules of the agency may provide and/or further criminal prosecution, as provided by applicable laws, for the following violations:

- i. Indulging in Corrupt, Fraudulent as well as Collusive & Coercive Practices.
- ii. Submission of eligibility requirements containing false information or falsified or spurious documents
- iii. Submission of false/forged/unauthentic Bid Security/Pay Order/CDR or infringement of documents to get undue monetary or any other benefit.
- iv. Submission of Bids that contain false information or falsified documents, or the concealment of such information in the Bids or making frivolous complaints and allegations in order to influence the outcome of eligibility screening or any other stage of the public bidding.

- v. Unauthorized use of one's name, or using the name of another for purpose of public bidding.
- vi. Withdrawal of a bid after submission, or refusal to accept an award, or enter into contract with the government without justifiable cause, after he had been adjudged as having submitted the Lowest Calculated Responsive Bid or Highest Rated/ranked Responsive Bid.
- vii. Refusal or failure to submit the required performance security within the prescribed time limit.
- viii. Any documented unsolicited attempt by a bidder to unduly influence the outcome of the bidding in his favor.
- ix. All other acts that tend to defeat the purpose of the competitive bidding, such as but not limited to: an eligible contractor not buying bid documents from procuring agency or not complying with the requirements during bid evaluation, and contractors habitually withdraw from bidding for at least three (3) times within a year.
- x. Bidder(s) (prior to or after bid submission) designed to establish bid prices at artificial, non-competitive levels and to deprive the procuring agencies of the benefit(s) of free and open competition and any request for, or solicitation of anything of value by any public official in the course of the exercise of his duty;
- xi. Involved in litigation or needless petitioning to influence or obstruct the procurement process either on his own behalf or at the behest of any other vested interest.
- xii. Breach of confidentiality of evaluation process as mentioned in Appendix-I based on illegal access or in any way to get undue benefit or to provide benefit or to frustrate the bidding/evaluation process. This will also include attempts to sabotage the bidding process directly or indirectly.
- xiii. Any effort by the bidder to influence the procuring agency in the examination, evaluation, ranking of Proposals, and recommendation for award of Agreement.

In addition to the penalty of suspension, the bid security posted by the concerned bidder or prospective bidder shall also be forfeited.

2.3 Grounds at Contract Implementation Stage

Without prejudice to the imposition of additional administrative sanctions as the internal rules of the procuring agency may provide and/or further criminal prosecution as provided by applicable laws, the procuring agency shall take against the contractors after the termination of the contract, the action of suspension for specific period from participating in the public bidding process, for violations committed during the contract implementation stage, which include but not limited to the following:

- a. Indulging in Corrupt, Fraudulent as well as Collusive & Coercive Practices.
- b. Extraordinary delay in signing or refusal to accept the Notification of Award (NOA) and/or the contract without any cogent reason.
- c. Failure of the contractor, due solely to his fault or negligence, to mobilize and start work or performance within the specified period in the Notice of Award (NOA).
- d. Submission of fake / frivolous or mutilated Performance Guarantee or Advance Payment guarantee etc.
- e. Failure by the contractor to fully and faithfully comply with its contractual obligations without valid cause, or failure by the contractor to comply with any written lawful instruction of the procuring entity or its representative(s) pursuant to the implementation of the contract. For the procurement of infrastructure projects or consultancy contracts, lawful instructions include but are not limited to the following:
 - i. Employment of competent technical personnel, competent engineers and/or work supervisors; and Deployment of committed equipment, facilities, support staff and manpower; and
 - ii. Provision of warning signs and barricades in accordance with approved plans and specifications and contract provisions;
 - iii. Stockpiling in proper places of all materials and removal from the project site of waste and excess materials, including broken pavement and excavated debris in accordance with approved plans and specifications and contract provisions;
 - iv. Renewal of the effective dates of the performance security after its expiration during the course of contract implementation.
- f. Assignment and subcontracting of the contract or any part thereof or substitution of key personnel named in the proposal without prior written approval by the procuring entity.
- g. For the procurement of goods, unsatisfactory progress in the delivery of the goods by the manufacturer, supplier or distributor arising from his

fault or negligence and/or unsatisfactory or inferior quality of goods, as may be provided in the contract or as under:

- i. Deviations from specifications and terms & conditions of the purchase order/contract.
- ii. Provision of fake prototype/type test reports
- iii. Provision of fake inspection call FAT/Type test
- iv. Failure to rectify the fault/damage/problem during period of warrantee
- v. Supply of goods through inappropriate way such as smuggling of goods
- vi. Supply of stolen goods/re-sold goods.
- vii. Provision of fake /forged custom /taxes /duties documents
- h. For the procurement of consulting services, poor performance by the consultant of his services arising from his fault or negligence. Any of the following acts by the consultant shall be construed as poor performance and is liable to be Blacklisted:
 - i. Defective design resulting in substantial corrective works in design and/or construction;
 - ii. Failure to deliver critical outputs due to consultant's fault or negligence; and
 - iii. Specifying materials which are inappropriate, substandard, or way above acceptable standards.
 - iv. Allowing defective workmanship or works by the contractor being supervised by the consultant.
 - v. Submitting CV's of key personnel in the prequalifying process or bid documents of professionals that are not in actual employment of the bidder or without consent of experts.
 - vi. Acting together (Contractor & Consultant) in secret toward a fraudulent or illegal end
- i. For the procurement of infrastructure projects, poor performance by the contractor or unsatisfactory quality and/or progress of work arising from his fault or negligence. Any of the following acts by the constructor shall be construed as poor performance:

- i. Negative slippage of 15% and above within the critical path of the project due entirely to the fault or negligence of the contractor; and
- ii. Quality of materials and workmanship not complying with the approved specifications/Drawing(s) arising from the contractor's fault or negligence.
- iii. Unnecessary delay in completion of project
- iv. Failure to rectify fault/problem/damages during defect liability.
- j. Willful or deliberate abandonment or non-performance of the project or contract by the contractor resulting to substantial breach thereof without lawful and/or just cause.
- k. In addition to above, other grounds for blacklisting of firms/individuals include but are not limited to the following:
 - i. Obtaining fraudulent payments;
 - ii. Obtaining contracts by misleading the purchaser;
 - iii. Refusal to pay IESCO dues etc.;
 - iv. Failure to fulfill contractual obligations Changes in the status of firm's ownership/partnership etc., causing dissolution of the firm which existed at the time of inspection prior to original registration of the firm
 - v. Registration of a firm with a new name by the Proprietor or family or a nominee thereof of a firm that has been already blacklisted;
 - vi. Contractors who have negotiated Plea Bargain under the National Accountability Ordinance 1999, or contractors involved with any other criminal proceedings conducted by any investigation agency where default has been proved specifically in relation to supplies made to or contracts concluded with IESCO or department thereof;.
 - vii. Non-compliance of the existing policy/rules/law of GoP during execution of contract.
 - viii. Hiring of underage personnel for assignments or works violating Child Labor (Prohibition and Regulation) Amendment Bill, 2016.
 - ix. Non-Adherence to safety codes.

For the Blacklisting of a Firm, in addition to the penalty of suspension for a certain period, the performance security posted by the contractor shall also be forfeited.

CHAPTER NO. 3

FORMULATION OF “IESCO STANDING COMMITTEE FOR BLACKLISTING”

3.1 Defining Structure of Committee

A permanent Committee namely “IESCO’s Standing Committee for Blacklisting” comprising of the following members shall examine the justification of the reasons given by the Project Authority prior to blacklisting / debarment of any firm/supplier/contractor/ individual.

i. General Manager Technical	Convener
ii. Director General/ Manager (Legal) IESCO	Member
iii. Representative of Finance Director (Not Less than the Rank of Manager)	Member
iv. Deputy Manager (Village Electrification Cell)	Member
v. Deputy Manager Procurement PMU	Member

The quorum for committee meeting will be 3 members including the Convener, the presence of Convener is mandatory. Committee shall evaluate the case and develop consensus however, in case of conflict among the member of committee, decision of convener shall be considered final.

3.2 Provision of Additional Member

Depending upon the nature of the case, the Committee may consult or appoint / nominate additional members from within IESCO with the approval of Chief Executive Officer (CEO) IESCO, provided that the Committee consists of an odd number of individuals as per spirit of Rule 48(1) of the PPRA Rules. Independence of any additional members shall be ensured while making the selection of such additional members. Furthermore, the aforementioned Standing Committee shall also be authorized to seek external expert advice or call any employee of IESCO as and when required.

3.3 Timeline for Finalization of Recommendations

The committee shall finalize its recommendations within the time specified in this mechanism.

CHAPTER NO. 4

PROCEDURE FOR SUSPENSION AND BLACKLISTING.

4.1 The Competitive Bidding Stage

4.1.1 Initiation of Action

Upon receipt of or obtaining information and / or knowledge that any person(s) is involved in practices mentioned in Article 2.1 and 2.2 of the Mechanism, the concerned project Authority / formation may initiate the suspension and blacklisting proceedings by filing its recommendations with the procuring agency or procuring agency also motu proprio (by itself) commence the proceedings upon prima facie (self-sufficient) determination that the bidder/ prospective bidder/ JV/ Person/Entity has committed any of the grounds for blacklisting during the competitive bidding stage as mentioned in article-2.1 & article-2.2 of the policy.

The Project Director or Project implementation Agency shall provide substantial evidence for the person/entity/JV/Firm against whom the case for blacklisting has been initiated.

4.1.2 Notification

Upon verification of the existence of grounds for blacklisting, the procuring agency shall immediately notify the contractor concerned in writing, advising him that:

- a. Complaint for suspension and blacklisting has been filed against him, or he has been considered by the procuring agency for suspension and blacklisting, stating the grounds for such;
- b. He has the opportunity to explain his position regarding why he should not be suspended and blacklisted;
- c. Hearing shall be conducted before the procuring agency or “IESCO’s Standing Committee for Blacklisting”, upon his request, where he may present documentary evidence, verbal testimony and cross-examine the witnesses presented against him; and
- d. The consequences of being suspended and blacklisted.

Within seven (7) calendar days from receipt of notification, the bidder shall submit its written answer with documentary evidence to the procuring agency or “IESCO’s Standing Committee for Blacklisting” with a manifestation for request of hearing to determine questions of fact, if he so desires. No time extension shall be allowed. if contractor fail to answer within the stipulated period, the procuring agency shall issue a resolution recommending its blacklisting with the immediate suspension of the contractor from participating in any bidding process of the agency for a certain period and the forfeiture of his bid security.

4.1.3 Hearings

If a hearing is requested by the contractor, the procuring agency shall immediately set the date and time for hearing. The hearing shall be non-litigious and shall be terminated within five (5) days. The procuring agency shall constitute an independent "Hearing Committee" comprising of odd Number members. The procuring agency may also invite a representative from PPRA or a duly recognized private group in a sector or discipline relevant to the procurement at hand as an observer for each hearing.

If no request is made, the procuring agency shall make a determination of the case based on the complaint, answer, documentary evidence submitted and facts verified. If the procuring agency is convinced that the contractor/bidder is at fault, it shall issue a resolution recommending for its blacklisting with suspension of the bidder from participating in any bidding process of the agency and the forfeiture of his bid security.

4.1.4 Decision

The Head of the Procuring Entity shall, within fifteen (15) days from receipt of the resolution and the records of proceedings, determine whether reasonable cause exists for the suspension of the contractor and the forfeiture of the latter's bid security. If the Head of the Procuring Entity determines that such reasonable cause exists, he shall issue a decision regarding its blacklisting and suspending the contractor from participating in any bidding process of the agency, and further declaring that his bid security is forfeited. Otherwise, he shall dismiss the case.

The decision shall clearly and distinctly state the facts, evidence and the law on which it is based, as well as the date of effectiveness of the penalty, if any.

In case a contractor commits more than one offense or a combination of offenses for the same project/contract in a particular agency, each violation shall be met the corresponding penalty.

4.1.5 Notice of Decision

The procuring agency shall furnish the suspended contractor a copy of the decision immediately from its promulgation.

4.2 Contract Implementation Stage

4.2.1 Initiation of Action

Procuring Agency shall commence the proceedings upon prima facie (self-sufficient) determination that the contractor has committed any of the grounds for blacklisting during the contract implementation stage as mentioned in bidding document/Contract agreement or any event as mentioned in article-2.1 & article-2.3 of the policy of written complaint from Engineer/ consultant/ supervisory office.

The Project Director or Project implementation Agency shall provide substantial evidence for the person/entity/JV/Firm/Contract against whom the case for blacklisting has been initiated.

4.2.2 Notification

Upon verification of the existence of grounds for blacklisting, the procuring agency shall immediately notify the contractor concerned in writing, advising him that:

Within seven (7) calendar days from receipt of notification, the contractor shall submit its written answer with documentary evidence to the procuring agency with a manifestation for request of hearing to determine questions of fact, if he so desires. No time extension shall be allowed.

If the contractor fail to answer within the stipulated period, the procuring agency shall issue a resolution recommending the blacklisting with immediate suspension of the contractor from participating in any bidding process of the agency and the forfeiture of his bid security.

4.2.3 Hearings

If a hearing is requested by the contractor, the procuring agency shall immediately set the date and time for hearing. The hearing shall be non-litigious and shall be terminated within five (5) days. The procuring agency shall constitute an independent "Hearing Committee" comprising of odd Number members. The procuring agency may also invite a representative from PPRA or a duly recognized private group in a sector or discipline relevant to the procurement at hand as an observer for each hearing.

If no request is made, the procuring agency shall make a determination of the case based on the complaint, answer, documentary evidence submitted and facts verified. If the procuring agency is convinced that the contractor is at fault, it shall issue a resolution recommending for blacklisting with suspension of the contractor from participating in any bidding process of the agency and the forfeiture of his performance security.

4.2.4 Decision

The procuring agency shall, within fifteen (15) days from receipt of the resolution and the records of proceedings, determine whether reasonable cause exists for the suspension of the contractor and the forfeiture of the latter's performance security. If the Head of the Procuring Entity determines that such reasonable cause exists, he shall issue a decision for blacklisting the contractor with suspending the contractor from participating in any bidding process of the agency, and further declaring that his performance security is forfeited. Otherwise, he shall dismiss the case.

The decision shall clearly and distinctly state the facts, evidence and the law on which it is based, as well as the date of effectivity of the penalty, if any.

In case a contractor commits more than one offense or a combination of offenses for the same project/contract in a particular agency, each violation shall be met the corresponding penalty

4.2.5 Notice of Decision

The procuring agency shall furnish the blacklisted contractor a copy of the decision immediately from its promulgation.

CHAPTER NO. 5

REVIEW AGAINST DECISION OF THE PROCURING AGENCY

5.1 Filing an Appeal for Review against decision

The Contractor shall have the right to lodge request to review the blacklisting decision, if the same is convinced that some concrete evidence proves the case otherwise in favor of the Contractor. For this purpose, the same will file an appeal within five (5) days from receipt of the notice of decision.

5.2 Constituting Decision Review Committee

The procuring agency shall constitute an independent “Decision Review Committee” comprising of three members and external observer(s) preferably PPRA representative.

5.3 Timeline for Deciding the Appeal

Committee shall resolve with finality the review application within ten (10) days from the filing thereof and furnish blacklisted/suspended contractor/bidder a copy of the resolution immediately from its promulgation.

5.4 Finalization of the Decision

The decision of the committee shall become final and executor after the lapse of fifteen days from the receipt of the notice of decision or decision of review application. If an appeal is filed, the affirmed, modified or reversed decision shall become final and executory upon receipt thereof by the department and person/entity concerned. Upon finality of the decision suspending the contractor, the procuring agency shall issue a Blacklisting Order disqualifying the erring contractor from participating in the bidding of all projects.

CHAPTER NO. 6

APPEAL

6.1 Filing an Appeal with the Authority

The Contracting Firm shall have the right to file an appeal with the Authority within ten days from the date of receipt of the decision for either or both of the following causes, provided that only a single application shall be filed with the Authority:

- a. The decision is not in conformity with the evidence and/or facts presented, hence does not construe grounds for Blacklisting laid down under Rule 19 of the PPRA Rules – 2004; and
- b. Newly discovered evidence or facts which could not be discovered and produced at the investigation and which when presented would probably alter the result of the investigation.

CHAPTER NO. 7

PERIOD OF DEBARMENT

7.1 Period of Debarment for Blacklisted Firms

The Blacklisting shall be for a reasonable specified period of time and as a general rule of prudence, the period may not exceed three years. The following time periods shall be considered for debarment on account of blacklisting;

Causes of Blacklisting	Time for Debarment
Corrupt & fraudulent & collusive practices, criminal breach of trust.	03 years
Submission of fake documents including financial instruments like securities & guarantees, submission of false Financial statement / Audit reports etc.	03 years and forfeiture of securities
Making false statement and allegation to gain undue advantage	03 years and forfeiture of securities
Commission of embezzlement, theft, cheating, forgery, bribery, falsification or destruction of records, receiving stolen property, false use of trademark, securing fraudulent registration, giving false evidence, furnishing false information.	03 years and forfeiture of securities
Breach of confidentiality of evaluation process as mentioned in Appendix 1 hereto	06 month to 02 years as mentioned in Appendix-1 and forfeiture of securities
Extraordinary delay in signing or refusal to accept a procurement contract without cogent reasons, when the bid has been accepted by IESCO	06 month to 02 years as determined by the committee and forfeiture of securities
Non-satisfactory performance as mentioned in Appendix-2	2 years and forfeiture of securities
The contractor was blacklisted by the government or the donor agency and subsequently adopted by IESCO	3 years or the time period for which the concerned agency debarred the contractor, whichever is higher

In case the person/ contractor / firm/ consortium appeared in Consolidated Blacklisting Report shall also be considered debarred in participation of bidding process.

Note: All the penalties given herein above will be in addition to the consequences already agreed upon by the parties in the contract or any other documents.

CHAPTER NO. 8

APPRAISAL TO PROCUREMENT COMMITTEE/BOARD OF DIRECTORS

8.1 Appraisal of Blacklisted Firms to Procurement Committee/ Board of Directors (BoD)

The Procuring Agency shall apprise the Procurement Committee/Board of Directors (BoD) before communicating its Blacklisting decision to the Authority, if a Firm/Company/Bidder/JV/Manufacturer/Subcontractor/Consultant etc. is declared blacklisted by the IESCO.



CHAPTER NO. 9

COMMUNICATION OF NOTIFICATION TO AUTHORITY

9.1 METHODOLOGY FOR COMMUNICATION OF NOTIFICATION TO THE PPRA/NTDC/WAPDA/DISCOS

9.1.1 Unless otherwise provided in these policies, the blacklisting agency concerned shall submit to the PPRA /NTDC/WAPDA /DISCOs, within seven (7) calendar days after the issuance of the blacklisting order/delisting orders made by the agency, the following documents:

- a. Blacklisting Order duly signed by the Head of procuring agency containing, among others, Department/Office Order or Board Resolution number, name and address of the blacklisted person/entity, license number, if applicable, project/contract and location/amount, specific ground(s)/offense(s) committed as provided in article-9, sanction imposed and its date of start and completion, date of issuance of the order to blacklist, and other conditions which can extend duration of sanctions in article-9.
- b. Delisting Order duly signed by the blacklisting agency containing, among others, Department/Office Order or Board Resolution number, name and address of the blacklisted person/entity, name of project/contract and location, specific sanction being lifted and the number of previously issued blacklisting Department/Office Orders or Board Resolutions, effectively date of delisting, and date of delisting approval.

9.1.2 The PPRA shall prepare the Consolidated Blacklisting Report every quarter, based on the submitted Blacklisting Orders and disseminate the same to procuring agencies. The report shall be further posted in the PPRA website and shall indicate the number of times a person/entity has been blacklisted, the type of offense/violation committed, the penalty imposed, and the blacklisting agency concerned. The PPRA shall delist from such report those whose sanctions are lifted automatically after serving the given penalty as provided for in article-9 hereof and those whose sanctions are lifted through the issuance of Delisting Orders.

9.1.3 In the case of procurement of infrastructure projects, a blacklisting agency should decide to refer the case of its blacklisted person/entity to Pakistan Engineering Council (PEC)/SECP for license suspension/revocation, it shall submit

to PEC/SECP a copy of the decision accompanied with supporting documents.

- 9.1.4** All existing blacklisting reports of the Government or any of its procuring agencies, as well as the list of constructors/Consultant/consulting firms whose licenses are suspended or revoked by the PEC as of the date of effectiveness, are hereby adopted and made part of the PPRA Consolidated Blacklisting Report upon the issuance of these orders.

9.2 EFFECTIVENESS

These guidelines / mechanism or any amendments thereof shall take effect immediately after its approval from Board of Directors of IESCO.

9.3 AMENDMENTS

In the implementation of this policy, the IESCO/PPRA may introduce modifications thereto through the amendment of its specific provisions as the need arises. Any amendment to this policy shall be applicable to government projects advertised for bid after the effectiveness of the said amendment.

9.4 DELISTING

A blacklisted person/entity shall automatically be delisted after the period for the penalty shall have elapsed, unless the blacklisting agency requests the PPRA/NTDC/DISCOs/WAPDA to maintain the blacklisted person/entity in the PPRA/PPRA/NTDC/DISCOs/WAPDA Consolidated Blacklisting Report due to justifiable reasons. In the latter case, the blacklisted person/entity shall be delisted only upon the blacklisting agency's issuance of a Delisting Order.

APPENDIX-1

PROCESS TO DEAL WITH COMPLAINTS

It has been frequently observed that after opening of tenders, the bidders start to influence the evaluation process. Such misleading attempts results in delay in finalizing of award of contract and cause financial loss to the National exchequer and stain its sanctity. The evaluation process is confidential till publication of award of contract process.


Provision of guidelines of international donor agencies and PPRA provides sufficient opportunity to bidders for redressal of their grievances. Hence, the attempts made by the bidders during evaluation process or thereafter to influence the contract award decisions fall under the definition of corrupt and fraudulent practices. Therefore, during bidding stage, the following mechanism shall be adopted in case of receipt of any complaint from the bidder.

- i. Anonymous complaints shall not be entertained.
- ii. The Procuring Agency reserves the right to call for an affidavit from the complainant verifying the truthfulness and correctness of the contents of the complaint.
- iii. The notice of displeasure and explanation will be immediately sent to those firms who lodge the complaint during the evaluation process.
- iv. If the firm itself or through its agent or any third party does not refrain from making complaints in the same tender, the official warning will be sent and their case will be sent to IESCO's Rights Protection Committee which may analyses the situation and suggest action including the rejection of the bid of the complainant, However, Project Authority with prior approval of CEO IESCO. May reject the bid even in first instance depending upon nature of the case or provision of the Bidding Documents.
- v. If the same bidder itself or through its agent or any third party lodges complaint in another tender floating in parallel before decision of Committee, its bid will straight forwardly be rejected by the project authority. It may also be debarred to participate in the next tender for six months under intimation to the Committee and CEO IESCO.
- vi. If the same bidder itself or through its agent or any third party lodges complaint third time in the same or any other tender within a period of one years, its bid will be rejected and bid security will be forfeited by the project authority. It may also be debarred to participate in the next tender for one year under intimation to the committee and CEO IESCO.
- vii. In order to monitor the record of the bidders, a data base will be maintained at IESCO's website and the offices of the project authorities regarding firms / supplier / contractors/consultant who consistently lodge complaints during the evaluation process by making clandestine access to confidential record and hamper the award of contract process.

- viii. In order to monitor the record of the persons, a data base will be maintained at IESCO's website and offices of the project authorities regarding such persons who consistently lodge frivolous complaints during the evaluation process by making clandestine access to confidential record and hamper the award of contract process.

NOTE:

It is clarified that the process provided above in Appendix-I is to discourage anonymous and frivolous complaints only and does not mean to prevent any person aggrieved by any act of the procuring agency from lodging a genuine complaint /grievance as provided under Rule-48 of the PPRA Rules-2004.



APPENDIX-2

GUIDELINES FOR EVALUATION OF PERFORMANCE OF CONTRACTORS

- i. After signing of the contract, the Project authority (or the Consultant / Engineer) must monitor and evaluate the Contractor's performance, that is, whether the Contractor is fulfilling his obligations based on the terms of the contract and plans that were developed and agreed upon with the Project authority at the time of signing of contract or during kick-off meetings. In case of breach of contract or consistent non-performance security or debarment / blacklisting.
- ii. Though the contractor's performance evaluation is an on-going process, which takes place throughout the duration of the contract and also during the Defect Liability / Warranty Period, hence a Contractors Performance Evaluation Report shall be drafted by the project authority once all of the contractual obligations of the latter have been completed so that the project authority have gained a more complete picture that will help it in formulating a more objective judgment.
- iii. The performance evaluation report may be prepared for all contracts of more than Rs. 50 million. When based on the Evaluation Report, the performance of the contractor is non-satisfactory in. EPC contract(s) (or the contractor receives 02 No Notices of Default within same contract or against consecutive contract (s) within a period of 2 years) and 03 No supply contracts awarded within a period of 02 years, the procuring agency may initiate the case of blacklisting of the contractors in accordance with the terms of this mechanism.
- iv. In case of any extra-ordinary delay in performance of a single contract of vital and critical importance, the procuring agency shall have the right to terminate the contract, recover the loss and debar the bidder/firm/JV/contractor/consultant from participation in future tenders. The procuring agency shall be the sole judge to determine the importance of the project.
- v. The above said assessment will be in addition to the provisions already agreed by the parties in the contract or any other documents.



No.

/IESCO/ISB

Dated:

Form for Hearing

Through Registered AD, Courier Service or email or Fax

1. A committee for investigation of blacklisting Proceedings in furtherance of Rule 19 PPRA, 2004 has been constituted to investigate and decide upon the allegations at Para-2/below. You are required to appear in person or defend in writing with evidence on _____ at IESCO Head Office as to why you should not be blacklisted for:
2.

*****Add charge*****
3. You are being given an opportunity to be heard and are required to appear in person or defend in writing with evidence on _____ at IESCO Head Office. In case of you failure to attend or pay heed the Committee shall proceed ex-parte.
4. [To be added in the third notice]. As of final notice you are directed to furnish a satisfactory explanation in writing with supporting evidence within three days of receipt of this notice, to show cause as to why the blacklisting penalty may not be imposed. Failing to pay heed to this last notice shall stand a presumption against you that you have no explanation to offer and the matter shall be proceeded ex-part.

General Manager (Technical)
IESCO Head Office,
Street No. 40, Sector G-7/4.
Islamabad - 46000

Correction of defects in the warranty period

The period for taking remedial action for failure of correction of defects in the warranty period is:
Thirty (30) Days from the date defect notified to the supplier at his cost and expense.



TYPE TEST Requirements

The contractor shall supply valid type test reports according to WAPDA/NTDC specification along with the bid for the material offered. In case the type test reports furnished by the bidder are not from one of the laboratories mentioned below or any other reputed independent testing laboratories accredited by STL (Short-Circuit Testing Liaison) or are not relevant to the material offered or do not meet or comply with the ratings and other requirements of the Purchaser's Specifications included in this bidding document or are otherwise not to the satisfaction of the Purchaser in any respect, the bidder has to arrange Type testing at any one of the laboratories mentioned in the NTDC revised Type Testing Policy 2023 at his cost/Price of the bid without disturbing the stipulated delivery period/ bid price given above duly witnessed by 02 Nos. IESCO Engineers.

1. HV & SC Lab, Rawat, Pakistan
2. KEMA Lab, Holland
3. CESI, Italy
4. CRIEPI Lab, Japan
5. KERI Lab, Korea
6. Any other lab approved by STL
7. ILAC Lab

Price Schedule: Goods Manufactured in Pakistan

Name of Bidder Page of

NCB	Sr. No	ITEM DESCRIPTION	Unit	Qty	Unit rate on *EXW without sales tax [in Rs] (including all transportation charges, loading , Un loading etc upto IESCO Regional Store New Wah	Total Price on EXW without sales tax [in Rs] including transportation charges, loading , Un loading, all types of duties etc, upto IESCO Regional Store New Wah
1		2	3	4	5	6=(4x5)
PMU/Goods/ NCB-289	1	132KV Lightening Arrester with Supported Steel Structure (SSS)	No.	65		
Total Price of NCB-289 without GST / PST						
Total Price of NCB-289 Including GST / PST						

Note:

1. The Bidder must fill the price in this Form in accordance with the instructions otherwise bid will be rejected
2. In case of discrepancy between unit price and total, the unit price shall prevail.
3. The Currencies should be in accordance with instruction BDS-12

*EXW price included all taxes and duties excluding GST

IESCO Designated Store/place: *IESCO Regional Store, Hassan Abdaal Road, New Wah.*

Name in the capacity of

Signature of Bidder: _____

Duly authorized to sign the Bid for and on behalf of

Dated on day of 20

Price Schedule: Goods Manufactured Outside Pakistan, to be Imported

Name of Bidder Page of

NCB	Sr. No	ITEM DESCRIPTION	Unit	Qty	Unit rate on *DDP upto Karachi Port without sales tax [in Rs] (including all transportation charges, loading , Un loading etc upto IESCO Regional Store New Wah	Total Price on *DDP upto Karachi Port without sales tax [in Rs] including transportation charges, loading , Un loading, all types of duties etc, upto IESCO Regional Store New Wah
1		2	3	4	5	6=(4x5)
PMU/Goods/ NCB-289	1	132KV Lightening Arrester with Supported Steel Structure (SSS)	No.	65		
Total Price of NCB-289 without GST / PST						
Total Price of NCB-289 Including GST / PST						

Note:

1. The Bidder must fill the price in this Form in accordance with the instructions otherwise bid will be rejected
2. In case of discrepancy between unit price and total, the unit price shall prevail.
3. The Currencies should be in accordance with instruction BDS-12

*DDP price included all taxes and duties excluding GST

IESCO Designated Store/place: *IESCO Regional Store, Hassan Abdaal Road, New Wah.*

Name in the capacity of

Signature of Bidder:

Duly authorized to sign the Bid for and on behalf of

Dated on day of 20

NATIONAL TRANSMISSION AND DESPATCH COMPANY

NTDC SPECIFICATION P-181:2012



METAL – OXIDE SURGE ARRESTERS WITHOUT GAPS
(FOR 11KV, 33KV, 66KV, 132KV, 220kV & 500KV A.C. SYSTEMS)

DESIGN DEPARTMENT NTDC

C O N T E N T S

<u>CLAUSE</u>	<u>DESCRIPTION</u>	<u>PAGE</u>
0	FOREWORD	3
1	SCOPE	3
2	REFERENCE STANDARD	4
3	DEFINITIONS	4
4	SERVICE CONDITIONS	8
5	RATINGS AND CHARACTERISTICS	10
6	CONSTRUCTIONAL REQUIREMENTS	11
7	BUSHING/POST INSULATOR	14
8	NAME PLATE MARKING	15
9	SUPPORTING STEEL STRUCTURE	16
10	TERMINAL CONNECTOR	18
11	TESTS	19
12	DRAWINGS AND DESCRIPTIVE DATA	21
13	PACKING	23
14	ENCLOSURES:	23
	- SCHEDULE OF TECHNICAL DATA	24
	- DRAWINGS	34

PRINTING HISTORY

FIRST EDITION
SECOND EDITION
THIRD EDITION

FEBRUARY 1985
SEPTEMBER 1996
SEPTEMBER 2012



NTDC SPECIFICATION P-181:2012**METAL – OXIDE SURGE ARRESTERS WITHOUT GAPS
(FOR 11KV, 33KV, 66KV, 132KV, 220kV & 500KV A.C. SYSTEMS)****0.0 FOREWORD**

0.1 This specification has been prepared by Standards & Research Directorate of the Design Department NTDC. This third edition cancels and replaces the earlier editions published in 1985 & 1996 and its amendments and draft specification for 500kV surge arresters.

0.2 This specification is intended for the procurement of material but does not include all the necessary provisions of the contract.

0.3 This specification is subject to revision as and when required by S&R directorate of Design NTDC only. No other department is authorized to make/issue amendment in the said specification.

1.0 SCOPE

This specification is applicable to single phase/pole non-linear, metal-oxide resistor type surge arresters without spark gaps along with steel supporting structures, grouting bolts, terminal connector for connection to external aluminium conductor as applicable and operation on three phase solidly earthed system having voltages of 11kV, 33kV 66kV, 132kV, 220kV, & 500kV, 50 Hz, A.C. systems for protection of power transformers, and other electrical equipments by limiting the lightning and transient/switching surge voltages.

1.2 The Surge Arresters shall be designated as follows:

Sr. No.	Description	Designation
i.	Surge Arresters for 11 kV AC System	A
ii.	Surge Arresters for 33 kV AC System	B
iii.	Surge Arresters for 66 kV AC System	C
iv.	Surge Arresters for 132 kV AC System	D
v.	Surge Arresters for 220 kV AC System	E
vi.	Surge Arresters for 500 kV AC System	F

- 3 -

2.0 REFERENCE STANDARD

- 2.1 The surge arresters shall generally be designed, constructed and tested in accordance with the International Electro-technical Commission No. 60099-4 "Metal-Oxide Surge Arresters without gaps for AC system" amended to-date.
- 2.2 The definitions given in the IEC 60099-4 shall apply herein.
- 2.3 In case the requirements laid down herein differ from those given in the IEC Publications in any particular aspect, the requirements listed herein shall prevail.

3.0 DEFINITIONS

The definitions of IEC 60099-4 shall apply. Some of them are recalled here for ease of reference.

3.1 **Metal-oxide surge arrester without gaps**

An arrester having non-linear metal-oxide resistors connected in series and/or in parallel without any integrated series or parallel spark gaps.

3.2 **Non-linear metal oxide resistor**

The part of the surge arrester which by its non-linear voltage versus current characteristics acts as a low resistance to over-voltages, thus limiting the voltage across the arrester terminals and as a high resistance at normal power frequency voltage.

3.3 **Grading ring of an arrester**

A metal part, usually circular in shape, mounted to modify electrostatically the voltage distribution along the arrester.

3.4 **Pressure relief device of an arrester**

A means for relieving internal pressure in an arrester and preventing violent shattering of the housing following prolonged passage of fault current or internal flashover of the arrester.

3.5 **Rated voltage of an arrester (U_r)**

The maximum permissible r.m.s. value of power frequency voltage between its terminals at which it is designed to operate correctly under temporary over-voltage conditions as established in the operating duty tests. The rated voltage is used as a reference parameter for the specification of operating characteristics.

3.6 Continuous operating voltage of an arrester (U_c)

The continuous operating voltage is the designated permissible r.m.s. value of power frequency voltage that may be applied continuously between the arrester terminals, under specified conditions.

3.7 Steep current impulse

A current impulse with a virtual front time of $1\mu s$ with limits in the adjustment of equipment such that the measured values are from $0.9\mu s$ to $1.1\mu s$. The virtual time to half value on the tail shall be not longer than $20\mu s$.

3.8 Lightning current impulse

An 8/20 current impulse with limits in the adjustment of equipment that the measured values are from $7\mu s$ to $9\mu s$ for the virtual front time and from $18\mu s$ to $22\mu s$ for the time to half value on the tail.

3.9 Long duration current impulse

A rectangular impulse which rises rapidly to maximum value, remains substantially constant for a specified period and then falls rapidly to zero. The parameters which defines a rectangular impulse are polarity, peak value, virtual duration of the peak and virtual total duration.

3.10 Discharge current of an arrester

The impulse current which flows through the arrester.

3.11 Nominal discharge current of an arrester (I_n)

The peak value of lightning current impulse which is used to classify an arrester.

3.12 High current impulse of an arrester

The peak value of discharge current having 4/10 impulse shape which is used to test the stability of the arrester on direct lightning strokes.

3.13 Switching current impulse of an arrester

The peak value of discharge current having a virtual front greater than $30\mu s$ but less than $100\mu s$ and a virtual time to half value on the tail of roughly twice the virtual front time.

3.14 Continuous current of an arrester

The continuous current is the current flowing through the arrester when energized at the continuous operating voltage.

3.15 Residual voltage of an arrester (U_{res})

The peak value of the voltage that appears between the terminals of an arrester during the passage of discharge current.

3.16 Reference voltage of an arrester (U_{ref})

The peak value of power frequency voltage divided by $\sqrt{2}$ which shall be applied to the arrester to obtain the reference current. The reference voltage of a multi-unit arrester is the sum of the reference voltages of the individual units.

3.17 Power frequency withstand voltage versus time characteristics of an arrester

The power frequency withstand voltage versus time characteristics shows the maximum time duration for which corresponding power frequency voltages may be applied to arrester without causing damage or thermal instability, under specified conditions.

3.18 Protective characteristics of an arrester

The combination of the following:

- a) Residual voltage for steep current impulse, under specified conditions.
- b) Residual voltage versus discharge current characteristics for lightning impulses, under specified conditions.
The lightning impulse protection level of the arrester is the maximum residual voltage for the nominal discharge current.
- c) Residual voltage for switching impulse, under specified conditions.
The switching impulse protection level of the arrester is the maximum residual voltage at the specified switching impulse currents.

3.19 Thermal runaway of an arrester

The term "thermal runaway" is used to describe a situation when the sustained power loss of an arrester exceeds the thermal dissipation capability of the housing and connections, leading to a cumulative increase in the temperature of the resistor elements culminating in failure.

3.24 Housing

External insulation part of an arrester which provides the necessary creepage distance and protects the internal parts from the environment.

3.20 **Porcelain housed arrester**

Arrester using porcelain as housing material, with fittings and sealing systems.

3.21 **Polymer housed arrester**

Arrester using polymeric and composite material for housing, with fittings.

3.22 **Thermal stability of an arrester**

An arrester is thermally stable if, after an operating duty causing temperature rise, the temperature of the resistor elements decreases with time when the arrester is energized at specified continuous operating voltage and at specified ambient conditions.

3.23 **Arrester disconnecter**

A device for disconnecting the arrester from the system in the event of arrester failure, to prevent a persistent fault on the system and to give visible indication of the failed arrester.

3.25 **Bending Moment**

Horizontal force acting on the arrester housing multiplied by the vertical distance between the mounting base (lower level of the flange) of the arrester housing and the point of application of the force.

3.26 **Terminal line force**

Force perpendicular to the longitudinal axis of the arrester measured at the centre line of the arrester.

3.27 **Torsional Loading**

Each horizontal force at the top of a vertical mounted arrester housing which is not applied to the longitudinal axis of the arrester.

3.28 **Breaking load**

Force perpendicular to the longitudinal axis of a porcelain housed arrester leading to mechanical failure of the arrester housing.

3.29 **Damage limit**

Lowest value of a force perpendicular to the longitudinal axis of a polymer housed arrester leading to mechanical failure of the arrester housing.

7- 

3.30 Specified long term load (SLL)

Force perpendicular to the longitudinal axis of a arrester, allowed to be applied during service without causing any mechanical damage to the arrester.

3.31 Specified Short term load (SSL)

Greatest force perpendicular to the longitudinal axis of an arrester, allowed to be applied during service for short periods and for relatively rare events (e.g. short-circuit loads and extreme wind gusts) without causing any mechanical damage to the arrester. SSL does not relate to mechanical strength requirements for seismic loads.

3.32 Mean breaking load (MBL)

The average breaking load for porcelain or cast resin-housed arresters determined from tests.

3.33 Temporary over-voltage (TOV)

It is transient over voltage of oscillatory nature, other than surge over voltage, of relatively long duration such as appearing in case of system disturbances e.g. ferro resonance, line-to-ground fault, load rejection etc.

3.34 Line discharge class

It specifies rated duty cycle and associated test requirements for arresters in respect of discharging long duration current impulse.

3.35 Pressure relief class

It represents the minimum rms value of symmetrical fault current that will operate the pressure relief device.

4.0 SERVICE CONDITIONS

The surge arresters and all accessories shall be suitable for satisfactory operation under the following service conditions:-

4.1 Climatic Conditions

4.1.1 Ambient Temperature

Maximum	50°C.
Maximum mean over any 24 hours	45°C.
Mean in any year	30°C
Minimum	-10°C

4.1.2 Relative Humidity

The relative humidity may range from 0 to 100 percent. The maximum value of the ambient temperature and humidity, however, do not occur simultaneously. During the monsoons, high humidity may persist for many days at a time along with temperatures ranging from 30°C to 40°C.

4.2 Altitude

The surge arresters shall be suitable for installation upto 1000 m above sea level.

4.3 Atmospheric Conditions

It may be assumed that the air is not normally heavily polluted by dust, smoke, aggressive gases, vapours or salt spray. However, at certain times of the year severe dust storms may be experienced.

4.4 Wind Load

The maximum wind load shall be taken as 122 kg/sq. m. (corresponding to wind speed of 44.2 m/s).

4.5 Seismic Conditions

The surge arresters along with steel supporting structures and foundation shall be suitable to withstand the seismic stress/magnitude according to Richter-scale up to 7 (horizontal acceleration up to $4m/s^2$ (0.4g) for safety of equipment under heavy earth quake conditions unless otherwise specified in the tender. The foundation arrangement shall be designed using the soil bearing capacity of 0.5 to 1.0 kg/cm². Design calculations and guidelines shall also be supplied with the bid.

Supply System

The surge arresters shall be suitable for installation in 11kV, 33kV, 66kV, 132kV, 220kV, & 500kV, three phase A.C solidly earthed supply system of the following characteristics:

Sr. No.	Designation of Surge Arresters →	A	B	C	D	E	F
a.	Highest System Voltage, kV rms.	12	36	72.5	145	245	550
b.	Nominal System Voltage, Un, kV rms.	11	33	66	132	220	500
c.	Frequency, Hz.	50	50	50	50	50	50

5.0 RATINGS AND CHARACTERISTICS

5.1 The surge arresters shall be so designed as to comply with the following ratings, characteristics and to meet all test requirements laid down herein :

Sr. No.	Designation of Surge Arresters →	A	B	C	D	E	F
a.	Highest System Voltage, (Um), kV rms.	12	36	72.5	145	245	550
b.	Nominal System Voltage, Un, kV, rms.	11.5	33	66	132	220	500
c.	Arrester Rated Voltage (Ur), kV.	12	36	60	120	198	444
d.	Rated Frequency, Hz.	50	50	50	50	50	50
e.	Continuous operating voltage (Uc), kV.	10.2	28.8	48	96	156	348
f.	Temporary over voltage (TOV), Is /10 s, kVrms.	12/ 11	36/ 33	70/ 64	138/ 130	228/ 216	515/ 488
g.	Nominal discharge current (In), kA peak.	10	10	10	10	10	20
h.	Line discharge class	1	1	2	3	3	5
i.	Short circuit withstand current, (0.2 s) kA sym.	20	20	20	40	50	63
j.	Pressure relief class	B	B	B	A	A	A
k.	High Current 4/10 μ s Impulse withstand, kA peak.	100	100	100	100	100	100
l.	Switching Current Impulse Withstand (Upper value), Amp.	250	500	500	1000	1000	2000
m.	Max. Residual Voltage at 10kA Steep Impulse current wave of 1/20 μ s, kV.	45	110	175	330	545	1132
n.	Max. Residual voltage at lightning impulse current waves of 8/20 μ s:						
	- 5 kA, kV peak.	36	93	156	282	456	960
	- 10 kA, kV peak.	40	100	168	300	486	1010
	- 20 kA, kV peak.	42	110	180	320	528	1110
	- 40 kA, kV peak.	44	126	204	360	600	1215

Sr. No.	Designation of Surge Arresters →	A	B	C	D	E	F
o.	Max. residual Voltage at Switching Impulse current wave of 30/60 μ s:						
-	500 A, kVpeak.	28	78	120	234	384	830
-	1000 A, kVpeak.	30	80	126	246	402	865
-	2000 A, kVpeak.	33	84	132	252	420	896
-	3000 A, kVpeak.	35	88	136	258	429	920
p.	1.2/50 μ s Lightning Impulse Withstand Voltage, kVpeak (Dry)	95	170	325	650	1050	1550
q.	Power frequency withstand voltage:						
-	Dry, kV for 1 min.	42	80	160	315	530	780
-	Wet, kV for 1 min.	38	70	140	275	460	680
r.	Internal partial discharge at 1.05 times the continuous operating voltage, $\leq$ pC.	10	10	10	10	10	10
s.	Max. RIV at 1.05 times continuous operating voltage, μ V.	500	500	500	500	500	500
t.	Energy absorption capability, kJ/kV(Ur).						
-	Thermal, kJ/kV.	3	4	5	7	8	15
-	Impulse, kJ/kV.	2	2	3	5	5	10

6.0 CONSTRUCTIONAL REQUIREMENTS

6.1 General

6.1.1 Surge arresters shall be of non-linear, metal-oxide resistors type having no spark gaps. The metal-oxide blocks employed shall have minimum power loss which shall not increase during the life of the arrester when operating under the specified service conditions, especially the elevated ambient temperature, and with the maximum continuous operating voltage.

6.1.2 The metal-oxide resistors assembly shall be housed in a porcelain insulator of sufficient thermal and mechanical strength which shall be hermetically sealed to ensure against ingress of the moisture throughout the life of the arrester. The space

- 11 -

between the metal-oxide resistors blocks and the external housing shall be filled with a dry inert gas. Alternatively, this space may be filled with some suitable, field-proven, solid polymeric material such as silicone rubber.

6.1.3 The metal-oxide resistors shall possess superior nonlinear V-A characteristics and high energy/over-voltage absorption capability, high protection margin of discharge voltages at steep, lightning and switching surges. In addition, suitable means may be adopted as necessary to ensure rapid and effective self-cooling of the resistor blocks by efficient heat transfer in order to afford adequate temporary over voltage (TOV) capability.

6.1.4 Surge arresters shall be able to withstand the combination of stresses arising in service as demonstrated by the operating duty test. These stresses shall not cause damage or thermal runaway.

6.1.5 The design of the arrester shall be such that a reasonably uniform potential drop will exist across each section of the arrester when operating under the specified service conditions. Moreover, the arrester will not flash over and the temperature increase of the arresters remains within the specified maximum temperature during live washing of arrester.

6.1.5 The 12kV arresters shall be built generally in accordance with Drawing No. PDW/TS-3205. The 33kV, 66kV, 132kV, 220kV & 500kV surge arresters shall be of pedestal type built generally in accordance with the enclosed drawings as applicable.

6.1.6 The 132kV, 220kV & 500 kV arresters shall be fitted with grading rings assembly. The metallic grading ring and ring support shall be of rugged design and construction to maintain the ring properly spaced under the specified service conditions.

6.1.7 The external housing in case of the arresters for 11kV, 33kV and 66kV systems may alternatively consist of suitable polymeric composite insulators of high mechanical strength and complying with the requirements of relevant IEC Standards in addition to the other applicable requirements given in this specification.

6.2 Mounting

6.2.1 The mounting arrangement of 12kV surge arrester shall be as per enclosed Drawing No. PDW/TS-7282.

6.2.2 The arresters of 33KV, 66kV, 132kV, 220kV & 500kV ratings shall be self supporting and designed to be mounted on steel structures as per enclosed drawings as applicable. The supporting steel structures shall be supplied with the arresters.

6.3 Terminal Connectors

- 6.3.1 The 12kV surge arrester shall be provided with a flexible fully insulated lead for the line terminal. All connections and parts shall be insulated so that no live metal parts are exposed. This insulated lead shall be of stranded tinned copper of not less than 13sq. mm cross section and shall be at least 45 cm in length. For grounded connection, a solderless clamp type terminal, capable of securely clamping stranded copper conductor of 6 to 10 mm diameter, shall be provided.
- 6.3.2 The line terminal of the 33kV & 66kV surge arrester shall consist of solderless clamp type connectors. The connector shall be made of high strength aluminum alloy and shall be designed for receiving stranded conductors of 12 mm to 26 mm diameter either in a horizontal or vertical direction.
- 6.3.3 The line terminal of the 132kV surge arrester shall consist of solderless clamp/connector. The connector shall be made of high strength aluminum alloy and shall be designed for receiving stranded conductors of 20 mm to 38 mm diameter either in a horizontal or vertical direction.
- 6.3.4 The line terminal of 220kV arresters shall be a vertical stud of 30 mm dia and 80 mm length as per Drawing No. PDW/DF-387 and shall be made of tin/silver plated copper.
- 6.3.5 The line terminal of 500kV arresters shall comply with the requirements of the relevant international standard and subject to approval by the Purchaser.
- 6.3.6 For ground connections of 33kV, 66kV, 132kV, 220kV & 500kV ratings, a solderless clamp type terminal, capable of securely clamping stranded copper conductor of 10 to 15mm diameter, shall be provided to receive the conductor in horizontal direction.
- 6.3.7 The Specified Long term Load (SLL), Specified Short term Load (SSL) and Mean Breaking loads (MBL) shall be as per reference standards.

6.7 Earthing Terminals

Two number earthing terminals at diagonally opposite position shall be provided in arresters of 33KV, 66kV, 132kV, 220kV, & 500kV ratings. Each terminal shall be capable of carrying full short circuit current and be suitable for accommodating 95 to 120 sq mm copper earthing lead.

6.4 Surge Counter

- 6.4.1 132kV, 220kV and 500kV arresters shall be equipped with 3- digit cyclometer dial type surge counters without resetting facility for indicating through a transparent window the number of times the arrester has operated on account of lightning or

13- *[Signature]*

switching surges with built in ammeter for measurement of leakage current complying with the following parameters:

Sr. No.	Performance Required	Parameters
1.	Indication of counter	3 digit cyclometer
2.	Minimum operating current	50A (8/20 us)
3.	Max. high current withstand capability	100kA (4/10 us)
4.	Ammeter scale	0-5mA rms

6.4.2 The counters shall be of the type which permits measuring/monitoring/analyzing of the continuous leakage current without being disconnected. The monitor shall be supplied with an auxiliary contact rated 0.5A, 230V for remote signaling. Surge counters shall be sensitive enough to record the minimum discharge current likely to take place inside the arrester. Counters shall not require any refill charts or graphs.

6.4.3 The leakage current shall be indicated in three different color ranges in the ammeter to assess the healthiness of the surge arrester. One range indicate the normal range (surge arrester is in healthy status), second range indicate out of normal range (surge arrester or system to be checked) while third range indicate over normal range (surge arrester must be repaired/replaced).

6.4.4 Two terminals similar to the ground terminals of the arrester shall be provided with the counter. The counter shall be fully weather-proof and explosion-proof for full short-circuit current. It shall be visible and readable from outside.

6.4.5 The surge counter shall be subjected to severe electrical, mechanical and climate conditions. The type test reports for the following type tests shall be furnished by the arrester manufacturer.

- a) Shock test as per IEC 60068.
- b) Vibration test as per IEC 60068.
- c) Temperature test as per IEC 60068.
- d) Humidity test as per IEC 60068.
- e) Impulse test as per IEC 60099-4.
- f) Short-circuit test as per IEC 60099-4.
- g) Salt fog test (For polymeric housed arresters).

7.0 BUSHING/POST INSULATOR

7.1 All porcelain insulators shall be wet process, homogeneous and free from cavities and other defects. The color of insulators shall be chocolate glazed brown and tested in accordance with IEC-60273. Manufacturer's type & routine Test reports shall be submitted at the time of pre-delivery inspection.

Porcelain insulators shall be designed to withstand internal pressure of three times the maximum operating pressure and shall have the same Insulation Level as the surge arrester. These shall be airtight under pressure and shall have adequate mechanical strength to withstand the wind loads, seismic stress, static and dynamic forces from conductor.

Porcelain insulators shall have following minimum creepage distance from live to earthed parts for operation under the prevailing atmospheric conditions:

Arrester Designation	Bushing Highest Voltage (kV)	Minimum Creepage Distance (mm)
A	12	350
B	36	970
C	72.5	1960
D	145	3900
E	245	7000
F	550	15000

The type test reports of the insulator shall be furnished by the arrester manufacturer as per relevant international standard and conforming to above requirements.

NAME PLATE MARKING

A corrosion resistant stainless steel name plate shall be securely attached to the surge arrester and shall include at least the following information marked in an indelible manner in accordance with IEC 60099-4. In case the arrester is composed of a number of a number of units, each unit shall also have an individual name plate. The name plate of lower unit shall be visible in position of nominal service and installation.

- Manufacturer's name.
- Designation and type.
- Serial number.
- Contract No./Purchase Order No. and date.
- Rated voltage.
- Continuous operating voltage.
- Nominal discharge current.
- Line discharge class and absorption capability in kJ.
- Pressure relief class and rated fault current in kA.
- Residual voltages at 5, 10 & 20kA.
- Maximum permissible value of the resistive component of leakage current.
- Rated short circuit withstand current in kA.
- Identification of assembling position of the unit.
- Unit weight in Kg.

9.0 SUPPORTING STEEL STRUCTURE

9.1 Each surge arrester shall be supplied along with steel supporting structures, its foundations/grouting bolts etc. The origin of steel supporting structures shall be same as that of surge arresters. All structural material shall be hot dip galvanized.

9.2 The dimensions indicated in enclosed drawing are minimum values. The manufacturer shall submit their own design/drawings without affecting the interchangeability requirement of the foundation arrangement as indicated in detail B of the drawings. The manufacturer may design the steel supporting structure according to their requirements and fulfilling the wind load, wind speed and other forces involved on the surge arrester under fault conditions. The change in dimensions of foundation arrangement is not allowed.

9.3 The steel shall conform to the requirements as prescribed below:

Tensile strength:

Minimum, kg/mm ²	50
Maximum, kg/mm ²	80

Yield points kg/mm ² Min.	35
--------------------------------------	----

Elongation in 200mm gauge Length:

Upto 8mm Thickness, % min.	15
Over 8mm Thickness, % min.	18

9.4 All nut and bolts shall be hexagonal type made from steel grade 6.8 (ISO 898) and provided with one flat and one lock washer under each nut. All connection bolts, nuts, lock nuts and washers shall be furnished in excess of at least 5% greater than actual requirements sufficient to compensate for normal field losses.

9.5 All grouting bolts for fixing the structures to the foundation shall be from High Tensile Steel. Washers shall not be less than 5 mm thickness and only one thickness of washer shall be used. The diameter of the washer and bolt holes shall be 1.5mm larger than the bolt diameter and the outside diameter of washer shall not be less than 1.5mm larger than the diagonal of the nut.

9.6 All main legs/structural material shall be coupled with foundation arrangement & top plate with nuts & bolts only. No connection with welding at the base and top is allowed.

9.7 All members with its identification marks shall be coupled with main structural members/legs through nuts & bolts only. Welding of members with legs is not allowed.

9.8 Prior to galvanizing, material shall be drilled, punched, cut or otherwise fabricated as required, free from burrs, cleaned so that zinc coating shall be adherent, dense, smooth, continuous and uniform. It shall also be completely free from lumps, blisters, uncoated or porous spots, black spots, dross, flux or any other imperfection.

9.9 The weight and thickness of zinc coating on angles shall not be less than 600gm/m^2 and 0.010 mm respectively.

9.10 The weight and thickness of zinc coating on nuts & bolts shall not be less than 380gm/m^2 and 0.035 mm respectively. The brinell hardness of bolts & nuts shall be between 120 to 200 HB. The ultimate strength and other properties of the nuts & bolts not listed above shall conform to relevant International standard viz British/ASTM/IEC etc.

9.11 Acceptance Tests:

The following acceptance tests shall be carried out on one complete structure out of lot offered for inspection.

For Section and Plates

1. Visual examination
2. Verification of dimensions and weights
3. Assembly tests
4. Tensile tests
5. Bend Tests
6. Impact tests
7. Galvanizing tests
 - Weight of zinc coating
 - Uniformity of zinc coating
 - Adherence of zinc coating
 - Embitterment test

For Nuts and Bolts

1. Verification of dimensions
2. Visual inspection
3. Proof load test
4. Ultimate tensile strength test
5. Hardness test
6. Galvanizing tests
 - Weight of zinc coating
 - Uniformity of zinc coating
 - Adherence of zinc coating
 - Embitterment test

Test reports shall be furnished by the manufacturer as per relevant international standard and conforming to above requirements.

10.0 TERMINAL CONNECTOR

10.1 Mono-metallic or Bimetallic terminal connectors as per requirement of terminal head with stainless steel nuts and bolts suitable for connection between terminal heads and aluminum conductor having dia of 26 to 38mm shall be provided with the surge arrester. The connectors with single bolt technology i.e. without nut & washers are not acceptable. The bimetallic connectors shall have separate copper and aluminium bodies joined by a suitable bimetal strip joint with 2mm of thickness. The connectors employing bimetallic shims shall not be accepted.

10.2 The material and composition of the Aluminum alloy used on monometallic connectors and the Aluminum portion of the bimetallic connectors shall be properly heat treated. Keepers and components which are subjected to high forces during service, will be obtained by gravity die casting. Aluminum alloy and keepers shall have the following characteristics:

Ultimate tensile strength, min	=	24 kg/mm ²
Yield strength, min	=	15.5 kg/mm ²
Elongation, min	=	3% on 50 mm scale
Electrical conductivity, min	=	38% IACS
Brinell hardness, min	=	100 HB

10.3 The copper alloy shall be from the Copper/Nickel base family of alloys with a minimum of 96.4% of copper in order to guarantee high conductivity properties as well as high strengths characteristics. Copper alloy shall be heat treated. Bronze or Brass alloys are not acceptable.

The copper alloy and keepers shall have the following characteristics:

Ultimate tensile strength, min	=	20 kg/mm ²
Yield strength, min	=	10 kg/mm ²
Elongation (min)	=	18% on 50 mm scale
Electrical conductivity at 20°C	=	32% IACS (min)

10.4 The bolts, nuts and washers shall be of stainless steel having following properties:

Breaking strength, min	=	65 kg/mm ²
Yield strength, min	=	40 kg/mm ²
Brinell hardness, min	=	140 HB

10.5 The type test reports for the following tests for connector bodies, keepers shall be furnished by the connector manufacturer as per relevant international standard and conforming to above requirements.

- Material composition test
- Tensile strength test
- Elongation test
- Brinell hardness test
- Heat cycle test
- Conductivity test

11.0 **TESTS**

11.1 Tests shall be performed to ascertain that, as regards design, size, material and manufacture, the surge arresters comply with the specified rating, characteristics and operational requirements. The arrangement, test conditions, and criteria to pass the tests shall be in accordance with relevant clauses of IEC 60099-4 amended to date.

11.2 **Type Tests**

11.2.1 Duly certified and complete type test reports for tests carried out at KEMA Lab Holland and CESI Lab Italy on the surge arresters having same design, voltage ratings shall be acceptable in lieu of actual tests. The validity of the type test reports shall be 10 years. In case of non-production of the requisite type test reports or if the type test reports are otherwise not acceptable to the Design NTDC, the following tests shall be performed on the surge arrester having same voltage ratings as ordered in presence of two representatives one from Design, NTDC and other from purchaser at any STL approved Lab or any other lab approved by design NTDC at the cost and arrangement of the manufacturer including travel expenses, boarding, lodging and daily allowance for the representatives.

- a) Insulation withstand tests on arrester housing (Dry & Wet):
 - i) Lightning impulse voltage test (dry).
 - ii) Switching impulse voltage test (dry) (For type E & F arresters only)
 - iii) Power frequency voltage test (Dry & Wet).
- b) Residual voltage tests:
 - i) Steep current impulse residual voltage test.
 - ii) Lightning impulse residual voltage test.
 - iii) Switching impulse residual voltage test.
- c) Long duration current impulse withstand test.
- d) Operating duty tests:
 - i) High current impulse operating duty test.
 - ii) Switching surge operating duty test.
- e) Short circuit Test.
- f) Tests of arrester disconnectors (For arresters fitted with disconnectors)
- g) Artificial pollution test (For porcelain housed multi unit surge arresters).
- h) Internal partial discharge test.
- i) Bending moment test (For porcelain housed surge arresters for $U_m > 52kV$)
- j) Environmental test (For porcelain housed surge arresters)
- k) Seal leak rate test.
- l) Radio interference voltage (RIV) test.
- m) Weather ageing test (For polymer housed arresters).
- n) Current distribution test (For multi column arresters).
- p) Power frequency voltage verses time test.
- q) Pressure relief test.
- r) Salt fog test (For polymeric housed arresters).

11.2.2 The housing shall withstand the following voltages during Insulation withstand tests on arrester housing:

- The lightning impulse protection level of the arresters multiplied by 1.3.
- The switching impulse protection level of the arresters multiplied by 1.3.
- Housing of type A, B, C & D arresters shall withstand a power frequency voltage with a peak value equal to the switching impulse protection level multiplied by 1.06 for a duration of 1 minute.

11.2.3 Visual examination of the samples after type tests shall reveal no evidence of puncture, flashover, cracking or other significant damage of the metal-oxide resistors. The residual voltage measured before and after the long-duration current test shall not have changed by more than 5%.

11.2.4 Following visual inspection/checks on the assembly subject to type tests shall also be carried out and made part of the type test report.

- i) Verification of name plate data.
- ii) Check of constructional and performance requirements.
- iii) Visual & dimensional verification of arrester assembly, steel supporting structures, terminal connectors and earth terminals.
- iv) Measurement of creepage distance.

11.2.5 Test Reports

The type test report for the above tests along with complete outline drawings, data, photographs, details of supporting structure, record of test quantities of tested surge arrester duly stamped by the independent lab shall be submitted with the bid. The type test reports shall incorporate details sufficient to identify the design of the tested surge arrester. Such information shall include, but is not restricted to the following:

- i) Drawing of arrester general assembly.
- ii) The details of mountings, fixings and insulators.
- iii) Rated cantilever strength of insulators.
- iv) Rated torsional strength of insulators.
- v) Creepage length and shed profile.
- vi) Height of insulators.
- vii) Type test reports of Insulator.

11.3 Routine Tests

11.3.1 The manufacturer shall perform routine tests on all surge arresters according to respective clauses of IEC-60099-4 and test reports shall be submit at the time of pre-delivery inspection.

11.4 Acceptance Tests

11.4.1 The following acceptance tests shall be made on 5% of the quantity of ordered surge arresters to be selected randomly from the total lot offered for pre-delivery inspection/testing in presence of two representatives one from Design, NTDC and other from Purchaser at the cost and arrangement of the manufacturer including travel expenses, boarding, lodging and daily allowance for the representatives. The arrangement, test conditions, and criteria to pass the tests shall be in accordance with relevant clauses of IEC 60099-4 amended to date.

- a) Measurement of power frequency voltage.
- b) Lightning impulse residual voltage.
- c) Internal partial discharge test.
- d) Seal leak rate test.
- e) Current distribution test (For multi column arresters).
- f) Special thermal stability test.

11.4.2 One complete surge arrester shall be fitted on the steel supporting structure for following examination:

- i) Visual inspection and Measurement of dimensions
- ii) Verification of name plate data.
- iii) Check of constructional and performance requirements.
- iv) Visual & dimensional verification of supporting structures, terminal connectors and earth terminals.
- v) Verification of type, model, test report, data & drawing, and creepage distance of bushing/post insulator.
- vi) Verification of Metal Oxide Blocks data, drawing, test report.

4.3 The acceptance/inspection certificate clearly indicate the performance of above tests during pre-delivery inspection/testing and test results shall be submitted to the Purchaser. A copy of bill of quantity indicating the total quantity of each component, parts, structure, their accessories, etc, duly signed by the inspectors(s) required for consignor for verification on receipt of material in warehouse/store shall also be attached with the inspection certificate.

DRAWINGS AND DESCRIPTIVE DATA

Data to be submitted with the bid

1 Supply record of offered type, voltage rating of surge arresters for last five years on the following format:

Sr. No.	Contract/Purchase Order No. & date with quantity.	Type of Arrester	Rated Voltage	Delivery period	Client Address/ Phone/ Fax No./ E-mail, etc.
---------	---	------------------	---------------	-----------------	--

- 12.1.2 The schedule of technical data duly filled-in attached hereto along with supporting documents. The word indicating "as per specification/standard" will not be acceptable.
- 12.1.3 Dimensional & outline drawing of surge arresters showing dimensions and each individual part including, pressure relief device, operation counter, terminal head for high voltage connections, size of terminals for earthing, terminal connector and details of the mounting arrangements.
- 12.1.4 Non submission of completely filled-in schedule of technical data and supply record on the above format or submission of incomplete information/data as mentioned above with the bid may render the bid non-responsive.
- 12.2 **Approval Drawings and Data to be submitted after Award of Contract/Purchase Order**

The following drawings/descriptive data shall be submitted for approval of Design Department NTDC before manufacturing the equipment:

- i. Schedule of technical data duly filled-in along with supporting documents.
- ii. Instruction Manual for installation indicating site test procedure before energizing/operation, maintenance/replacement of components procedure and storing requirements of the surge arresters.
- iii. Dimensional & outline drawing of surge arresters showing dimensions and each individual part including, pressure relief device, operation counter, terminal head for high voltage connections, size of terminals for earthing, terminal connector and details of the mounting arrangements.
- iv. Sectional drawing of the surge arrester indicating the inner details.
- vi. Power frequency voltage versus time characteristics of an arrester.
- vii. Technical catalogue in respect of the bushings.
- viii. Installation, erection, maintenance and operation instruction manuals.
- ix. Type test reports for similar type of arresters and operation counters shall be furnished. The test reports shall incorporate all necessary details and relevant data/information about the tested equipment in sufficiency for ascertaining the validity of the test report and evaluation of the tests results.
- x. Drawings of steel supporting structure, foundation/grouting bolt drawing showing static and dynamic loading of surge arresters. Photographs in fully arranged and erected condition.
- xi. Type test reports of insulator, terminal connectors.
- xii. Rating plate drawing and earth quake simulation and response calculations.



13.0 PACKING

The surge arrester and all allied material including steel supporting structure, connector, etc. shall be supplied in individual wooden box suitable for transport by rail/road and sea as per international practice. Special precaution may be essential for protection of insulation during transport to prevent moisture absorption, for instance, due to rain, snow or condensation. In every pack of equipment for shipment one number installation, erection, maintenance and operation instruction book enclosed in water proof material shall be provided. Bill of quantity shall indicate the quantity, size, length, weight and assembly mark of each member of structure including nuts & bolts, washers, plates, foundation bolts and all fittings complete for structure, connector etc.

14.0 ENCLOSURES

- a. Schedule of Technical Data for Surge arresters.
- b. Supporting Steel Structure for Surge Arresters Drawing No. PDW/TS/3203 (Revision dated 03-09-2012).
- c. Typical 12kV Surge Arrester Drawing No. PDW/TS/3205 (Revision dated 03-09-2012).
- d. Mounting arrangement for 12kV Surge arresters Drawing No. PDW/TS/7282 (Dated 03-09-2012).
- e. 33kV and 66kV Surge Arresters with insulating base Drawing No. PDW/TS/3206 (Revision dated 03-09-2012).
- f. 132kV Surge Arresters with insulating base Drawing No. PDW/TS/3207 (Revision dated 03-09-2012).
- g. Supporting Steel Structure for 220kV Surge Arrester Drawing No. PDW/TS/4968 (Revision dated 03-09-2012).
- h. Typical 220kV Surge Arresters with insulating base Drawing No. PDW/DF/387 (Revision dated 03-09-2012).
- i. Typical 500kV Surge Arresters with Supporting Steel Structure Drawing No. PDW/TS/7283 (Dated 03-09-2012).
- j. Mono-metallic Terminal Connector Drawing No. PDW/DF-308 (1).
- k. Bimetallic Terminal Connector Drawing No. PDW/DF-308 (Revision dated 01-01-2011).

SCHEDULE OF TECHNICAL DATA
METAL - OXIDE SURGE ARRESTERS WITHOUT GAPS
(FOR 11KV, 33KV, 66KV, 132KV, 220kV & 500KV A.C. SYSTEMS)

Bid/Tender No. _____

Sr. No.	DESCRIPTION		
A.	General		
1.	Manufacturer's name & address. (Attach Manufacturer's catalogue with the bid)		
2.	Type/designation of offered surge arrester		
3.	Data of Type Tested Arrester:		
-	Copy of type test reports attached.	Yes/No.	
-	Rated Voltage of arrester (U_r).	kV	
-	Rated Frequency.	Hz	
-	Continuous operating voltage (U_c).	kV	
-	Reference voltage of arrester (U_{ref})	kV	
-	Nominal discharge current (I_n).	kA	
-	Internal partial discharge.	pC	
-	Line discharge class.		
-	Pressure relief class.		
-	Metal-oxide Block Manufacturer's name & address.		
-	Diameter of Metal-oxide Block	Mm	
-	Thickness of Metal-oxide Block		
-	Quantity of Metal-oxide Blocks used in the arrester.	Nos.	
-	Energy absorption capability.	kJ/kV(U_r).	
4.	Details of Type Test on Arrester if performed.	Date of Test	Name of Lab.
a.	Lightning Impulse voltage test (dry).		
b.	Switching impulse voltage test (dry) (For type E & F arresters).		
c.	Power frequency voltage test (Dry).		
d.	Power frequency voltage test (Wet).		
e.	Steep current impulse residual voltage test.		

	f.	Lightning impulse residual voltage test.		
	g.	Switching impulse residual voltage test.		
	h.	Long duration current impulse withstand test.		
	i.	High current impulse operating duty test.		
	j.	Switching surge operating duty test.		
	k.	Short circuit Tests.		
	l.	Tests of arrester disconnectors (For arresters fitted with disconnectors).		
	m.	Artificial pollution test (For porcelain housed multi unit surge arresters).		
	n.	Internal partial discharge test.		
	o.	Seal leak rate test.		
	p.	Current distribution test (For multi column arresters).		
	q.	Bending moment test.		
	r.	Environmental test		
	s.	Radio interference voltage (RIV) test.		
	t.	Moisture ingress test (For polymer housed arresters).		
	u.	Weather ageing test (For polymer housed arresters).		
5.	Details of Type Test on Surge counter if performed.		Date of Test	Name of Lab.
	a.	Shock test as per IEC 60068.		
	b.	Vibration test as per IEC 60068.		
	c.	Temperature test as per IEC 60068.		
	d.	Humidity test as per IEC 60068.		
	e.	Impulse test as per IEC 60099-4.		
	f.	Short-circuit test as per IEC 60099-4.		
	g.	Salt fog test (For polymeric housed arresters).		

B.	Ratings		
1.	Highest System Voltage, (Um).	kVrms	
2.	Nominal System Voltage, (Un).	kVrms	
3.	Arrester Minimum Rated Voltage (Ur).	kV rms	
4.	Rated Frequency.	Hz	
5.	Reference Voltage, (Uref)	kVpeak	
6.	Continuous Operating Voltage(COV), (Uc).	kV	
7.	Temporary Over Voltage (TOV), 1s/10s.	kVrms	
8.	Nominal discharge current (In).	kApeak	
9.	Line discharge class		
10.	Short circuit withstand capability.	kAsym.	
11.	Pressure relief class.		
12.	High Current 4/10 μ s Impulse withstand.	kApeak	
13.	Switching Current Impulse Withstand (Upper value).	A	
14.	Max. residual Voltage with 10kA Steep Impulse current wave of 1/20 μ s.	kV	
15.	Energy absorption capability of arrester.	kJ/kV	
16.	Max. Residual voltage with following lightning impulse current waves of 8/20 μ s:		
	- 5 kA, kV peak.		
	- 10 kA, kV peak.		
	- 20 kA, kV peak.		
	- 40 kA, kV peak.		
17.	Max. residual Voltage with following Switching Impulse current wave of 30/60 μ s:		
	- 500 A, kVpeak.		
	- 1000 A, kVpeak.		
	- 2000 A, kVpeak.		
	- 3000 A, kVpeak.		

18.	Arrester insulation 1.2/50 μ s Lightning Impulse Withstand Voltage, (Dry).	kVpeak	
19.	Arrester insulation Power frequency withstand voltage,		
	- Dry, kV		
	- Wet, kV		
20.	Internal partial discharge at 1.05 times continuous operating voltage.	pC	
21.	Highest value of the current in a column of a multi-column arrester.		
22.	Seal leak rate		
23.	Specified long term load (SLL)	Nm.	
24.	Specified short term load (SSL)	Nm.	
25.	Mean Breaking load (MBL)	Nm.	
26.	Power loss at elevated ambient temperature, and with the maximum continuous operating voltage.		
27.	Guaranteed temporary over voltage capability for duration of:		
	- 0.5 sec	kV	
	- 1.0 sec	kV	
	- 3.0 sec	kV	
	- 10 sec	kV	
	- 1.0 min	kV	
	- 20.0 min	kV	
28.	Number of individual units per arrester		
29.	Maximum permissible continuous (leakage) current		
	- Total continuous current maximum	μ A	
	- Resistive component of the continuous (leakage) current	Max. μ A	
30.	Symmetrical fault current causing operation of pressure relief Device within 1/2 cycle of initiation.	kA	
31.	Internal pressure required to operate pressure relief device, percent of pressure required to burst housing	%	

32.	Metal-oxide Resister Block Manufacturer's name & address.		
33.	Outer diameter of Metal-oxide resister blocks used in the arrester.	mm	
34.	Inner diameter of Metal-oxide resister blocks used in the arrester.	mm	
35.	Thickness/height of Metal-oxide resister blocks used in the arrester.	mm	
36.	Quantity of Metal-oxide resister blocks used in the arrester.	Nos.	
37.	Leakage Rate	Torr.	
38.	No. of digits of cyclometer	Nos.	
39.	Minimum operating current of cyclometer	Amp	
40.	Max. high current withstand capability of cyclometer	kA	
41.	Residual voltage at 100kA (4/10 us) of cyclometer	kV	
42.	Switching impulse current withstand of cyclometer	A	
43.	Ammeter scale of cyclometer	mA	
44.	Overall/Total height of arrester	Mm	
45.	Weight of arrester	Kg	
46.	Wind loading capability	kg/sq.m	
47.	Ultimate bending moment	kg-m	
48.	Whether surge arrester is fitted with insulating base ?		
C.	Construction (Attach photograph of surge arrester showing all parts and a detail legend with the bid)		
1.	Material of Housing.	Porcelain/ Polymer	
2.	Color of Housing.		
3.	Material of Grading Ring.		
4.	Size of Grading Ring		
5.	Overall Diameter of Grading Ring		

NTDC SPECIFICATION P-181:2012

6.	No. of supports for grading ring		
7.	Weight of grading ring including supports.	Kg	
8.	Whether operation counter is without resetting facility?	Yes/No.	
9.	Whether two number earthing terminals at diagonally opposite position shall be provided?	Yes/No.	
D.	Bushing/Post Insulator		
1.	Manufacturer's name & address. (Attach Manufacturer's catalogue with the bid).		
2.	Type of Insulator.		
3.	Type tests (Attach copy of type test reports)		
4.	Details of Type Tests if performed.	Date of Test	Name of Lab.
	- Mechanical test.		
	- Impulse withstand voltage, peak.	kV	
	- Power frequency withstand voltage (Dry).	kV	
	- Power frequency withstand voltage (wet).	kV	
	- Temperature cycle test on porcelain components		
	- Porosity test on porcelain components		
	- Inner pressure test	MPa	
	- Bending test	kNm.	
	- Radio interference Voltage.		
5.	Rated Voltage of bushing/insulator.	kV	
6.	Type/Model of bushing/insulator.		
7.	Inner pressure withstand of bushing/insulator.	MPa	
8.	Outer diameter of bushing/insulator.	mm	
9.	Inner diameter of bushing/insulator.	mm	
10.	Shed diameter.	mm	
11.	Height of the bushing/insulator.	mm	
12.	Weight of housing without metal-oxide blocks.	kg.	

[Handwritten signature]

13.	Name of polymeric material used (in case of polymeric housing)		
14.	Whether polymeric material is fire-retardant and self extinguishing and is not subject to erosion & ultra violet radiation?	Yes/No.	
15.	No. of units per column.	No.	
16.	Creepage distance (Phase to Earth).	Mm	
17.	Phase to phase clearance.	Mm	
18.	Max RIV at 1 MHz.	μ V	
19.	Impulse withstand voltage.	kV	
20.	Power frequency withstand test voltage.		
	a. Dry 1 minute.	kV	
	b. Wet 10 sec.	kV	
21.	Ultimate strength of column.	Kg	
22.	Withstand Pressure:		
	a. Cantilever Strength	N	
	b. Tensile strength.	N	
	c. Torsional strength.	N	
	d. Compression strength.	N	
	e. Bending.	N	
23.	Material of bushing/insulator.		
24.	Color of bushing/insulator.		
25.	Reference Manufacturing Standard.		
E.	Steel Support Structure		
1.	Manufacturer's name & address. (Attach drawing/photograph of the support structure with the bid).		
2.	Dimensions for steel support structure:		
	- Height.	Mm	
	- Breadth.	Mm	
	- Width.	Mm	

	Structure fixing foundation details.		
3.	Tensile Strength of Angles/plates.	Kg/mm ²	
4.	Tensile Strength of Nuts & Bolts.	Kg/mm ²	
5.	Yield Strength of Angles/plates.	Kg/mm ²	
6.	Yield Strength of Nuts & Bolts.	Kg/mm ²	
7.	Elongation in 200m guage.	%	
8.	Weight of Zinc Coating of angles/nuts & bolts.		
9.	Thickness of zinc coating angles/nuts & bolts.		
10.	Hardness of nuts & bolts.	HB	
11.	Material of Angles		
12.	Material of Nuts & Bolts with washers		
13.	Diameter & thickness of Washers	mm	
14.	Diameter of bolts.	mm	
15.	Grade of Steel used.		
16.	Whether one flat and one lock washer under each nut is provided?	Yes/No	
17.	Whether 5% extra bolts nuts, lock nuts and washers than actual requirements is provided?		
18.	Weight of zinc coating on angles.	gm/m ²	
19.	Thickness of zinc coating on angles.	mm	
20.	Weight of zinc coating on nuts & bolts.	gm/m ²	
21.	Thickness of zinc coating on nuts & bolts.	mm	
22.	Designed soil bearing capacity.		
23.	Seismic withstand stress/magnitude. (Attach design calculations).		
24.	Total weight of supporting steel structure with foundation bolts.	Kg	



F.	Terminal		
1.	Manufacturer's name & address. (Attach drawing/photograph with the bid).		
2.	Material of terminal.		
3.	Size of terminal.		
4.	Current Carrying Capacity of terminal.	A	
5.	Whether two earthing terminals are provided?	Yes/No	
6.	Material of earthing terminal.		
7.	Specified Long term Load (SLL), Nm.	Nm	
8.	Specified Short term Load (SSL), Nm.	Nm	
9.	Mean Breaking Load (MBL), Nm.	Nm	
G.	Connector		
1.	Manufacturer's name & address. (Attach drawing/photograph with the bid)		
2.	Type of connector		
3.	Type tests (Attach copy of type test reports).		
4.	Details of Type Tests if performed.	Date of Test	Name of Lab.
	- Tensile strength & elongation.		
	- Brinell hardness.		
	- Conductivity.		
	- Short circuit withstand.		
	- Heat cycle.		
5.	Material of connector (Monometallic or Bimetallic).		
6.	Material of connector.		
7.	Material of keeper.		
8.	Current carrying capacity of connector.	A	
9.	Tensile Strength of connector.	kg/mm ²	
10.	Tensile Strength of keeper.	kg/mm ²	
11.	Hardness of connector.	HB	
12.	Hardness of keeper.	HB	

13.	Elongation of connector.	%	
14.	Elongation of keeper.	%	
15.	Electrical conductivity of connector.	%	
16.	Electrical conductivity of keeper.	%	
17.	Short Circuit Rating of connector.	kA	
18.	Short Circuit Rating of keeper.	kA	
19.	Material of Nuts & Bolts.		
20.	Tensile Strength of Nuts & Bolts.	Kg/mm ²	
21.	Brinell Hardness of Nuts & Bolts.	HB	
H.	Name Plates		
1.	Whether the data as required is marked/ engraved on the name plates?	Yes/No	
2.	Material of name plate.		
3.	Thickness of name plate.	mm	




SIGNATURE AND STAMP OF MANUFACTURE

- 33 -





NET & BOLT 12mm SIZE FIXED WITH WASHERS 3mm THICKNESS ON BOTH SIDE



VOLTAGE	A
33KV	2320
66KV	3835
132KV	4340



ALL DIMENSIONS ARE IN MILLIMETER

NATIONAL TRANSMISSION AND DISPATCH COMPANY

DESIGN DEPARTMENT

REVISIONS	REVISED ON - 3-9-2012	CHECKED	MAKIMAN	sd	SUPPORTING STEEL STRUCTURE FOR SURGE ARRESTERS	
1. TITLE CHANGED FROM WAPDA TO NTDC	PERVAZ KHAN MANAGER DESIGN S & R	ASSIST. DIRECTOR	MUSAWAR KHAL	sd		
2. ANGLE SIZE OF MAIN & DIAGONAL CHANGED	NAZAR ABBAS C.M. DESIGN NTDC	DEPUTY DIRECTOR	IKRAM-UL-HAQ	sd		
		DIRECTOR	E.A. BAKI	sd		
					SCALE -	DATE - 28-1-1966
					DWG. NO. PDWTS - 3203	

45mm LONG 15mm² MIN. AREA
INSULATED LINE LEAD




NATIONAL TRANSMISSION AND DISPATCH COMPANY

DESIGN
DEPARTMENT

REVISIONS	REVISED ON : 3-9-2012	DRAWN	M. REHMAN	sd	TYPICAL 12KV SURGE ARRESTER	
1. TITLE CHANGED FROM WAPDA TO NTDC	PERVAZ IQBAL MANAGER DESIGN S & R	CHECKED	M.A. KHAN	sd		
2. ADDITION OF POLYMER HOUSING ARRESTER		ASST. DIRECTOR	SHAHID ALI	sd		
		DEPUTY DIRECTOR	IKRAMUL HAQ	sd		
	NAZAR ABBAS G.M. DESIGN NTDC	DIRECTOR	K.A. BAKI	sd	SCALE:- N.T.S.	DATE:- 24-1-1998
					DWG. NO. PDW/TS - 3205	

3.5


FOR MY SWITCH GEAR PANELS




FOR WOOD CROSS ARM 100x125

TWO 10 x 130 CARRIAGE BOLTS.
THREADED SECTION 45 LONG
EACH WITH ONE 10 ROUND WASHER
AND SQUARE NUT.

12 x 40 CARRIAGE BOLT
13 EXTERNAL LOCK WASHER



DETAIL OF PART - (1)




DETAIL OF PART - (2)

ALL DIMENSIONS ARE IN MILLIMETER


NATIONAL TRANSMISSION AND DISPATCH COMPANY			DESIGN DEPARTMENT
DRAWN	HAC MATHEWOOD	MOUNTING ARRANGEMENT FOR 12KV SURGE ARRESTER	SCALE - N.T.S DATE - 3-9-2012 DWG. NO. PDW/TS-7282
CHECKED			
ASST. MANAGER	UMAR AZIZ		
DEPUTY MANAGER	MUHAMMAD ADNAN ZAHR		
MANAGER	MURVAZ IQBAL		
C. M.	NAFAR ADEES		

TOP TERMINAL




FOR RECEIVING STRANDED CONDUCTORS OF 12mm TO 25mm DIA EITHER IN HORIZONTAL OR VERTICAL DIRECTION

BOTTOM TERMINAL



FOR CLAMPING STRANDED COPPER CONDUCTOR OF 10mm TO 15mm



INSULATING BASE





FIG-3




NATIONAL TRANSMISSION AND DISPATCH COMPANY

DESIGN DEPARTMENT

		DRAWN: M.A. REHMAN		sd	33kV AND 66kV SURGE ARRESTER WITH INSULATING BASE		
REVISIONS		REVISED ON :- 3-9-2012		CHECKED: M.A. KHAN			sd
TITLE CHANGED FROM WAPDA TO NTDC	PERVAZ IQBAL MANAGER DESIGN S & R		ASST DIRECTOR	SHAHEED ALTAUF			sd
			DEPUTY DIRECTOR	JUDRAM-BI-JANU			sd
	NAZAR ABBAS C.E. DESIGN NTDC		DIRECTOR	S.A. BAIG	sd	SCALE: >	DATE: 26-01-1996
						DWG. NO. PDW/TS - 3206	

TOP TERMINAL



FOR RECEIVING STRANDED CONDUCTORS OF 12mm TO 32mm DIA EITHER IN HORIZONTAL OR VERTICAL DIRECTION.




INSULATING BASE



4 HOLES FOR 16mm DIA BOLTS

BOTTOM TERMINAL




FOR CLAMPING STRANDED COPPER CONDUCTOR OF 10mm TO 15mm DIA






FIG - 4

NATIONAL TRANSMISSION AND DISPATCH COMPANY						DESIGN DEPARTMENT
REVISIONS	REVISED ON :- 3-9-2012	DRAWN	M.A. ERFMAN	sd	132kV SURGE ARRESTER WITH INSULATING BASE	
		CHECKED	M.A. KHAN	sd		
		ASST. MANAGER	SHAFIQ ALTAF	sd		
		DEPUTY MANAGER	IRFAN-UDDIN	sd		
		MANAGER	R.A. BAK	sd		
TITLE CHANGED FROM WAFDA TO NTDC	PERVAZ IQBAL MANAGER DESIGN S & R				SCALE :	DATE :- 26-1-2006
	NAZAR ABBAS G. M. DESIGN NTDC				DWG. NO. PDW/TS - 3207	



NATIONAL TRANSMISSION AND DISPATCH COMPANY				DESIGN DEPARTMENT
REVISIONS	REVISED ON:- 3-9-2012	CHECKED	A. LATIF	SE
1. TITLE CHANGED FROM WAPDA TO NTDC	PERVAZ IQBAL MANAGER DESIGN S&R	ASST. DIRECTOR	M. ANWAR	SE
		DEPUTY DIRECTOR	CAPT. ZULFIKAR ALI KHAN	SE
	NAZAR ABBAS C.M. DESIGN NTDC	DIRECTOR	M. ASLAM KHALIL	SE
		CHIEF ENGINEER	SHAHID SIDDIQI	
TYPICAL 220KV SURGE ARRESTER WITH INSULATING BASE				SCALE: 1:1
DWG. NO. PDW/DF - 387				DATE: 6-4-1985



DISCRIPTION	A - TOTAL HEIGHT OF SURGE ARRESTER & STEEL STRUCTURE
FOR LINE SURGE ARRESTER	9000 mm
FOR TRANSFORMER SURGE ARRESTER	11000 mm

NOTES :-
 THE SIZE / DIMENSIONS FOR STEEL STRUCTURE ARE FOR GUIDANCE ONLY. THE MANUFACTURER MAY SUPPLY AS PER HIS OWN DESIGN SUBJECT TO APPROVAL BY THE ENGINEER.

NATIONAL TRANSMISSION AND DISPATCH COMPANY			DESIGN DEPARTMENT
DRAWN	GAZ MARIKOO		
CHECKED			
ASST. MANAGER	UMMA AZIZ		
DEPUTY MANAGER	MUHAMMAD AFTAN ZAHID		
MANAGER	PREVAD JORAL		
CLERK	NAZAR ABBAS		
TYPICAL 500kV SURGE ARRESTER WITH SUPPORTING STEEL STRUCTURE			SCALE:- NTS
			DATE:- 3-9-2012
			DWG. NO. PDW/TS - 7283

41

ALUMINUM ALLOY

TYPE DESIGNATION	A	B
OPA	20 - 26	30 - 40
OPH	28 - 32	30 - 40
ONC	30 - 38	30 - 40



NOTES.

1 - ALL DIMENSIONS ARE IN MILLIMETERS.

2 - BODY MANUFACTURED IN ALUMINUM ALLOY.

3 - THIS DRAWING IS FOR GUIDANCE ONLY.

NATIONAL TRANSMISSION AND DISPATCH COMPANY				DESIGN DEPT. (NTDC)	
REVISIONS	REVISED ON: 01-21-2011 PERVAZ EBAL MANAGER DESIGN (SGR)	TRACED I. H. ASGHAR CHECKED SHARAF RASID APPROVED A. HANFEE DESIGNED PERVAZ EBAL DATE 01/21/2011	STRAIGHT MONOMETALLIC CONNECTOR (BOLTED TYPE)		
1 - TITLE CHANGED FROM WAPDA TO NTDC. 2 - TYPE DESIGNATION CHANGED AS OPA, OPH AND ONC.	HAZAD AHMAD CHIEF ENGINEER DESIGN (NTDC)	SCALE H. T. S. DATE DWG. NO. POW/DF - 300(1)			



TYPE DESIGNATION	A	B
QQA	AL 20 - 25	CU 34 - 40
QQH	AL 20 - 32	CU 36 - 40
QBC	AL 30 - 35	CU 38 - 40

1. ALL DIMENSIONS ARE IN MILLIMETERS.
2. BODY MANUFACTURED IN AL-ALLOY AND COPPER ALLOY.
3. THIS DRAWING IS FOR GUIDANCE ONLY.

NATIONAL TRANSMISSION AND DESPATCH COMPANY DESIGN DEPT-NTDC

REVISIONS	REVISED ON: 01-07-2009	DRAWN	S.M. ASGHAR	IN CHARGE	STRIGHT BIMETALLIC CONNECTOR (BOLTED TYPE)
1. TYPE CHANGED FROM WAPDA TO NTDC.	PERVAZ KHALIL MANAGER DESIGN IS & EO	CHECKED	GHULAM BASIR	Manager	
2. TYPE DESIGNATION CHANGED AS QQA, QQH & QBC.	HAJARI ANWAR CHIEF ENGINEER DESIGN DIVISION	APPROVED	A. HAMEED	Manager	
		DESIGNER	ABDUL RAUF	Manager	
		CHECKER	AJLAZI	Manager	
		CHIEF ENGINEER	JAVED AHMAD	Manager	
					SCALE:- HT.S DATE: 09-6-1990
					DWG: NO. POW/DF 308

Payment (GCC Clause 19)

The method and conditions of payment to be made to the Supplier under this Contract shall be as follows:

Payment for Goods supplied from abroad:

- A) payment will be made by the Finance Director IESCO Islamabad on production of the following documents:**
- a) Bill in triplicate mentioning clearly NTN No. & GST No.
 - b) Delivery Challan and GRN duly stamped and signed by the consignee (in original).
 - c) Warranty Certificate.
 - d) General Sales Tax Invoice.
 - e) Inspection Certificates
 - f) Certificate from Chief Engineer (Development) IESCO Islamabad regarding acceptance of Performance Bond.
 - g) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
 - h) Custom clearance certificate
 - j) Certificate issued from consignee store Manager that materials received vide GRN No. ___ dated ___ has been taken on stock against stock code No. ___
 - k) The payment of General Sales Tax, fixed by the Government, shall be made to the firm on production of General Sales Tax return cum payment Challan
 - l) Advance payment is not applicable.
 - L IESCO local committee certificate

OR

- B) Finance Director IESCO will establish a confirmed and irrevocable Letter of Credit for Rs. _____/- through any nationalized bank of Pakistan in your favor. All charges relating to opening of Letter of Credit and negotiation thereon, shall be borne by contractor. The amount of material excluding General Sales Tax i.e. Rs. _____/- in the Letter of Credit shall be available for negotiation and en-cashable on submission of following documents: -**
- i) Bill in triplicate mentioning clearly NTN No. & GST No.
 - ii) Delivery Challan and GRN duly stamped and signed by the consignee
 - iii) Warranty certificate
 - iv) Inspection certificate from Nominated Inspector
 - v) Certificate issued by the Chief Engineer (Development), IESCO Islamabad regarding acceptance of Performance Bond.
 - vi) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
 - vii) General Sales Tax Invoice.
 - viii) Certificate issued from consignee store Manager that materials received vide GRN No. ___ dated ___ has been taken on stock against stock code No. ___

- ix) The payment of amount of 17% General Sales Tax i.e. Rs. _____/- in the Letter of Credit shall be available for negotiation and en-cashable on production of General Sales Tax invoice and General Sales Tax return cum payment Challan, as envisaged in Payment.
- x) Advance payment is not applicable.

The method and conditions of payment to be made to the Supplier under this Contract shall be as follows:

Payment for Goods and Services supplied from within Pakistan:

A) 100% payment will be made by the Finance Director IESCO Islamabad on production of the following documents:

- a) Bill in triplicate mentioning clearly NTN No. & GST No.
- b) Delivery Challan and GRN duly stamped and signed by the consignee (in original).
- c) Warranty Certificate.
- d) General Sales Tax Invoice.
- e) Inspection Certificates
- f) Certificate from Chief Engineer (Development) IESCO Islamabad regarding acceptance of Performance Bond.
- g) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
- h) Custom clearance certificate
- j) Certificate issued from consignee store Manager that materials received vide GRN No. ___ dated ___ has been taken on stock against stock code No. ___
- k) The payment of General Sales Tax, fixed by the Government, shall be made to the firm on production of General Sales Tax return cum payment Challan
- l) Advance payment is not applicable.

OR

B) Finance Director IESCO will establish a confirmed and irrevocable Letter of Credit for Rs. _____/- through any nationalized bank of Pakistan in your favor. All charges relating to opening of Letter of Credit and negotiation thereon shall be borne by contractor. The amount of material excluding General Sales Tax i.e., Rs. _____/- in the Letter of Credit shall be available for negotiation and en-cashable on submission of following documents: -

- i) Bill in triplicate mentioning clearly NTN No. & GST No.
- ii) Delivery Challan and GRN duly stamped and signed by the consignee
- iii) Warranty certificate
- iv) Inspection certificate from Nominated Inspector
- v) Certificate issued by the Chief Engineer (Development), IESCO Islamabad regarding acceptance of Performance Bond.

- vi) Certificate from Excise & Taxation Department, certifying the fact that all payable professional taxes have been cleared by the supplier.
- vii) General Sales Tax Invoice.
- viii) Certificate issued from consignee store Manager that materials received vide GRN No. ____ dated ____ has been taken on stock against stock code No. ____
- ix) The payment of amount of 17% General Sales Tax i.e., Rs. _____/- in the Letter of Credit shall be available for negotiation and en-cashable on production of General Sales Tax invoice and General Sales Tax return cum payment Challan, as envisaged in Payment.
- x) Advance payment is not applicable.



Past Experience / Contracts

Contracts over <i>[insert amount]</i> during the last three years:				
Procuring Agency	Value	Year	Goods/Services Supplied	Country of Destination



Historical Contract Non-Performance, and Pending Litigation and Litigation History

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

☐ Not debarred due to deviation from commitment of Bid Securing Declaration- ☐ Not debarred due to non-performance			
Year	Non-performed portion of contract	Contract Identification	Total Contract Amount (current value, currency, exchange rate and PKR equivalent)
<i>[insert year]</i>	<i>[insert amount and percentage]</i>	Contract Identification: <i>[indicate complete contract name/ number, and any other identification]</i> Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Reason(s) for nonperformance: <i>[indicate main reason(s)]</i>	<i>[insert amount]</i>
Pending Litigation, in accordance with Section III, Qualification Criteria and Requirements			
☐ Pending litigation in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.3 as indicated below.			
Year of dispute	Amount in dispute (currency)	Contract Identification	Total Contract Amount (currency), US\$ PKR Equivalent (exchange rate)

<i>[insert year]</i>	<i>[insert amount]</i>	Contract Identification: [indicate complete contract name, number, and any other identification] Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Matter in dispute: <i>[indicate main issues in dispute]</i> Party who initiated the dispute: <i>[indicate "Procuring Agency" or "Supplier"]</i> Status of dispute: <i>[Indicate if it is being treated by the Adjudicator, under Arbitration or being dealt with by the Judiciary]</i>	<i>[insert amount]</i>
☐ No consistent history of court/arbitral award decisions in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.4. ☐ Consistent history of court/arbitral award decisions in accordance with Section III, Qualification Criteria and Requirements, Sub-Factor 2.4 as indicated below.			
Year of award	Outcome as percentage of Net Worth	Contract Identification	Total Contract Amount (currency), PKR Equivalent (exchange rate)
<i>[insert year]</i>	<i>[insert percentage]</i>	Contract Identification: [indicate complete contract name, number, and any other identification] Name of Procuring Agency: <i>[insert full name]</i> Address of Procuring Agency: <i>[insert street/city/country]</i> Matter in dispute: <i>[indicate main issues in dispute]</i> Party who initiated the dispute: <i>[indicate "Procuring Agency" or "Supplier"]</i> Court/ arbitral award decision: <i>[Indicate if the award decision was against the Applicant or any member of a joint venture.]y]</i>	<i>[insert amount]</i>

Current Contract Commitments / Works in Progress

Bidders and each member to a JV should provide information on their current commitments on all contracts that have been awarded, or for which a letter of intent or acceptance has been received, or for contracts approaching completion, but for which an unqualified, full completion certificate has yet to be issued.

Current Contract Commitments					
No.	Name of Contract	Employer's Contact Address, Tel, Fax	Value of Outstanding Work [Current Eq. PKR]	Estimated Completion Date	Average Monthly Invoicing Over Last Six Months [Eq. PKR/month]
1					
2					
3					
4					
5					

Financial Situation and Performance

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

1. Financial data

Type of Financial information in (currency)	Historic information for previous <i>[insert number]</i> years, <i>[insert in words]</i> (amount in currency, currency, exchange rate*, PKR equivalent)				
	Year 1	Year 2	Year 3		
Statement of Financial Position (Information from Balance Sheet)					
Total Assets (TA)					
Total Liabilities (TL)					
Total Equity/Net Worth (NW)					
Current Assets (CA)					
Current Liabilities (CL)					
Working Capital (WC)					
Information from Income Statement					
Total Revenue (TR)					
Profits Before Taxes (PBT)					
Cash Flow Information					
Cash Flow from Operating Activities					

* Refer ITA 14 for the exchange rate

3. Financial documents

The Applicant and in case of JV, members of JV shall provide copies of financial statements for *[number]* years pursuant Section III, Qualifications Criteria and Requirements. The financial statements shall:

- (a) reflect the financial situation of the Applicant or in case of JV member, and not an affiliated entity (such as parent company or group member).
 - (b) be independently audited or certified in accordance with local legislation.
 - (c) be complete, including all notes to the financial statements.
 - (d) correspond to accounting periods already completed and audited.
- ☐ Attached are copies of financial statements¹ for the *[number]* years required above; and complying with the requirements.

¹ If the most recent set of financial statements is for a period earlier than 12 months from the date of Application, the reason for this should be justified.

Average Annual Turnover (Annual Sales Value)

[The following table shall be filled in for the Applicant and for each member of a Joint Venture]

Applicant's Name: *[insert full name]*

Date: *[insert day, month, year]*

Joint Venture Member Name: *[insert full name]*

IFP No. and title: *[insert IFP number and title]*

Page *[insert page number]* of *[insert total number]* pages

Annual Turnover Data			
Year	Amount Currency	Exchange rate* (If applicable)	PKR equivalent
<i>[indicate calendar year]</i>	<i>[insert amount and indicate currency]</i>		
		Average Annual Turnover **	

* Refer ITA for date and source of exchange rate.

** Total PKR equivalent for all years divided by the total number of years. See Section III, Qualification Criteria and Requirements, ITA.