



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RC-9990AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018204

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provsn and installation of Signage and Fascia Structures at NVROS of Sahiwal division(PM MODULE)

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Blue Bars and Signage Misc At Sahiwal</u>	<u>PSO House</u>				
1.01	<u>Aluco Bond/ Panaflex/Blue Bar</u> Repasting of old blue bars with Avery or 3M blue vinyl. Job includes removal of old/faded vinyl, cleaning of acrylic sheet and pasting of new blue vinyl of PSO approved specification. Note: Above rates are inclusive of PST 16%, labor & transportation charges. Unit of measurement is Running feet, EA=RFT.		<u>EA</u>	500		
1.02	<u>CANOPY FASCIA</u> Provision and installation of canopy signage supporting structure MS Frame of 16 SWG 3/4"x3/4" Square pipe with 1.5"x3/4" square pipe. Job also includes removal of fascia signage with existing supporting structure and re-installation of canopy fascia signage after fixing of new frame. Unit of measurement is Running feet, SFT=RFT. Note: Above rates are inclusive of PST 16%, labor & transportation charges.		<u>SFT</u>	1,180		
1.03	<u>SUPPLY & INSTALLATION OF CANOPY FASCIA L</u> Provision and installation of L channel structure as per PSO approved design and specification. Unit of Measurement is Running feet, EA=RFT. Note: Above rates are inclusive of PST 16%, Labor & transportation charges		<u>EA</u>	1,180		
1.04	<u>SUPPLY & INSTALLATION OF CANOPY FASCIA A</u> Provision and installation of Z channel structure as per PSO approved design and specification. Unit of Measurement is Running feet, SFT=RFT. Note: Above rates are inclusive of PST 16%, Labor & transportation charges.		<u>SFT</u>	1,180		
1.05	<u>Supply and Installation of Blue Bar</u> New Acrylic Blue bars-5mm, fitted with blue vinyl (3M 3630 VT 1986/Avery CC 5500-763. Unit of measurement is Running feet, FT=RFT. Note: Above rates are inclusive of PST 16%, Labor & transportation charges.		<u>FT</u>	250		
	TERMS & CONDITIONS:					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RC-9990AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018204

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provsn and installation of Signage and Fascia Structures at NVROS of Sahiwal division(PM MODULE)

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	1) All labour, tools, material and transportation to be provided by the contractor. 2) Payment will be made as per actual work done. 3) All HSE standards to be followed by the contractor. 4) Job is subject to inspection and verification of divisional Engineer 5) Work should be completed within 50 days of issuance of work order 6) Contractor will be responsible for the removal / disposal of debris outside retail outlet premises as per the instruction of the engineer incharge 7)<(>,<)>Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. 8) The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment, undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves, Helmets, Googles, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. 9)The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 10)All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 11)<(>,<)>Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. 12)<(>,<)>Wherever applicable, contractor is bound to engage certified / licensed electrician for electrical works. 13)<(>,<)>Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm, etc.). For any special case, approval from DE will be required and work will be performed under supervision of DE. 14)<(>,<)>The contractor					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RC-9990AM	
DATE	14.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018204

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

29.09.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Provsion and installation of Signage and Fascia Structures at NVROS of Sahiwal division(PM MODULE)

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 15)<(,>,<)>The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in #no smoking# area, etc) during work. Contractors will also ensure proper work planning and risk assessment prior to start of work. 16)<(,>,<)>The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 17)<(,>,<)>The contractor shall indemnify PSO, its offices, employees, agents and representatives from and against all losses, costs, penalties, fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by this contract. 18)<(,>,<)>Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO. 19) All rates are Inclusive of All Kinds of Taxes **All the work done and task completed within 30 days, after the issuance of Service Order**					