

B.O.Q (Lot-1)

REGARDING CONSTRUCTION OF APPROACH ROAD AROUND 3 Nos. GRIDS AT 132KV GRID STATIONS BODHOMALHI, KOT AGHA & PASRUR.

Sr. No.	Description of Items	Unit	Quantity	Rate	Amount
LOT-1					
1	Site Clearance	job	3.00	50000.00	150000.00
2	Cement concrete plain including placing compacting finishing and curing complete (Including screening and washing of stone aggregate) without shuttering. 1:4:8	cum	45.91	9748.54	447555.47
3	PCC 1:2:4	cum	460.56	12264.08	5648344.68
4	Pacca brick work in F/P in 1:6:	sqm	32.38	12418.97	402126.25
5	Filling Watering and ramming earth under floors with new earth (excavation from outside) lead upto 30 m and lift upto 1.5 m	cum	363.54	373.76	135876.71
6	Carage of earth lead up to 5 K.M Same quantity as item no.5	cum	363.54	335.59	122000.39
7	Providing and fixing WAPDA monogram on the main entry gate of G/station prepared from 16 gauge MS sheet.	each	3.00	2722.64	8167.92
Total Amount (Rs.)					6914071.42
AS PER WCSR 2022 VIDE.NO G.M (C&M) W/DR-13/835-42 DATED 09/08/2023,(inflation factor @ 43.76%)					3025597.66
G.Total Amount (Rs.)					9939669.08
say (Rs.)					9939669.00

✓

ABD-2

SUB
Engineer
Civil