

BOQ REPAIR & MAINTENANCE OF GSO COMPLEX BUILDING / OFFICES GEPCO GUJRANWALA.

Sr. No.	Description	UNIT	Qty	Rate	Amount
1	Providing & laying flooring comprising of first class Granite glazed tiles 24 x 24 (Master / Full Body) (as per approved by the Engineer Incharge)	Sqm	380.00	468.00	177,840.00
2	Providing & Fixing False ceiling comprising iron L & T section and gypsum board complete in all respect	Sqm	170.00	1569.09	266,745.30
3	Glazed tiles dado 6mm thick jointed in white cement & laid over 1 :2 cement sand mortar 20mm thick including finishing:	Sqm	160.00	3854.65	616,744.00
4	providing & laying painting weather shield paint on painted/old surface, 2 coats	Sqm	1999.32	248.10	496,031.29
5	Distempering 2-coats	Sqm	1660.98	150.30	249,645.29
6	Providing & fixing plastic wall penalling complete in all respect (marfex extreme quality)	Sqm	122.55	79.80	9,779.49
7	Making & fixing Almirah including R.C.C slab	Sqm	16.34	9152.94	149,559.04
8	Marble Flooring 3/4"(19mm) thick P 22-10/397	Sqm	17.95	4788.00	85,944.60
9	(i) Providing & fixing of bent metal 16 SWG frame 345mm wide for door size 915mm x 2.134m (3' x 7') complete in all respect (ii) Providing & fixing aluminum natural anodized openable hingd doors including glazing with plate glass 6mm thick using PVC gasket	Each	22278.00	6.00	133,668.00
10	aluminum door repairing	job	11.11	40000.00	444,400.00
11	Pacca bricks work at 1st floor (including striking of joints) in Cement sand mortar. 1:	Cum	7.07	11728.35	82,919.43
12	Cement concrete R.C.C (1:2:4)	Cum	0.50	24312.54	12,156.27
13	Cement plaster : 13mm thick. 1:4	Sqm	21.84	378.50	8,266.44
14	Cement concrete plain including placing compacting finishing and curing complete (Including screening and washing of stone aggregate) without shuttering. 1:4:8	Cum	0.38	9748.54	3,704.45
15	P/L Flooring comprising of white glazed tiles 6mm thick laid in white cement mortar 1:2 over 20mm thick cement mortar 1:2 complete	Sqm	4.18	3451.70	14,428.11
16	Dismantling of Bricks work in cement mortar	Cum	0.75	1661.61	1,246.21
17	P/L White Glazed tiles dado 6mm thick jointed in white cement & laid over 1:2 cement sand mortar 20mm thick including finishing:	Sqm	11.15	3664.07	40,854.38
18	Providing, laying, jointing & testing heavy water or steam quality G.I or W.I pipes & specials inside buildings & trenches.25 mm	meter	22.50	755.59	17,000.78
19	Providing laying into trenches jointing & testing PVC class "B" pipe line with specials for internal. 100 mm	meter	60.00	1661.60	99,696.00
20	Providing & fixing glazed earthen ware Water closet squatting type domestic Indian pattern of best quality	Each	3.00	4910.70	14,732.10
21	Providing & fixing P.Trap	Each	6.00	521.77	3,130.62
22	Providing & fixing low level flushing cistern 13.5 litres capacity best quality.	Each	3.00	3171.79	9,515.37
23	Providing & fixing floor Trap 100mm X 50mm (i/c 50mm concrete chamber all round) with C.I grating.	Each	3.00	781.25	2,343.75

24	Providing & fixing Chromium plated mixing valves.	Each	3.00	2590.44	7,771.32
25	Providing & fixing Waste pipe for wash hand basin 32mm Ø PVC	Each	3.00	175.45	526.35
26	Providing & fixing C.P. waste coupling: 32 mm Ø	Each	4.00	508.29	2,033.16
27	Providing & fixing PVC flushing bend: 32mm Ø	Each	4.00	174.45	697.80
28	Providing & fixing Looking glass 560mm X 405mm size 1st quality Pak made	Each	3.00	1226.50	3,679.50
29	Providing & fixing Chromium plated stop cocks 13mm	Each	6.00	769.51	4,617.06
30	Providing & fixing white glazed earthen ware Wash hand basin 55 / 56 CM with Pedestal domestic of supreme quality complete with all accessories	Each	3.00	4525.46	13,576.38
31	Providing & fixing Chromium plated bib tap 13mm	Each	3.00	824.28	2,472.84
32	Providing & fixing Chromium plated Pillar cocks 13mm dia	Each	3.00	855.88	2,567.64
33	Providing and fixing of Exhaust fan 305mm (12") dia Plastic body best quality (i.e. Royal, GFC, Pak etc)	Each	3.00	3970.94	11,912.82
34	Wiring light or fan point with 1/1.13 (3/0.029) PVC insulated wire in 20mm (3/4"), 1.50mm thick PVC conduit recessed in the wall or column complete with switch, plastic plate, ceiling rose / button holder.	NO	4.00	2191.34	8,765.36
35	Providing & fixing fiber glass door (PVC) complet in all respect (Market Rate)	Sqm	30.00	752.00	22,560.00
36	Providing & fixing of PVC DOOR	job	2.00	70000.00	140,000.00
37	Providing & fixing Plastic bath accessories set complete in all respect	Each	3.00	3300.00	9,900.00
				TOTAL	6,605,329.00


LeB Engineer
Civil (Rso)


EXECUTIVE ENGINEER
SS&T/ DIVISION GEPCO
GUJRANWALA