



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RC-20028SJ	
DATE	17.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018288

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Signage Works at CF and DFA Sites - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Canopy Fascia Works</u>	<u>PSO House</u>				
1.01	<u>Signage Miscellaneous</u> CANOPY FASCIA ACM CANOPY FASCIA (ALUMINUM COMPOSITE MATERIAL) Installation of existing ACM sheet (provided by PSO) with new frame. Job includes bending, cutting where required, workmanship complete in all respect. The job also includes: Providing and installation of MS structure 18 SWG 3/4" square pipe with White oil paint ICI/Burger for proper fixing of ACM sheets as per PSO approved design. Providing and installation of fascia GI top sheets 24 SWG as per PSO approved standard. Providing and installation Aluminium section Z and L as per PSO approved design and specification. Providing service for removal of old fascia from site complete in all respects as per site requirement. Note: Quoted item rates are based on old materials scrap value included. Unit: RFT		<u>JOB</u>	1,080		
1.02	<u>Aluco Bond/ Panaflex/Blue Bar</u> ACRYLIC LIGHT BAR (BLUE BAR) Providing and Installation of Acrylic / Perspex light bar in 5mm thick Acrylic / Perspex sheet. The light bar is to be moulded to shape as per attached sketch (PSO Dwg No: S-006 Rev:5 dated 5th May 2017) and fitted with Philips/Equivalent LED tube lights up to 14 Watts. 3M film i.e. 3M (3630 VT 1986) /Avery CC (5500-763 Blue)/Equivalent should be applied by a qualified and approved converters / applicator. Joint of adjacent two acrylic bars to be covered with same material. Warranty 5 Years. The job includes all necessary electric works with Pakistan Cables. Back Sheet of LED T/L, Cable Connector, insulated with silicon etc as per PSO approved specifications.		<u>EA</u>	1,080		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RC-20028SJ	
DATE	17.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018288

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Signage Works at CF and DFA Sites - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Unit: RFT,, TERMS AND CONDITIONS: - Contractor will be responsible for the removal / disposal of debris outside retail outlet premises as per the instruction of the engineer incharge - Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. - The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment, undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves, Helmets, Goggles, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. - The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. - All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. - Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. - Wherever applicable, contractor is bound to engage certified / licensed electrician for electrical works. - Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm, etc.). For any special case, approval from DE will be required and work will be performed under supervision					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RC-20028SJ	
DATE	17.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018288

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

07.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Signage Works at CF and DFA Sites - Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	of DE. 9.The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 10.The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in #no smoking# area, etc) during work. Contractors will also ensure proper work planning and risk assessment prior to start of work. 11.The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contracto shall keep PSO absolutely indemnified and free from such responsibility. 12.The contractor shall indemnify PSO, its offices, employees, agents and representatives from and against all losses, costs, penalties, fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated bythis contract. 13.Contractors shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO.					