



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet,False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>M&R Works at NVR0s QA-2228</u>	<u>PSO House</u>				
1.01	<u>22 SWG CGI SHEET FOR CANOPY ROOF</u> Replacement of Canopy Top Sheets Job includes removal of old canopy top GI Sheets and providing, fabrication and fixing of corrugated G.I. continuous sheet, 22 SWG (at least 30-micron powder coated) including overlaps, crown and edge elements, expansion joints and making openings. Also included are fixings such as galvanized steel J -bolts, nuts and washer or self-screw as per site requirement. Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Bending sharing of sheet should be as per automatic machine. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft. 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material.		<u>SET</u>	3,000		
1.02	<u>16 SWG GI SHEET, GUTTER & CLADDING</u> Providing Fabricating and fixing in position on existing structure,16 SWG plain GI Sheet drain water channel including self-tapping screw or galvanized M S J-Bolts, Rubber washer(>,<)> Cup washer and Nuts etc. Joining each other rivet and Silicon filing in joins, making opening for drainage and fixing UPVC drain cover. Note:		<u>SET</u>	350		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet, False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises. 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft. 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material. 22 SWG CGI SHEET FOR CANOPY ROOF		SET	420		
1.04	Providing and Laying of 22 Swg(at least 30 micron powder coated) Plain top sheet on fascia complete in all respects. Note: 1- Contractor will be responsible for the removal / disposal of debris outside retail outlet premises. 2- Overlapping is not payable which will be approximately 6" to 9" on either side of sheeting as per engineer incharge instruction. Payment shall be made only for actual measurable surface areas. Crown will be measured with roof sheeting in Sq.ft 3- Cost of Item = Cost of new material - Cost of old scrapped /removed material. P/L UPVC PIPE 4" DIA, CLASS-D		RET	400		
1.05	Providing and Installing 4" Dia(<,>) local made UPVC drain pipe complete with all fitting as per site requirements hanged with MS hanger/support for drainage of Rain water, job also includes complete with cutting, jointing, (<&>) wastage etc. Complete in all respect. Water Proofing		SET	3,000		
	Providing services for high elastomeric water proofing of canopy top sheet after complete replacement. providing and applying of two coats of sealing flex after complete cleaning and removal of dust from the sheet and apply two coats. Sealing flex is water based modified acrylic / synthetic rubber emulsion.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet,False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	Job also includes complete sealing of the holes and opening and ensure proper workmanship. Brand: Ultra Seal flex or approved equivalent. Unit of measurement is SFT. <u>INSTALLATION FALSE CEILING</u> "Replacement of False Ceiling Providing and fixing false ceiling under canopy with 4"" wide 26 SWG pre-painted (white color) steel sheet strips with no perforations and maximum length of 12 ft. hinges, bolts and all necessary fittings including soffit return of 14 swg for false ceiling finish of approved shades to be suspended with metal adjustable suspension system as per standard. Complete In all respect as per direction of engineer incharge. Dismantling and stacking of old False Ceiling at site is also included in the give rates. Job also includes removal and re-installation of canopy lights with wiring including installation of additional canopy lights. Additional canopy Lights to be provided by PSO. Job further includes removal and installation of canopy fascia (If required) blue bars, rewiring of blue bars arrangement, etc. complete in all respect while execution of work." UNit: SFT		SET	3,000		
1.07	<u>Carwash Tiles</u> Providing and fixing of porcelain tiles-first class make: Master/Shabbir or approved equivalent (Matt finished/Glazed), Size and color of tile to be communicated by PSO as per PSO approved standards & specifications on walls in cement slurry and cement concrete bed at any level of approved size including cost of all material, labor and equipment, grouting etc. complete in all respect. Job also includes Dismantling/cutting/excavation of existing tiles surface, removal/shifting of debris outside the retail outlets premises		SET	2,000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet, False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	complete as per the directions and satisfaction divisional engineer.					
1.08	Note: Prior approval of sample of tiles for size, color and design from PSO is mandatory before execution of work WALL LIGHT (WATER PROOF)		EA	12		
1.09	PSO is mandatory before execution of work PROVIDING <(>&<)> FIXING WATER PROOF LIGHTS ON WALL (PLEASE REFER RC ELECTRIC SPECIFICATION SHEET) Civil Work Miscellaneous		RET	1		
1.10	Car Wash Grating: Providing services for fabrication, welding, grinding, fixing of MS grill having 1/4" thickness for drainage of service station complete by using structural steel, flat bar, angle iron complete in all respects as per site requirement. Civil Miscellaneous		SET	600		
1.11	CEMENT PLASTER WORKS Providing and applying cement plaster 3/4" to 1" thick in 1:4 cement mortar to wall. Job Includes chipping off loose Material where require , roughing / rubbing the surface, and cement slurry to all surfaces i.e. curing and including scaffolding. Also including heavy duty metal Lethe strip Nailed at the joints of masonry and concrete structure wherever necessary; complete as per the directions of Engineer Incharge (unit square feet). Exterior Paint Weather Shield: Scrapping cleaning making minor repairs and glass papering, filling the putty in cavities to make the surface even and smooth~ applying two coats of approved paint ICI weather shield Sky Grey No 3160 or approved equivalent on sales room outside and boundary wall. CC Flooring (3" thick)		SET	1,500		
1.12	Providing services for repairing works of CC floor upto 3-4" thickness in the ratio of 1:2:4 Job includes cutting, dismantling, CC flooring, curing of CC floor at different location of outlets, job also includes removal of garbage from site complete in all respects. Unit of Measure is SFT. 12"X12" PORCELAIN TILE		M2	150		
1.13	Prov.Fix of Manhole Cover		EA	4		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet, False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.14	Manhole Covers: Providing and fixing of heavy duty MS 10mm Manhole covers, different Size as per site requirement and satisfaction of Engineer incharge. Job includes: - Removal of old/damaged Manhole covers. - Making Angle support for fixing manholes - fixing handling bars on top of manhole covers for safe removal/fixing for cleaning purposes. - CC repair works required for allied works. - Repair of Manholes before fixing of manhole covers. Miscellaneous		EA	1		
1.15	Providing and fixing of UPVC door with frame, as per PSO approved specs for Carwash compressor room. Job also includes necessary preparation works, installation of door locks, hinges, etc, complete in all respect. Size: 3x7 ft or as per site requirement. Prov. of Car wash Safety Items Providing and fixing / installation of Rubber Guard on car wash Pillars Specification : Item: Rubber Guard Material of construction: High impact resistant natural and synthetic rubber with molded reflective tape for proper visibility with one piece construction Size: 30 inch length per piece width 4 inch on each side Fixing Method: To be fixed using SS screws + adhesive solutions / construction adhesive Scope Includes: - Marking correct height on pillar - Drilling holes for screws - Applying Samad Bond on rubber guard - Fixing with screws for permanent hold - Cleaning after installation Providing and fixing / installation of wheel stopper 02 nos on car wash floor Item: Wheel Stopper Fixing Method: To be fixed using Rawal Bolts Size: 23.5 inch length per piece width 4.5 inch, height 4 inch Bolt Specification: 4 inch length, 10mm diameter, material ss Scope Includes: - Marking position of wheel stoppers as per layout - Drilling in floor for rawal bolts - Fixing wheel stoppers with 4" x 10mm rawal bolts - Tightening & alignment check General Notes All material to be provided as per approved sample Site to be cleaned after work completion Installation to be done without damaging existing structure/flooring		EA	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet,False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	TERMS AND CONDITIONS: 1., Contractor will be responsible for the removal / disposal Of debris outside retail outlet premises as per the instruction of the engineer incharge 2.<(>,<)>Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. 3.<(>,<)>The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment<(>,<)> undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves<(>,<)> Helmets, Goggles, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. 4.<(>,<)>The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 5.<(>,<)>All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 6.<(>,<)>Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. 7.<(>,<)>Wherever applicable, contractor is bound to engage certified / licensed electrician for electrical works. 8.<(>,<)>Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall<(>,<)> thunderstorm, etc.). For any special case, approval from DE					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018367

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Replacement of Canopy Top Sheet,False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	will be required and work will be performed under supervision of DE. 9.<(>,<)>The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 10.<(>,<)>The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in #no smoking# area, etc) during work. Contractors will also ensure proper work planning and risk assessment prior to start of work. 11.<(>,<)>The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 12.<(>,<)>The contractor shall indemnify PSO, its offices<(>,<)> employees, agents and representatives from and against all losses, costs, penalties, fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by this contract. 13.<(>,<)>Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO. 14.<(>,<)> All material, tools, labor, etc. to be provided by the Contractor. 15.<(>,<)>Quoted rates are inclusive scrap materials. 16.All material, tools, labor, etc to be provided by the Contractor.					



8	OF	8
RFQ No	CS20042SI	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018367

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	08.10.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: Providing Services for Replacement of Canopy Top Sheet,False Ceiling and Carwash Renovation at New Aero(CF)-Karachi Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	17.The rates are inclusive of all Govt. taxes, transportation<(>,<)> loading/unloading, labor, etc 18.The payment is subject to inspection / satisfaction of Engineer Incharge. 19.Work completion time is 45 days after site handed over to vendor 20. It is mandatory that the Contractor must visit the Site in order to understand / ascertain scope of work and site conditions prior to quoting rates in Tender. 21. Quantity may be use in other outlets as per instruction of divisional engineer. 22- All scrap material old GI sheet, drain channel etc, debris to shift/dispose off from outlets is contractor responsibility.					