



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	4
RFQ No	AM-20056AM	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018366

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

09.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Miscellaneous civil works required for placement of PFI Panel.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Miscellaneous Steel structure</u> Providing and laying Deformed Grade 60 reinforcement bars including cost of straightening, cutting, bending, binding, wastage, transportation and such overlap which are not shown in Drawings, placing in position on 1:4 CM spacer's block and in m.s chairs,tying with galvanized bindings wires including the cost of chairs & wire etc., in all kinds of RCC work in foundation, basement, plinth, column, slab etc. complete.at any floor at any height as directed by the Engineer in charge. Steel Reinforment= Razzak/Amreli.	<u>Karachi</u> <u>(Aviation)</u>	<u>KG</u>	720.000		
2	<u>Service 0010</u>	<u>PSO House</u>				
2.01	<u>Demolition Work (JOB)</u> - Removal of all asbestos sheets required. Their disposal shall be the responsibility of the vendor. - The removal works shall be directed by the Engineer in charge, and it is not limited to the aforementioned tasks.		<u>JOB</u>	1		
2.02	<u>Dismantling</u> Dismantling cement concrete block masonry work in cement mortar in foundation, basement, plinth and in any floor at any height including stacking the salvaged material (serviceable) and disposal of surplus material out of PSO premises as directed by the ngeiner-in-charge. It should be noted that only debris will be disposed or in accordance with engineer directives.		<u>M3</u>	42.000		
2.03	<u>Excavation</u> Excavation for foundation all kinds of soil and in hard rock including back filling the excavated material in foundation, plinth or under floor with breaking clods, levelling, dressing, watering and consolidation by ramming in layers not exceeding 9" in epth to full compaction with hand roller or by manual means as required and disposal of surplus excavated stuff as directed. including the cost of dewatering etc.as required.		<u>M3</u>	12.000		
2.04	<u>Providing and laying stone soling</u> Supplying, stacking, spreading and filling stones of required size to required depth from approved quarries in plinth or under floor and consolidation by ramming layers not exceeding 9 inches in depth to full compaction with hand roller or by manual mean as directed by the		<u>M3</u>	4.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	4
RFQ No	AM-20056AM	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018366

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

09.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Miscellaneous civil works required for placement of PFI Panel.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.05	Engineer in charge. PCC 1:4:8 Providing and laying 1:4:8 C.C bed in foundation, under floor using graded crush 3/4" & down gauge with levelling and ramming, finishing and curing etc. complete. O.P.C/S.R= Pakland/Falcon/ Lucky.		M3	1.000		
2.06	PCC 1:3:6 Providing laying 1:3:6 cement concrete block masonry using approved machine made block for non load bearing walls 4" to 6" thick graded screened bajri 3/4" & down gauge set in 1:4 c.m including scaffolding <(>,<)> raking out joints & curing etc. completeat any height any floor as directed by the Engineer in charge. O.P.C= Pakland/Falcon/ Lucky<(>,<)> Blocks=Machine made.		M3	10.000		
2.07	Laying of R.C.C 1:2:4 Providing and laying 1:2:4 Reinforced cement concrete floor using crush graded aggregate 3/4 " and down gauge as per specification as in floors, slabs with smooth finish including fair face form work and its removal compaction, levelling, steel trowl finshing and curing etc. complete at any height any floor as directed by the Engineer-in-Charge but excluding the cost of reinforcement. O.P.C= Pakland/Falcon/ Lucky		M3	12.000		
2.08	Providing and applying Paint Providing and applying Two coats of of Renewal Matt finish paint of approved make ICI, BURGER and shade including surface preparation by sand papering dusting and using filling materials putty for filling the cracks, holes and inequalities if on plaster<(><<)>><(>,<)> wood<(>,<)> iron surface including scaffolding at any height any floor as directed by the Engineer in charge. Above 6 feet height & upto 40') Matt Finish= ICI/Burger.		M2	135		
2.09	Associated Civil Works Electrical - Associated electrical works required after completing civil works. - The scope of work includes conduiting and cable laying for electrical equipment such as lights, AC, and the like. - Install dedicated circuits/switch boards for appliances. - Any additional work shall have to be completed as per the location engineer along with the supply of material.		JOB	1		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	4
RFQ No	AM-20056AM	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018366

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

09.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Miscellaneous civil works required for placement of PFI Panel.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Terms and Conditions 1) All labour, tools, tackles and material to be provided by the contractor. 2) All HSE/Security Standards to be followed by the Contractor. 3) Contractor will provide adequate and fully functional Personal Protective Equipment to all its workers including Safety Shoes, Hard Hat, Safety Goggles, Gloves, Face masks, life lines and Safety Harnesses depending upon the nature and requirement of job and ensure their proper usage as per requirement and instructions of the Site In-charge. 4) All direct / indirect cost of material, labour, transportation required to carry out the activity is included in this item. 5) Contractor to provide third party fitness certificates from a reputable third-party inspection firm for all the equipment to be used for execution of work including but not limited to lifting equipment, safety harness, safety equipment etc. complete in all respects. 6) Acceptance of the equipment / materials is subjected to inspection by PSO representatives. 7) Contractor shall be responsible to rectify any damage occurred to PSO property during execution of work without charging any cost to PSO. 8) Contractor will utilize skilled manpower for the execution of complete Project. Manpower should be provided with required PPEs, overalls, and identification by the contractor. Contractor is also responsible for providing all Third Party Certified Too Equipment required to execute the complete Job / Project is the sole responsibility of the Contractor. 9) Scope of work and/or Quantity(is) of any items can be changed according to requirement of PSO. All scope changes will follow PSO internal approval process and subsequently change order to be issued for new scope / cost change. PSO will ensure timely issuance of change order after approvals. Contractor has to perform job as per directives of PSO Project Engineer. 10) PSO shall disqualify a supplier or contractor if it finds, at any time, that the information submitted by him concerning his qualification as supplier or contractor was false and materially inaccurate or incomplete.					



4	OF	4
RFQ No	AM-20056AM	
DATE	23.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018366

Company PSO Dummy Vendor PAKISTAN	QUOTATION REQUIRED			
	ON (Date)	09.10.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith **EARNEST MONEY %**
Rs. _____ **PO/DD NO.** _____

Title: Miscellaneous civil works required for placement of PFI Panel.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	11) The Contractor will be responsible to take away all the Construction waste or demolition debris from the Station. 12) The Contractor will be responsible for the airport entry passes (Including Police verifications) of all its workers and employees that are deputed to work at Karachi Airport. PENALTY: In the event of Contractor's / Supplier failure to deliver the Services / Goods within the time mention in Purchase Order / Service Order, in that event PSO shall be entitled to deduct from his bills /outstanding payments or other works done by m for PSO or from any amount due to him by PSO a sum of Rs.0.1% of Purchase Order / Service Order value per day as liquidated damages for the period which the said services / material remains incomplete or fails to pass the quality tests subject to a maximum 10% of Work Order amount to be recovered from the contract on his default. 13) Scaffolding third party certificate shall be provided by the vendor. 14) Job to be completed within 60 days after issuance of Purchase Order.					