



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Canopy Bluebar Maintenance Works</u>	<u>PSO House</u>				
1.01	<u>Supply and Installation of Blue Bar</u> The scope comprises complete supply, fabrication, installation<(>&<)> electrification, testing and commissioning of illuminated Acrylic Bluebars at designated PSO New Vision Retail Outlets (NVROs) M/s Virk P/s, M/s Choudhary Bros P/s, M/s Khan Brothers P/s, M/s Golden Star P/s <(>&<)> M/s Mian P/s, or as advised by concerned Divisional Engineer including all associated materials, accessories, dismantling, rewiring and fixing works, complete in all respects as per approved drawings and PSO standards. 1. Acrylic Bluebar # Fabrication & Graphics Supply and fabrication of 5 mm thick clear acrylic sheet<(>&<)> thermoformed/moulded to the required shape, dimensions and profile as per approved drawing. Acrylic shall be thermoplastic with good mechanical strength, stiffness <(>&<)> optical clarity, light transmittance, moisture resistance and suitable for thermoforming, fabrication and adhesive bonding. Acrylic shall have minimum compressive strength of 11 ksi, tensile strength of 560 psi, Rockwell hardness M80#100, and water absorption of approximately 0.2#0.4%. Graphics shall be electronically cut and applied using translucent blue outdoor-grade vinyl of 3M, Avery Dennison or equivalent premium international brand, colour-matched to approved PSO branding. Vinyl shall have permanent pressure-sensitive acrylic adhesive, minimum thickness 80 microns, minimum adhesion 15 N/25 mm after 24 hours or manufacturer's tested equivalent, minimum 5-year outdoor durability<(>&<)> ,<(>&<)> UV/weather/moisture and fuel/chemical splash resistance, and suitability for temperatures of approximately -20°C to +80°C. Vinyl shall be smoothly applied without wrinkles, bubbles, lifting<(>&<)> ,<(>&<)>	<u>ET</u>	1,025			



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	peeling or visible defects. All joints between adjoining Bluebar sections shall be properly aligned and covered with end caps made of acrylic (thickness 2mm) and pasted with vinyl using compatible 3M/Avery Dennison/equivalent premium-grade tape to ensure a continuous and neat appearance. 2. Installation & Structural Fixing Bluebars shall be accurately aligned, moulded and fixed to the existing steel structure provided for ACM/canopy fascia installation. Vendor shall provide all required brackets, fasteners, clips, supports <(>&<)> connectors, adhesives and other accessories necessary for complete and secure installation. For 8-ft Bluebars, two 4-ft sections shall be considered for supply<(>&<)> installation and electrification. Existing Bluebar/branding components shall be dismantled where applicable, with removed materials handled as directed by PSO. 3. LED Tube Rods & Electrification Supply and installation of 4-ft LED Tube Rods, Philips or approved equivalent, suitable for installation inside the acrylic Bluebar. Minimum technical requirements: Body: Plastic Length: 4 ft LED: LED technology Body thickness: #1200 mm (to be verified/corrected as per OEM datasheet) Luminous output: #1600 lumens Power: 10.5#16 W maximum Colour temperature: 5000#6000 K CRI: #70 Rated life: #15,000 hours Average illumination: #2000 lux Operating temperature: -10°C to +60°C LED tube rods shall be properly positioned and securely fixed inside the acrylic Bluebar to ensure uniform illumination.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	IP67-rated tube connectors shall be provided wherever required. Adjacent LED rods shall have a minimum 3-inch overlap to prevent visible dark spots/light leakage from outside. Suitable connecting devices, holders, clips, insulation and accessories shall be provided to ensure safe and reliable operation. 4. Wiring & Rewiring Supply and installation of 2-core 7/0.029 gauge PVC-insulated copper cable, Pakistan Cables or approved equivalent, for Bluebar wiring. Existing wiring shall be removed where required and replaced with new wiring conforming to PSO standards. Complete rewiring, termination and connection of LED tube rods shall be carried out using suitable connectors, holders, clips and insulation. All electrical connections shall be properly insulated, secured and protected against moisture and environmental exposure. Vendor shall carry out testing of wiring, insulation, polarity<(>&<)> continuity and illumination before commissioning. 5. Dismantling & Associated Works Dismantling/removal of existing tube rods, wiring, connectors, holders <(>&<)> clips and other components where required. Supply and installation of all new connectors, holders, clips, fasteners and associated accessories. Proper disposal/stacking of dismantled materials as instructed by PSO. Making good of any minor damages resulting from the installation works. 6. Testing, Commissioning & Quality Requirements Complete testing and commissioning of each Bluebar after installation. Ensure proper illumination, uniform light distribution, secure fixing<(>&<)> electrical safety and satisfactory overall appearance. Contractor shall rectify, at its own cost, any defects including improper alignment, visible joints, wrinkles/bubbles in vinyl, light leakage, dark spots, loose fixing, peeling/lifting of graphics or electrical malfunction. All works shall be carried out strictly in accordance with approved drawings, PSO branding requirements, HSE requirements and applicable PSO					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.02	standards. The quoted rate shall include all labour, materials, transportation<(>,<)> tools, equipment, scaffolding/lifting arrangements, dismantling<(>,<)> installation, testing, commissioning and all incidental works required for completion of the job. 7. Mandatory OEM Conformity Requirement The bidder/vendor shall submit a Letter of Conformity confirming compliance of the proposed Acrylic, Bluebar vinyl, LED Tube Rods and associated materials with the specified PSO technical requirements. The Letter of Conformity must be issued on the respective OEM's official letterhead and duly signed and stamped by the OEM/authorized representative. Submission of this document shall be mandatory for technical qualification in the tender. Signage Miscellaneous Replacement of Canopy Signage Supporting Structure Dismantling of Existing Bluebars Carefully dismantle and remove the existing 4-ft Bluebar sections from the canopy fascia/steel structure without causing damage to the Bluebars or supporting structure. Removed Bluebars shall be safely shifted and stored at a designated location for subsequent re-use. Dismantling of LED & Electrical Components Carefully remove the existing LED tube rods, holders, connectors and associated wiring from the Bluebar assembly. All reusable components shall be safely removed, segregated and stored at a designated location for subsequent re-use. Removal of Existing ACM Cladding Safely dismantle and remove the existing Aluminum Composite Material (ACM) sheets from the canopy fascia structure, ensuring minimum damage to the sheets. Reusable ACM sheets shall be properly stacked and stored at a designated location for reinstallation. Removal of Existing Signage Supporting Structure Dismantle and remove the existing obsolete/damaged signage supporting		JOB	1,025		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	framework from the canopy structure. All dismantled scrap/waste material shall be removed from the work area and disposed of at an appropriate location as directed by the Engineer-in-Charge. Fabrication & Installation of New Supporting Framework Supply, fabricate and install/weld a new signage/Bluebar supporting framework using 16-SWG minimum thickness GI/MS sections, comprising 3/4" x 3/4", 1-1/2" x 3/4" sections and 24-SWG GI sheet, as per approved drawings and PSO specifications given in Annexure-02. All cutting, drilling, welding, grinding, alignment, levelling and finishing required for complete installation shall be included in the scope. Note: The minimum permissible material thickness for the structural pipe sections shall be 16-SWG. Use of thinner gauge material shall not be permitted. Surface Preparation & Protective Coating Complete surface preparation of the fabricated framework, including scraping, cleaning, removal of rust/scale, grinding and finishing. Apply two coats of approved enamel primer/protective coating uniformly over the complete framework, in accordance with PSO-approved specifications and manufacturer's recommendations. Reinstallation of ACM Cladding Reinstall the existing reusable ACM sheets onto the newly fabricated supporting framework in accordance with PSO-approved specifications and Annexure-02. Sheets shall be properly aligned, levelled and securely fixed to provide a neat, uniform and structurally sound fascia. All required connectors, brackets, holders, hooks, fasteners, joining accessories and other fixing materials shall be supplied by the contractor and shall be deemed included in the quoted rate. Final fixing shall be to the satisfaction of the Engineer-in-Charge. Reinstallation of Bluebars					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Reinstall the existing reusable 4-ft, 5-mm thick Bluebar sections at their designated locations after completion of the LED tube rod and electrical wiring works. Bluebars shall be properly aligned, levelled and securely fixed to the supporting framework in accordance with the approved drawings, PSO specifications and Annexure-02. Final Alignment, Finishing & Commissioning Contractor shall ensure proper alignment, levelling, rigidity and finishing of the complete canopy fascia/Bluebar assembly. All installation-related works, including minor adjustments, drilling, cutting, fastening, welding, touch-up painting and associated accessories required for completion of the job, shall be deemed included in the scope. Unit of Measurement The Unit of Measurement (UOM) for the complete job shall be Square Feet (SFT) of the installed canopy fascia/Bluebar area. General Requirement: The quoted rate shall be deemed inclusive of all labour, materials, transportation, tools, equipment, access arrangements, dismantling, fabrication, welding, installation, fixing, surface preparation, painting, shifting/storage of reusable materials, disposal of scrap and all incidental works necessary to complete the job in accordance with PSO-approved specifications, drawings, HSE requirements and the satisfaction of the Engineer-in-Charge. TERMS & CONDITIONS 1.,,Scope Inclusivity The quoted rates shall be inclusive of all materials, labour, tools, equipment, transportation, loading/unloading, shifting, dismantling, fabrication, welding, installation, testing, commissioning, access arrangements and all other incidental works required for completion of the job in all respects. No additional payment shall be admissible for items necessary for satisfactory completion of the work.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	2.,,Completion Period The complete job shall be executed and completed within 40 calendar days from the date of issuance/signing of the Purchase Order (PO), unless otherwise approved in writing by PSO. Per day penalty of 1000 Rs will be charged after 40 days. 3.,,Pre & Post-Work Photographic Record The contractor shall submit clear before-and-after photographs of each activity, numbered and corresponding to the respective scope/activity/item numbers, along with the bill for verification and certification by the Engineer-in-Charge. 4.,,Responsibility for Damages The contractor shall be fully responsible for any damage caused to existing/reusable ACM sheets, Bluebars, LED tube rods, holders, wiring, supporting structures or any other PSO property during dismantling, shifting, storage, fabrication or reinstallation. Any damaged item shall be repaired/replaced by the contractor with an equivalent approved item at no additional cost to PSO. 5.,,Compliance with PSO SOPs & Standards The contractor shall strictly comply with the applicable PSO SOP for Structure Replacement dated 19-10-2020, approved drawings, specifications, HSE requirements, work methodology and instructions issued by the concerned Divisional Engineer (DE)/Engineer-in-Charge throughout execution of the job. 6.,,Material & Gauge Verification All structural pipes/sections proposed for fabrication shall be presented to the concerned DE/Engineer-in-Charge for sample inspection and physical gauge/thickness verification prior to commencement of fabrication/installation. No work shall proceed using material not approved by the concerned DE. 7.,,Material Quality & Workmanship All materials shall be new, genuine, good quality and compliant with PSO-approved specifications unless specifically identified for reuse. The contractor shall ensure proper dimensions, alignment, levelling, welding, grinding, surface preparation, painting, fixing and finishing. Any defective or substandard material/workmanship shall be rectified or					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	replaced by the contractor at no additional cost. 8.,,HSE Compliance # General The contractor shall comply with all applicable PSO HSE policies, procedures and safe work practices. A suitable Job Hazard Analysis (JHA)/Job Safety Analysis (JSA) and work methodology shall be prepared and submitted/approved, wherever required, before commencement of work. 9.,,Work at Height & Fall Protection All work at height shall be carried out using appropriate and certified access equipment. Workers exposed to fall hazards shall use full-body safety harnesses with suitable anchorage/lifelines, as applicable. Unsafe practices such as climbing on Bluebars, ACM sheets, canopy structures or unsupported surfaces shall not be permitted. 10.,,Scaffolding, Lifting & Equipment Certification Scaffolding, ladders, safety harnesses, cranes, lifters, welding machines, electrical equipment and other relevant tools/equipment shall be properly maintained, inspected and certified by an authorized/competent third party, wherever applicable. Operators shall possess the required competency/licence/certification for operating such equipment. 11.,,Electrical Safety Electrical works shall be carried out by a qualified/certified and licensed electrician, wherever applicable. Proper isolation, earthing, insulation, protection and safe termination of electrical connections shall be ensured. No temporary or unsafe electrical connections shall be permitted. 12.,,Barricading & Public Safety The contractor shall properly cordon off and barricade the work area using suitable warning signs/barriers. Necessary precautions shall be taken to protect outlet staff, customers, pedestrians, vehicles and other persons from falling objects, electrical hazards, welding sparks and other risks associated with the work. 13.,,Site & Structural Assessment Before commencement of work, the contractor shall inspect the work area and assess the ground condition, stability and strength of the supporting structure, access arrangements, overhead obstructions,					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	proximity of electrical power lines, weather/wind conditions and other site hazards. Work shall only commence after ensuring that identified hazards have been adequately controlled. 14.,,Weather & Working Hours Work shall not be commenced or continued after sunset or during heavy rainfall, thunderstorms, high winds or other adverse weather conditions that may compromise safety. Any exceptional requirement shall require prior approval from the concerned DE and shall be carried out under appropriate supervision and safety controls. 15.,,Work Area Housekeeping The contractor shall maintain proper housekeeping throughout execution. All waste, debris, removed materials, packaging, welding waste and other generated material shall be cleared from the work area on a continuous basis. The site shall be left clean, safe and free from debris before submission of the bill. 16.,,Protection of Existing Assets The contractor shall take all necessary precautions to protect the existing canopy, electrical systems, dispensers, signage, civil works, customer facilities and other PSO assets. Any damage attributable to the contractor shall be rectified/replaced at the contractor's own cost. 17.,,Handling & Storage of Reusable Materials All dismantled materials identified for reuse, including ACM sheets, Bluebars, LED tube rods, holders, connectors, wiring and other reusable components, shall be carefully removed, properly labelled/segreated and stored at the location designated by the concerned DE. Reusable materials shall be handed over to the concerned DE/Engineer-in-Charge after completion of the relevant activity. 18.,,Scrap & Disposal of Dismantled Structure Obsolete/damaged structural material and other non-reusable waste generated during the job shall be segregated and disposed of strictly as directed by PSO. The contractor shall transport the designated scrap material to Habibabad Depot, or any other location specifically instructed by PSO, at the contractor's own cost. 19.,,Scrap Handover & Gate Pass All scrap material designated for PSO shall be handed over to the					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	11
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	authorized PSO representative at Habibabad Depot against a valid Depot Gate Pass/Material Handover document. The contractor shall obtain and submit the duly acknowledged gate pass/handover document to the concerned DE as evidence of disposal/handover. No PSO-owned scrap shall be removed, sold, disposed of or retained by the contractor without written authorization. 20.,,Segregation of Reusable Material and Scrap The contractor shall ensure proper segregation between reusable PSO assets and scrap material. No material shall be classified as scrap or disposed of without approval/instruction from the concerned DE/Engineer-in-Charge. 21.,,Quality Inspection & Acceptance PSO reserves the right to inspect materials, workmanship and ongoing activities at any stage. The contractor shall provide reasonable access and cooperation for inspection. Any work/material not conforming to approved specifications shall be rectified/replaced by the contractor at no additional cost to PSO. 22.,,Final Testing & Handover Upon completion, the contractor shall conduct all necessary structural, electrical, illumination and functional checks and rectify any deficiencies identified by PSO. The completed installation shall be handed over only after satisfactory inspection and acceptance by the concerned DE/Engineer-in-Charge. 23.,,Tools, PPE & Worker Competency The contractor shall provide all required PPE, safety equipment, tools and machinery to its workforce. All personnel shall be competent, adequately trained and briefed regarding site-specific hazards and safe working procedures before commencing work. 24.,,Hot Work & Fire Safety Welding, grinding, cutting and other hot-work activities shall be carried out only after implementing appropriate hot-work safety controls, including removal/protection of combustible materials, provision of suitable fire extinguishers and fire watch where required. Sparks and hot materials shall be controlled to prevent damage or fire. 25.,,Work Methodology & Supervision					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	11
RFQ No	RC20044SJ	
DATE	24.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018371

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

08.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Repair, Replacement <(>&<)> Reinstallation of Canopy Bluebars <(>&<)> Associated Electrical Works at NVROs of Lahore Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	The contractor shall deploy a competent supervisor at site throughout execution. Work shall be carried out in accordance with the approved methodology and under the supervision/inspection of the concerned DE/Engineer-in-Charge, wherever required. 26.,,Statutory Taxes & Levies All applicable government taxes, duties, levies, fees and statutory charges shall be deemed included in the quoted rates. PSO shall have the right to deduct applicable withholding taxes as per prevailing laws. 27.,,Measurement & Payment Measurement and payment shall be made based on the actual completed and accepted work, measured in accordance with the applicable BOQ/UOM and certified by the authorized PSO representative. 28.,,No Unauthorized Modification The contractor shall not alter, modify, remove or relocate any existing structure, equipment, electrical connection or PSO asset beyond the approved scope without prior written approval from PSO. 29.,,Compliance with Instructions The contractor shall comply with all reasonable technical, operational, HSE and quality-related instructions issued by the concerned DE/Engineer-in-Charge during execution of the job. 30.,,Completion in All Respects The contractor shall be responsible for completing the entire job in a safe, technically sound, aesthetically acceptable and workmanlike manner, fully complying with PSO specifications, approved drawings, HSE requirements and the satisfaction of the Engineer-in-Charge.					