



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 1      | OF         | 5 |
| RFQ No | AV20072-FF |   |
| DATE   | 29.09.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018428

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

13.10.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Installation of Skid-Mounted Receipt Filter Unit at Gwadar Aviation Station

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Location                        | Unit              | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|-------------------|-----|-------------------|---------------|
| 1     | <b><u>Installation of Skid-Mounted Filtration</u></b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | <b><u>Gwadar (Aviation)</u></b> |                   |     |                   |               |
| 1.01  | <b><u>Excavation &amp; backfilling</u></b><br>Excavation of a 2-feet deep trench and laying of the provided 4-Core, 16 mm <sup>2</sup> LT cable, including sand cushioning and installation of warning cable tiles as per the directions of the Engineer-in-Charge.<br>Complete electrical installation and connection of the cable from the main power trolley/power supply up to the Skid-Mounted Receipt Filtration Unit including all required termination connections and installation work as instructed by the Engineer-in-Charge |                                 | <b><u>EA</u></b>  | 145 |                   |               |
| 1.02  | <b><u>M&amp;R ELECTRICAL WORKS</u></b><br>Making termination of 16 mm <sup>2</sup> 4 core armored copper conductor including providing & fixing proper lugs, tapping etc. as per directions of Engineer in Charge and requirement.                                                                                                                                                                                                                                                                                                       |                                 | <b><u>JOB</u></b> | 1   |                   |               |
| 1.03  | <b><u>M&amp;R ELECTRICAL WORKS</u></b><br>Providing and fixing 40 Amps (High Breaking Capacity) T.P MCCB fixed on existing board, I/c inter-connection as required (Chint. Siemens. Schneider or equivalent)                                                                                                                                                                                                                                                                                                                             |                                 | <b><u>JOB</u></b> | 1   |                   |               |
| 1.04  | <b><u>M&amp;R ELECTRICAL WORKS</u></b><br>Providing & fixing DB Box (2.5 ft Length × 1.5 ft) with suitable metal enclosure, locking arrangement vermin protected and duly powder coated including all necessary fasteners. internal wiring and accessories.<br>complete in all respects as required<br><br>Incoming:<br>01 No. 40 Amps, TP, MCCB<br>Metering:<br>01 No. Three Phase Energy Meter<br>Accessories:<br>01 No. Neutral Link<br>01 No. Earth Link                                                                             |                                 | <b><u>JOB</u></b> | 1   |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 2      | OF         | 5 |
| RFQ No | AV20072-FF |   |
| DATE   | 29.09.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018428

Company PSO Dummy Vendor  
PAKISTAN

QUOTATION REQUIRED

ON  
(Date)

13.10.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Installation of Skid-Mounted Receipt Filter Unit at Gwadar Aviation Station

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Location | Unit              | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------------------|-----|-------------------|---------------|
| 1.05  | 01 Set R.Y.B Phase Indication Lamps<br>01 Set Danger Sign<br>Complete with all necessary wiring, lugs, glands, terminals, supports and other required accessories for proper installation and operation.<br><br><b><u>M&amp;R ELECTRICAL WORKS</u></b><br>Providing & fixing Three Phase 15 to 90 Amps, 400/440 Volts<br><br>Energy Meter fitted on DB Box, including all necessary connections<(>,<)><br>wiring, lugs,terminals and accessories as required.<br>Recommended brand: Syed Brothers, PEL, or equivalent approved brand.                                                                                                                                                                                                                                                                                                |          | <b><u>JOB</u></b> | 1   |                   |               |
| 1.06  | <b><u>Providing &amp; Laying of Pipelines</u></b><br><br>Providing and laying 2" (50 mm) diameter Galvanized Iron (GI) pipe along with all required specials and fitting accessories by cutting existing concrete floor slab up to 6 inches depth, cleaning and refilling with PCC not leaner than 1:1½:3 including making good any damages etc. complete in all respects as per directions of Engineer in charge.                                                                                                                                                                                                                                                                                                                                                                                                                   |          | <b><u>JOB</u></b> | 70  |                   |               |
| 1.07  | <b><u>M&amp;R ELECTRICAL WORKS</u></b><br>Providing and laying/fixing complete earthing set comprising a 2' x 2'x1/8" copper plate, buried in the ground at a depth of 12 feet or less if water is encountered, including excavation of the earthing pit in all types of soil (excluding soft or hard rock), provision of salt and charcoal or approved earthing chemical powder, and fixing of 8 SWG copper wire enclosed in 1/2" GI conduit.<br>The earthing system shall also include 70 feet of 10 mm² copper cable for connection from the earthing electrode to the required equipment/DB complete with suitable earthing clamps, copper thimbles/lugs cable termination, connections, and all necessary fittings and accessories complete in all respects as required and in accordance with Directions of Engineer Incharge. |          | <b><u>JOB</u></b> | 1   |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 3      | OF         | 5 |
| RFQ No | AV20072-FF |   |
| DATE   | 29.09.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018428

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

13.10.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Installation of Skid-Mounted Receipt Filter Unit at Gwadar Aviation Station

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Location | Unit | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----|-------------------|---------------|
| 1.08  | <p><b><u>Crane services over 15 tons upto 25 tons</u></b></p> <p>Crane service IF required for lifting and positioning of the Skid Unit.<br/>The crane must be safe, sound, properly maintained, and suitable for the required load. The crane operator must have a valid licensee/certification and relevant experience. All lifting work shall be carried out as per HSE requirements and safe lifting practices.</p> <p>TERMS AND CONDITIONS:<br/>=====</p> <p>1- Contractor shall complete the installation of the skid-mounted receipt filter unit, including lifting, positioning, fixing, alignment piping connections, electrical Connection work, earthing/bonding testing and commissioning.</p> <p>2- PSO will provide 4-Core × 16 mm<sup>2</sup> cable, 145 meters. Contractor shall carry out cable laying, routing, dressing and termination.</p> <p>3- Contractor shall provide all required cable glands, lugs ferrules, termination kits and other cable accessories.</p> <p>4- The skid unit shall be properly earthed and bonded. For Copper plate the earthing plate shall be minimum 600 × 600 × 6.3 mm or as approved by Engineer Incharge.</p> <p>5- Contractor should strictly follow the safety and security rules of PSO.</p> |          | HR   | 1.0 |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 4      | OF         | 5 |
| RFQ No | AV20072-FF |   |
| DATE   | 29.09.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018428

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

13.10.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Installation of Skid-Mounted Receipt Filter Unit at Gwadar Aviation Station

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                | Location | Unit | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----|-------------------|---------------|
|       | 6- Contractor's labor to follow Company's rules and procedures as well as HSE guidelines and safety procedures.                                                                                                                                                                           |          |      |     |                   |               |
|       | 7- Contractor will provide Equipment and PPEs i.e. Safety Shoes, Gloves<br><br>Helmets, Goggles, Safety Harness, Safety Belts etc. to his labor during execution of work.                                                                                                                 |          |      |     |                   |               |
|       | 8- All service, tools (nonferrous if required), first aid box, materials and transportation to be provided by contractor.                                                                                                                                                                 |          |      |     |                   |               |
|       | 9- Payment will be made as per actual quantity of work done.                                                                                                                                                                                                                              |          |      |     |                   |               |
|       | 10- If the Contractor fails to complete the work within time stipulated , the Engineer In-charge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Work Order per day and subject to minimum 10% Value of P.O. |          |      |     |                   |               |
|       | 11- Contractor should maintain housekeeping of the worksite during progress of work and shall clear and remove all surplus materials and rubbish from site after completion of job as per instruction of Engineer In-charge.                                                              |          |      |     |                   |               |
|       | 12- The work will only be accepted after inspection and approval by the Engineer Incharge.                                                                                                                                                                                                |          |      |     |                   |               |
|       | 13- Work should be completed within 30 days of issuance of work order.                                                                                                                                                                                                                    |          |      |     |                   |               |
|       | 14- Quality is the prime concern of PSO, no compromise shall be made in this regard. Only first class approved quality material, workmanship and supervision will be utilized by the contractor which shall strictly conform to the WO/SO specification.                                  |          |      |     |                   |               |
|       | 15- Contractor should strictly follow the safety and security rules of                                                                                                                                                                                                                    |          |      |     |                   |               |



# Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan  
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

|        |            |   |
|--------|------------|---|
| 5      | OF         | 5 |
| RFQ No | AV20072-FF |   |
| DATE   | 29.09.2026 |   |

## REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018428

Company PSO Dummy Vendor  
PAKISTAN

### QUOTATION REQUIRED

ON  
(Date)

13.10.2026

BY  
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. \_\_\_\_\_ EARNEST MONEY %  
PO/DD NO. \_\_\_\_\_

**Title:** Installation of Skid-Mounted Receipt Filter Unit at Gwadar Aviation Station

| S.No. | Description/Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Location | Unit | Qty | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|-----|-------------------|---------------|
|       | <p>PSO, PAA and ASF.</p> <p>16- The contractor must apply for and obtain valid Airside Entry Passes for all personnel and vehicles through the PAA and ASF before commencing any work within the airside area.</p> <p>17- All contractor staff shall strictly comply with airport security rules, regulations, and identification procedures as defined by PAA and PSO Aviation. Any breach of security protocol may result in immediate removal from the premises.</p> <p>18- The contractor shall arrange all logistical support, equipment, and material transportation and their Airside pass.</p> <p>19- The contractor will be fully responsible for the conduct, safety &lt;(&gt;,&lt;)&gt; and security of its staff, equipment, and materials inside the airport premises.</p> <p>20- If any change or modification is required during the work, it will be mandatory for the contractor to carry out the revised work as directed by Engineer Incharge.</p> <p>21- After completion of work, the site must be cleaned, leveled.</p> |          |      |     |                   |               |