



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Rehab of CCTV Room</u>	<u>Lahore (LPG)</u>				
1.01	<u>Rehab. of CCTV Room</u> Room Size 14'x17' = 238 sft 1.,Existing floor dismantling and removal of brick flooring Dismantling of existing floor and removal of brick flooring to make base for concrete flooring 2.,Plain Cement Concrete (PCC 1:3:6): Providing and laying plain cement concrete where required using approved quality 3/4" maximum size graded crushed aggregate, stone or gravel with approved quality local river sand/equivalent i/c all formwork, rodding <(>,<)> vibrating, leveling and curing etc. Class 'D' P.C.C (1:3:6) 3.,Reinforced Cement Concrete (RCC 1:2:4): Providing and laying RCC 1:2:4 OPC/SR Cement (if required) for flooring and roof slab etc. of specified strength (Min 2500 PSI cylindrical Strength) approved quality 1/2" max: size graded crushed stone and fine aggregate (hill sand) preferably Plant Mix Concrete (if available) of required properties including form work installation & removal<(>,<)> mixing, transporting, placing, compacting, finishing and curing<(>,<)> scaffolding complete in all respects as specified. To confirm the desired cylindrical crushing strength of Min. 2500 PSI (minimum) at 28 days Cylinder tests for 7 & 28 days (3+3 No's) will be carried out by contractor from Company/Institute approved laboratory at his own cost. 4.,60 Grade Reinforcement: Providing and Laying steel reinforcement bars including straightening<(>,<)> removing twists, cutting, bending, binding, wastage and such overlaps as are not shown on drawings, placing in position on precast concrete or steel chairs, tying with binding wire complete as per the instructions of Plant In charge. Note: Overlaps and other binding of reinforcement shall not be paid separately. a.,Deformed steel reinforcement of yield strength 60,000 psi. NOTE: Contractor to submit the Mill report of the deformed steel bars provided at Site.		<u>FT2</u>	238		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	5.,Brick/Block Masonry: Providing and laying First Class bricks/solid block masonry of specified thickness set in 1:4 cement sand mortar i/c required scaffolding racking out and cleaning of joints and curing of masonry complete as per the instruction/direction of engineer in charge. In order to check the strength of Brick/Blocks, contractor to submit the compressive strength test reports of bricks/blocks and should be as per the specifications and approved by Plant in charge. The compressive strength of Brick/Block should be in range from 1500 psi and above. NOTE: Contractor to provide the proper dowels between Concrete Columns and Brick/Block masonry in order to avoid the cracks at the joints. 6.Plaster: Providing and applying cement plaster 1/2" to 3/4" thick in 1:4 cement sand mortar to walls, columns, beams etc. i/c all corners, recesses, jams and racking out joints of masonry, roughing the surface and cement slurry backing to all surfaces i/c curing and scaffolding Scope also includes the provision of 6" wide heavy-duty metal lath strip nailed at the joints of masonry and concrete structural members (where required). 07.Water Proofing over slab of building: Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. Or 1.72 Kg/Sq.m bitumen coating sand blinded. 08.PB 4 on exposed Surfaces of Concrete: Providing and applying water proofing treatment on exposed surface of concrete in contact with earth using flood coat of P.B.4 each of 30 lbs. per 100 Sq. Ft. coverage.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	09.U-PVC Main Doors/Windows/Ventilators: Providing and fixing fully/Partial glazed [Hinged/Sliding/Fixed Doors, Windows and ventilators] of Europrofilo (u-PVC) white colour extruded section with Net sash in all sliding windows/Ventilators using 5 mm thick clear float glass [with solid panel up to half/full height in doors], as per the instructions of engineer in charge, of approved quality fitted with full steel reinforcements and rubber gasket i/c all hardware and appropriate locking mechanism and caulking all joints with silicone sealant complete in all aspects. The u-PVC material should be durable, highly insulated, weather proof and fire resistant and must comply with BS EN 12608-1:2016. Vendor to provide heavy duty mechanical latches of brass door handles with lock and key arrangement. Lintels to be provided for Door & Windows. Entire job to be done as per the instructions of engineer in charge. Note: Cutting of existing walls for installation of windows and door is in scope of this job 10.Steel Grill inside the windows and ventilators: Providing & fitting steel Jalli over the Windows with 8 mm Square Ms Bar in the shape of Jali with specified size, design and shape to be approved by Plant incharge. Job includes anti rust paint and three coats of enamel paint necessary fittings and fixtures including approved locking system and as per the instructions of Plant In charge. 11. Plinth Protection (1.5'x2' Wide, 3 Sides) Plinth protection on 3 sides 12.SERVICES ELECTRICAL WORKS:					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1)	Supply, Installation, Testing and Commissioning of Distribution Board: Supply, Installation, testing and commissioning of Distribution Board<(>,<)> indoor/Outdoor type and wall mounting/Flush type. 16 SWG sheet steel fabricated, totally enclosed, dust tight and vermin proof. It shall be complete in all respect with material and accessories, factory assembled and tested. It shall consist of following components:- Incoming: 1 x 32 A TP MCB 5KA 3 x Phase Indication Lights 3 x Control Fuses Outgoing: 2 x 10 A SP MCBs 5 KA 4 x 6 A SP MCBs 5KA ..					
2)	Wiring from DB to Switch Boards (2 Nos): Circuit wiring from Main Board to switch board in appropriate/specified size of PVC Conduit on surface/concealed with 2 X 2.5 SQ.MM. + ECC 1 X 2.5 SQ.MM PVC insulated wires, including any wiring between on the same circuit. The job also includes the supply and provision of approved quality switch board including the 16 SWG sheet steel box as per the instructions of Plant<(>,<)>					
3)	Wiring of Switch Board to Light point (10 Nos): Wiring of single light point to point with 1.5 sq.mm 1 core wires for ECC green in colour and 2x2.5 sq.mm common neutral and live including 16 SWG sheet steel back boxes PVC insulated wire in 3/4" or 1" dia. PVC conduit of approved make or approved equivalent is recessed in wall, ceiling, columns etc. complete with all conduit accessories such as junction boxes, bent etc., including sheet cover fixed with CP screws, roses dimmers complete in all respect. Cables/ Switch boards of approved					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	make or approved equivalent to be used. The job also includes the supply and provision of approved quality switch board including the 16 SWG sheet steel box in the wash room and as per the instructions of Plant In-charge. 4)Wiring of 5 AMP Socket (2-Pin) (2 Nos): Wiring with 3x7/.029 sq. mm in PVC conduit of approved equivalent conduit for 5A Switch socket of approved Make or equivalent gauge on common board connected any nearest light circuit. Complete with all conduit accessories including providing and fixing 2 in, 5A switch socket unit fixed on 16 SWG steel board of suitable size recessed in wall or columns. in all as required. Cables/ Switch boards of approved make or approved equivalent to be used. 5)Wiring of 5 AMP Socket (3-Pin) (3 Nos): Wiring with 3 x 7/.029 sq. mm in PVC conduit of approved or equivalent for 5A 3 pin switch socket of approved Make or equivalent gang on common board connected any nearest light circuit. Complete with all conduit accessories including providing and fixing 3 pin, 5A switch socket unit fixed on 16 SWG steel board of suitable size recessed in wall or columns. in all as required. Cables/ Switch boards of approved make or approved equivalent to be used. 6)Earthing Rod: Providing and fixing 20 mm dia 99% copper earthing electrode (10 ft. Length) directly driven in ground complete as per drawing and instruction of Plant -in-Charge including earthing leads up to earth connecting point and inspection chamber. Connecting earth to wall mounted bus with 16 sq.mm single core cable as per drawing with 10 R. Ft 50 sq. mm PVC insulated flexible copper conductor lead and connected to					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

6	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	main DB for earthing purposes.					
	7)Bracket/Wall Fan (1 Nos): S/I Bracket/Wall hanging fan of approved make and size or as per the instructions of Plant In-charge.					
	8)Ceiling Fans (1 Nos): S/I Ceiling Fans of 56 inch of approved make or as per the instructions of Plant In-charge.					
	9)S/I of LED Bulbs (2 Nos): S/Installation and commissioning of LED light fixture of approved make or approved equivalent on concrete ceiling with all fixtures/ fittings in all respects and as per the instructions of Plant Incharge.					
	10)S/I of LED Tube Rods (4 Nos): S/Installation and commissioning of LED tube rods of approved make or approved equivalent on concrete ceiling with all fixtures/ fittings in all respects and as per the instructions of Plant In-charge.					
	12) Installation of air conditioner: Installation and commissioning of air conditioner.					
	13.SERVICES PLUMBING WORKS: 1)S/Installation of 3" Dia u-PVC Pipe:					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

7	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Supply/Laying in trenches or on surface/ wall of class B 3" dia u-PVC pipe sleeves of approved make or approved equivalent including tees, bends, leak proof sealant, joints branches as per requirements embedded in floor or wall or clamped to walls or suspended from slab(>,<)> cutting and fixing of pipe ,provided of clamps, hangers, collars and supports, making requisite number of holes in walls, plinth and floor, cutting chases and embedding the pipe in wall where directed etc. Making good the same in C.C.1: 2:4 including the cost of cement mortar joints and providing pipes sleeves in walls, slabs, any excavation and backfilling if required etc. 14.Epoxy Flooring: Preparing surface and painting with Matt/Glossy high chemical resistant/hardwearing Polyurethane paint (Epoxy Paint) by sprayer/Brush i/c the cost of Primer coat in required colour as per site requirements, all material and Labor complete in all respects as approved and directed by the Plant In-charge. 15.Weather shield Paint: Providing and applying 3 coats of WEATHER SHIELD paint on newly plastered surface of required colour and shade. Job also includes (if required) removal of the existing paint and preparation of the base by rubbing the surface with suitable material filling the depressions with putty, cutting the surface and rubbing smooth finally with sand paper complete as per specifications and directions of the Plant In charge. 16.Distemper Paint: Providing and applying 3 coats of Distemper Paint of required colour and shade. Job includes the preparation of plastered surface by rubbing the surface with carborandum stone filling the depressions with putty(>,<)> cutting the surface and rubbing smooth finally with sand paper complete as per specifications and directions of the Plant In charge.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

8	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
2.01	<u>Supply installation of spiral stairs</u> <u>Supply and inst. of spiral stairs</u> SUPP, FAB, INST.OF STAIRCASE WITH RAILING: (4 No.) Providing and fixing 5.00 ft dia MS spiral stair comprising of triangular steps made of MS Checkered Plate duly welded supported with 1/4"x1-1/4"x3/16" duly welded with 3/8" MS square bars steps(>,<)> supported/welded with main vertical post of 4" dia GI pipe (Medium Quality) embedded in RCC foundation in ground i/c the cost of pipe railing comprising of 2" dia MS pipe of 16 SWG supported with 2 no 5/8" square bars in each step, i/c fixing & painting complete in all respects as approved and directed by the Engineer Incharge. Job also includes the proper embedding in the ground with RCC foundation as per the designer requirements. 1.,,CCTV Room (Height: 12') 2.,,Office Block (Height: 13') 3.,,Prayer Room (Height: 16') 4.,,Worker's washroom (Height: 14')		<u>JOB</u>	4		
3	<u>Deformed Steel Bars</u> Supply steel reinforcement bars including straightening, removing twists, cutting, bending, binding, wastage and such overlaps as are not shown on drawings, placing in position on precast concrete or steel chairs, tying with binding wire complete as per drawings and specifications and as per the instructions of Engineer In charge. Note: Overlaps and other binding of reinforcement shall not be paid separately. Deformed steel reinforcement of yield strength 60,000 psi. NOTE: Contractor to submit the Mill report of deformed steel bars provided at site. Scope of work: 1. Rehabilitation of CCTV room in all aspects including roof slab(>,<)>	<u>Lahore (LPG)</u>	<u>KG</u>	500.000		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

9	OF	*
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	flooring, touchup work on walls, fixing of door and windows, electrical wiring and other allied tasks, plinth protection, water proofing<(>,<)> paint from inside & outside, etc. 2. Supply & installation of Spiral stairs on CCTV Room, Office Block, Mosque and Worker's washroom. NOTE 1- All rates include levies and transportation charges. 2- Sales Tax Invoice shall be provided by contractor for supplied material. 3-All installation shall be done as per satisfaction of Engineer Incharge. 4- The contractor shall make and submit the As-Built Drawings in a professional manner & Test Reports on completion of the project. 5- Contractor shall provide at least 1 year warranty of entire project. 6- All resistance, continuity tests shall be performed during installation in the presence of Engineer Incharge. 7- Contractor shall restore the site at its original condition after completion of respective jobs. Clearing of debris would also be the responsibility of contractor. 8- Contractor shall rectify any damage caused during construction work to PSO property. 9- Contractor shall strictly adhere and comply with the HSE policy. No compromise would be allowed on HSE during construction works. Contractor shall arrange PPEs (Presonal Protective Equipment) and ensure that staff wear the PPEs during execution of work. 10- Prior Approval must be taken for all material to be supplied before commencement of works. Sample to be provided if required / asked by the concerned Engineer. 11- Contractor shall provide a complete schedule for the execution of the Project along with the name, details of the Project team within a week after award of work. 12- Acceptance of the equipments / materials is subjected to inspection of PSO representatives.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

10	OF	11
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	13- Contractor will provide firefighting equipment, PPE's and fulfill all HSE requirement and measure during the execution of works. PSO's Construction Safety Booklet should be referred in this regard. 14- All supplied materials and accessories should be brand new and from fresh stock. 15- Contractor shall responsible/rectify any damage occurred to PSO property during execution of work without charging any cost to PSO. 16- Contractor will jointly visit with Site Engineer to ascertain the actual quantities of material required for the job before delivery at the site. 17- Contractor will submit the MTC's of the material wherever required. Further, any testing for verification will be at Contractor Risk and Cost. 18- Contractor will depute Site Engineer BE (Engineering) atleast 5 years minimum work experience for the execution of job & HSE Supervisor. 19- Contractor must maintain project log book and Quality Inspection Plans at site, as per PSO's approved format. 20- Contractor will utilize skilled manpower for the execution of complete Project. 21- Providing of all Tools & Equipment's required to execute the complete Job / Project is the sole responsibility of the Contractor. 22- Contractor / Supplier to provide welder procedure specification and qualification record. Contractor will carry out Welding Qualification Procedure Test, Welder Qualification Test for all welders and all related NDT and mechanical test as per applicable codes / standards at their own cost. 23- Contractor will follow Quality Control Procedure and will comply the all quality standards given by PSO time to time. 24- Quantities of any items can be changed according to requirement of PSO. Contractor has to perform job as per directives of PSO Engineer. 25- For Supply item, Payment to be made according to actual dimensions. 26- Contractor will arrange inspection / testing of all supplies /materials that will be provided / supplied by the Contractor. All cost pertaining to this inspection / testing shall be borne by the Contractor.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

11	OF	11
RFQ No	GF-20082AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018453

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Rehabilitation of CCTV Room, supply and installation of spiral stairs on various buildings at LPG Plant Lahore

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	27- Contractor should provide activity based schedule after issuance of work order. 28- If required, crange facility for lifting, shifting and placing activities will be done by contractor. 30- All types of consumables, arrangements, required for complete scope of work shall be provided by Contractor, without any additional cost. 31- Project completion date is 60 days after the issuance of PO. 32-.Panelty Clause: "a. Penalty Rate: A penalty at the rate of 0.1% of the total value of the undelivered quantity per day of delay shall be levied <(>,<)> subject to a maximum of 10 % of the value of the work order. b. Calculation: Penalty = (Value of Undelivered Quantity) × (Penalty Rate per day) × Number of days delayed)." Terms & Conditions: All the work done and task completed within 60 days, after the issuance of Service Order**					