



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	RF20063SZ	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018452

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing services for Removal and Reinstallation of Signages at NVROs South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Signages</u>	<u>PSO House</u>				
1.01	<u>Installation & Removal</u> Providing services for dismantling and removal of existing ACM fascia Signage including fascia logo, old blue bars, frames, angles, Z & L section, holders /connector, wiring etc complete in all respect. The job includes transportation of materials from one site to another site. JOB-EA (EA is equivalent to one NVRO station). Note: Quantity of this item represent number of site(s)		<u>EA</u>	32		
1.02	<u>Signage Miscellaneous</u> Providing and installation of existing MS structure repairing<(>,<)> cutting, welding with red oxide primer (Two coats) along with finish paint White oil (two coats) ICI/Burger for proper fixing of ACM sheets as per PSO approved design. Job further includes 1. Routing, cutting, bending and installation of old ACM sheets with new fascia sheet (24 SWG Gauge Precoated) and old fascia logo as per PSO approved design. 2. Installation of new holder sheet (22 SWG gauge MS white paint) and new wiring (2 core 2.5sqmm PVC insulated cable). 3. Installation of old blue with acrylic end covers on both sides of the blue bar, applying PSO blue vinyl over the covers from both sides<(>,<)> making the side covers free from blue taping, and reinstalling them in their original position. Job is in RFT		<u>JOB</u>	3,392		
1.03	<u>Installation & Removal</u> Providing services for dismantling and removal of existing Name sign with frame, Wall logo, spreaders, shopstop sign, IN & Out sign, Tyre shop sign, car wash / Autocare sign, tank & office area signages as per site requirements complete in all respect. The job includes transportation of materials from one side to other site. JOB-EA (EA is equivalent to one NVRO station).		<u>EA</u>	32		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RF20063SZ	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018452

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing services for Removal and Reinstallation of Signages at NVROs South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	Means Quantity of this item represent number of site(s) <u>Signage Miscellaneous</u> Providing Services for installation of existing Nameplate, Wall logo , spreaders, IN & OUT sign, Tyre shop sign, carwash / Autocare sign<> ,<> tank and office area signages as per site requirements complete in all respect. JOB-EA (EA is equivalent to one NVRO station). Means Quantity of this item represent number of site(s)		<u>JOB</u>	16		
1.05	<u>Signage Miscellaneous</u> Shop Stop Signage removal complete in all respect.		<u>JOB</u>	16		
1.06	<u>Signage Miscellaneous</u> Vinyl pasting Providing services removal of existing vinyl from blue bars / spreaders/ nameplate and pasting of new vinyl of 3M(3630 VT 1986)/Avery CC (5500-763 Blue) complete in all respects. Unit: SQFT Terms and Condition,, 1. The rates of items are inclusive of all taxes or any other tax applicable and contractor is required to submit GST/ SST invoice at the time of invoice. 2. Contractor will arrange testing of equipment at his own cost, if required. 3. Quality of work is the prime concern of PSO. The contractor will be required to produce best quality work. 4. Work must be completed within 180 days after site handed over to contractor.		<u>JOB</u>	1,017.600		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RF20063SZ	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018452

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing services for Removal and Reinstallation of Signages at NVROs South Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	5. Contractor has to comply with all HSE procedures and policies during execution of the work. 6. Contractor should strictly follow the safety and security rules of PSO. Contractor's team has to follow Company's rules and procedures as well as HSE guidelines and safety procedures. 7. All services, tools, materials and transportation to be provided by contractor. 8. Payment will be made as per actual quantity of Work Done. 9. If the Contractor fails to complete the work with in time stipulated ,the Engineer Incharge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of SO. 10. Contractor should maintain housekeeping of the workplace during progress of work and shall clear and remove all surplus materials and rubbish from workplace after completion of job as per instruction of Incharge. 11. The work will only be accepted after inspection and approval by the DE. 12. Bidder must visit the site before quoting for the job to properly asses the scope of work. 13. Damage to the False Ceiling during replacement of sheets is to be born by contractor himself. 14. Rates are inclusive of scrap materials 15. Work will be performed using proper PPEs like, harness safety helmets, Shoes etc complete in all respect.,,					