



SAP No 6100018417

RC-19969AM

30.09.2026

QUOTATION REQUIRED

BY
(Time)

EARNEST MONEY %

PO/DD NO.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Upgradation of Site M/s Mehr ASIQ & CO</u>	<u>PSO House</u>				
1.01	<u>Canopy False Ceilings</u> Providing and fixing false ceiling under canopy with 4" wide 26 SWG pre-painted steel / aluminium sheet strips with no perforations and maximum length of 4 ft. hinges,bolts and all necessary fittings I/C sofit return of 16swg for false ceiling finish oapproved shades to be suspended with metal adjustable suspension system."		<u>SFT</u>	4,800		
1.02	<u>Civil Work Miscellaneous</u> Provision and Installation of ACM material Eurobond 4102or approved equivalent by concerned engineer at Mehr brother fs. Job includes provision of all the relevant material required for installation of ACM at site.		<u>RFT</u>	3,550		
1.03	<u>P/L CUT OFF DRAIN</u> Proving services for construction of drain channel as per site requirement scope of work also include fabrication, welding, grinding<(> ,<(> fixing of MS grill having 1/4" thickness for drainage of service station complete by using structural steel, flat bar, angle iron complete in all respects as per site requirement " TERMS AND CONDITIONS: 1.,,Contractor will be responsible for the removal / disposal of debris outside retail outlet premises as per the instruction of the engineer incharge 2.,,Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. 3.,,The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment, undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves, Helmets<(>,<(> Googles, Safety harness, etc) during execution of work. PSO reserves the		<u>RFT</u>	80		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	RC-19969AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018417

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Upgradation of M/s Mehr Ashiq(>&<) Co Ex:Zoom fs,Islamabad Div

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. 4.,,The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 5.,,All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 6.,,Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. 7.,,Wherever applicable, contractor is bound to engage certified /licensed electrician for electrical works. 8.,,Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm, etc.). For any special case, approval from DE will be required and work will be performed under supervision of DE. 9.,,The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 10.,,The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in #no smoking# area, etc) during work. Contractors will also ensure proper work planning and risk assessment prior to start of work. 11.,,The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 12.,,The contractor shall indemnify PSO, its offices, employees, agents					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	RC-19969AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018417

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Upgradation of M/s Mehr Ashiq(>&<)> Co Ex:Zoom fs,Islamabad Div

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	and representatives from and against all losses, costs, penalties(>,<)> fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by this contract. 13.,,Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO. **All the work done and task completed within 60 days, after the issuance of Service Order**					