



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	3
RFQ No	OP-20075AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018445

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of Car Parking Shed at Sihala Installation

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Car Parking Shed</u>	<u>Sihala (Inst.)</u>				
1.01	<u>"Providing and construction of Steel str</u> The scope of work includes construction, fabrication, and installation of a car parking shed for 03 cars with an overall structure size of 24 ft × 17 ft consisting of 02 spans of 17 ft × 12 ft each designed to provide durable, weather-resistant, and aesthetically pleasing coverage. The work shall include supply, fabrication, painting, and erection of the following items of below mentioned specifications: · Base Pole # 6 in 10 SWG, 8#10 feet (as required) · Cantilever Truss Top Pipe # 3 in 12 SWG, 20 feet · Cantilever Truss Bottom Pipe # 3 in 12 SWG, 17 feet · Central Purlins # 3 in 14 SWG, 18 feet 4 in · Truss Connector Pipe # 2 in 16 SWG, 18 in # 4 in · Truss Top Support # 2 in 14 SWG, 45 in · Metal Plate Base # 16 mm, 18 in × 18 in · J Bolts # 24 mm, 30 in · Fabric # 820 GSM, 24 ft × 17 ft · Metal Wire # 6 mm, as required · Aluminium Channel # 8 mm sides, as required · Paint Work # 1 base coat and 2 finish coats, as required The work shall be carried out in accordance with relevant international standards (ASTM, AWS for welding, ISO 12944 for coating, and AISC for structural fabrication) and shall include but not be limited to the following: ***** CIVIL WORKS ***** · Site Preparation: ·<(>,,<)>Clear, level, and grade the designated area. ·<(>,,<)>Remove debris, vegetation, and obstacles. ·<(>,,<)>Mark layout as per approved drawings and ensure accurate positioning. · Foundation Works: ·<(>,,<)>Excavate for foundations/pedestals to required depth considering soil conditions. ·<(>,,<)>Provide lean PCC bedding and cast RCC pedestals with anchor bolts (J-bolts) fixed in correct alignment. ·<(>,,<)>Ensure pedestals are cured properly for structural strength	<u>KG</u>	1.000			



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	3
RFQ No	OP-20075AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018445

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of Car Parking Shed at Sihala Installation

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	before steel erection. Structural Steel Fabrication All structural members shall be fabricated using high-quality steel as per specifications given below, ensuring straightness, accurate cutting, and proper welding as per AWS D1.1 standards. S. No<(>,<)>Component<(>,<)>Specification<(>,<)> Dimensions<(>,<)> 1<(>,<)>Base Pole<(>,<)>6 in 10 SWG<(>,<)>8#10 ft (as required)<(>,<)> 2<(>,<)>Cantilever Truss Top Pipe<(>,<)>3 in 12 SWG<(>,<)>20 ft<(>,<)> 3<(>,<)>Cantilever Truss Bottom Pipe<(>,<)>3 in 12 SWG<(>,<)>17 ft<(>,<)> 4<(>,<)>Central Purlins<(>,<)>3 in 14 SWG<(>,<)>18 ft 4 in<(>,<)> 5<(>,<)>Truss Connector Pipe<(>,<)>2 in 16 SWG<(>,<)>18 in # 4 in<(>,<)> 6<(>,<)>Truss Top Support<(>,<)>2 in 14 SWG<(>,<)>45 in<(>,<)> 7<(>,<)>Metal Plate Base<(>,<)>16 mm<(>,<)>18 in × 18 in<(>,<)> 8<(>,<)>J Bolts<(>,<)>24 mm<(>,<)>30 in<(>,<)> Roofing and Cladding Fabric Roofing: ·<(>,<)>Supply and install 820 GSM tensile fabric (UV-resistant, waterproof) in size 24 ft × 17 ft. ·<(>,<)>Fix fabric with 6 mm metal wire and 8 mm Aluminium channels ensuring uniform tension and wrinkle-free installation. ·<(>,<)>Provide edge trimming, rainwater run-off slope, and drainage arrangements. Surface Treatment and Painting · Perform surface preparation by sandblasting/cleaning to remove rust and contaminants. · Apply 1 coat of anti-corrosive epoxy primer followed by 2 coats of PU/epoxy finish paint, complying with ISO 12944 coating standards for long-term corrosion protection.					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan

Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	3
RFQ No	OP-20075AM	
DATE	30.09.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018445

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

16.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Construction of Car Parking Shed at Sihala Installation

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	· Color shade to be approved by the client before final application. ----- TERMS AND CONDITIONS ----- 1- Rates must be inclusive of all govt. levies and taxes. 2- Quality is the prime concern of PSO and only 1st class approved material after acquiring approval from Terminal Engineer/Location Incharge to be installed. 3- Vendor must visit the site for assessing the required components before quoting rates. 4- Contractor should strictly follow the safety and security rules of PSO. Contractor to follow Company's rules and procedures as well as HSE guidelines and safety procedures. Contractor will provide and ensure usage of PPEs i.e.<(>,<)> Safety Shoes, Goggles, Helmets, Safety Harness, Safety Belts etc during execution of work. HSE Manual & Instructions are provided for information & compliance. 5- All service, tools (nonferrous if required), first aid box, ladder materials, consumables and transportation required for execution of work to be arranged and provided by contractor. 6- As the quantities may vary (increase or decrease according to the job requirements), therefore, payment will be made as per actual quantity of work done. 7- Work is subject to inspection of Terminal Engineer/Location Incharge. 8- Work has to be completed within 30 Days after issuance of service order. 9- In the event of Contractor's / Supplier failure to deliver the Services / Goods within the time mention in Purchase Order / Service Order value per day as liquidated damages for the period which the said services / material remains incomplete or fails to pass the quality tests subject to a maximum 10% of Work Order amount to be recovered from the contract on his default.					