



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	5
RFQ No	RF20086SZ	
DATE	05.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018485

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

21.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Removal, and Reinstallation of Signages at NVROs North Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Signage Installation Works</u>	<u>PSO House</u>				
1.01	<u>Signage Miscellaneous</u> SAFE REMOVAL OF SIGNAGE ITEMS INCLUDING FACIA ACM/FACIA STRUCTURE ,BLUE BARS,LED RODS, SPREADERS, FRAMES COMPLETE SIGNAGE AT SITE; Job includes: 1. Complete and safe removal/dismantling/uninstalling of existing Blue-bars from the canopy structure and keeping on a safe place (to be re-used). 2. Safe removal of tube rods, holders and wiring from the structure and keeping on a safe place (to be re-used). 3. Safe Removal of existing Aluminum Composite Material (ACM) from the Canopy Structure and keeping on a safe place (to be re-used). 4. Removal of signage supporting Structure including L/Z & Lapping Sheet from the canopy and keeping on a safe place. 5. Removal of other Signage items i.e , Wall Logo complete with frames, Logos etc. as directed by Engineer in charge HERE Unit of Measure for JOB is EA (No. of site)		<u>JOB</u>	20		
1.02	<u>LOADING AND TRANSPORTATION</u> SAFE LOADING, TRANSPORTATION AND TRANSPORTATION OF SIGNAGE ITEMS AS PER INSTRUCTIONS OF ENGINEER INCHARGE Job Includes; 1- Safe loading of the retrieved signage in available Vehicle for transportation. 2- Transportation of these items to the site as directed by Engineer incharge 3- Safe Unloading and placement at site All job to be done in such a way that no damage occurs to the delicate signage items Here EA = Complete JOB Note: Within radius of 120KM will be counted as 1 (More than 120Km will be counted as 2)		<u>JOB</u>	20		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	5
RFQ No	RF20086SZ	
DATE	05.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018485

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

21.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Removal, and Reinstallation of Signages at NVROs North Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	<u>Supply and Installation of Blue Bar</u> RE-INSTALLATION OF SIGNAGE INCLUDING FACIA ACM ,FACIA STRUCTURE, BLUE BARS,LED RODS; 1. JOB INCLUDE REMOVAL & DISMANTLING OF EXISTING SIGNAGE AT SITE (To be placed at safe place as directed by Engineer Incharge) 2. Installing/Welding the 16-SWG pipe frame of 3/4"*3/4", 1-1/2"*3/4"(as per PSO approved specification 3. Applying two coats of Red Oxides and two coats of Enamel Paint (Smoke Gray) on the pipe frame (scrapping and finishing included). 4. Routing, cutting, bending and installation of old ACM sheets (in PSO approved specification). Note: Supply of All connectors, holders, hooks and other joining material is included in the scope as per satisfaction of engineer in charge. 5. Installation of L and Z channel on the installed pipe frame as per drawing (Annexure-02) 6. Complete wiring for canopy fascia for LED Rods and canopy logo. Complete Wiring of Canopy Fascia by providing and laying Wire 3/0.29 for LED tube rods in duct strip with proper dressing. Wiring will be laid on as required basis. At least 05 Nos circuit loops to be laid for canopy fascia. Only PSO approved cables brands are acceptable for the job. 7. Installation of old blue with acrylic end covers on both sides of the blue bar, applying PSO blue vinyl over the covers from both sides, making the side covers free from blue taping, and reinstalling them in their original position. After installation of LED Tube rods (removed earlier/Provided by PSO) and wiring works.		ET	3,800		
1.04	<u>SHOP STOP SIGN</u> Shop Stop Signage removal/shifting and transportation complete in all respect.		EA	16		
1.05	<u>Supply and Installation of Spreader</u> Providing Services for installation of existing Nameplate, Wall logo,		EA	20		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	5
RFQ No	RF20086SZ	
DATE	05.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018485

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

21.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Removal, and Reinstallation of Signages at NVROs North Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.06	spreaders, IN & OUT sign, Tyre shop sign, carwash / autocare sign, tank and office area signages as per site requirements complete in all respect. JOB-EA (EA is equivalent to one NVRO station). Means Quantity of this item represent number of site(s) Signage Miscellaneous Providing and pasting of vinyl of Signage items i.e Blue bars(>,<)> Spreaders, nameplates etc. The scope of work includes removal of vinyl and pasting of new approved vinyl on the existing spreaders/name plate/bluebar as per pso approved specifications The job includes printing/plotting and pasting of new brand name with approved vinyl (3M or equivalent) as per site requirement of approved PSO color all respects; TERMS AND CONDITIONS 1. All material `services and tools are included in the scope. 2. Contractor to mobilize multiple team simultaneously for execution of work Time frame will be 5 days for removal of signage from date of go-ahead and 10 days for installation of signage. And 120 Days for the complete PO. If the Contractor fails to complete the work with in stipulated time, the Engineer In charge will be entitled to deduct from his bills for work given in this order or other payments due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of Work Order/per site(>,<)> Housekeeping of the workplace is sole responsibility of contractor (>,<)> removal of scrap/debris and other waste material to be done on daily		JOB	1,400		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	5
RFQ No	RF20086SZ	
DATE	05.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018485

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

21.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Removal, and Reinstallation of Signages at NVROs North Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	basis after completion of daily job. In any case the waste material/debris or any material reporting lying at site, the contractor will be liable to pay penalty amounting Rs.50,000/- per site on each warning. 3. Contractor to submit before and after pics. of each activity (i.e. Numbers wise for each activity mentioned in item 01 TO 06 respectively) with the submission of bill. 4. Any damages occurred while uninstalling and re-installing any item (i.e. ACM, Blue-bars LED rods, holders and others) will be reimbursed by the contractor without any extra charges. 5. The contractor needs to ensure all necessary HSE precautionary measures (i.e. JHAs and as instructed by Divisional Engineer as per PSO policy) before executing the job. 6. Cleaning of the site and removal of waste recovered from the job is the sole responsibility of contractor. Neat and clean area of work must be ensured before submitting the bill. 7.The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 8. All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 9. Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required License/certification of it. 10.Wherever applicable, contractor is bound to engage					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	5
RFQ No	RF20086SZ	
DATE	05.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018485

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

21.10.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Removal, and Reinstallation of Signages at NVROs North Zone

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	certified licensed electrician for electrical works. 11. Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm, etc.) For any special case, approval from DE will be required and work will be performed under supervision of DE. 12. The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines <(>,<)> overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment.					