



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

1	OF	5
RFQ No	RF20129SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018776

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Upgradation of Fascia Signage Works at Various NVROs of Islamabad Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	<u>Upgradation of Fascia Signage at NVROs</u>	<u>PSO House</u>				
1.01	<u>Supply and Installation of Blue Bar</u> SUPPLY & FABRICATION OF ACRYLIC BLUE BAR Acrylic Light Bar Supply and fabrication of Acrylic light bar in 5mm thick Acrylic sheet. The light bar is to be moulded to shape as per sketch (PSO Dwg No: S-006 Rev:5) 3M film i.e. 3M (3630 VT 1986) /Avery CC (5500-763 Blue)/Equivalent should be applied by a qualified and approved converters / applicator. Both ends acrylic bars to be covered with Acrylic End caps having grooves for LED lights as per instruction of Engineer. Warranty 5 Years List of Sites is as follow; (Sites may change as per instruction of Engineer) 1- M/S Miraj F/S - 272 RFT 2- M/S Daud F/S - 272 RFT 3- M/S Tarnaul F/S- 212 RFT 4- Malik Mehar F/S- 160 RFT 5- M/S Saaghri F/S- 100 RFT 6- M/S Mian F/S- 184 RFT		<u>ET</u>	1,200		
1.02	<u>Signage Miscellaneous</u> Supply & Installation of L+Z channels (Both) for blue bars I/C Transportation charges Job Includes: (UOM is RFT) L-Channel for Canopy Signage		<u>JOB</u>	800		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

2	OF	5
RFQ No	RF20129SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018776

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Upgradation of Fascia Signage Works at Various NVROs of Islamabad Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.03	Providing and Fixing aluminium 'L' channels for Canopy Signage structures (as per PSO approved specification, refer to drawing No.S-006, Rev.05 dated 05-05-2017) Z-Channel For Canopy Signage Providing and Fixing aluminium 'Z' channels for Canopy Signage structures (as per PSO approved specification, refer to drawing No.S-006, Rev.05 dated 05-05-2017) List of Sites is as follow; (Sites may change as per instruction of Engineer) 1- M/S Miraj F/S 2- M/S Daud F/S 3- M/S Tarnaul F/S 4- Malik Mehar F/S 5- M/S Qureshi F/S 6- M/S Malik P/S					
	Supply and Installation of Blue Bar Providing and pasting of vinyl of blue bars. The scope of work includes safely removal OF existing blue bars, removal of existing vinyl tape from blue bars and providing and pasting of new approved vinyl on the bluebar as per pso approved specifications The job includes printing/plotting and pasting approved vinyl (3M or equivalent) as per site requirement of approved PSO color complete in all respects. Sites can be changed as per Engineer Incharge.		BT	600		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

3	OF	5
RFQ No	RF20129SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018776

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Upgradation of Fascia Signage Works at Various NVROs of Islamabad Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1.04	List of Sites is as follow; (Sites may change as per instruction of Engineer) 1- M/S Qureshi F/S 2- M/S Madina F/S 3- M/S Taxila F/S 4- M/S MUSA F/S Signage Miscellaneous P<(>&<)>I OF END CAPS FOR BLUE BARS AT NVROs Job Includes; The scope of work includes safe removal of existing blue bars<(>&<)> Fixing of End caps (having proper grooves for LED rods as per instruction of Engineer In-charge) Re-Installation of BBs in Cahnnels as per instruction of Engineer Incharge; List of Sites is as follow; (Sites may change as per instruction of Engineer) 1- M/S Musa F/S 2- M/S Nadir F/S 3- M/S Nadir F/S 4- M/S Qureshi F/s 5- M/S Saaghri F/S 6- M/S Sarhad F/S TERMS AND CONDITIONS:		JOB	300		



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

4	OF	5
RFQ No	RF20129SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018776

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Upgradation of Fascia Signage Works at Various NVROs of Islamabad Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	1. Contractor will be responsible for the removal / disposal of debris outside retail outlet premises as per the instruction of the engineer incharge. 2. Contractor will provide adequate and fully functional PPEs to all workers and ensure their proper safety. 3. The contractor must follow all HSE standards laid down by PSO. They must also abide by any other instructions / notifications issued by the company from time to time. Contractor will be responsible to ensure risk assessment, undertake steps to mitigate risk and work planning for the high risk jobs. Contractor will be responsible to ensure usage of all applicable good quality PPEs (i.e. Safety Shoes, Gloves, Helmets<(>,<(> Google, Safety harness, etc) during execution of work. PSO reserves the right to terminate the contract on non-compliance/violation of HSE instructions given by PSO to the contractor. 4. The contractor must ensure to cordon off the specific area where work is in progress and must take all necessary measures to ensure safety of outlet staff and specially customers. 5. All tools, equipment used by the contractor must be properly maintained and remain HSE compliant. 6. Scaffolding, safety harness, crane, lifter, welding plant and miscellaneous electrical equipment (where required) must be third party certified and the operator/worker should have required license/certification of it. 7. Wherever applicable, contractor is bound to engage certified/ licensed electrician for electrical works. 8. Contractor will not start/continue the works after sunset or during unusual weather conditions (like heavy rain fall, thunderstorm, etc.).					



Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

PAGE

5	OF	5
RFQ No	RF20129SZ	
DATE	22.10.2026	

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)

SAP No.6100018776

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON
(Date)

03.11.2026

BY
(Time)

Please quote your best price for all items of following specifications. Please read the instructions attached herewith Rs. _____ EARNEST MONEY %
PO/DD NO. _____

Title: Providing Services for Upgradation of Fascia Signage Works at Various NVROs of Islamabad Division

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	For any special case, approval from DE will be required and work will be performed under supervision of DE. 9.The contractor must ensure that the "work area" and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines, overhead obstructions, and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 10.The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in #no smoking# area, etc) during work. Contractors will also ensure proper work planning and risk assessment prior to start of work. 11.The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 12.The contractor shall indemnify PSO, its offices, employees, agents and representatives from and against all losses, costs, penalties<(>,<)> fines, damages, claims or liabilities arising out of, resulting from or in connection with services contemplated by this contract. 13.Contractor shall be responsible to rectify any damage that occurs to PSO property during execution of work without charging any cost to PSO.					