Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Quick Oil Change Canopy** QUICK OIL CHANGE CANOPY (SOUTH ZONE i.e. Karachi, Hyderabad, Sukkur, Quetta). Quick Oil Change Canopy as per drawings and below mentioned specification: - Oil Change Canopy Providing/Fabrication of ACM/ Fiber Glass Oil Change Canopy with all required mechanical, electrical and signage/graphics works complete in all respect. - Size: 10ft x 10ft x 11ft approx. as per set of drawings attached. - Composition / Material: -- Steel / MS Structure as per approved design. -- Roof Ceiling Top (3mm corrugated fiberglass sheet). -- Signage/Graphics works of Acrylic / Vinyl / Flexible Substrate. -- LED Lights / Module - Electrical Accessories - - Colors: Color references will be provided by PSO at the time of fabrication. - Steel Structure: Supply and Fabrication of Steel structure as per approved standards and set of drawings and specs including all trusses, purlins, runner, columns, studs, bolts and all other steel structure. All welding electrodes shall conform to the latest edition of American Welding Society and ASTM 233. The electrodes should have a minimum yield strength of 60,000 psi and ultimate strength of 73,000 psi. - Job includes Mechanical cleaning of all steel structure members by using hand tools up to the Swedish Standard of SSPC-SP10 and supply and application of minimum two coats of Red Lead Primer to DFT of 50 microns and finish coat of enamel paint of same make to DFT of 50 microns in smoke grey colour in a minimum of two coats. - All steel structure shall be painted before erection and finally touched after erection for required finishing. Signage: Supply of 3D fascia Signage "auto care" as per approved design and artwork lighted with LED module. Acrylic channel letters in 3mm thick milky white 2.5" collar/depth	**PSO House**	**EA**	50		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	backlit with LED modules on 1" clear acrylic / foam board / equivalent back frame material at the back with complete fixtures. The job also includes supplying and installation of fiberglass casing and 3D PSO logo moulded in 3mm thick acrylic milky white as per approved design and artwork lighted with LED module on 1" clear acrylic / foam board / equivalent back-frame material at the back with complete fixtures. The job also includes vinyl pasting on PSO Logo using PSO approved colours. Supply and installation of 3mm acrylic white pasted vinyl of approved color as per drawing with LED back light. Supply of Acrylic angular bar 3mm thick milky white 2.5" collar/depth backlit with LED modules on 1" clear acrylic / foam board / equivalent back frame material at the back with complete fixtures The job includes all electrical connections required for lighting the logo and bar. Supply and installation of 2mm Aluminium back tray with 3"to 4" depth. Supply and installation of 4mm ACM with .3 AL on both sides of approved color on the fascia with 3D cut out letters. The ACM with back tray to be provided on perimeter of the canopy Note The name "AUTO CARE", or similar name and its graphics will be provided later on **********LED modules specifications**********					

Pakistan State Oil Company Limited

PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Color: WHITE Color Temperature 6000-10,000 Kelvin (Cool day light) Color Rendering Index 80 or above Luminous efficacy 100 Lumens / watts or above IP 67 or above L50 Life time is 50,000 Hours Operating Environment -10°C to + 55°C or above lumens/module >= 80 lumens or above Watt/ Module <= 1.2 W nominal Certification: CE/UL/IEC approved or equivalent Warranty: 3 years replacement warranty Backing tray for LED module fixing **********POWER SUPPLY/ LED Driver********** Input Voltage Range AC: 230V +/- 20% Output Voltage Range DC: 12V +/- 10% Power factor >= 0.90 Output Power DC: 150W or above (as per requirement) Efficiency 85% or above Over temperature protection, Overload protection and Short-circuit protection Operating temperature: -10°C to + 55°C or above IP -65 or above Certification: CE/UL/IEC approved or equivalent Warranty: 3 years replacement warranty ----- Roof: Supply & installation of corrugated 3mm fiberglass sheet with necessary fittings. Electrical Works: Supply of following items including all materials, labor, tools and accessories, complete in all respects ready to operate. Job includes all wiring to be done in PVC conduit of specified/appropriate size concealed in wall/column/ceiling. Contractor to submit samples of conduits<(>,<)> fittings, junction boxes, switches sockets for approval. - Circuit Wiring from distribution board to Switchboard = 2x2.5 sq.mm. + (Earth					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Continuity Conductor) ECC 1x2.5 sq.mm 1-core PVC insulated wires. - Wiring of lighting point to switch with 1.5 sq.mm 1-core wires for ECC green in colour and 2- 2.5 sq.mm common Neutral, <(>&<)>Live including 16 SWG sheet steel back boxes. circuit. # Provide and install a suitable weatherproof socket board on the 4# × 4# column within the oil change canopy. # All electrical wiring shall be routed through suitable flexible protective conduit, neatly concealed/routed along the column and canopy structure, with proper fittings and terminations. # The socket board shall be suitably rated for the intended electrical loads and protected against dust and water ingress, as appropriate for the installation environment. # All required wiring, accessories, and electrical connections shall be provided as necessary to ensure safe and reliable operation other connected equipment. # The complete installation shall comply with applicable electrical safety requirements Column Guard Supply and install heavy-duty, high-impact-resistant natural/synthetic rubber column guards, 10#12 mm minimum thickness, with yellow reflective strips for high visibility. Guards shall be suitable for the column dimensions<(> ,<)>					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	resistant to weathering, oil and abrasion, and securely fixed using manufacturer- recommended mechanical fasteners or an approved adhesive system. Provide full protection to exposed column corners or faces within the vehicle impact zone<(>,<)> including all necessary fittings and installation. Supply & Installation of Ceiling Fan: Supply and installation of 56-inch energy-efficient inverter/BLDC ceiling fan<(>,<)> 220#240V AC, 50 Hz, with weather-resistant construction and suitable mounting arrangement with necessary wiring point wiring from switch board. ----- Earthing: Supply of 20 mm diameter 99% copper earthing electrode (10 ft. Length) directly driven in ground including earthing leads up to earth connecting point/ DB and inspection chamber. To be done as per drawing and instruction of Engineer including earthing leads upto earth connection point/DB. Include installation at site ----- LED Panel: (min.6a Panels each canopy) LED light panel in ceiling of canopy as per following specifications: Class Ingress Rating: IP 65 or above LED panel size : 1 ft x 1 ft Operating temperature: -10 deg. C to + 50 deg. C Colour: Neutral White/Daylight White, colour temperature 4000K#5000K, or as per approved 3D design and PSO Engineer's approval.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Total Lumens : 3240 Lumens or above / 36W Accessories: Ceiling-Mounting accessories along with wiring. Operating Voltage: 12 V DC Life Span: 45000 hours or greater Approvals/Certifications: CE or UL/IEC or equivalent. The job includes all electrical connections and wiring. Note: The contractor shall be capable of undertaking the simultaneous construction of min. 9 canopies per month i.e. within 30 calendar days from the date of go-ahead.					
2	**Quick Oil Change Canopy** XPRESS OIL CHANGE CANOPY (SOUTH ZONE i.e. Karachi, Hyderabad, Sukkur, Quetta) Xpress Oil Change Canopy as per drawings and below mentioned specification Oil Change Canopy Providing/Fabrication of ACM/ Fiber Glass Oil Change Canopy with all required mechanical, electrical and signage/graphics works complete in all respect. Size: 6 ft x 6 ft x 11ft approx. as per set of drawings attached Composition / Material: - Steel / MS Structure as per approved design - Walls 4mm ACM on Back side dual. - Roof Ceiling inside (Gypsum board ceiling as per design mentioned in drawings) - Roof Ceiling Top (3mm corrugated fiberglass sheet) - Wall, Roof Framing. - Signage/Graphics works of Acrylic / Vinyl / Flexible Substrate - LED Lights / Module -Electrical Accessories -Tempered Glass 8mm / 12mm -Floor Tiles Colors:	**PSO House**	**EA**	4		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Color references will be provided by PSO at the time of fabrication. ACM: Supply & installation of 4mm ACM of approved color, having thickness of Aluminum sheet 0.3 mm each side. The ACM to be installed on back walls as per approved drawing. Fabrication of Shelves from ACM with necessary structure to hold 10KG load per shelves as per drawing. Steel Structure: Supply and Fabrication of Steel structure as per approved standards and set of drawings and specs including all trusses, purlins, runner, columns, studs<(>,<)> bolts and all other steel structure. All welding electrodes shall conform to the latest edition of American Welding Society and ASTM 233. The electrodes should have a minimum yield strength of 60,000 psi and ultimate strength of 73,000 psi. Job includes Mechanical cleaning of all steel structure members by using hand tools up to the Swedish Standard of SSPC-SP10 and supply and application of minimum two coats of Red Lead Primer to DFT of 50 microns and finish coat of enamel paint of same make to DFT of 50 microns in smoke grey colour in a minimum of two coats. All steel structure shall be painted before erection and finally touched after erection for required finishing. Signage: Supply of 3D fascia Signage "Xpress Care" as per approved design and artwork					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	lighted with LED module. Acrylic channel letters in 3mm thick milky white 2.5" collar/depth backlit with LED modules on 1" clear acrylic / foam board / equivalent back frame material at the back with complete fixtures. The job also includes supplying and installation of fiberglass casing and 3D PSO logo moulded in 3mm thick acrylic milky white as per approved design and artwork lighted with LED module on 1" clear acrylic / foam board / equivalent back-frame material at the back with complete fixtures. The job also includes vinyl pasting on PSO Logo using PSO approved colours. Supply and installation of 3mm acrylic white pasted vinyl of approved color as per drawing with LED back light. Supply of Acrylic angular bar 3mm thick milky white 2.5" collar/depth backlit with LED modules on 1" clear acrylic / foam board / equivalent back frame material at the back with complete fixtures The job includes all electrical connections required for lighting the logo and bar. Supply and installation of 2mm Aluminium back tray with 3"to 4" depth. Supply and installation of 4mm ACM with .3 AL on both sides of approved color on the fascia with 3D cut out letters. Note The name "Xpress Care", or similar name and its graphics will be provided later on					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	**********LED modules specifications********** Color: WHITE Color Temperature 6000-10,000 Kelvin (Cool day light) Color Rendering Index 80 or above Luminous efficacy 100 Lumens / watts or above IP 67 or above L50 Life time is 50,000 Hours Operating Environment -10°C to + 55°C or above lumens/module >= 80 lumens or above Watt/ Module <= 1.2 W nominal Certification: CE/UL/IEC approved or equivalent Warranty: 3 years replacement warranty Backing tray for LED module fixing **********POWER SUPPLY/ LED Driver********** Input Voltage Range AC: 230V +/- 20% Output Voltage Range DC: 12V +/- 10% Power factor >= 0.90 Output Power DC: 150W or above (as per requirement) Efficiency 85% or above Over temperature protection, Overload protection and Short-circuit protection Operating temperature: -10°C to + 55°C or above IP -65 or above Certification: CE/UL/IEC approved or equivalent Warranty: 3 years replacement warranty ----- Ceiling: Supply and Installation of Gypsum Board in False ceiling of white color with 2- in profile light of 4000K as per drawing. Roof: Supply & installation of corrugated 3mm fiberglass sheet with necessary fittings. Electrical Works: Supply of following items including all materials, labor, tools and accessories, complete in all respects ready to operate.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Job includes all wiring to be done in PVC conduit of specified/appropriate size concealed in wall/column/ceiling. Contractor to submit samples of conduits<(>,<)> fittings, junction boxes, switches sockets for approval. - Circuit Wiring from main to Switchboard = 2x2.5 sq.mm. + (Earth Continuity Conductor) ECC 1x2.5 sq.mm 1-core PVC insulated wires. - Wiring of lighting point to switch with 1.5 sq.mm 1-core wires for ECC green in colour and 2- 2.5 sq.mm common Neutral, <(>&<)>Live including 16 SWG sheet steel back boxes. circuit. - Wiring for 15- Amp switch socket = 3 x 4 sq.mm in PVC conduit from distribution board All wires are of 600/1000 V and with PVC insulation BS-6346 "Electrical Cables PVC insulated" or equivalent compliant. The c # Provide and install a suitable weatherproof socket board on the column or location advised by divisional engineer within the oil change canopy. # All electrical wiring shall be routed through suitable flexible protective conduit, neatly concealed/routed along the column and canopy structure, with proper fittings and terminations. # The socket board shall be suitably rated for the intended electrical loads and protected against dust and water ingress, as appropriate for the installation environment. # All required wiring, accessories, and electrical connections shall be provided as necessary to ensure safe and reliable operation other connected equipment.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	The complete installation shall comply with applicable electrical safety requirements ------- LED Running Profile Light (Front Fascia and Columns): Class Ingress Rating: IP 65 or above LED panel size: 1 in Operating temperature: -10 deg. C to + 50 deg. C Color: Colour: Warm Yellow/Golden Amber, colour temperature 2200K#3000K for warm white LED, or equivalent amber LED, as per approved 3D design and PSO Engineer's approval. Total Lumens: Minimum 600 lumens per running metre for warm white LED profiles<(>,<)> or suitable equivalent luminous intensity for amber LED profiles, ensuring continuous and uniform illumination without visible dark spots. Accessories: Chain-link along with wiring. Operating Voltage: 12 V DC Life Span: Minimum 50,000 operating hours (L70 rated). Approvals/Certifications: CE or UL/IEC or equivalent. The job includes all electrical connections and wiring. Power Supply to be installed as per the specs mentioned in signage. ----- - Earthing: Supply of 20 mm diameter 99% copper earthing electrode (10 ft. Length) directly driven in ground including earthing leads up to earth connecting point/ DB and inspection chamber. To be done as per drawing and instruction of Engineer including earthing leads upto earth connection point/DB. Include installation at site					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.

	LED Panel: (min. 4 Panels each canopy)					
	LED light panel in ceiling of canopy as per following specifications:					
	Class Ingress Rating: IP 65 or above					
	LED panel size : 1 ft x 1 ft					
	Operating temperature: -10 deg. C to + 50 deg. C					
	Colour: Neutral White/Daylight White, colour temperature 4000K#5000K, or as per approved 3D design and PSO Engineer's approval.					
	Total Lumens : 3240 Lumens or above / 36W					
	Accessories: Ceiling-Mounting accessories along with wiring.					
	Operating Voltage: 12 V DC Life Span: 45000 hours or greater					
	Approvals/Certifications: CE or UL/IEC or equivalent. The job includes all electrical connections and wiring.					
	Note: The contractor shall be capable of undertaking the simultaneous construction of min. 4 canopies per month i.e. within 30 calendar days from the date of go-ahead.					
3	**Oil Change Canopy (South)**	**PSO House**				
3.01	**Oil Change Canopy (Single Bay)**		**EA**	50		
	Transportation and installation of Oil Change Canopy (10ft x 10ft x 11ft) as per drawings and below mentioned specification					
	Construction of Foundation:					
	Foundation to be done as per drawing Foundation (2# × 2# × 2# Depth)					
	Description of Work Excavation in normal soil for foundation including dressing and disposal.					
	PCC (1:4:8) under foundation.					
	RCC Foundation (1:2:4) including mixing, pouring & vibration.					
	Reinforcement steel (approx.) including cutting, bending & binding.					
	Shuttering / formwork for foundation.					
	Anchor bolts / base plate fixing (if required) Backfilling with excavated soil including compaction					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.

	Flooring Provide and apply a 6 mm thick heavy-duty epoxy flooring system comprising epoxy primer, epoxy screed/body coat incorporating graded silica aggregate, and a chemical-resistant epoxy seal/topcoat. The system shall be resistant to engine oil, lubricants, grease, diesel spills and abrasion. The finished surface shall have a uniform anti-slip texture suitable for vehicle traffic and oil change operations, applied over properly prepared concrete in accordance with the manufacturer's recommendations. Example of branded products available in Pakistan: Sika # Sikafloor®-161 (primer), Sikafloor®-263 SL (epoxy binder) and Sika floor®-264 (epoxy seal coat); or Ressichem # three-component heavy-duty epoxy flooring system or equivalent. # Complete job shall include surface preparation as per manufacturer recommendation, materials, labour, tools, equipment, application and curing, complete in all respects to the satisfaction of PSO Engineer.					
3.02	**Installation of cable size 10 sq. mm,Sin** - Provision and installation of 3 Core 10 sq.mm cable. - Connection to be made with DB or nearest connection point. - Payment to be made on the basis of actual utilization. - Scope of work includes removal and relaying of pavers.		**M**	810		
3.03	**Oil Change Canopy (Mini Bay)** Transportation and installation of Express Oil Change Canopy (6ft x 6ft x 11ft) as per drawings and below mentioned specification Construction of Foundation: Foundation to be done as per drawing Foundation (2# × 2# × 2# Depth) Description of Work Excavation in normal soil for foundation including dressing and disposal. PCC (1:4:8) under foundation. RCC Foundation (1:2:4) including mixing, pouring & vibration. Reinforcement steel (approx.) including cutting, bending & binding. Shuttering / formwork for foundation. Anchor bolts / base plate fixing (if required) Backfilling with		**EA**	4		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	excavated soil including compaction --- Flooring Provide and apply a 6 mm thick heavy-duty epoxy flooring system comprising epoxy primer, epoxy screed/body coat incorporating graded silica aggregate, and a chemical-resistant epoxy seal/topcoat. The system shall be resistant to engine oil, lubricants, grease, diesel spills and abrasion. The finished surface shall have a uniform anti-slip texture suitable for vehicle traffic and oil change operations, applied over properly prepared concrete in accordance with the manufacturer's recommendations. Example of branded products available in Pakistan: Sika # Sikafloor®-161 (primer), Sikafloor®-263 SL (epoxy binder) and Sika floor®-264 (epoxy seal coat); or Ressichem # three-component heavy-duty epoxy flooring system or equivalent. # Complete job shall include surface preparation as per manufacturer recommendation, materials, labour, tools, equipment, application and curing, complete in all respects to the satisfaction of PSO Engineer. ========== SPECIAL TERMS & CONDITIONS: 01. Canopy works at a site shall be commenced by the contractor within 03 days after the go-ahead for site and shall be completed passing the quality tests in 12 days' time, total 15 days for each site. 02. Payment of each site will be done through Running Bills as per actual work done at site and verified by PSO Site Engineer. 03. Contractor will develop 3D drawing containing the details of artworks of signage works for the approval prior to start of work. 04. Contractor will be responsible for provision of all facilities required for the erection of canopies e.g. electrical connections, material for civil works. 05. PSO reserves the right to terminate the contract by giving one month notice if the performance of contractor will be found "poor". 06. Contractor shall carry out detailed job hazard analysis before carrying out the job.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	07. The contractor shall inform the site dealer / Engineer at least 2 to 3 days before mobilization at site so the necessary arrangements can be made. 08. installation of components of canopy at site and the contractor shall be liable to rectify/remove any defects occur during transportation/installation. 09. The transportation of components from contractor's workshop to site will be carried out in slake hours to avoid any untoward situation. 10. All tools, equipment and vehicles used by the contractor must be properly maintained and remain PSO HSE compliant during the whole contract period. 11. The contractor must ensure that the 'Job site' and other conditions are inspected and evaluated to determine ground conditions or strength of supporting structure, proximity of electric power lines<(>,<)> overhead obstructions<(>,<)> and wind conditions. The contractor must ensure to mitigate (if any of the unfavorable condition exist) and plan work execution accordingly. The contractor must ensure safe placement and connection of their equipment. 12. The contractor will be responsible to ensure continuous supervision of their staff activities during work. Staff should not get involved in unethical or illegal activities (consuming illegal drugs, smoking in 'no smoking' area<(>,<)> etc.) during work. Contractors will also ensure proper work planning and risk assessment. 13. The contractor will be responsible to train their staff on regular basis on fire fighting, First Aid and safe procedures to carry out work (specifically for electrical & work at height). 14. The contractor shall be fully responsible for any accident (fatal or otherwise) caused while executing work for himself or his representatives. In all such cases, compensation payable to the claimant shall be on the contractors account and contractor shall keep PSO absolutely indemnified and free from such responsibility. 15. The contractor will have to cordon off the site before carrying out the job. 16. PSO property during execution of work without charging any cost to PSO.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	17. The contractor must follow all HSE standards laid down by the Company and any other specific guidelines or HSE instructions available in their work orders lined with company's Safety Booklet. They must also abide by any other instructions / notifications issued by the company from time to time. 18. Contractor should strictly follow the safety and security rules of PSO. Contractor to follow Company's rules and procedures as well as HSE guidelines and safety procedures. Contractor will provide and ensure usage of PPEs i.e. Safety Shoes, Gloves, Helmets, Goggles, Safety Harness, Safety Belts etc. during execution of work. Construction Safety Booklet, Electrical Safety Booklet, JHA's & Instructions are provided for information & compliance. 19. All service, tools (non-ferrous if required), first aid box, ladder <(>,<)> materials and transportation required for execution of work to be arranged and provided by contractor. 20. As the quantities may vary (increase or decrease according to the job requirements), therefore<(>,<)> payment will be made as per actual quantity of work done. However, part payment on part delivery is permissible. 21. The work will only be accepted after inspection and approval by the Engineer In-charge. 22. Contractor should maintain housekeeping of the worksite during progress of work and shall clear and remove all surplus materials and rubbish from site after completion of job as per instruction of Engineer In-charge. 23. Quality is the prime concern of PSO, no compromise shall be made in conform to the WO / SO specification. 24. Terms and Conditions (C-06), JHA, Safety Booklets, Drawings <(>&<)> Specification etc. as provided, which constitute part of this contract. 25. Contractor must complete the entire project within stipulated time. 26. The Contractor/Supplier hereby represents that he has paid the requisite amount of stamp duty to the concerned revenue authority on this Purchase/service/work Order. The Contractor/ Supplier shall indemnify and hold PSO and its officials harmless against any and all					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100018890

RFQ No	RC-20161IA
DATE	04.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	16.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Supply of Quick and Xpress Oil Change Canopies at PSO Retail Outlets - South Zone.

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	claims raised by the concerned revenue authority or any other authority, established under the law for the time being in force, in respect of any deficiency or non-payment of stamp duty or penalty on this Purchase/service/work Order. 27. PENALTY FOR DELAY i) Applicability: - If the Contractor fails to complete work or delivery at any Site by the Scheduled Completion Date for that Site, specified in section 1.3, the Contractor shall be liable to pay Liquidated Damages (LD). The Scheduled Completion Date for a Site shall stand extended, and no LD shall accrue for the corresponding period, where the delay is directly attributable to PSO. ii) Rate and Cap: - LD shall be levied at the rate of Rs. 2,700/- (Rupees Two Thousand Seven Hundred only) per day of delay<(>,<)> per Site, computed from the day immediately following the Scheduled Completion Date of that Site until actual completion/acceptance, subject to a maximum cap of 10% (ten percent) of the Work Order. This cap shall apply independently to each Site and shall not be aggregated across Sites. iii) Mode of Recovery: - LD amounts, once accrued, may be deducted from any amount payable to the Contractor against invoices raised for that Site, from Security Deposit<(>,<)> without prejudice to PSO's other rights and remedies under the contract<(>,<)> including the right to terminate. iv) Nature of LD; No Waiver of Other Remedies: - Recovery of LD does not relieve the Contractor of its obligation to complete the work, nor does it act as a cap on any other damages PSO may be entitled to for defects, non-performance, or breach unrelated to delay. The 10% cap under this clause applies only to delay-related LD. AMOUNT OF BID SECURITY: - RS. 200,000/-.					