PAFQ - 7

THE PRESIDENT OF PAKISTAN DOES NOT BIND HIMSELF TO ACCEPT THE LOWEST OR ANY TENDER

Contract No. **GC /PSC / of 2026 – 27 Job No. 2011 of 2026-27 – Provision of Officer / Unit Fur against newly Const 8x D Type Flats at 11 Corps and 1x 32 Men SM Bk AS&RC Psc Pri List Capital Works and Specific Projs – Garrison Headquarters Peshawar** The contract comprises of **20 Pages** as detailed below:-

a.	Tender Form	-	02	Pages
b.	Schedule A	-	01	Page
c.	Schedule B	-	01	Page
d.	Schedule C	-	01	Page
e.	General Specification	-	03	Pages
f.	Conditions of Contract	-	08	Pages
g.	Particular Specification	-	01	Page
h.	Notice of Tender	-	01	Page
i.	Errata Sheet	-	01	Page
j.	Drawings	-	01	Booklet
	Total	-	**20**	**Pages**

TENDER AND RUNNING CONTRACT FOR SUPPLY OF NEW FURNITURE IN **Garrison Furniture Yard Peshawar** UNDER **Garrison Commander Peshawar** *LUMP SUM TENDER AND CONTRACT FOR SUPPLY OF NEW FURNITURE FOR **– Provision of Officer / Unit Fur against newly Const 8x D Type Flats at 11 Corps and 1x 32 Men SM Bk AS&RC Psc Pri List Capital Works and Specific Projs – Garrison Headquarters Peshawar** This tender, complete with all annexure, issued to :-

M/s

is to be delivered to:

*QMG's Branch, GHQ

***Gar Comd Peshawar**

*HQ Log Area Comd, Div Comd & Station Comd

By **1200 hrs on 08 Dec 2026**

The undersigned (hereinafter called the 'contractor', which expression shall include his/their heirs and legal representative where the context so admits) hereby Offr (s) to supply, to THE PRESIDENT OF PAKISTAN (HEREINAFTER CALLED 'THE GOVERNMENT' WHICH EXPRESSION SHALL INCLUDE HIS SUCCESSORS IN OFFICE AND ASSIGNS), The articles of FURNITURE specified in the attached Schedule 'A' , at the prices shown in the said Schedule 'A' upon the terms and conditions herein set out in accordance with the drawings referred to in the said Schedule 'A' and attached hereto and the specifications annexed hereto.

_____

Signature of Contractor or his attorney

Postal Address: M/s

Witness _____ CNIC No. _____

Scanned with CamScanner

SCHEDULE B

ISSUE OF STORES TO CONTRACTORS ON PAYMENT

S/No	Particulars of Stores	Rates at which stores etc will be issued to contractor			Place of issue (By Name)
		Unit	Rs	Ps	
-	-	-	-	-	-

NOTES:

1. The contractor shall give the Operating Officer reasonable notice in writing of his requirements of Govt stores and material and on approval of his demand being notified to him, shall make immediate arrangements for the drawing of the same. Such stores and materials shall be transported by the contractor at his own expense direct from the place of issue to the place of manufacture of the furniture.

2. Surplus stores and / or materials returned by the contractor will be credited to them at a price not exceeding at which the said stores and materials were originally issued to him but due consideration shall be given and allowance claimed by Govt in respect of any depreciation or damage suffered by the stores and / or materials while in the custody of the contractor. In the event of a contractor failing to return the surplus stores and/ or material issued to him under Schedule 'B' for incorporation in the furniture but which are not actually incorporated therein, recovery will be effected from at the Stock Book rate or the market rate whichever is the higher.

_____

Contractor
M/s

Dated _____ Nov 2026

Signature of Officer
Authorized by accepting officer

Dated _____ Nov 2026

Scanned with CamScanner

SCHEDULE 'C'

SCHEDULE OF DELIVERY

S/No	Description	Unit	Qty	Date on or before by which delivery required
FQ-06	Bed Hard Single with Foam Mattress	Set	16	
FQ-88	Bed Hard Double with Foam Mattress and 2 x Side Tables Eco quality	"	8	As per Work Order
FQ-29	Dining Set (Set of 6x Chairs) Eco quality	"	8	
FQ-40	Sofa Set 5 x Seater Cushioned Eco quality	"	8	
FQ-45	Table Cen with 2 x Teapoys Eco quality	"	16	
FQ-47	Table Computer Eco quality	Nos	8	
FQ-50	Table Cook House	"	8	
FQ-08	Book Shelf Open Eco quality	"	8	
FQ-12	Chair Computer	"	8	
FQ-18	Chair Officer Visitors Eco quality	"	32	
FQ-23	Charpoy TS with Tape Newar and Pole MN Set of Four complete	"	32	

_____

Contractor
M/s

Dated _____ Dec 2026

Signature of Officer
Authorized by accepting officer

Dated _____ Dec 2026

Scanned with CamScanner

GENERAL SPECIFICATIONS

1. **Wood Work**

a. **Quality of Timber**

(1). Timber to be well seasoned, free from sap wood, dry wood borers, cracks, shakes or loose knots. All noticeable wood borers, cracks knots to be tested for looseness means of striking them with a small harmer. On economical grounds, the following limits will be followed in according knots:-

(a) Dead Impts$^{1/2''}$ in diameter and under may be neglected provided they do not exceed two per Sft or any of the surfaces, and those up to ¼" in diameter provided they do not exceed one per Sft.

b. Knots should not occur in clusters.

(1) Timber should be straight in the grain but for curved members the timber should be so selected so that as far as possible the grain conforms to the shape of the timber.

(2) Moisture content of the timber should 12% with a tolerance of plus/min 2%

(3) Hard of soft wood will be used a specified on the plan. Timber specified in the particular specification will supersede the one specified in the plans.

(4) **SOFT WOOD**. To be deodar if other kind is not stated in the plan or particular specification.

(5) **HARD WOOD**. To be shisham if other kind is not stated in the plan or particular specification

(6) **JOINTS**. All joints to fit fully and truly without wedging for filling. Plans will be joined by secret screws joints as under:-

(a) Drive a number of screws into the edge of one plank following the heads to project a little above the surface. Holes are cored at a distance of about $^{3/4"}$ in front of their actual final position in the plank to be jointed to the heads of the screws. Narrow channels about ¼" in the length are then out in the second plank, the screw. After gluing the plank is to be placed so that the screw heads enter the holes in the other piece and is then driven from the end until assumes its correct position. The heads of the screw tent to work

upwards as they out channels for themselves and thus tighten the joints.

Scanned with CamScanner

2. **POLISHING/PAINTING/VARNISHING**

a. **FINISH**. All wood work to be well smoothed and finished with No. 0 sand paper. All sharp edges to be very slightly rounded. After sand papering all wood work will be polished, varnished or painted as specified in the plans or particular specifications.

3. **POLISH**

a. Primary coat of mixture of plaster of Paris, water and color (Burnt sena, turkey amber and yellow Amber) to match wood, will be applied on hard wood and then sand paper to remove the material not absorbed in the grains of wood.

b. Primary coat of mixture of glue, water, burnt sena, Turkey Amber and Yellow sena will be applied on soft wood and then sand prepared to remove the excess material.

c. After preparation of the surface as stated above repeated application with muslin cloth and cotton of polish of composition as under will be made on the out side (visible) surface of the wood and finished to glossy surface. Sand papering will be done by sand paper No. 0 after 1st application to make the surface even. Polish can be thinned with addition of spirit as necessary for final coat:-

(1).	Methylated spirit	-	1	Gallon
(2).	Schellace 1st quality	-	1	Lb
(3).	Sundrus	-	1/8	"
(4).	Rumi Mustagi	-	1/8	"
(5).	Loban	-	1/16	"

4. **VARNISH**. After papering the surface as explained above for polish two coats of good quality varnish will be applied.

5. **PAINTING**

a. One priming and two subsequent coat will be applied before priming coat is applied wood work to be toughly cleansed, sand papered smoothed/dusted.

b. Paint with proper paint brushes will be carefully maintained through the work so as to be always pliable and free from loose bristles will be applied evenly and well over the surface.

Scanned with CamScanner

c. The surface of the priming and under coat paint to be rubbed down with the sand paper No. 0 before the application of the next coat. Great care to be taken with the final coat to ensure that no bush made are visible to the frame on the inner side of the glass sheet.

6. **GLAZING**. All glazing work to be of sheet glass of not less than 16 OZ per Sft free from specks bubbles or other defect and where not otherwise specified will fixed nailing wooden fillets to the frame on the inner side of the glass sheet.

7. **NETTING**

a. Nylon plastic strips 1/19 in of even width and thickness and of superior quality and free from discoloration to be used for netting.

b. Weaving will be done double horizontals and verticals and single diagonal small to be inter woven, Horizontals and verticals will be half centre to center. Holes will be bored in frames accordingly.

c. Before caning all edges of seat frames etc, will be rounded and holder slightly counter sunk to prevent under wear of the canner.

8. **IRON WORK**

a. All steel and iron work to be confirmed to BSS and to be as specified on the plans or in particulars specification.

b. Rivets must fit fully truly the holes made for them they must tight and closely driven all gas removed after snapping. Cast-iron to be uniform in thickness clean, sound and free form air bubbles or defects of any kind.

9. **FINISH** All rust to be removed and sharp edges to be filled/smoothed. Then to be dusted and painted or coal tarred as specified. Painting to be done as already specified. In tarring the lacquer be heated to near boiling paint, thinned by the addition one part of kerosene oil, four parts of tar by volume and applied while still hot. Parts of tar by volume and applied while still hot. 2 Lbs of unslacked lime to be mixed with each gallon of tar when nearing boiling paint to prevent ruming.

_____

Contractor
M/s

Signature of Officer
Authorized by accepting officer

Dated _____ Dec 2026

Dated _____ Dec 2026

CONDITIONS OF CONTRACT

Scanned with CamScanner