Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019002

RFQ No	RC-20195SJ
DATE	13.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	24.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for modification of existing tower and subsequent installation at Gaddani SS KHI DIV

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
1	**Signages**	**PSO House**				
1.01	**Tower Product Plate** Supply of Milky White Acrylic sheets 4mm thick with vinyl pasting for following Product Names as per the artwork provided: 1- Octane + 2- Premier 3- Hi-Cetane Electronically cutting and pasting of approved translucent vinyl of 3M/Avery/equivalent or acrlyic moulding of product plate and pasting of vinyl of 3m/ Avery/approved as per the approved design in PSO's approved colors for the required services name on Monolith Individual Panel complete in all respect. Clear Acrylic Sheet 3/4 mm thick with required shape and size and relevant adhesive material /silicon will be used for support at the back for fixing the product plates. Backlit illumination with minimum 24 LED* Modules for maximum glow and Power Supply as per requirement / details provided. This job shall be conducted to the entire satisfaction of PSO Engineer Incharge. Note: Each side of the item will be billed separately		**EA**	4		
1.02	**WIRING FOR SIGN POLE** Providing services for repairing and removal of old / burnt wires and installation of new wiring as per the requirement inside the tower panels. RFT= Job , complete in all respect		**RFT**	1		
1.03	**Tower Rate Digits Plates** Supply of Price Digital Display Units as per Specifications mentioned in specification sheet job includes supply of power supply / driver for price display units and supply of handheld remote control and remote communication for changing prices at monolith tower		**EA**	4		
1.04	**MONOLITH FOUNDATION**		**EA**	1		

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019002

RFQ No	RC-20195SJ
DATE	13.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	24.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for modification of existing tower and subsequent installation at Gaddani SS KHI DIV

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	Civil Work : Foundation of Monolith Tower as per drawing # 219-CIV-DT-001 Foundation works, job includes but not limited to following: Job Includes: - Excavation for foundation, trenches in any kind of strata as available as per site requirement and backfilling the excavated earth in foundation back fill material should be free from lumber,trash and other deleterious material drssing of bottom of excavation to perfect level<(> ,<)> dressing, watering and compaction to obtain 95% modified AASHTO density etc. and removal of surplus excavated stuff with a lead of as directed <(>,<)> by the engineerincharge. Working space shall not be allowed seperately ii) Providing and laying earth fill of approved quality and origin in foundation, plinth etc i/c breaking clods<(>,<)> dressing, watering and consolidating by rammming in layers not exceeding 6" depth to attain 95 % modified AASHTO density i/c all lead and lifts. NOTE: Actual compacted depth shall be considered for measurement/payment.(if required) iii) Providing and laying stone soling 6" to 9" depth thick of approved quarry including packing and filling voids with spawls and chips, khaka consolidating and and compacting with power compactor or hand compactor.(if required) iv) Providing and laying plain cement concrete using approved quality 1" maximum size graded crushed aggregate, stone or gravel with approved quality local river sand i/c all formwork<(>,<)> rodding ,vibrating, levelling and curing etc. a) Class 'D' C.C (1:3:6) cast in situ in floors, foundations etc.Using SR cement b) Class 'E' C.C (1:4:8) in foundations, Using SR cement v) Providing and laying reinforced concrete of specified strength using approved quality 3/4" max. size graded crushed aggregate and fine aggregate including approved formwork and its removal as per drawing, levelling<(>,<)> compacting,rodding, vibrating, finishing, curing etc. Class 'C' C.C					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019002

RFQ No	RC-20195SJ
DATE	13.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	24.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for modification of existing tower and subsequent installation at Gaddani SS KHI DIV

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	(1:2:4). a) Foundation.Using SR cement b) Columns upto plinth & Plinth Beam in SR cement Note: Job also includes following a) Supply/Providing steel reinforcement bars as per drawings and specifications. a) Deformed steel reinforcement of yield strength 60,000 psi. Note: Drawings Attached b) Laying steel reinforcement bars including straightening<(>,<)> removing twists, cutting, bending, binding, wastage and such overlaps as are not shown on drawings, placing in position on precast concrete or steel chairs, tying with binding wire complete as per drawings and specifications. Note: - Drawings Attached. - Payment will be made for the complete job Terms and Condition,, 1. The rates of items are inclusive of all taxes or any other tax applicable and contractor is required to submit GST/ SST invoice at the time of invoice. 2. Contractor will arrange testing of equipment at his own cost, if required. 3. Quality of work is the prime concern of PSO. The contractor will be required to produce best quality work. 4. Work must be completed within 120 days after site handed over to contractor. 5. Contractor has to comply with all HSE procedures and policies during execution of the work. 6. Contractor should strictly follow the safety and security rules of PSO. Contractor's team has to follow Company's rules and procedures as well as HSE guidelines and safety procedures. 7. All labour, tools, materials and transportation to be provided by contractor. 8. Payment will be made as per actual quantity of Work Done.					

Pakistan State Oil Company Limited
PSO House, Khayaban-e-Iqbal, Clifton, Karachi-75600, Pakistan
Telephone (021) 9203866-85 Fax (021) 9203796

REQUEST FOR QUOTATION

(THIS IS PRICE ENQUIRY-NOT AN ORDER)
SAP No.6100019002

RFQ No	RC-20195SJ
DATE	13.11.2026

Company PSO Dummy Vendor
PAKISTAN

QUOTATION REQUIRED

ON (Date)	24.11.2026	BY (Time)	

Please quote your best price for all items of following specifications. Please read the instructions attached herewith EARNEST MONEY % Rs._____ PO/DD NO. _____

Title: Providing services for modification of existing tower and subsequent installation at Gaddani SS KHI DIV

S.No.	Description/Specifications	Location	Unit	Qty	Unit Price Rs.	Amount Rs.
	9. If the Contractor fails to complete the work with in time stipulated ,the Engineer Incharge will be entitled to deduct from his bills for work given in this order or other monies due to him by PSO, a value of 0.1% of Service Order per day and subject to maximum 10% Value of SO. 10. Contractor should maintain housekeeping of the workplace during progress of work and shall clear and remove all surplus materials and rubbish from workplace after completion of job as per instruction of Incharge. 11. The work will only be accepted after inspection and approval by the DE. 12. Bidder must visit the site before quoting for the job to properly asses the scope of work. 13. Damage to the False Ceiling during replacement of sheets is to be born by contractor himself. 14. Rates are inclusive of scrap materials 15. Work will be performed using proper PPEs like, harness safety helmets, Shoes etc complete in all respect.,,					